

PLANNING COMMITTEE

NOTICE AND AGENDA

For a meeting to be held in the Penn Chamber, Three Rivers House, Northway, Rickmansworth on Thursday, 22 January 2026 at 7.30 pm

Members of the Planning Committee:-

Councillors:

Chris Whately-Smith (Chair)
Oliver Cooper
Harry Davies
Steve Drury
Philip Hearn
Stephen King

Elinor Gazzard (Vice-Chair)
Chris Lloyd
Abbas Merali
Chris Mitchell
Debbie Morris

*Joanne Wagstaffe, Chief Executive
Wednesday, 14 January 2026*

The Council welcomes contributions from members of the public to aid discussions on agenda items at Planning Committee meetings. Details of the procedure are provided below.

For those wishing to speak:

Members of the public are entitled to register and identify which item(s) they wish to speak on from the published agenda for the meeting. Those who wish to register to speak are asked to register on the night of the meeting from 7pm. Please note that contributions will be limited to one person speaking for and one against each item for not more than three minutes.

In the event of registering your interest to speak on an agenda item but not taking up that right because the item is deferred, you will be given the right to speak on that item at the next meeting of the Planning Committee.

For those wishing to observe:

Members of the public are welcome to attend the meetings. If you wish to observe you can arrive on the night from 7pm.

In accordance with The Openness of Local Government Bodies Regulations 2014 any matters considered under Part I business only of the meeting may be filmed, recorded, photographed, broadcast or reported via social media by any person.

Recording and reporting the Council's meetings is subject to the law and it is the responsibility of those doing the recording and reporting to ensure compliance. This will include the Human Rights Act, the Data Protection Legislation and the laws of libel and defamation.

The meeting may be livestreamed and an audio recording of the meeting will be made.

1. Apologies for Absence

2. Minutes

(Pages 5 - 12)

To confirm as a correct record the minutes of the Planning Committee meeting held on 11 December 2025.

3. Notice of Urgent Business

Items of other business notified under Council Procedure Rule 30 to be announced, together with the special circumstances that justify their consideration as a matter of urgency. The Chair to rule on the admission of such items.

4. Declarations of Interest

To receive any declarations of interest.

5. 24/2073/OUT - Outline application: development of up to 600 residential dwellings (Use Class C3(a)), construction of a 5-bedroom property for childrens social care and supported living (Use Class C3(b)). Two vehicular access points from Little Green Lane and further pedestrian / cycleway accesses. A one form entry primary school (Use Class F1(a)) (plus expansion land for a two form entry primary school). A mixed use local centre including provision for NHS health and social care services (Use Class E(e)), community building (Use Class F2), retail and cafe provision (Use Class E(a-c)), car parking and associated infrastructure. A country park, areas for play and recreation, allotments, community orchard and landscaping with associated infrastructure including sustainable urban drainage systems. (Layout, scale, appearance and landscape as reserved matters) at Land to North of Little Green Lane, Croxley Green WD3 3SP

(Pages 13 - 208)

Outline application: development of up to 600 residential dwellings (Use Class C3(a)), construction of a 5-bedroom property for childrens social care and supported living (Use Class C3(b)). Two vehicular access points from Little Green Lane and further pedestrian / cycleway accesses. A one form entry primary school (Use Class F1(a)) (plus expansion land for a two form entry primary school). A mixed use local centre including provision for NHS health and social care services (Use Class E(e)), community building (Use Class F2), retail and cafe provision (Use Class E(a-c)), car parking and associated infrastructure. A country park, areas for play and recreation, allotments, community orchard and landscaping with associated infrastructure including sustainable urban drainage systems. (Layout, scale, appearance and landscape as reserved matters) at Land To North Of Little Green Lane, Croxley Green.

Recommendation: that the application be delegated to the Head of Regulatory Services to grant planning permission 24/2073/OUT following the completion of a S106 Agreement to secure the Heads of Term set out at section 7.20 and subject to the conditions set out at section 8.

6. 25/0195/FUL: Demolition of existing dwelling and construction of detached building containing 5 residential flats, with associated landscaping, provision of new vehicular access, car parking, cycle

(Pages 209 - 246)

and refuse storage at 80 The Drive, Rickmansworth, Herts WD3 4DU

Demolition of existing dwelling and construction of detached building containing 5 residential flats, with associated landscaping, provision of new vehicular access, car parking, cycle and refuse storage at 80 The Drive, Rickmansworth.

Recommendation: that planning permission is refused.

7. **25/1671/FUL – Variation of Conditions 2 (Plans) and 25 (Obscure Windows) pursuant to planning permission 22/1148/FUL to allow alterations to fenestration detailing, omission of terrace balconies, addition of AOV rooflights and submission of hard and soft landscaping details including landscape management at Beesons Yard, Bury Lane, Rickmansworth, Herts.** (Pages 247 - 290)

Variation of Conditions 2 (Plans) and 25 (Obscure Windows) pursuant to planning permission 22/1148/FUL to allow alterations to fenestration detailing, omission of terrace balconies, addition of AOV rooflights and submission of hard and soft landscaping details including landscape management at Beesons Yard, Bury Lane, Rickmansworth.

Recommendation: that planning permission is granted, subject to the completion of a Deed of Variation to a Section 106 Agreement pursuant to planning permission 22/1148/FUL dated 18 December 2023; securing an occupancy age restriction, affordable housing contribution, controls on parking permits, amendment to Traffic Regulation Order and Waste Management Scheme, and planning conditions as set out at Section 7.

8. **25/1722/RSP – Part retrospective: construction of two outbuildings and alterations to rear land levels and landscaping works at 38 Moor Lane, Rickmansworth, Hertfordshire WD3 1LG** (Pages 291 - 300)

Part retrospective: construction of two outbuildings and alterations to rear land levels and landscaping works at 38 Moor Lane, Rickmansworth.

Recommendation: that part retrospective planning permission be approved subject to conditions.

9. **25/1754/ADV - Advertising Consent: Display of flags at Three Rivers House, Northway, Rickmansworth, Hertfordshire WD3 1RL** (Pages 301 - 310)

Advertising consent for display of flags at Three Rivers House, Northway, Rickmansworth.

Recommendation: that advertisement consent be granted subject to conditions.

10. **25/1987/FUL - Construction of part-single, part-two storey side and rear extensions and single storey side extension at 18 Greenways, Abbots Langley, Hertfordshire WD5 0EU** (Pages 311 - 324)

Construction of part-single, part-two storey side and rear extensions and single storey side extension at 18 Greenways, Abbots Langley.

Recommendation: that planning permission be granted subject to conditions.

- 11. 25/2091/RSP – Retrospective: construction of single storey rear extension at 39 - 41 High Street, Abbots Langley, Hertfordshire WD5 0AA** (Pages 325 - 334)

Retrospective: construction of single storey rear extension at 39 - 41 High Street, Abbots Langley.

Recommendation: that retrospective planning permission be granted.

- 12. 25/2102/FUL - Erection of a timber pergola at Croxley Guild Bowls Club, The Green, Croxley Green, Rickmansworth, Hertfordshire WD3 3HT** (Pages 335 - 346)

Erection of a timber pergola at Croxley Guild Bowls Club, The Green, Croxley Green, Rickmansworth.

Recommendation: that planning permission be granted subject to the conditions set out below.

- 13. 25/2150/FUL - Extension of existing crossover and alterations to driveway at 10 Oak Green, Abbots Langley, Hertfordshire WD5 OPG.** (Pages 347 - 360)

Extension of existing crossover and alterations to driveway at 10 Oak Green, Abbots Langley.

Recommendation: that planning permission be granted subject to conditions.

- 14. Other Business - if approved under item 3 above**

Exclusion of Public and Press

If the Committee wishes to consider any items in private, it will be appropriate for a resolution to be passed in the following terms:

“that under Section 100A of the Local Government Act 1972 the press and public be excluded from the meeting on the grounds that it involves the likely disclosure of exempt information as defined in Part I of Schedule 12A to the Act. It has been decided by the Council that in all the circumstances, the public interest in maintaining the exemption outweighs the public interest in disclosing the information.”

(Note: If other confidential business is approved under item 3, it will also be necessary to specify the class of exempt or confidential information in the additional items).

General Enquiries: Please contact the Committee Team at
committeeteam@threerivers.gov.uk



Three Rivers House
Northway
Rickmansworth
Herts WD3 1RL

Planning Committee MINUTES

Of a meeting held in the Penn Chamber, Three Rivers House, Rickmansworth, on Thursday, 11 December 2025 from 7.30 - 9.02 pm

Present: Councillors Chris Whately-Smith (Chair), Harry Davies, Steve Drury, Philip Hearn, Stephen King, Chris Lloyd, Abbas Merali, Chris Mitchell and Debbie Morris

Also in Attendance:

Councillor Jon Tankard, Parish Councillor Diana Barber (Batchworth Community Council) and Councillor Oliver Cooper

Officers in Attendance:

Matthew Barnes, Principal Lawyer - Planning
Emma Lund, Senior Committee Officer
Matthew Roberts, Development Management Team Leader
Kimberley Rowley, Head of Regulatory Services
Scott Volker, Principal Planning Officer
Claire Westwood, Development Management Team Leader

PC65/25 APOLOGIES FOR ABSENCE

An apology was received from Councillor Cooper who had expressed a wish to speak as a ward councillor on agenda item 8 (25/1294/FUL – Land Adjoining Sarratt Lane, Loudwater) and had decided to recuse himself as a Member of the Committee for this meeting to do so.

An apology for absence was also received from Councillor Gazzard.

PC66/25 MINUTES

The minutes of the Planning Committee meeting held on 20 November 2025 were confirmed as a correct record and signed by the Chair.

PC67/25 NOTICE OF URGENT BUSINESS

There were no items of urgent business.

PC68/25 DECLARATIONS OF INTEREST

There were no declarations of interest.

PC69/25 24/2089/FUL - CONSTRUCTION OF A SINGLE STOREY REAR EXTENSION; DRIVEWAY EXTENSION AND CONVERSION OF GARAGE INTO HABITABLE ACCOMMODATION AT 20 TOWNFIELD, RICKMANSWORTH, HERTFORDSHIRE WD3 7DD

The application was for construction of a single storey rear extension, driveway extension and conversion of garage into habitable accommodation at 20 Townfield, Rickmansworth.

The Planning Officer reported that the application had first been considered at the Planning Committee in March, at which time the committee had resolved to grant planning permission. However, following a complaint (the details of which were summarised in the report) officers had considered it prudent to delay issuing planning permission and allow time to look into the matters raised. Following submission of an amended land ownership certificate (Certificate B) on a without-prejudice basis, and a re-consultation exercise, the Case Officer had provided their recommendation within the updated committee report which was now before the Committee.

The Planning Officer clarified that the applicant maintained the view that the land which was the subject of the application was owned by them. In support of this view a report had been submitted by A D S Property Services which concluded that Certificate B was not required. An adjoining neighbour had also submitted representations and documentation asserting that they owned part of the application site. However, on the basis that Certificate B had been submitted officers were content that the application could now be determined. The Planning Officer confirmed that other than the submission of Certificate B there were no other changes to the application which had been considered in March.

A local resident spoke against the application.

The applicant spoke in favour of the application.

Parish Councillor Diana Barber of Batchworth Community Council spoke on the application.

Committee Members asked questions about the detail of the application which were responded to by officers. The Committee's discussions included the following:

- There were examples within Townfield of other garage conversions and extensions, albeit not within the same terrace as the application. However, these single storey rear extensions were to properties which were staggered. The application site was set back within the stagger, and therefore there was potential in this case for the extension to be more impactful. However, the assessment of Planning Officers was that the proposal would not adversely affect the amenity of neighbouring properties and that the depth of 3.6m, along with the proposed height and design, was acceptable. It was also in accordance with the Local Plan. The Planning Officer commented that in assessing the application officers had had regard to the wider context of Townfield as a whole, rather than just the individual terrace of properties in which the application site was situated.
- It was acknowledged that the proposal would result in a slight shortfall (14 sqm) in amenity space. However, this was not considered by officers to be of a level which would be harmful. Officers considered that the proposal would provide suitable usable amenity for everyday living which would not adversely affect the occupants. A Committee Member proposed that in light of the amenity shortfall a condition to remove Schedule 2, Part 1, Class E permitted development rights should be added in the event that the planning permission was granted, in order to prevent further development in the future.
- A Committee Member commented that many garages within the district (including those at Townfield) were no longer of a sufficient size to accommodate modern vehicles and consequently were not used for their intended purpose.
- In response to a point raised by a speaker about the impact on the neighbouring properties and any possible detriment to privacy, officers responded that whilst the proposal would obviously affect views from the rear elevation of the property, the views from the proposed extension would not be different to the existing and therefore would

have no impact on privacy. The impact on neighbouring properties was not considered to be detrimental for the reasons set out in the report.

Councillor Hearn moved, and Councillor Morris seconded, that planning permission be granted subject to conditions and an additional condition removing Schedule 2, Part 1, Class E permitted development rights. On being put to the vote this was carried, the voting being unanimous.

RESOLVED: that planning permission be granted subject to conditions and an additional condition removing Schedule 2, Part 1, Class E permitted development rights.

**PC70/25 PRELIMINARY REPORT 25/0484/OUT – OUTLINE APPLICATION:
ERECTION OF UP TO 75 NEW DWELLINGS, PARKING AND LANDSCAPING WITH
ASSOCIATED ACCESS ONTO CHALFONT ROAD (APPEARANCE, LAYOUT,
LANDSCAPING AND SCALE AS RESERVED MATTERS) AT LAND AT NORTH OF
CHALFONT ROAD, CHALFONT ROAD, MAPLE CROSS, HERTFORDSHIRE**

The Committee received a preliminary report on an outline application for the erection of up to 75 new dwellings, parking and landscaping with associated access onto Chalfont Road (Appearance, Layout, Landscaping and Scale as reserved matters) at Land at North of Chalfont Road, Chalfont Road, Maple Cross.

The Committee was invited to note the report, comment on any material planning considerations and consider undertaking a site visit. The application would be brought back to the Committee at a later date for determination.

The Planning Officer provided an update that correction was required to paragraph 8.1.22 of the report to clarify that due the amount of hedging and vegetation which would be lost, the proposal would not provide a link to Footpath 008 but only to Footpath 009. The applicant had provided a markup plan highlighting all tree and hedge removals (both partial and full) in response to comments from the Highway Authority: these were covered at paragraph 8.17.5 of the report and a plan was included in the presentation to the committee.

A local resident spoke against the application.

The applicant spoke in favour of the application.

Committee Members asked questions about the detail of the proposal which were responded to by officers. Members' comments included the following:

- A speaker drew attention to regular localised flooding at the site location, the potential impact on vehicular access, and flood risk to neighbouring properties arising from the proposal. The view was expressed that the flood risk assessment did not comprehensively cover the threat which was posed. Additionally, the drains were not adequately maintained and therefore flooding represented a greater risk than had been accounted for. Comment was also made that there was a risk in relation to foul water and sewage and a lack of drain capacity; that the traffic assessments did not accurately reflect the congestion experienced on Chalfont Road; and that a development of 300 houses in Buckinghamshire would further impact on road capacity. Committee Members considered that full details on these issues should be covered in the officer report when the application comes to the committee for determination.
- It was requested that details of the road and water infrastructure improvements mentioned by the applicant be included in the officer report, as well as further details of the play equipment to be provided (including maintenance arrangements); car parking provision and EV charging facilities; the attenuation pond; access issues; and the energy strategy for the site. A Committee Member expressed the view that there should be compulsory EV charging for every property.

- Committee Members' comments also included that it was important to retain as much hedging as possible; that assurance should be sought in relation to the proportion of affordable housing to be provided, in order to try to ensure that this was not reduced by the developer at a later date; that the option of moving the site entrance further westwards, or siting the open space closer to Oakhill Road, be considered in order to reduce the impact on properties in Oakhill Road; that the option of moving the attenuation pond be considered due to its visual impact; and that a requirement for obscured glazing be considered to prevent any overlooking of properties in Oakhill Road.
- Officers clarified that whilst the wider site was Green Belt, the parcel of land which formed the application site had been assessed as Grey Belt for the reasons set out in the report. The reasons for Maple Cross not being considered a large built-up area were addressed at paragraph 8.1.11.
- A Committee Member questioned the sustainability of the site location given that it was 5km from Rickmansworth Station, the cycle routes to other transport hubs and employment sites were difficult, and buses were often impacted by the congestion on Chalfont Road. The Committee Member also commented that the facilities to be provided on the site appeared to be minimal, with the only public benefit seeming to be housing and a small amount of open space. Public amenity in the form of green space, walks, and play areas already existed in the nearby vicinity.
- A Committee Member commented that a condition requiring a permanent wheel washing facility should be required as part of any planning consent.

By general assent the Committee agreed the recommendations as set out in the report.

RESOLVED: that

- 1) Members agree for officers to arrange a site visit prior to this application being presented to Planning Committee for a decision; and
- 2) the Committee notes the report and makes general comments with regards to the material planning issues raised by the application as set out above.

PC71/25 25/1182/RSP – PART RETROSPECTIVE: VARIATION OF CONDITION 13 (SURFACE WATER DRAINAGE SCHEME TO BE SUBMITTED) AND CONDITION 20 (COMPLIANCE WITH SURFACE WATER DRAINAGE SCHEME MITIGATION) PURSUANT TO OUTLINE PLANNING PERMISSION 23/0701/OUT TO ALLOW ALTERATIONS TO POND DEPTH AT LAND TO SOUTH OF FOXGROVE PATH/HEYSHAM DRIVE, SOUTH OXHEY, WATFORD WD19 6YL

The application was part retrospective for variation of Condition 13 (Surface Water Drainage Scheme to be submitted) and Condition 20 (Compliance with Surface Water Drainage Scheme Mitigation) pursuant to outline planning permission 23/0701/OUT to allow alterations to pond depth at Land To South Of Foxgrove Path/Heysham Drive, South Oxhey.

The Planning Officer clarified that the drainage pond which formed part of the approved sustainable drainage scheme had been constructed deeper than was set out within the approved outline planning application. The Lead Local Flood Authority had raised no objection to the increased depth of the pond, which would allow greater capacity as a result.

Councillor Whately-Smith moved, and Councillor King seconded, that retrospective outline planning permission be granted subject to conditions. On being put to the vote this was carried unanimously.

RESOLVED: that retrospective outline planning permission be granted subject to conditions.

PC72/25 25/1294/FUL - CONSTRUCTION OF 9NO. RESIDENTIAL DWELLINGS (USE CLASS C3), WITH ASSOCIATED REROUTING OF PUBLIC FOOTPATH, ACCESS, PARKING AND LANDSCAPING WORKS AT LAND ADJOINING SARRATT LANE, LOUDWATER, HERTFORDSHIRE

The application was for construction of 9no. residential dwellings (Use Class C3), with associated rerouting of public footpath, access, parking and landscaping works at Land Adjoining Sarratt Lane, Loudwater.

The Planning Officer provided the following updates:

- Further to the publication of the report, two additional ecology reports had been received. These related to dormice and badgers. Having reviewed their findings, officers were satisfied that the matter could be dealt with by condition, and as such reason for refusal 5 (ecology) would fall away.
- Ecology would also be removed from the weightings at the end of the report which were summarised in the table at 7.15.22. However, this did not change the overall conclusion and recommendation for refusal.
- One further objection had been received since the publication of the report. However, this did not raise any new material considerations which had not already been addressed in the report.
- Following its recent adoption, the Sarratt Neighborhood Plan was now to be afforded full weight as a material consideration. Relevant policies were considered to include:

Policies 2 (Design), 4 (Housing mix), 5 (AH), 6 (Biodiversity), 8 (RoW) and 10 (Car parking).

Reason for refusal 2 should be updated to include Policy 2 and the design guidance.

Reason for refusal 3 should be updated to include Policy 5 (AH).

Reason for refusal 6 should be updated to include Policy 10 (highways).

A local resident spoke against the application.

Councillor Oliver Cooper spoke on the application.

Committee Members asked questions about the detail of the application which were responded to by officers. The Committee's discussions included the following:

- A speaker commented that Sarratt Lane was a very narrow, single track lane with no pavement or street lighting and minimal passing places. The application site was therefore not appropriate for 9 large houses. Objections were made on the grounds of traffic congestion; unsuitability of the lane for heavy construction vehicles and the likely damage which would arise; the unsustainable location of the site; adverse impact on the character of the area; lack of infrastructure capacity; lack of compliance with the Sarratt Neighbourhood Plan; and ecology impacts of the proposal to divert the wooded public footpath. These comments were endorsed by Committee Members.
- A Committee Member noted that objections had been received from Sarratt Parish Council, Hertfordshire Highways, the Conservation Officer, the Lead Local Flood Authority and the Landscape Officer, as well as 71 public objections.
- A speaker commented that the site adjoined Chorleywood, which also had an up-to-date Neighbourhood Plan. In addition to the recently adopted Sarratt Neighbourhood Plan, the

proposal was also not compliant with a number of policies within the Chorleywood Neighbourhood Plan. Comment was also made that both areas had been subject to a number of applications which, had they all been approved, would have resulted in a level of housing delivery which would have by far exceeded their allocations.

Councillor Lloyd moved, and Councillor Drury seconded, that the application be refused for the reasons set out in the report and with the following amendments:

- (i) removal of reason for refusal 5; and
- (ii) amendment of reasons for refusal 2, 3 and 6 to include reference to the Sarratt Neighbourhood Plan.

On being put to the vote this was carried, the voting being unanimous.

RESOLVED: that the application be refused for the reasons set out in the report and with the following amendments:

- (i) removal of reason for refusal 5; and
- (ii) amendment of reasons for refusal 2, 3 and 6 to include reference to the Sarratt Neighbourhood Plan.

PC73/25 25/1851/FUL - VARIATION OF CONDITION 2 (PLANS) PURSUANT TO PLANNING PERMISSION 23/1619/FUL TO ALLOW THE OMISSION OF CENTRAL RIDGE SPANNING THE FRONT FACING GABLES, AND ALTERATION TO THE WINDOW BLADES ON THE FRONT ELEVATION AT GARAGES BETWEEN 83 AND 89 THE QUEENS DRIVE, MILL END

The application was for variation of Condition 2 (plans) pursuant to planning permission 23/1619/FUL to allow the omission of the central ridge spanning the front facing gables, and alteration to the window blades on the front elevation at Garages Between 83 and 89 The Queens Drive, Mill End.

The Planning Officer provided an update that having reviewed the amended plans which reinstated the window blades, Chorleywood Parish Council had revised its comments to confirm that it had no objection to the proposal and had withdrawn its call-in.

A Committee Member commented the proposal represented an improvement on the previous design.

Councillor Morris moved, and Councillor King seconded, that planning permission be granted subject to conditions. On being put to the vote this was carried, the voting being unanimous.

RESOLVED: that planning permission be granted subject to conditions.

PC74/25 25/1852/FUL – VARIATION OF CONDITION 2 (PLANS) PURSUANT TO PLANNING PERMISSION 23/1569/FUL TO ALLOW REPOSITIONING OF BUILDING, ALTERATIONS TO THE PLACEMENT OF BALCONIES, ALTERATIONS TO WINDOWS, ERECTION OF DORMER ABOVE STAIRCASE, REMOVAL OF GREEN ROOF TO BIN/BIKE STORES AT GARAGES ADJACENT 13 TO 23 POLLARDS, MAPLE CROSS, HERTFORDSHIRE

The application was for variation of Condition 2 (plans) pursuant to planning permission 23/1569/FUL to allow repositioning of building, alterations to the placement of balconies, alterations to windows, erection of dormer above staircase and removal of green roof to bin/bike stores at Garages Adjacent 13 To 23 Pollards, Maple Cross.

The Planning Officer clarified that the application sought to make minor changes to the planning approval previously granted. The approved plans included a single dormer window

to the rear elevation with a central recessed section and two dormers to the front elevation. It was proposed to replace the two approved front dormers with a single dormer with recessed section which would reflect that approved to the rear elevation.

The approved plans included recessed balconies to all flats across the ground, first and second floors, with the main elevations of those to the western end of the building facing the front and the main elevation of those to the eastern end of the building facing to the east (side). No changes were proposed to those to the western end of the building, however, the balconies to the eastern end were proposed to be re-orientated so that their main elevations would also face towards the front. There would be some associated alterations to fenestration to the front and flank as a result. The proposed changes would introduce a more symmetrical appearance to the front elevation than approved, however it was not considered that this would be harmful on character or appearance grounds. The reasons why the changes were considered acceptable from a character and amenity point of view were set out in the report.

It was also proposed to omit the green roof originally approved to the bin and bike store in order to comply with Building Regulations.

A Committee Member commented that the proposal represented an improvement to the approved application.

Councillor Whately-Smith moved, and Councillor Drury seconded, that planning permission be granted subject to conditions. On being put to the vote this was carried unanimously.

RESOLVED: that planning permission be granted subject to conditions.

**PC75/25 25/1909/FUL – CREATION OF VEHICLE ACCESS AND DROPPED KERB
ONTO HENDERSON PLACE AT 318 TOMS LANE, KINGS LANGLEY, HERTS WD5 0RB**

The application was for creation of vehicle access and dropped kerb onto Henderson Place at 318 Toms Lane, Kings Langley.

The Planning Officer provided updates as follows:

- The report should have included reference to Policy DM11 of the Development Management Policies Local Development Document, of which paragraph B stated that *'un-coordinated and ad-hoc proposals for vehicle crossovers which involve fragmentation and loss of grass verges and other spaces will be discouraged.'* In the event of approval Condition 2 would need to be updated to include reference to Policy DM11 in the reason for the condition.
- Condition 3 required an amendment to substitute *'before any building operations'* with *'before any above ground works'* and an informative should be included referring to the fact that the applicant would need to apply to Three Rivers District Council Property Services for approval for a crossover.

Committee Members asked questions about the detail of the application which were responded to by officers. The Committee's discussions included the following:

- A Committee Member noted that Condition 4 referred to a requirement that *'the development shall not be occupied until visibility splays have been provided in accordance with the approved details.'* It was agreed that this should be amended to refer to prior to first use of the crossover.

Councillor Drury moved, and Councillor King seconded, that planning permission be granted subject to conditions and the following amendments to conditions:

- an update to Condition 2 to refer to Policy DM11 of the Development Management Policies Local Development Document;
- an update to Condition 3 to refer to above ground works and an additional informative advising that consent from Three Rivers District Council Property Services was required; and
- an update to Condition 4 to require visibility splays to be provided prior to first use of the vehicle access following installation of the dropped kerb.

On being put to the vote this was carried unanimously.

RESOLVED: that planning permission be granted subject to conditions and the following amendments to conditions:

- an update to Condition 2 to refer to Policy DM11 of the Development Management Policies Local Development Document;
- an update to Condition 3 to refer to above ground works and an additional informative advising that consent from Three Rivers District Council Property Services was required; and
- an update to Condition 4 to require visibility splays to be provided prior to first use of the vehicle access following installation of the dropped kerb.

CHAIR

PLANNING COMMITTEE – 22 January 2026

24/2073/OUT - Outline Application: Development of up to 600 residential dwellings (Use Class C3(a)), construction of a 5-bedroom property for childrens social care and supported living (Use Class C3(b)). Two vehicular access points from Little Green Lane and further pedestrian / cycleway accesses. A one form entry primary school (Use Class F1(a)) (plus expansion land for a two form entry primary school). A mixed use local centre including provision for NHS health and social care services (Use Class E(e)), community building (Use Class F2), retail and cafe provision (Use Class E(a-c)), car parking and associated infrastructure. A country park, areas for play and recreation, allotments, community orchard and landscaping with associated infrastructure including sustainable urban drainage systems. (Layout, scale, appearance and landscape as reserved matters) at LAND TO NORTH OF LITTLE GREEN LANE, CROXLEY GREEN, WD3 3SP

Parish: Sarratt Parish Council/Croxley Green Parish Council¹

Ward: Chorleywood North & Sarratt / Durrants²

Expiry of Statutory Period: 30.01.2026 (Agreed Extension)

Case Officer: Claire Westwood

Development type: Large Scale Major Dwellings

Recommendation: The APPLICATION BE DELEGATED TO THE HEAD OF REGULATORY SERVICES TO GRANT PLANNING PERMISSION 24/2073/OUT following the completion of a S106 Agreement to secure the Heads of Term set out at section 7.20 below and subject to the conditions set out at section 8 below.

Reason(s) for consideration by the Committee:

1. Called in by Members of the Planning Committee for the following reasons: 1) Highways; 2) Impact on Green Belt; 3) Impact on other local services/utilities; and 4) Flooding.
2. Called in by Sarratt Parish Council for the reasons set out at 9.23 below (if officers are minded to approve).
3. Called in by Croxley Green Parish Council for the reasons set out at 9.5 below (if officers are minded to approve).

To view all documents forming part of this application please go to the following website:

[24/2073/OUT | Outline Application: Development of up to 600 residential dwellings \(Use Class C3\(a\)\), construction of a 5-bedroom property for childrens social care and supported living \(Use Class C3\(b\)\). Two vehicular access points from Little Green Lane and further pedestrian / cycleway accesses. A one form entry primary school \(Use Class F1\(a\)\) \(plus expansion land for a two form entry primary school\). A mixed use local centre including provision for NHS health and social care services \(Use Class E\(e\)\), community building \(Use Class F2\), retail and cafe provision \(Use Class E\(a-c\)\), car parking and associated infrastructure. A country park, areas for play and recreation, allotments, community orchard and landscaping with associated infrastructure including sustainable urban drainage systems. \(Layout, scale, appearance and landscape as reserved matters\). | Land To North Of Little Green Lane Croxley Green WD3 3SP](#)

¹ The majority of the site falls within Sarratt Parish area, however, the access points fall within Croxley Green Parish area. Both Sarratt and Croxley Green Parish Councils were consulted.

² The majority of the site falls within Chorleywood North and Sarratt ward, however, the access points fall within Durrants ward.

Executive Summary

This report makes a full assessment of planning application 24/2073/OUT, for the proposed development including 600 residential dwellings; a one form entry primary school; a mixed use local centre including provision for NHS health and social care services, community building, retail and cafe provision, car parking and associated infrastructure at land to the north of Little Green Lane, Croxley Green. The application is in Outline, with details of access provided for full consideration. Appearance, landscape, layout and scale are reserved matters.

The assessment has considered all relevant material planning considerations, including the provisions of the National Planning Policy Framework (NPPF) and The Three Rivers Local Development Plan. The responses from consultees have also been considered, and a list of all consultees is included at section 4 of the report with their full comments provided in Appendix 1 at section 9. The majority of consultees raised no objection subject to conditions and/or S106 agreement. All statutory consultees raise no objection.

The primary planning considerations include the principle of the development in the Green Belt; impact on landscape, character and heritage; housing provision; highways and access considerations and residential amenity. Officers have assessed these matters and all other planning considerations and conclude that the proposal is acceptable.

In relation to Green Belt, officers consider that the site is Green Belt and the proposal accords with clauses (a) – (d) of Paragraph 155 of the NPPF. As such, it is considered that the development is an appropriate form of development in the Green Belt. In relation to landscape and heritage, there would be localised harm to the landscape as set out at 7.2 and less than substantial harm (low – mid level and low level respectively) to the setting of the Grade II Listed Durrants House and the Grade II Registered Cassiobury Park. Subject to conditions/S106 there are no objections on highways, amenity or other grounds.

The benefits of the scheme are considered at section 7.22 and include the need for housing, the need for affordable housing, compliance with the 'Golden Rules', a new 1FE Primary School and provision for NHS health and social care services – all of which are afforded significant weight in support of the application.

It is considered that the substantial public benefits of the proposal outweigh the less than substantial harm to the heritage assets. Similarly, having regard to the tilted balance, any adverse impacts of the development are significantly and demonstrably outweighed by the benefits identified. This report therefore recommends approval, subject to conditions and a S106 agreement.

This executive summary provides an overview. It is not exhaustive and should be read in conjunction with the full report for a complete understanding.

Update

A preliminary report was discussed at the Planning Committee meeting on 17 July 2025, where the Committee were asked to note the report and make general comments with regard to the material planning issues raised by the application.

The analysis has been updated to provide a full justification for the officer recommendation, including in relation to the material points raised when the preliminary report was discussed.

At the July 2025 meeting Members also agreed for officers to arrange a site visit ahead of the application being returned to committee for determination. The site visit has taken place.

1 Relevant Planning History

- 1.1 24/1220/EIA - EIA Screening Request: Up to 600 new residential dwellings (Use Class C3), 1FE Primary School plus expansion land, mixed use local centre including Doctor's surgery, open and green space and associated infrastructure. Determined. Not EIA development.

2 Description of Application Site

- 2.1 The site has an area of approximately 40 hectares. It is a greenfield site predominantly used for agriculture, with existing woodland comprising approximately 7% of the site area. Little Green Lane borders the site to the south, with the existing residential streets of Croxley Green and existing Little Green Junior School beyond this. To the north and east of the site is Rousebarn Lane, a predominantly single track route which runs between the site and Whippendell Woods. To the west of the site is woodland and agricultural fields. A public footpath (Sarratt 017) runs through the site between Rousebarn Lane to the east and Dell Wood to the west.
- 2.2 The site is located to the northern edge of Croxley Green, and falls within Sarratt Parish area. The centre of Croxley Green is located approximately 2km to the south with Watford approximately 4km to the east.
- 2.3 The site is less than 2km from Croxley Station (Metropolitan Line) which provides regular services to central London via Northwood and Harrow. The closest bus links are on Baldwins Lane to the south. Junction 18 of the M25 is approximately 6km from the site.
- 2.4 In terms of site constraints, the site is situated wholly within the Metropolitan Green Belt. There are Ancient Woodlands (Dell Wood and Long Newlands Spring) adjoining the site to the west and north-west and within the site (Green Lane Wood). These are also Local Wildlife Sites. Public footpath (Sarratt 017) runs through the site. A Tree Preservation Order (TPO) TPO935 was confirmed on the 14 October 2025. This comprises of 10 individual trees (9 x English Oak and 1 x Common Holly) and 1 group (mixed woodland) all located within the application site. Six individual trees are located to the west of Green Lane Wood (the group protected), 2 are located to the northern site boundary and 2 are located to the southern site boundary with Little Green Lane.
- 2.5 Whippendell Wood SSSI is sited to the east and north-east, separated by Rousebarn Lane. Cassiobury Park (Registered Park Grade II, NHLE 1000219) is also sited to the east. Durrants House (Listed Building Grade II, NHLE 1403581) is directly opposite the site boundary on Little Green Lane. It is a Tudor/Jacobean revival-style country house built in 1866-7. The Croxley Green Conservation Area is to the west, south-west of the site – the site does not adjoin the conservation area boundary. The site is wholly within Flood Zone 1 as defined by the Environment Agency. Flood Zone 1 signifies areas with the lowest probability of flooding (less than a 0.1% annual probability of river or sea flooding, equating to less than 1 in 1000 chance).

3 Description of Proposed Development

- 3.1 This application seeks outline planning permission for the; 'Development of up to 600 residential dwellings (Use Class C3(a)), construction of a 5-bedroom property for childrens social care and supported living (Use Class C3(b)). Two vehicular access points from Little Green Lane and further pedestrian / cycleway accesses. A one form entry primary school (Use Class F1(a)) (plus expansion land for a two form entry primary school). A mixed use local centre including provision for NHS health and social care services (Use Class E(e)), community building (Use Class F2), retail and cafe provision (Use Class E(a-c)), car parking and associated infrastructure. A country park, areas for play and recreation, allotments, community orchard and landscaping with associated infrastructure including sustainable urban drainage systems'.

- 3.2 This application has been submitted in Outline with the matter of Access submitted for approval, and matters of Appearance, Landscaping, Layout and Scale reserved for later consideration. Access is defined in the Development Management Procedure Order as meaning 'the accessibility to and within the site, for vehicles, cycles and pedestrians in terms of the positioning and treatment of access and circulation routes and how these fit into the surrounding access network'.
- 3.3 The detailed application drawings 001 Rev E (Proposed Site Access Durrants Drive) and 002 Rev D (Proposed Site Access Links Way) show the position of the two proposed points of vehicular access to the site across Little Green Lane from Durrants Drive and Links Way.
- 3.4 The application is accompanied by a Land Use Parameters Plan (ref. P24-1200_DE_0014_S1_Rev F) which demonstrates how the different components of the scheme can be incorporated. The Parameters Plan identifies areas for residential development; open space; mixed use local centre; 1FE primary school; and school expansion land. The Land Use Parameters Plan also illustrates indicative areas for access to the site and within the site. In the event that Outline planning permission was granted, a condition would require that subsequent Reserved Matters accord with the Land Use Parameters Plan.
- 3.5 The application is accompanied by an illustrative masterplan (page 57 of Design and Access Statement) which accords with the Land Use Parameters Plan and demonstrates how the site could be developed, with open space and sustainable drainage to the east and built development to the south and west with a series of roads and walking/cycling routes. It is important to note that the masterplan is submitted for illustrative purposes only to demonstrate how the site could be developed at the quantum proposed.
- 3.6 A Design Code has been submitted with the application. The purpose of the Design Code is to provide a series of clear instructions/rules to inform subsequent Reserved Matters applications.
- 3.7 The application was initially accompanied by the following plans/reports:
- Application Form
 - Land Use Parameters Plan (P24-1200_DE_0015 Sheet 1 Rev C)
 - Location Plan (P24-1200_DE_001)
 - Proposed Site Access Links Way (T24544.001 Rev C)
 - Proposed Site Access Durrants Drive (T24544.002 Rev C)
 - Affordable Housing Statement (Tetlow King Planning, December 2024, M24/0511-01.RPT)
 - Agricultural Land Classification and Soil Resources Report (Reading Agricultural Consultants, July 2024)
 - Air Quality Assessment (BWB, December 2024, 233574-01-AQA)
 - Biodiversity Calculation Metric
 - Biodiversity Checklist
 - Design and Access Statement and Design Code (Richborough, January 2025, Rev A)
 - Ecological and Biodiversity Impact Assessment (RammSanderson, December 2024, RSE_8239_R1_V4_EcIA)
 - Education Report (EFM, December 2024)
 - Energy Statement (Greengage, December 2024)
 - Flood Risk Assessment (BWB, December 2024, 233574_FRA)
 - Health Impact Assessment (RPS, December 2024, 1.0)
 - Heritage Statement (Pegasus Group, December 2024, P24-1200)
 - Landscape and Visual Impact Assessment (iceni, December 2024)
 - Local Centre Capacity Statement (Lambert Smith Hampton, December 2024)
 - Noise Impact Assessment (BWB, December 2024, 233574_002)

- Phase 1 GEO-Environmental Assessment (BWB, December 2024, 233574)
- Planning Statement (RPS, December 2024)
- Preliminary Arboricultural Impact Assessment (Tyler Grange, December 2024, 11702_R02_NC RevD)
- Sports and Leisure Strategy (Sports Planning Consultants, December 2024)
- Statement of Community Involvement (Catus Group, December 2024)
- Sustainability Statement (Greengage, December 2024)
- Sustainable Drainage Strategy (BWB, December 2024, 233574-SDS)
- Transport Assessment (hub, January 2025, Rev A)
- Travel Plan (hub, December 2024)
- TRDC 5 Year Housing Land Supply Assessment (Emery Planning, December 2024, 24-305)
- Utilities Statement (BWB, December 2024, 233574)

3.8 Amendments/additional information submitted during the application include:

- Response to TRDC Heritage Officer comments (Pegasus Group 27/03/25 received 28/03/25).
- Response to Lead Local Flood Authority comments (BWB Ref. 233574-BWB-ZZ-XX-T-W-0005_LLFA received 07/05/25).
- Response to Sport England comments (RPS 22/05/25).
- Green Belt Addendum Assessment (Iceni, March 2025).
- Amend Travel Plan (hub Transport Planning Ltd, 26/6/2024) (NB. The agent has confirmed that the amended travel plan received July 2025 should be dated 26/6/2025).
- Amended Transport Assessment and Appendices (hub Transport Planning Ltd, Rev C 3/7/25).
- Active Travel Route Audit (hub Transport Planning Ltd, 2/7/25).
- Technical Note TN2 – Impact on the SRN (hub Transport Planning Ltd, 18/8/25).
- Green Belt: Purpose A Note (Iceni, August 2025).
- Technical Note TN3 – All Modes Travel Demand (hub Transport Planning Ltd, 1/9/25).
- Stage 1 Road Safety Audit Report (hub Transport Planning Ltd, July 2025).
- Woodland Recreational Management Plan (Outline), ref. RSE_8239_R2_V2 October 2025.
- Planning Statement Addendum (RPS October 2025). Including (2) 'Planning Policy Changes and Implications' such as the Sarratt Neighbourhood Plan and (3) Response to themes and matters raised at the preliminary Planning Committee, by consultees and public consultation.
- Amended Transport Assessment and Appendices (hub Transport Planning Ltd, Rev E 23/10/25).
- Amended Preliminary Arboricultural Impact Assessment (Tyler Grange, 11702_R02_NC, 9 October 2025).
- Amended Design and Access Statement and Design Code (Revision C, October 2025).
- Amended Landscape Strategy (iceni, ref. DL02 G – previously Appendix 11 of LVIA).
- Response to TRDC Stage 4 Green Belt Review (iceni, September 2025).
- M1 Junction 5 VISSIM Model Tests Technical Note (WSP, 13/11/2025).
- Transport Assessment Addendum (hub Transport Planning Ltd, 10/12/2025).
- Addendum to M1 Junction 5 VISSIM Model Tests Report (12/12/2025, WSP).
- Updated Affordable Housing Position Statement (Email from RPS, 15/12/2025).
- Perimeter Plans – Various (6/1/26). NB. No changes have been made to the parameter plans at this stage, they have simply been provided as standalone drawings (previously contained within D&A).

4 Consultation

A summary is provided below, with the full comments set out in **Appendix 1 at Section 9**.

Active Travel England:	9.1	No objection subject to condition(s)
Affinity Water	9.2	No objection
British Pipeline Agency	9.3	No comments on application
Chiltern Conservation Board	9.4	No objection
Croxley Green Parish Council	9.5	Objection
Forestry Commission	9.6	Concerns, condition(s) if minded to approve
HCC Footpath Section	9.7	No response received (see Hertfordshire Highways)
HCC Growth and Infrastructure Unit	9.8	No objection, S106 contributions requested
HCC Healthy Places	9.9	No objection
HCC Lead Local Flood Authority	9.10	No objection subject to condition(s)
HCC Waste and Minerals Team	9.11	No objection subject to condition(s)
HCC Water Officer	9.12	No objection
Hertfordshire Archaeology	9.13	No objection subject to condition(s)
Hertfordshire and West Essex ICB	9.14	No objection, S106 contributions requested
Hertfordshire Constabulary	9.15	No objection
Hertfordshire Ecology	9.16	No objection subject to condition(s)
Hertfordshire Highways	9.17	No objection, conditions & S106 contributions requested
London Underground Limited	9.18	No comments on application
National Grid	9.19	No objection
National Highways	9.20	No objection
Natural England	9.21	No objection subject to condition(s)
Ramblers	9.22	Advisory comments re. PROW
Sarratt Parish Council	9.23	Objection
Sport England	9.24	No objection subject to condition(s) and S106 contribution(s)
Thames Water	9.25	No objection subject to condition(s)
Transport for London	9.26	No objection, S106 contribution requested
TRDC Environmental Health (Residential)	9.27	No objection subject to condition(s)
TRDC Environmental Protection	9.28	Advisory comments regarding resources required
TRDC Heritage Officer	9.29	Objection (less than substantial harm)
TRDC Housing Officer	9.30	No objection
TRDC Tree and Landscape Officer	9.31	No objection (subject to suitable compensation/mitigation)
TRDC Leisure Development Officer	9.32	No objection subject to condition(s)
TRDC Planning Policy Team	9.33	Advisory comments re. policy framework
Watford Borough Council	9.34	No response received.

Watford Environmental Health (Commercial)	9.35	No objection subject to condition(s)
Woodland Trust	9.36	Objection

4.1 Public/Neighbour Consultation

4.1.1 Number consulted: 2143

4.1.2 No of responses received: 741 representations (**708 objections** including from Croxley Green Residents Association, CPRE – Campaign to Protect Rural England, Governing Bodies of local primary schools; and Little Green Junior School and **33 supporting comments**).

4.1.3 Site Notice(s): x 5 Displayed 23/01/25 Expired 13/02/25

4.1.4 Press Notice: Published 24/01/25 Expired 14/02/25

4.1.5 Summary of Responses:

4.1.5.1 Objections:

The site is prime agricultural land and is used for agriculture.
Loss of farmland reduces capability to produce own food sources.

Object to destruction of Green Belt.

Green Belt should be protected.

The Green Belt is crucial in preventing the encroachment of Croxley Green into Chandlers Cross, Sarratt and beyond.

There would be extensive harm to the openness of green belt land.

The Green Belt is inherently connected to the ecology of the whole area including SSSI and Ancient Woodland.

The Very Special Circumstances required by the NPPF have not been demonstrated.

This area is not Grey Belt.

The proposal would undermine the purpose of restricting sprawl of large built-up areas. The site plays a significant contribution in this regard and the proposal would undermine this purpose.

Would result in urban sprawl.

The Green Belt stage 2 review undertaken by LUC in October 2019 states release of the site for development would have a significant impact on preventing urban sprawl and encroachment onto the countryside.

600 new residences would fundamentally alter the character of an area / village.

Overdevelopment.

High density development does not relate to Croxley Green.

Inappropriate to build a new town on this area.

Four storey buildings out of character.

Design is out of keeping.

Visual impact.

Impact on landscape

Heritage and conservation – the site is near listed buildings and conservation areas which must be protected.

Regularly used for running, walking and enjoying the countryside.

Negative impact on local community.

Negative impact on physical and mental wellbeing.

Fails to address need for sporting facilities in Croxley Green.

Impact on quality of life.

Highways safety concerns, particularly for school children.

Access roads are unsuitable for the expected traffic from a development of this scale.

Access roads are narrow and heavily parked.

It is more appropriate for such a large residential area to be served from a Type 2 or Type 1 road rather than residential roads proposed.

Baldwins Lane is already solid in rush hour, this will be exacerbated.

The traffic challenges make this development unviable and unsafe.

The traffic congestion will increase dramatically in all areas.

Hertfordshire Highways object.

National Highways object.

No credible plans for improved transport links.

Parking is already limited in the area.

Impact of overflow parking on local streets.

Lack of sustainable transport options / reliance on cars over public transport.

Poor public transport links.

Proposed bus service would not be sufficient mitigation.

Existing roads in disrepair.

Concerns regarding access for emergency services.

The potential cycle lane would reduce the parking for current residents on an already narrow road.

Destroy valuable green space.

Negative impact on protected species in the area.

The application fails to sufficiently address mitigations for the dormice, badgers, bats, muntjac, foxes

and protected bird species like skylarks, swifts and red kites that are on the land.

Development will impact biodiversity and ecology of ancient woodland and SSSI including hedgerow removal and damage to root systems and drainage.

Damaging loss of habitat, and foraging grounds for a wide range of species.

Significant environmental impact.

Unclear how 10% BNG will be achieved.

Major impact on flora and fauna.

Impact on River Chess, protected chalk stream.

Impact on SSSI.

Impact on Local Wildlife Sites.

Disappointed to see ancient trees cut down.

Swift bricks should be included.

No need for additional primary school / struggling to fill others.

Data suggests falling demand linked to falling birth rate.

Will add pressure on waste and water treatment and many other services.

Medical centre should be in central Croxley, not this site.

Local infrastructure is already struggling, this will be exacerbated.

Will the community services offered actually get built? Will the school be built?

Inadequate drainage.

Impact on water pressure.

Connection to utilities will put further strain on existing.

Pressure on local schools.

No local benefit.

Country Park could attract large numbers of visitors and no parking has been proposed.

If the scheme goes ahead then it would be important that Country Park is maintained

Impact of construction over an extended period including high volumes of dust.

Environmental risks to both natural and human ecology generated both during and at the completion.

Noise pollution.
Light pollution.
Air quality.

Increased hard surfaces will worsen flooding on Rousebarn Lane.
Heavy flooding including surface water.
No clear sustainable drainage plan.

Will not provide affordable housing as evidenced by other new builds.
There is already considerable new housing provision recently completed, under construction or with planning permission.
Alternative solutions for housing such as unused office buildings in better locations.
Brownfield sites should be prioritised.
Recognise need for housing but this is not the right location.
Killingdown Farm development should be the limit for the area.
This development fails to deliver genuinely affordable housing.

Misleading information within application.
Have application documents / reports been diligently reviewed.
Houses on nearby sites are not sold.
Contrary to policy.
Although Three Rivers lacks 5-year housing supply, speculative developments should not bypass planning process.
Approving could set precedent.
Likely extension of development in future into proposed green spaces.
Driven by developer greed.
Violation of human rights.
Croxley is being overdeveloped, no one is considering cumulative impacts.
Lacks sustainable building practices or commitments to renewable energy.
Not allocated in draft local plan

4.1.5.2 Support:

Much needed new homes in desirable location.
Need for housing is overwhelming.
Enable next generation to stay here.
Includes provision of new primary school and other community uses / facilities and space for play and recreation.
Infrastructure plans are good.
The village has always grown so has already changed character.
Doctors surgery may be required.
Traffic is never as bad as feared.
It is large but will create modern vibrant district.
In absence of other suitable land need to look at Green Belt.
Things have changed since Green Belt introduced.
The alternative is tower blocks.
Proposal includes screening and protection to woodland.
I believe that better education provision would be served by building a 3 or 4 form infant school on the site.

5 Reason for Delay

- 5.1 The application has been extended beyond its original statutory determination period in order to enable the applicant to work with those statutory consultees who have raised technical objections.

6 Relevant Planning Policy, Guidance and Legislation

6.1 Legislation

Planning applications are required to be determined in accordance with the statutory development plan unless material considerations indicate otherwise as set out within S38(6) Planning and Compulsory Purchase Act 2004 and S70 of Town and Country Planning Act 1990.

S66(1) of Planning (Listed Buildings and Conservation Areas) Act 1990 requires LPAs to have special regard to the desirability of preserving the listed building or its setting or any features of special architectural or historic interest which it possesses when considering whether to grant planning permission.

Countryside and Rights of Way Act 2000

Levelling-up and Regeneration Act 2023

The Localism Act received Royal Assent on 15 November 2011. The Growth and Infrastructure Act achieved Royal Assent on 25 April 2013.

The Wildlife and Countryside Act 1981 (as amended), the Conservation of Habitats and Species Regulations 2017, the Natural Environment and Rural Communities Act 2006 and the Habitat Regulations 1994 may also be relevant.

The Environment Act 2021

6.2 National Planning Policy Framework and National Planning Practice Guidance

In December 2024 the National Planning Policy Framework (NPPF) was updated and may be read along with the National Planning Practice Guidance (NPPG) as relevant government planning guidance. As is recognised in the NPPF, planning law requires that applications for planning permission be determined in accordance with the development plan unless material considerations indicate otherwise. The NPPF and NPPG are ‘material considerations’ relevant to planning decision making. The NPPF is equally clear that “existing [development plan] policies should not be considered out-of-date simply because they were adopted or made prior to the publication of this Framework. Due weight should be given to them, according to their degree of consistency with this Framework” (NPPF Annex 1: 225).

A number of NPPF chapters are relevant to the consideration of this application, with the most important being:

- 2 – Achieving sustainable development
- 5 – Delivering a sufficient supply of homes
- 8 – Promoting healthy and safe communities
- 9 – Promoting sustainable transport
- 12 – Achieving well-designed and beautiful places
- 13 – Protecting Green Belt land
- 14 – Meeting the challenge of climate change, flooding and coastal change
- 15 – Conserving and enhancing the natural environment
- 16 – Conserving and enhancing the historic environment

6.3 The Three Rivers Local Development Plan

The planning merits of the application have been assessed against the policies of the development plan, namely, the Local Plan, including the Core Strategy (adopted October 2011), the Development Management Policies Local Development Document (adopted July 2013), the Site Allocations Local Development Document (adopted November 2014) as well

as government guidance. The policies of Three Rivers District Council reflect the content of the NPPF.

The Core Strategy was adopted on 17 October 2011 having been through a full public participation process and Examination in Public. Relevant policies include Policies CP1 (Overarching Policy on Sustainable Development), CP2 (Housing Supply), CP3 (Housing Mix and Density), CP4 (Affordable Housing), CP6 (Employment and Economic Development), CP7 (Town Centres and Shopping), CP8 (Infrastructure and Planning Obligations), CP9 (Green Infrastructure), CP10 (Transport and Travel), CP11 (Green Belt) and CP12 (Design of Development).

The Development Management Policies Local Development Document (DMLDD) was adopted on 26 July 2013 after the Inspector concluded that it was sound following Examination in Public which took place in March 2013. Relevant policies include DM1 (Residential Design and Layout), DM2 (Green Belt), DM3 (Historic Built Environment), DM4 (Carbon Dioxide Emissions and On Site Renewable Energy), DM6 (Biodiversity, Trees, Woodland and Landscaping), DM7 (Landscape Character), DM8 (Flood Risk and Water Resources), DM9 (Contamination and Pollution), DM10 (Waste Management), DM11 (Open Space, Sport and Recreation Facilities and Children's Play Space), DM12 (Community, Leisure and Cultural Facilities), DM13 (Parking), Appendix 2 (Design Criteria) and Appendix 5 (Parking Standards).

Sarratt Neighbourhood Plan (adopted 2025). Relevant Policies include: Policy 2 (Design Principles); Policy 4 (Housing Mix); Policy 5 (Affordable Housing); Policy 6 (Biodiversity); Policy 7 (Landscape); Policy 8 (Public Right of Way); Policy 9 (Community Facilities); Policy 10 (Car Parking); and Policy 12 (Renewable Energy & Green Infrastructure).

Croxley Green Neighbourhood Plan (2018). As previously noted, the majority of the application site falls within Sarratt Parish area. It is only the two access points proposed from Little Green Lane that fall within the Croxley Green Neighbourhood Plan area and that can be assessed against the Neighbourhood Plan. Policy H03 (Connections to existing footpaths and cycle ways in new developments) advises that all new development should connect into the existing networks and improve their connectivity.

Hertfordshire County Council's adopted Minerals Local Plan 2002 – 2016.

The Waste Core Strategy and Development Management Policies 2011–2026.

The Waste Site Allocations Development Plan Document 2011–2026.

6.4 Other

The Community Infrastructure Levy (CIL) Charging Schedule (adopted February 2015).

Stage 1 Green Belt Review – Strategic Analysis (2017).

Stage 2 Green Belt Assessment for Three Rivers and Watford Borough (2019).

South-West Herts Local Housing Needs Assessment Update (March 2024).

Stage 4 Green Belt Review (2025) – Draft form only.

7 **Planning Analysis**

7.1 Principle of Development – Impact on the Green Belt

- 7.1.1 Paragraph 142 of the NPPF states “the Government attaches great importance to Green Belts. The fundamental aim of Green Belt policy is to prevent urban sprawl by keeping land permanently open; the essential characteristics of Green Belts are their openness and their permanence”. Paragraph 143 states that Green Belt serves five purposes:
- a) to check the unrestricted sprawl of large built-up areas;
 - b) to prevent neighbouring towns merging into one another;
 - c) to assist in safeguarding the countryside from encroachment;
 - d) to preserve the setting and special character of historic towns; and
 - e) to assist in urban regeneration, by encouraging the recycling of derelict and other urban land.
- 7.1.2 Paragraph 145 of the NPPF states that “Once established, Green Belt boundaries should only be altered where exceptional circumstances are fully evidenced and justified through the preparation or updating of plans. Strategic policies should establish the need for any changes to Green Belt boundaries, having regard to their intended permanence in the long term, so they can endure beyond the plan period. Where a need for changes to Green Belt boundaries has been established through strategic policies, detailed amendments to those boundaries may be made through non-strategic policies, including neighbourhood plans”. This application does not seek to alter Green Belt boundaries. It proposes development within the Metropolitan Green Belt.
- 7.1.3 Paragraph 151 of the NPPF states that “Once Green Belts have been defined, local planning authorities should plan positively to enhance their beneficial use, such as looking for opportunities to provide access...”
- 7.1.4 Paragraph 153 of the NPPF states that “Inappropriate development is, by definition, harmful to the Green Belt and should not be approved except in very special circumstances”. Paragraph 153 states “When considering any planning application, local planning authorities should ensure that substantial weight is given to any harm to the Green Belt. ‘Very special circumstances’ will not exist unless the potential harm to the Green Belt by reason of inappropriateness, and any other harm resulting from the proposal, is clearly outweighed by other considerations”.
- 7.1.5 Paragraph 154 of the NPPF states “A local planning authority should regard the construction of new buildings as inappropriate in the Green Belt. Exceptions to this are as follows:
- a) buildings for agriculture and forestry;
 - b) the provision of appropriate facilities (in connection with the existing use of land or a change of use) for outdoor sport, outdoor recreation, cemeteries and burial grounds and allotments; as long as the facilities preserve the openness of the Green Belt and do not conflict with the purposes of including land within it;
 - c) the extension or alteration of a building provided that it does not result in disproportionate additions over and above the size of the original building;
 - d) the replacement of a building, provided the new building is in the same use and not materially larger than the one it replaces;
 - e) limited infilling in villages;
 - f) limited affordable housing for local community needs under policies set out in the development plan (including policies for rural exception sites);
 - g) limited infilling or the partial or complete redevelopment of previously developed land (including a material change of use to residential or mixed used including residential), whether redundant or in continuing use (excluding temporary buildings), which would not cause substantial harm to the openness of the Green Belt;
 - h) Other forms of development provided that they preserve its openness and do not conflict with the purposes of including land within it. These are:
 - i) mineral extraction;
 - ii) engineering operations;

- iii) local transport infrastructure which can demonstrate a requirement for a Green Belt location;
- iv) the re-use of buildings provided that the buildings are of permanent and substantial construction;
- v) material changes in the use of land (such as changes of use for outdoor sport or recreation, of for cemeteries and burial grounds; and
- vi) development, including buildings, brought forward under a Community Right to Build Order or Neighbourhood Development Order.

- 7.1.6 Policy CP11 of the Core Strategy (adopted October 2011) sets out that the Council will maintain the general extent of the Green Belt in the District and will encourage appropriate positive use of the Green Belt and measures to improve environmental quality. There will be a presumption against inappropriate development that would not preserve the openness of the Green Belt, or which would conflict with the purpose of including land within it.
- 7.1.7 Policy DM2 of the Development Management Policies LDD (adopted July 2013) notes that “as set out in the NPPF, the construction of new buildings in the Green Belt is inappropriate with certain exceptions, some of which are set out below”. Relevant to this current application is a) New Buildings, which states “Within the Green Belt, except in very special circumstances, approval will not be given for new buildings other than those specified in national policy and other relevant guidance”. Policy DM2 was adopted prior to the publication of the current NPPF. However, it was adopted after the publication of the original 2012 NPPF, and the Green Belt policies in the current NPPF in relation to inappropriate development are not materially different between the two. On that basis, it is considered that Policy DM2 is in accordance with the NPPF and may be afforded full weight. The NPPF is considered to contain national policy and therefore relevant guidance and a relevant material consideration.
- 7.1.8 This application, submitted in outline form with only details of access provided at this time, proposes the ‘Development of up to 600 residential dwellings (Use Class C3(a)), construction of a 5-bedroom property for childrens social care and supported living (Use Class C3(b)). Two vehicular access points from Little Green Lane and further pedestrian / cycleway accesses. A one form entry primary school (Use Class F1(a)) (plus expansion land for a two form entry primary school). A mixed use local centre including provision for NHS health and social care services (Use Class E(e)), community building (Use Class F2), retail and cafe provision (Use Class E(a-c)), car parking and associated infrastructure. A country park, areas for play and recreation, allotments, community orchard and landscaping with associated infrastructure including sustainable urban drainage systems’. As such, the proposed development would not meet any of the exceptions to inappropriate development as defined by Paragraph 154 of the NPPF.
- 7.1.9 Whilst the development would not be in accordance with Paragraph 154 of the NPPF it is also necessary to consider the development in relation to Paragraph 155 of the NPPF. This sets out *‘that the development of homes, commercial and other development in the Green Belt should not be regarded as inappropriate where all of the following apply:*
- a) *The development would utilise grey belt land and would not fundamentally undermine the purposes (taken together) of the remaining Green Belt across the area of the plan;*
 - b) *There is demonstrable unmet need for the type of the development proposed.*
 - c) *The development would be in a sustainable location with particular reference to paragraphs 110 and 115 of this framework.*
 - d) *Where applicable the development meets the ‘Golden Rules’ requirements set out in paragraphs 156-157.*
- 7.1.10 In considering whether the site would constitute Grey Belt land, reference must be had to Annexe 2 of the NPPF which defines Grey Belt as follows:

For the purposes of plan- making and decision making, ‘grey belt’ is defined as land in the Green Belt comprising previously developed land and/or any other land that, in either case does not strongly contribute to any of purposes (a), (b) or (d) in paragraph 143. Grey Belt excludes land where the application of the policies relating to the areas of assets in footnote 7 (other than Green Belt) would provide a strong reason for refusing or restricting development’.

- 7.1.11 In this case, the site is ‘any other land’, as it is not ‘previously developed land’. For it to be considered Grey Belt land, the land needs to not strongly contribute to any of the purposes (a), (b) or (d) of Paragraph 143 of the NPPF. These purposes are:

*a) to check the unrestricted sprawl of large built-up areas;
b) to prevent neighbouring towns merging into one another; and
d) to preserve the setting and special character of historic towns.*

- 7.1.12 In considering whether the application site contributes to the purposes (a), (b) or (d) regard must be had to Planning Practice Guidance (PPG) at Paragraph 005 Reference ID: 64-005-2025022 which provides guidance in relation to informing judgements as to whether land can be considered as Grey Belt. In addition, Paragraph 007 of the PPG is also relevant and sets out the following:

After consideration of the above criteria, any assessment area that is not judged to strongly contribute to any one of purposes a, b, or d can be identified as grey belt land, subject to the exclusion of land where the application of the policies relating to the areas or assets in footnote 7 to the NPPF (other than Green Belt) would provide a strong reason for refusing or restricting development.

- 7.1.13 a) to check the unrestricted sprawl of large built-up areas: ‘Large built-up area’ is not defined in the NPPF or PPG, however, the PPG is clear that “Villages should not be considered large built up areas”. Croxley Green is referred to by some residents as a village or is described as having a ‘village feel’. Whilst it is acknowledged that the existing settlement has grown from what was historically a village focussed around The Green, the settlement of Croxley Green today is not considered to comprise a village and this is reflected in Three Rivers Settlement Hierarchy. The Settlement Hierarchy set out within the Core Strategy (adopted October 2011) takes into account settlement size, population, existence of and access to a range of services and transport infrastructure and importance in economic and retailing terms. Croxley Green is identified as a Key Centre, with only Bedmond and Sarratt identified as villages within the District. Additionally, as a planning judgement, Croxley Green contains a number of schools (primary and secondary), several local shopping parades, churches, pubs and Croxley Green Station, such that it is considered that Croxley Green is a large built up area.

Principal Town
Rickmansworth
Key Centres
South Oxhey
Croxley Green
Abbots Langley
Chorleywood
Leavesden and Garston
Mill End
Secondary Centres
Kings Langley
Carpenders Park
Eastbury
Oxhey Hall
Maple Cross
Moor Park
Villages

Image 1: Three Rivers Settlement Hierarchy (from page 16, Core Strategy 2011)

- 7.1.14 It is noted that the applicants' Green Belt Assessment Addendum (Iceni, March 2025) comments on page 1 that; *"it could be seen to be a suburb of Rickmansworth (which is a town) and is therefore considered to form part of a large built-up area"*.
- 7.1.15 It is therefore an agreed position that Croxley Green forms part of a large built-up area.
- 7.1.16 The Stage 2 Green Belt Review for Three Rivers and Watford Borough (2019) considered the effect of releasing land for development. The application site corresponds to Parcel CG8 of that review, although it is noted that Parcel CG8 includes a small additional area of land to the south-west which falls outside of the redline of the application site. In relation to the contribution the parcel made to the purpose of checking the unrestricted sprawl of large built-up areas, the Stage 2 Green Belt Review concluded that it made a significant contribution to that purpose, stating that; *"The parcel is adjacent to the edge of Croxley Green which is contiguous with the large built up area of Greater London. The boundary with the urban edge (along Little Green Lane) provides some distinction from urbanising uses, giving the parcel a significant role in preventing urban sprawl"*.
- 7.1.17 The Stage 4 Green Belt Review (2025) is in draft form only at this time and therefore carries very limited weight in decision making. The Stage 4 Green Belt Review considers that Parcel CG8 makes a significant impact to purpose (a). One of the primary purposes of the 2025 Green Belt Review is mapping out provisional grey belt. The word provisional has been used to emphasise that there are still other factors to be considered prior to deciding whether land fully constitutes grey belt. Parcel CG8 is not identified as provisional grey belt. However, it is important to note that while the parcel level identification of grey belt is helpful at a strategic level for plan making, when considering the identification of grey belt in decision making, it is more relevant to assess at a site specific level.
- 7.1.18 The Stage 4 Green Belt Review (2025) also considers whether the releasing of Green Belt would fundamentally undermine the purposes of the remaining Green Belt across the plan area, identifying areas of the district where the Green Belt was performing a role of 'fundamental importance'. Seven broad areas of fundamental importance are identified where future growth should be considered carefully, to ensure that it does not fundamentally undermine the purposes of the Green Belt across the plan area. Parcel CG8 is not within or adjacent to an identified area of 'fundamental importance'.
- 7.1.19 In considering the site's contribution to checking the unrestricted sprawl of a large built-up area it is also appropriate to have regard to the PPG guidance (Paragraph: 005 Reference ID: 64-005-20250225) which lists illustrative features that might be associated with a strong contribution, moderate contribution or weak/no contribution as set out in Image 2 below.

Contribution	Illustrative features
Strong	Assessment areas that contribute strongly are likely to be free of existing development, and lack physical feature(s) in reasonable proximity that could restrict and contain development. They are also likely to include all of the following features: - be adjacent or near to a large built up area - if developed, result in an incongruous pattern of development (such as an extended "finger" of development into the Green Belt)
Moderate	Assessment areas that contribute moderately are likely to be adjacent or near to a large built up area, but include one or more features that weaken the land's contribution to this purpose a, such as (but not limited to):

	- having physical feature(s) in reasonable proximity that could restrict and contain development - be partially enclosed by existing development, such that new development would not result in an incongruous pattern of development - contain existing development - being subject to other urbanising influences
Weak or None	Assessment areas that make only a weak or no contribution are likely to include those that: - are not adjacent to or near to a large built up area - are adjacent to or near to a large built up area, but containing or being largely enclosed by significant existing development

Image 2: Taken from PPG. Guidance when considering contribution to purpose (a).

- 7.1.20 The PPG advises that areas that contribute ‘strongly’ are likely to be free from existing development, and lack physical features in reasonable proximity that could restrict and contain development. The PPG continues that they are also likely to include all of the following features: be adjacent or near to a large built-up area; if developed, result in an incongruous pattern of development such as an ‘extended finger’ of development into the Green Belt. It is recognised that a degree of judgement is required in assessing the strength of a contribution to Green Belt purposes and that there may be some overlap between categories.
- 7.1.21 Having regard to the illustrative features identified in the PPG, it is noted that the application site is free of existing development. In terms of physical features, the site is bounded by Little Green Lane to the south and the existing residential development of Croxley Green beyond this. The existing development partially encloses the site to the south. To the east and north the site is bounded by Rousebarn Lane with Whippendell Wood SSSI beyond this. Rousebarn Lane and Whippendell Wood SSSI are considered permanent physical features in reasonable proximity that would restrict and contain the development. To the west and north-west there are Ancient Woodlands (Dell Wood and Long Newlands Spring) that adjoin the site. These are considered permanent physical features in reasonable proximity that would restrict and contain the development. There are legal and policy restrictions that constrain the SSSI and wooded area’s development which would ensure their permanence as physical boundaries. The Ancient Woodland (Green Lane Wood) within the site would also restrict and contain development to some extent, with the illustrative masterplan concentrating built development to the west of Green Lane Wood. The site is adjacent to a large built up area (Croxy Green), and if developed, it is not considered that it would result in an incongruous pattern of development, rather it would extend the northern edge of the existing settlement.
- 7.1.22 Whilst the Stage 2 Green Belt Review concluded that the release of parcel CG8 for development would have a significant impact on preventing urban sprawl and encroachment, it noted that its release would have only a negligible impact on the adjacent Green Belt due to its containment by Cassiobury Registered Park and Garden and ancient woodland. The overall harm to Green Belt purposes from release of the land was therefore considered to be moderate high.
- 7.1.23 Having regard to the above, it is considered that the application site fits the ‘moderate’ contribution category more satisfactorily than the ‘strong’ contribution category. The ‘moderate’ contribution category in the PPG states that areas are likely to be adjacent to or near a large built-up area but include ‘one or more’ features that weaken the land’s contribution to purpose (a). The site meets this criteria: It has ‘physical features in reasonable proximity that restrict and contain development’; and it is ‘partially enclosed by existing development such that it would not result in an incongruous pattern of development’.

- 7.1.24 It is considered that the application site moderately contributes to purpose (a).
- 7.1.25 b) to prevent neighbouring towns merging into one another: The Stage 2 Green Belt Review (2019), in relation to purpose (b), concluded that Parcel CG8 made limited or no contribution as the parcel does not lie in a gap between neighbouring towns. Officers agree with this assessment. The site is therefore considered to make a weak or no contribution to purpose (b).
- 7.1.26 d) to preserve the setting and special character of historic towns: The site does not lie within or adjacent to a historic town and therefore it is considered to make a weak or no contribution to purpose (d).
- 7.1.27 In summary, the site makes a moderate contribution to purpose (a) and a weak or no contribution to purposes (b) and (d).
- 7.1.28 Annexe 2 of the NPPF which defines Grey Belt also notes that; *'Grey Belt excludes land where the application of the policies relating to the areas of assets in footnote 7 (other than Green Belt) would provide a strong reason for refusing or restricting development'*.
- 7.1.29 Footnote 7 of the NPPF is provided below. The assets that are not applicable in this case have been struck through and those that do apply have been bolded:
- The policies referred to are those in this Framework (rather than those in development plans) relating to: **habitats sites (and those sites listed in paragraph 194) and/or designated as Sites of Special Scientific Interest;** ~~land designated as Green Belt, Local Green Space, a National Landscape, a National Park (or within the Broads Authority) or defined as Heritage Coast;~~ **irreplaceable habitats; designated heritage assets (and other heritage assets of archaeological interest referred to in footnote 75);** ~~and areas at risk of flooding or coastal change.~~*
- 7.1.30 Impacts on the SSSI, irreplaceable habitats and designated heritage assets are considered in full below, however, none are considered to provide a strong reason for refusing or restricting development.
- 7.1.31 The application site is therefore considered to meet the NPPF definition of grey belt.
- 7.1.32 Criterion (a) of Paragraph 155 of the NPPF requires that the development would utilise grey belt land and would not fundamentally undermine the purposes (taken together) of the remaining Green Belt across the area of the plan. The five purposes of Green Belt are set out at 7.1.1 above. Purposes (a), (b) and (d) have been considered above. This leaves purposes (c) 'to assist in safeguarding the countryside from encroachment' and (e) 'to assist in urban regeneration, by encouraging the recycling of derelict and other urban land'. In relation to purpose (e), the proposal does not assist in urban regeneration and therefore the contribution is weak or none.
- 7.1.33 In relation to purpose (c), the site is a greenfield site predominantly used for agriculture, and therefore development of the site would run counter to the aim of safeguarding the countryside from encroachment. However, whilst there would be some encroachment into the countryside, the site's location at the existing urban edge of Croxley Green and its enclosure by defensible boundaries (Little Green Lane, Rousebarn Lane, SSSI, Ancient Woodland) means that the effect of the proposal would be limited in the wider context. Considering the Stage 2 Green Belt Review, whilst it concluded that the release of parcel CG8 for development would have a significant impact on preventing urban sprawl and encroachment, it noted that its release would have only a negligible impact on the adjacent Green Belt due to its containment by Cassiobury Registered Park and Garden and ancient woodland. The overall harm to Green Belt purposes from release of the land was therefore considered to be moderate high. As noted above, whilst in draft form only and of very limited weight, the Stage 4 Green Belt Review (2025) considers whether releasing Green Belt

would fundamentally undermine the purposes of the remaining Green Belt across the plan area, identifying areas of the district where the Green Belt was performing a role of 'fundamental importance'. Parcel CG8 (which includes the application site) is not within or adjacent to an identified area of 'fundamental importance'.

7.1.34 Overall it is considered that the proposal would not fundamentally undermine the purposes (taken together) of the remaining Green Belt. As such, criterion (a) of Paragraph 155 of the NPPF would be met.

7.1.35 Criterion (b) of Paragraph 155 of the NPPF sets out that development in the Green Belt would not be inappropriate where '*there is a demonstrable unmet need for the type of the development proposed*'. In this case, the applicant is proposing a residential development for the provision of up to 600 dwellings. National Policy places great emphasis on the delivery of housing with Paragraph 61 of the NPPF stating the following:

To support the Government's objective of significantly boosting the supply of homes, it is important that a sufficient amount and variety of land can come forward where it is needed, that the needs of groups with specific housing requirements are addressed and that land with permission is developed without unnecessary delay. The overall aim should be to meet an area's identified housing need, including with an appropriate mix of housing types for the local community.

7.1.36 The Council cannot demonstrate a five- year housing land supply as required by the NPPF, with the current housing land supply being at 1.7 years. Consequently, there is a significant need for housing within the district which must be afforded significant weight in the decision-making process. In this case, the scheme would deliver up to 600 residential dwellings of a range of unit sizes and types, providing an opportunity to meet different needs.

7.1.37 In addition, it is noted that there is also a significant need for affordable housing within the district. In this case 50% of the proposed residential units would be for affordable housing. This is discussed in more detail at section 7.4 below where it is noted that the affordable housing proposals are supported by the Housing Officer. Given the need for housing and affordable housing within the district, it is considered that the proposed development would be in accordance with criterion (b) of Paragraph 155.

7.1.38 Criterion (c) of Paragraph 155 sets out that the development should be in a sustainable location with particular reference to paragraphs 110 and 115 of the NPPF. In response, officers consider that the site is located in a sustainable location. It occupies an edge of settlement location at the edge of Croxley Green. In addition to the proposed services/facilities within the development, the site is also within walking distance of existing services including local shops and public transport links, all of which can be safely accessed via well-lit public footpaths. This includes Croxley Station at 1.9km, an approximate 26 minute walk via Links Way and Winton Drive; existing bus stops on Baldwins Lane at 0.6 miles, an approximate 13 minute walk via Links Way; and local shops on Baldwins Lane also at 0.9km. A package of sustainable transport initiatives is also proposed as part of the application, primarily focusing on encouraging alternatives to private car use to maximise the need for extensive new traffic infrastructure (as discussed in more detail at section 7.7 below). It is proposed to provide Beryl Bikes docking stations on site; It is proposed to introduce a dedicated bus service within and surrounding the site, including to key destinations such as Rickmansworth, Watford Station, Croxley Station, and Watford Junction. Similarly, a seasonal bus pass would be provided to each dwelling on initial occupation.

7.1.39 As such, officers are of the view that the proposed development would be in a sustainable location and thus would be in accordance with criterion (c) of Paragraph 155 of the NPPF.

7.1.40 Finally, criterion (d) sets out that the development must meet the 'Golden Rules' requirements set out in Paragraphs 156-157 of the NPPF as follows:

Where major development involving the provision of housing is proposed on land released from the Green Belt through plan preparation or review, or on sites in the Green Belt subject to a planning application, the following contributions ('Golden Rules') should be made:

- a. affordable housing which reflects either: (i) development plan policies produced in accordance with paragraphs 67-68 of this Framework; or (ii) until such policies are in place, the policy set out in paragraph 157 below;*
- b. necessary improvements to local or national infrastructure; and*
- c. the provision of new, or improvements to existing, green spaces that are accessible to the public. New residents should be able to access good quality green spaces within a short walk of their home, whether through onsite provision or through access to offsite spaces.*

- 7.1.41 With regard to criterion (a) of Paragraph 156, the affordable housing would comprise 300 dwellings, with 70% for Rent (of which 70% is Social Rent and 30% is Affordable Rent) and 30% Affordable Ownership (eg. Shared Ownership). As such, the proposed development would meet criterion (a) of Paragraph 156.
- 7.1.42 With regard to criterion (b) of Paragraph 156, necessary improvements to local infrastructure are proposed. This would include two proposed points of vehicular access to the site across Little Green Lane from Durrants Drive and Links Way; Footpath and cycleway connections throughout the scheme; and retention of the existing public right of way (017) and incorporation into the scheme, providing access to new publicly accessible open spaces such as the proposed Country Park. A financial contribution of £1,065,000 towards the delivery of step-free access at Croxley Underground Station; Contributions towards surrounding active travel links, such as the signage of routes; The provision of Beryl Bikes docking stations on site; and the introduction of a dedicated bus service within and surrounding the site, including to key destinations such as Rickmansworth, Watford Station, Croxley Station, and Watford Junction.
- 7.1.43 Further local infrastructure is proposed in the form of a new one form entry primary school (Use Class F1(a)) (plus expansion land for a two form entry primary school) and a medical centre for NHS health and social care services, discussed in more detail at 7.5 below.
- 7.1.44 The proposed development would therefore meet criterion (b) of Paragraph 156.
- 7.1.45 With regard to criterion (c) of Paragraph 156, the application proposes a country park, areas for play and recreation, allotments and community orchard, with approximately 60% of the site area to be set aside as open space, with play space included. The proposed development would meet criterion (c) of Paragraph 156.
- 7.1.46 Summary: In summary, it is considered that the site is Grey Belt as it does not strongly contribute to purposes (a), (b) or (d). It is also considered that there is a demonstrable unmet need for residential development in view of the fact that TRDC is unable to demonstrate a five year housing supply and that the site is located in a sustainable edge of settlement location in accordance with Paragraph 155 of the NPPF. Furthermore, it is noted that the site meets the Golden Rules set out in Paragraphs 156 and 157 of the NPPF. Paragraph 158 of the NPPF states that 'a development which complies with the Golden Rules should be given significant weight in favour of the grant of permission'.
- 7.1.47 It is considered that the development represents an appropriate form of development and consequently is acceptable in accordance with the provisions of the NPPF and in accordance with Policy CP11 of the Core Strategy (adopted October 2011).

7.2 Impact on the character and appearance of the locality

- 7.2.1 Paragraph 131 of the NPPF states that; *"The creation of high quality, beautiful and sustainable buildings and places is fundamental to what the planning and development process should achieve. Good design is a key aspect of sustainable development, creates*

better places in which to live and work and helps make development acceptable to communities”.

- 7.2.2 Policy CP1 of the Core Strategy (adopted October 2011) seeks to promote buildings of a high enduring design quality that respect local distinctiveness and Policy CP12 of the Core Strategy (adopted October 2011) relates to design and states that in seeking a high standard of design the Council will expect development proposals to 'have regard to the local context and conserve or enhance the character, amenities and quality of an area'. Development should make efficient use of land but should also respect the 'distinctiveness of the surrounding area in terms of density, character, layout and spacing, amenity, scale, height, massing and use of materials'; 'have regard to the local context and conserve or enhance the character, amenities and quality of an area' and 'incorporate visually attractive frontages to adjoining streets and public spaces'.
- 7.2.3 Policy 2 of the Sarratt Neighbourhood Plan (adopted 2025) relates to 'Design Principles' and requires that all development is of the highest standard of design and takes account of the design guidelines in the Sarratt Design Code.
- 7.2.4 Policy 7 of the Sarratt Neighbourhood Plan (adopted 2025) relates to Landscape and requires development proposals to respect and, wherever possible, enhance the characteristics, value and visual amenity of the parish landscapes. Permission will not be granted for proposals that affect the setting of the Chilterns National Landscape.
- 7.2.5 This application is submitted in outline, with only matters of access for detailed consideration. The application is accompanied by a Land Use Parameters Plan (ref. P24-1200_DE_0015 Sheet 1 Rev C) which demonstrates how the different components of the scheme can be incorporated. The Parameters Plan identifies areas for residential development; open space; mixed use local centre; 1FE primary school; and school expansion land. The Land Use Parameters Plan also illustrates indicative areas for access to the site and within the site. In the event that Outline planning permission was granted, a condition would require that subsequent Reserved Matters accord with the Land Use Parameters Plan.
- 7.2.6 The application is also accompanied by an illustrative masterplan (page 57 of Design and Access Statement) which accords with the Land Use Parameters Plan and demonstrates how the site could be developed, with open space and sustainable drainage to the east and built development to the south and west with a series of roads and walking/cycling routes. It is important to note that the masterplan is submitted for illustrative purposes only to demonstrate how the site could be developed at the quantum proposed.
- 7.2.7 The indicative Building Heights Plan (page 70 of Design and Access Statement) indicates development up to 4 storeys in height. Development to the south adjacent to Little Green Lane would be up to 2.5 storeys, with the majority of the development site up to 3 storeys in height. The higher 4 storey element would be limited to a small central section framing the green corridor. To the east the development would be up to 2 storeys in height, responding to its siting adjacent to Green Lane Wood.
- 7.2.8 It is acknowledged that the character of the site itself would change as a result of the proposed development, with the existing open arable land lost and replaced by a new residential development with associated open space and infrastructure. The submitted Landscape Visual Impact Assessment (LVIA) judges the effect on the landscape character of the site to be adverse due to the loss of open land, however, this does not mean that the resultant development would be unattractive or inappropriate.
- 7.2.9 It is considered that the proposed development would form a logical extension to the existing residential development to the south, forming a new northern edge. Vegetation to the site's boundaries, as well as the woodland within it, would be retained (other than the removal of two small sections of hedgerow to facilitate access). The existing Public Right of Way

running east-west across the northern portion of the site, beyond the proposed built development, would be retained.

- 7.2.10 In terms of visual effects, the proposed development would be visible from the Public Right of Way which crosses the north of the site. The existing residential development is visible from the Public Right of Way such that the proposed development would be set against this, albeit closer to the viewer. Views of Durrants House from the Public Right of Way would be maintained along the green corridor. The proposed vegetation will soften the built form in views from the public footpath. Views north from the public footpath would remain open. There will be views of the development from Little Green Lane although existing hedging and vegetation would provide some screening. Views would be greater in winter. Views of the western extent of the development would be screened from Rousebarn Lane by the existing woodland (Dell Wood) within the site and the proposed Country Park which would provide a buffer. The development would be visible in long distance views from taller buildings.
- 7.2.11 The LVIA concludes that the effects on the immediate surroundings of the site will be limited as a result of the careful design, and due to the existing dense vegetation which bounds the site to the north, east and west. The submitted Planning Statement sets out that transitional character areas are proposed within the development through the incorporation of areas of open space within the site between the built development and the woodland beyond, and that these areas and associated planting within them will further minimise effects on the immediate surrounding landscape. The clear northern edge to the development also limits the effects on the wider landscape, with the woodland physically and visually separating the development from the countryside beyond. Little Green Lane to the south also provides a further strong boundary line.
- 7.2.12 Prior to submission of the planning application, a Design Review Panel (DRP) presentation was carried out in September 2024. A DRP is a group of independent, expert professionals (like architects, urban planners, landscape architects) who provide impartial advice on new development and public realm proposals to help improve design quality. DRPs are encouraged by the NPPF (paragraph 138). The DRP applauded the emerging designs and commended the aspirations to design a development of high quality. The Design and Access Statement sets out how the recommendations made by the DRP have been addressed during subsequent design iterations and how the process informed the Design Code.
- 7.2.13 The purpose of the Design Code is to provide a series of clear instructions/rules to inform subsequent Reserved Matters applications. The Design Code includes 'Site Wide Codes' relating to uses; movement; built form; homes and buildings; identity; public spaces; nature; resources; and lifespan. It also includes 'Character Area Codes' which draw upon the Site Wide Codes with a particular focus on each of the proposed Built Character Areas (The Boulevard; Little Green Lane; The Villas; Durrants View and The Village) and Landscape Character Areas (Little Green Lane; Rousebarn Country Park; Rousebarn Wood; Dell Spring; Greenways; and Durrants Square). The Character Area Codes seek to reinforce distinctiveness as well as consistency, uniformity and integration across the development proposals.
- 7.2.14 The Design Code has had regard to the existing local area in order that the proposed development integrates with it, however, it does not seek to simply replicate the existing development. The Design Code considers the future neighbourhood in terms of place making and definition of character types as well as considering existing residential areas within the vicinity of the site. The proposals would form an extension of existing residential development within Croxley Green and it is noted that the Design Code explores the existing character of this area, rather than Sarratt, the Parish Area in which the site is located. This is considered an appropriate response as the proposed development would be most closely associated with existing residential development within Croxley Green, not Sarratt.

- 7.2.15 An appropriately worded planning condition requiring compliance with the Design Code is considered necessary to ensure that subsequent Reserved Matters applications are appropriately informed.
- 7.2.16 In relation to Policy 2 of the Sarratt Neighbourhood Plan (adopted 2025) the site is not covered by any statutory or non-statutory designations for landscape quality or value. The Chiltern Conservation Board (CCB) note that the statutory boundary of the Chilterns National Landscape is set away from the application site and lies some 2.4 to 2.6km to the west of the red line boundary. The CCB consider that there would be no physical impact upon the visual setting of the National Landscape.
- 7.2.17 In summary, the character of the site itself would change as a result of the proposed development, with the loss of a greenfield site, however, the effect on the wider landscape is limited as a result of the clear edges to the development created by physical features (woodland) and Little Green Lane and Rousebarn Lane themselves. The existing woodland would also serve to both physically and visually separate the site from the open countryside beyond. There would be localised harm to the landscape contrary to policy, however, harmful effects would diminish over time as landscaping becomes established.

7.3 Housing Mix

- 7.3.1 Policy CP3 sets out that the Council will require housing proposals to take into account the range of housing needs as identified by the Strategic Housing Market Assessment (SHMA) and subsequent updates. The need set out in the Core Strategy is 30% one-bedroom units, 35% two-bedroom units, 34% three-bedroom units and 1% four bedroom and larger units. However, the most recent version of the Local Housing Needs Assessment (LNHA) was finalised in 2024 and is the most recent update to the SHMA. The recommended mix for Three Rivers in terms of market housing, affordable home ownership and social/affordable rented housing identified in the LNHA is shown below:

	1-bed	2-bed	3-bed	4+ bed
Market Housing	4%	21%	42%	32%
Affordable Home Ownership	19%	39%	30%	13%
Social / Affordable Rented Housing	20%	32%	35%	12%

- 7.3.2 Policy 4 of the Sarratt Neighbourhood Plan (adopted 2025) relates to Housing Mix. Policy 4.1 requires a residential size mix of 50% three-bedroom, 30% two-bedroom and 20% one-bedroom, informed by the Sarratt Housing Needs Assessment 2020. Policy 4.2 notes that the provision of bungalows, accessible homes and all types of self-build will be considered favourably.
- 7.3.3 The housing mix is not a matter being determined at outline stage and would be determined at Reserved Matters stage.

7.4 Affordable Housing

- 7.4.1 The application proposes to deliver 50% (300 units) of the dwellings as affordable units, with the remaining 50% (300 units) being provided as open market dwellings.
- 7.4.2 Core Strategy Policy CP4 states that in order to increase the provision of affordable homes in the district and meet local housing need, the council will seek an overall provision of around 45% of all new housing as affordable housing, incorporating a mix of tenures. All new development resulting in a net gain of one or more dwellings will be expected to contribute to the provision of affordable housing. As a guide, 70% of affordable housing would be social rented and 30% intermediate.

- 7.4.3 For a major planning application such as this, it would be expected that all affordable housing is provided on site. This is reflected in Policy CP4 and the Affordable Housing SPD.
- 7.4.4 Policy 5 of the Sarratt Neighbourhood Plan (adopted 2025) relates to Affordable Housing. Policy 5.1 requires development resulting in a net gain of 1 or more units to provide 40% affordable housing. Policy 5.2 requires the affordable housing provision to usually be split as 75% Social Rent and 25% First Homes or affordable shared ownership products. Policy 5.3 requires that affordable housing is integrated into developments so that it is indistinguishable from other homes.
- 7.4.5 On 24 May 2021 the Government published a Written Ministerial Statement to set out plans for the delivery of First Homes. Following this, TRDC set out a Policy Position Statement on First Homes. First Homes are a specific kind of discounted market sale housing which must be discounted by a minimum of 30% against the market value, sold to a person meeting First Homes criteria and have a restriction to ensure this. Given the First Homes guidance, TRDC have been requiring 25% of affordable housing to be First Homes, 70% to be social rented and 5% to be intermediate. However, within paragraph 6 of the NPPF (2024), reference to the Written Ministerial Statement on Affordable Homes (24th May 2021), which contained policy on First Homes, has been removed and the prescriptive requirement that 10% of the total number of homes to be available for affordable home ownership as set out in former paragraph 66 has been deleted.
- 7.4.6 The application originally proposed 50% Affordable Housing with a mix of Social Rent (70%), Shared Ownership (5%) and First Homes (25%). As the publication of the revised NPPF at the end of 2024 removed the requirement to provide 25% First Homes, the applicant has updated their affordable housing position, removing the provision of First Homes.
- 7.4.7 The application continues to propose 50% Affordable Housing, but the tenure mix has been amended to reflect the Emerging Local Plan draft policies for Regulation 19 (as taken to the Local Plan Sub Committee on 25 November 2025) which seek to provide 70% for Rent (of which 70% is Social Rent and 30% is Affordable Rent) and 30% Affordable Ownership (eg. Shared Ownership).
- 7.4.8 As such, 50% Affordable Housing (300 units) is proposed comprising:
- **70% (210 units) for Rent**
 - **70% (147 units) Social Rent**
 - **30% (63 units) Affordable Rent**
 - **30% (90 units) for Affordable Ownership (eg. Shared Ownership)**
- 7.4.9 The table below indicates the affordable housing requirement set out in Policy CP4 alongside that proposed.

	Overall AH (%)	Total AH Units	Social Rent (%)	Social Rent (No.)	Affordable Rent (%)	Affordable Rent (No.)	Shared Ownership (%)	Shared Ownership (No.)
Policy CP4	45%	270	70%	189	N/A	N/A	30%	81
Proposal	50%	300	49%	147	21%	63	30%	90
Difference	+ 5%	+ 30	-21%	-42	+21%	+63	-	+9

- 7.4.10 The provision of 50% affordable housing would exceed the 40% requirement of Policy 5.1 of the Sarratt Neighbourhood Plan (adopted 2025) and the 45% requirement of Policy CP4 of the Core Strategy (adopted October 2011), providing an additional 30 affordable units over that required by Policy CP4. The proposal would also comply with these policies in so far as it would be provided on site.

- 7.4.11 It is recognised that the tenure mix split would not strictly accord with Policy CP4 of the Core Strategy (adopted October 2011) as indicated in the table above or the Sarratt Neighbouring Plan (adopted 2025), however, it fully accords with the draft affordable housing policy within the Emerging Local Plan which has been drafted in consultation with Housing colleagues and with regard to the South-West Herts Local Housing Needs Assessment Update (March 2024) and is therefore considered an up to date position in terms of the affordable housing needs of the District.
- 7.4.12 It is also considered important to note that Planning Policy Officers raise no objection to the proposed mix, noting that it aligns with the Emerging Local Plan. Similarly, Housing Officers raise no objection, advising that they are supportive of the revised approach, particularly the high proportion of rented provision and the inclusion of Social Rent within the overall mix. The Housing Officer notes that it remains important that the affordable housing delivered prioritises family-sized accommodation, particularly 2-bed and 3-bed units, to reflect current housing register demand and the need to move households out of temporary accommodation. As noted above at 7.3, whilst the tenure would be secured via the S106 Agreement at Outline stage, the mix (in terms of unit sizes) would be secured at Reserved Matters stage. It would be expected that any Reserved Matters application(s) reflect existing needs and the Housing Team would be consulted at the time of Reserved Matters application.
- 7.4.13 Whilst the application is in outline, the submitted Design Code sets out that the affordable housing will be provided in tenure blind clusters, dispersed across the site, in accordance with Policy 5.3 of the Sarratt Neighbourhood Plan (adopted 2025) and Policy CP4 of the Core Strategy (adopted October 2011).
- 7.4.14 In summary, the proposed development would exceed the requirements of Policy CP4 of the Core Strategy (adopted October 2011) and Policy 5.1 of the Sarratt Neighbourhood Plan (adopted 2025) in terms of the overall percentage of affordable housing provided, providing an additional 30 affordable units over that required by Policy CP4. The affordable housing would all be provided on site and would be tenure blind. The tenure mix would not strictly accord with these policies, with the inclusion of an element of Affordable Rent. However, overall, 70% (210 units) would be provided as a Rented product with an additional 30% (63 units) as Affordable Home Ownership (eg. Shared Ownership) in accordance with the Emerging Local Plan and the tenure mix is supported by TRDC Housing Services.
- 7.4.15 The application also proposes the construction of a 5-bedroom property for children's social care and supported living (Use Class C3(b)). HCC welcome and supports the inclusion of a children's home on the site, their full comments are at 9.8 below.

7.5 The Local Centre & Community Facilities

- 7.5.1 In addition to the residential element (up to 600 dwellings), the application proposes construction of a 5-bedroom property for children's social care and supported living (Use Class C3(b)); a one form entry primary school (Use Class F1(a)) (plus expansion land for a two form entry primary school); a mixed use local centre including provision for NHS health and social care services (Use Class E(e)), community building (Use Class F2), retail and cafe provision (Use Class E(a-c)); a country park, areas for play and recreation, allotments and community orchard.
- 7.5.2 Supporting documents submitted with the application include Education Report (EFM, December 2024); Health Impact Assessment (RPS, December 2024, 1.0); Local Centre Capacity Statement (Lambert Smith Hampton, December 2024); Planning Statement (RPS, December 2024); and Sports and Leisure Strategy (Sports Planning Consultants, December 2024).
- 7.5.3 Policy CP3 (Housing Mix and Density) of the Core Strategy advises that provision of specialist accommodation will be encouraged in suitable and sustainable locations.

- 7.5.4 Policy DM11 (Open Space, Sport and Recreation Facilities and Children's Play Space) of the Development Management Policies LDD (adopted July 2013) states that when granting planning permission for new residential development of 25 or more dwellings, the Council will expect developer contributions to the provision or enhancement of local sports facilities where a need is demonstrated to have arisen from the development concerned. Similarly, developments of 25 or more dwellings should make provision on site for open space and play space. 10% of the site area should be set aside as open space and where the development is likely to be occupied by families, 2% of the site area should provide formally equipped play facilities. Where open space is provided on site, the Council will seek to ensure the proper maintenance of the space.
- 7.5.5 Policy DM12 (Community, Leisure and Cultural Facilities) of the Development Management Policies LDD (adopted July 2013) advises that where development proposals are submitted for new or improved community, leisure or cultural facilities, they should be accessible by sustainable modes of transport.
- 7.5.6 Policy 9 of the Sarratt Neighbourhood Plan (adopted 2025) relates to Community Facilities and notes that proposals that improve the quality and/or extend the range of community facilities in a suitable and accessible location will be supported.
- 7.5.7 The Parameters Plan shows the local centre to be located towards the southern end of the site to ensure that it is accessible to both existing and future residents. The Design and Access Statement and Design Code places a strong emphasis on making the local centre a pedestrian friendly destination, encouraging the use of alternative modes of transport such as cycling and the use of buses. The Local Centre Capacity Statement concludes that the proposed local centre seeks to meet the needs that arise from the proposed development and the wider local area. It indicates that the commercial anchor of the local centre would be a convenience store and that the Capacity Statement has addressed the appropriate scale for such a store to demonstrate that it is a viable commercial proposition, but would not compete with existing services within Croxley Green. A community building is also proposed, which will be available as a multi-functional building. As noted below, Sport England have specified a minimum specification for the building.
- 7.5.8 As noted above, HCC welcome and supports the inclusion of a children's home on the site.
- 7.5.9 In relation to the primary school, HCC note that when they responded in 2018 to Three Rivers District Council Regulation 18 local plan consultation, their response set out that primary school sites may need to be identified in all settlements to meet pupil yield from new housing developments, depending on the number of sites and level of growth chosen. They acknowledge that the applicant has proposed a new 1FE (up to 2FE land) primary school on-site to accommodate the needs arising from their scheme. HCC therefore seek a financial contribution towards the delivery of a new 1FE (up to 2FE land) primary school in the area and/or provision serving the development.
- 7.5.10 Following concerns being raised by members and other stakeholders regarding the need for an additional 1FE primary school in Croxley Green when the preliminary report was discussed in July 2025, HCC have provided further clarification on both the short-term demand and the longer-term strategic rationale behind their request for a 1FE school site. HCC note that as of 16 July 2025 all three primary schools in Croxley Green with Reception class intakes were full, including Malvern Way Infant School, which is due to reduce its Published Admission Number (PAN) from September 2025, with a corresponding reduction at its linked junior school in 2028/29. Despite these planned reductions, HCC note that current forecasts indicate that demand continues to match available capacity. As such, the proposed 1FE primary school is intended to serve the new development directly, ensuring that the pupil yield generated by the site is met without placing additional pressure on existing schools. This self-sufficient approach supports the strategic goal of delivering infrastructure that is proportionate and responsive to the specific impact of development. HCC also note that the case for a new school on this site is not solely based on current

capacity. The request is equally informed by principles of placemaking and sustainable development. Schools delivered in this context are intended to meet the needs of the development in isolation, enabling children to walk or wheel to school in a safe, healthy environment and contribute towards the creation of a new community. The intention is not to attract pupils from other parts of the settlement who would need to travel by car.

- 7.5.11 HCC seek a Primary Education Contribution (£5,883,141 which has a land cost of £10,530 deducted index linked to BCIS 1Q2024) towards the delivery of a new 1fe primary school (up to 2fe land) in the area and/or provision serving the development. A Secondary Education Contribution towards the expansion of a Secondary School in the area and/or provision serving the development (£4,376,834 index linked to BCIS 1Q2024) and Special Educational Needs and Disabilities (SEND) Contribution towards new Severe Learning Difficulty (SLD) special school places (WEST) and/or provision serving the development (£784,006 index linked to BCIS 1Q2024).
- 7.5.12 The application includes provision for NHS health and social care services (Use Class E(e)). The Hertfordshire and West Essex Integrated Care Board (HWE ICB) comment that the development will create circa 1,440 new patients (based on an average occupancy of 2.4). The HWE ICB recognise that there is a clear need to address primary healthcare provision in Croxley Green. They comment that a new medical facility within this development would allow the co-location of New Road, Baldwins Lane and Sarratt branch surgery to a new, purpose-built premises in line with the needs of a modern General Practice. The HWE ICB are therefore supportive in principle to a new medical centre, subject to the approval of a full business case by the HWE ICB's Primary Care Commissioning Committee. The HWE ICB note that the applicant has agreed to build the 'shell' of the medical facility, with the 'fit out' funded by a combination of a financial contribution from the developer (£1.85 million) and CIL. The HWE ICB is also seeking financial contributions for community (£211,608) and mental healthcare (£203,352). The full comments of the ICB are set out at 9.14 below.
- 7.5.13 The application proposes a country park, areas for play and recreation, allotments and community orchard, with approximately 60% of the site area to be set aside as open space, with play space included.
- 7.5.14 Following the receipt of additional information during the application, Sport England have raised no objection (subject to conditions / S106 agreement). In relation to community sports provision Sport England request financial contributions being secured through a section 106 agreement towards indoor and outdoor provision within the area that is necessary as a consequence of the development. They also request a minimum specification for the community hall building being secured through a section 106 agreement and a planning condition being imposed to address the design and implementation of the NewGen Active Track. The financial contributions sought are set out in the table at section 7.20 below.
- 7.5.15 The local centre and community facilities proposed are considered to accord with relevant policies, including the NPPF, Policy CP3 of the Core Strategy (adopted 2011), Policies DM11 and DM12 of the Development Management Policies LDD (adopted July 2013) and Policy 9 of the Sarratt Neighbourhood Plan (adopted 2025).

7.6 Impact of proposal on heritage assets

- 7.6.1 Strategic Objective S10 of the Core Strategy is "To conserve and enhance the historic environment by resisting the loss of, or damage to, heritage assets including important buildings". Core Strategy Policy CP12 states that "in seeking a high standard of design, the Council will expect all development proposals to conserve and enhance natural and heritage assets".
- 7.6.2 Section 66 of the Planning (Listed Buildings and Conservation Areas) Act 1990 states:

"In considering whether to grant planning permission or permission in principle for development which affects a listed building or its setting, the local planning authority or, as the case may be, the Secretary of State shall have special regard to the desirability of preserving the building or its setting or any features of special architectural or historic interest which it possesses."

7.6.3 Paragraph 208 of the NPPF advises that:

"Local planning authorities should identify and assess the particular significance of any heritage asset that may be affected by a proposal (including by development affecting the setting of a heritage asset) taking account of the available evidence and any necessary expertise. They should take this into account when considering the impact of a proposal on a heritage asset, to avoid or minimise any conflict between the heritage asset's conservation and any aspect of the proposal."

7.6.4 Paragraphs 212 and 213 of the NPPF state that:

"When considering the impact of a proposed development on the significance of a designated heritage asset, great weight should be given to the asset's conservation (and the more important the asset, the greater the weight should be). This is irrespective of whether any potential harm amounts to substantial harm, total loss or less than substantial harm to its significance."

"Any harm to, or loss of, the significance of a designated heritage asset (from its alteration or destruction, or from development within its setting), should require clear and convincing justification."

7.6.5 Paragraph 215 of the NPPF advises that:

"Where a development proposal will lead to less than substantial harm to the significance of a designated heritage asset, this harm should be weighed against the public benefits of the proposal..."

7.6.6 The NPPG advises that public benefits may follow from many developments and could be anything that delivers economic, social or environmental objectives as described in the NPPF. Public benefits should flow from the proposed development. They should be of a nature or scale to be of benefit to the public at large and not just be a private benefit. However, benefits do not always have to be visible or accessible to the public in order to be genuine public benefits, for example, works to a listed private dwelling which secure its future as a designated heritage asset could be a public benefit.

7.6.7 Policy DM3 of the Development Management Policies LDD (adopted July 2013) refers to the historic built environment and notes that when assessing applications for development, there will be a presumption in favour of the retention and enhancement of heritage assets. Applications will only be supported where they sustain, conserve and where appropriate enhance the significance, character and setting of the asset itself and the surrounding historic environment.

7.6.8 The application is accompanied by a Heritage Assessment (HA) which identified Durrants House (Listed Building Grade II) and Cassiobury Park (Registered Park Grade II) as heritage assets which could be affected by the proposals through change within their settings. The Council's Heritage Officer agrees with these identifications. There are no other heritage assets that are considered to be affected by the proposals. This includes the Croxley Green Conservation Area, the boundary of which is sited approximately 400m from the south-west corner of the application site and which it is concluded has no association with the site either at present or historically and between which there is no intervisibility, a conclusion supported by the Council's Heritage Officer.

- 7.6.9 The submitted HA states that the development has been designed to minimise harm to the significance of Durrants House and Cassiobury Park through changes to their settings and taking into account retained views to and from the rear of Durrants House and the retained buffer of open space in the areas adjacent to Cassiobury Park, concludes that the scale of the effect is assessed as being less than substantial harm at the lower end of the spectrum in relation to Durrants House and at the lowest end for Cassiobury Park.
- 7.6.10 In relation to Durrants House, the Conservation Officer agrees that the proposal would result in less than substantial harm to the setting of Durrants House. They consider the level of harm would be low – mid level. Whilst they consider that the degree of harm could be mitigated to some extent, due to the scale of the proposal and change in land use and character they do not consider that the harm could be removed. In relation to Cassiobury Park the Conservation Officer agrees that the proposal would result in less than substantial harm at the lowest end of the spectrum as a result of the substantial landscaped buffer.
- 7.6.11 Following the receipt of comments from the Conservation Officer the applicant provided a response (Pegasus Group 27/03/25 received 28/03/25). This has been reviewed by the Conservation Officer but does not alter their comments set out in full at 9.29 below.
- 7.6.12 In summary, the proposal is considered to result in less than substantial harm (low – mid level and low level respectively) to the setting of the Grade II Listed Durrants House and the Grade II Registered Cassiobury Park.
- 7.6.13 As noted above, the NPPF advises that where a development proposal will lead to less than substantial harm to the significance of a designated heritage asset, this harm should be weighed against the public benefits of the proposal. When considering the impact of a proposed development on the significance of a designated heritage asset, great weight should be given to the asset's conservation, irrespective of whether any potential harm amounts to substantial harm, total loss or less than substantial harm to its significance.
- 7.6.14 The benefits of the scheme, including any public benefits, are considered at section 7.22 below.

Archaeological Considerations

- 7.6.15 Policy DM3 of the Development Management Policies LDD (adopted July 2013) advises that where an application site includes, or is considered to have the potential to include, heritage assets with archaeological interest, it must be accompanied by an appropriate desk-based assessment. The submitted HA considers archaeological interest.
- 7.6.16 The Historic Environment Advisor has reviewed the submitted details. They note that no heritage assets of archaeological interest are known from within the proposed development site, however, as noted in the HA, there is an underlying potential for prehistoric activity, which would be of regional significance. The site has not been subject to significant development or other disturbance and as a result, it is likely that if any archaeological remains are present on the remainder of the site, they are well preserved. The Historic Environment Advisor concludes that given the size and scope of the proposed development, it should be regarded as having the potential to have an impact on heritage assets of archaeological interest, and therefore they recommend archaeological field evaluation of the proposed development area, via trial trenching, prior to development commencing. They consider that appropriately worded conditions on any planning consent would be sufficient to provide for the level of investigation that this proposal warrants and have provided suggested wording.
- 7.6.17 In summary, in view of the specialist advice received, it is concluded that subject to conditions, there would be no adverse impacts on heritage assets of archaeological interest. The proposed development in this respect complies with the NPPF (2024) and Policy DM3 of the Development Management Policies LDD (adopted July 2013).

7.7 Highways, Access & Transport Impacts

- 7.7.1 Core Strategy Policy CP10 relates to Traffic and Travel, and states that Development proposals will be expected to contribute to the delivery of transport and travel measures identified as necessary for the development, either on-site as part of the development or through contributions to off-site provision as appropriate. Provision for interchange and access by public transport, walking and cycling will be regarded as particularly important. The policy explains that all development should be designed and located to minimise the impacts of travel by motor vehicle on the District. Clearly the development subject of this application is specifically designed to cater for travel by motor vehicle.
- 7.7.2 Policy CP10 states that Development will need to demonstrate that it provides a safe and adequate means of access, is appropriate in scale to the existing transport infrastructure and where necessary infrastructure can be improved. It is necessary for the impact of the proposal on transport to be fully assessed through a comprehensive Transport Assessment.
- 7.7.3 The NPPF at Paragraph 115 sets out that in assessing specific applications for development it should be ensured that;
- a) sustainable transport modes are prioritised taking account of the vision for the site, the type of development and its location;*
 - b) safe and suitable access to the site can be achieved for all users;*
 - c) the design of streets, parking areas, other transport elements and the content of associated standards reflects current national guidance, including the National Design Guide and the National Model Design Code; and*
 - d) any significant impacts from the development on the transport network (in terms of capacity and congestion), or on highway safety, can be cost effectively mitigated to an acceptable degree.*
- 7.7.4 Paragraph 116 states that “Development should only be prevented or refused on highways grounds if there would be an unacceptable impact on highway safety, or the residual cumulative impacts on the road network would be severe”.
- 7.7.5 Policy CP1 of the Core Strategy (adopted October 2011) advises that in ensuring all development contributes to the sustainability of the District, it is necessary to take into account the need to reduce the need to travel by locating development in accessible locations and promoting a range of sustainable transport modes.
- 7.7.6 Policy CP10 (Transport and Travel) of the Core Strategy (adopted October 2011) advises that all development should be designed and located to minimise the impacts of travel by motor vehicle on the District. Development will need to demonstrate that:
- i) It provides a safe and adequate means of access*
 - j) It is appropriate in scale to the existing infrastructure...*
 - k) It is integrated with the wider network of transport routes...*
 - l) It makes adequate provision for all users...*
 - m) It includes where appropriate, provision for public transport either within the scheme or through contributions*
 - n) The impact of the proposal on transport has been fully assessed...*
 - o) The proposal is accompanied by a draft Green Travel Plan*
- 7.7.7 As noted at the start of the report, the majority of the application site falls within Sarratt Parish area. It is only the two access points proposed from Little Green Lane that fall within the Croxley Green Neighbourhood Plan (2018) area. Policy H03 (Connections to existing footpaths and cycle ways in new developments) advises that all new development should connect into the existing networks and improve their connectivity.

- 7.7.8 Policy 8 of the Sarratt Neighbourhood Plan (adopted 2025) relates to Public Rights of Way and states that there is a presumption against the loss of a Public Right of Way. Policy 10 (Car Parking) notes that new developments should create or improve provision for active travel modes such as walking and cycling.
- 7.7.9 This application includes a number of highways works and as explained above, whilst the application is submitted in Outline form, matters of access are for full consideration as part of the application. The impact of the proposed highway works are to be assessed by Hertfordshire County Council as the Local Highway Authority, and National Highways as the Highway Authority for the strategic road network. Active Travel England are also a statutory consultee considering how active travel is incorporated into the development. Similarly Transport for London have been consulted on the application.
- 7.7.10 Highway infrastructure works proposed include: Two proposed points of vehicular access to the site across Little Green Lane from Durrants Drive and Links Way; Footpath and cycleway connections throughout the scheme; and retention of the existing public right of way (017) and incorporation into the scheme.

Hertfordshire County Council – the Local Highway Authority (HCCHA)

- 7.7.11 HCCHA note in their comments (6/1/26) that there has been extensive dialogue between the applicant's transport consultant and HCCHA. HCCHA raised an initial objection to the application, however, following the receipt and review of additional information during the course of the application, HCCHA have now confirmed that they raise no objection and do not wish to restrict the grant of planning permission subject to relevant planning conditions and planning obligations. This is discussed below in more detail.

Development Access Designs and 20mph Zone (Little Green Lane, Canterbury Way, Dover Way and Links Way)

- 7.7.12 Vehicular access to the site is proposed across Little Green Lane from Durrants Drive and Links Way. HCCHA note that a key consideration for the application is how the proposal connects to the surrounding highway network, noting that routes to the south (eg. Durrants Drive, Canterbury Way and Links Way) will have to accommodate additional pedestrian, cyclists, buses and vehicles.
- 7.7.13 HCCHA note that the applicant has investigated a variety of options to ensure that sustainable travel modes are prioritised and that residual traffic speeds remain in the region of 20mph (or less) to support active travel. The initial favoured option was for widened footways to allow for the creation of an off-carriageway cycle facility. However, following the safety concerns raised by the Road Safety Audit, the feasibility of shared footway cycleways from the site along Canterbury Way, Dover Way and Links Way was ruled out. HCCHA have concluded that the introduction of a 20mph zone to support the current vehicle speeds, along with supporting measures, such as raised junction tables at all junctions which will prioritise pedestrians and allow cycling from the development to be safely incorporated on-carriageway would be appropriate. HCCHA have a county wide 20mph programme and the application site forms part of a wider area including the adjoining residential area to the west. HCCHA note that if a 20mph zone is to be promoted to support the development (in conjunction with the network of junction tables) it will have to cover the 'wider area'. The 'wider area' is unlikely to require similar traffic calming measures, instead, the wider scheme is likely to rely purely on lines and signs. However, there is still a cost which will need to be provided to bring the scheme forward. The cost is based on similar schemes elsewhere in the County.
- 7.7.14 HCCHA note that the final design of the overall 20mph zone and specific measures (junction tables) in Durrants Drive and Canterbury and Links Way can be addressed via a planning condition/obligation and therefore, delivered by the developer. The wider 20mph scheme will also require financial contribution from the development.

- 7.7.15 In summary, HCCHA therefore request a condition requiring submission of a detailed scheme for offsite highway improvement works to deliver 20mph speed limits. Such works would be required to be completed prior to first occupation of the development. HCCHA also require that a proportion of the residual Strand 2 financial contribution is used to design, consult and implement Croxley Green 20mph.

Site Access

- 7.7.16 As noted above, vehicular access to the site is proposed across Little Green Lane from Durrants Drive and Links Way. The plans show new parking areas along Durrants Drive, introduced to ease parking pressure along the road which will be one of the main access routes to serve the development. HCCHA comment that a revised safety audit will need to be completed. Whilst this can be resolved during the S278 process, HCCHA suggest that it would be beneficial if this was concluded prior to the grant of planning permission so that any relevant drawings could be updated if required. The applicant will address this point.
- 7.7.17 The introduction of stop lines on Little Green Lane has been included as part of amendments to resolve safety audit comments. HCCHA request that the length of the raised tables along Little Green Lane is reduced so the hump is closer to the stop line. The applicant will address this point.
- 7.7.18 In summary, subject to the above HCCHA raise no objection to the site access but request a condition requiring a detailed scheme for the access and off-site highway improvement works to be submitted. This would be required to be completed prior to first occupation of the development.
- 7.7.19 HCCHA would also require details of arrangements for the future management and maintenance of the proposed streets to be submitted for approval.

General Comments

- 7.7.20 HCCHA raised initial concerns regarding baseline and development traffic data within the Transport Assessment (TA) but have confirmed that the TA has been updated / corrected.
- 7.7.21 In relation to accident data, HCCHA note that the amended TA has included additional locations as requested. In summary, most of the junctions within the study area have fewer than 5 accidents recorded. Whilst some of the larger junctions have higher levels, this would be expected as the volume of traffic passing through these junctions would be higher and the majority of the accidents are most likely to be rear end shunts. Two fatal accidents have been recorded one on Sarratt Road which involved a vehicle and cyclist and the other on Hempstead Road which involved a van and pedestrian. Whilst noted, HCCHA consider that there is no evidence that traffic generations from this proposed development would adversely affect highway safety.
- 7.7.22 HCCHA note that the amended TA has adopted a new approach to trip rate calculation which provides multi modal trip rates for the development site. The approach is supported by HCCHA. The amended TA has also considered the other proposed site uses which demonstrates that most will be internal trips with only a small proportion of external movements that would be fairly local, and in the view of HCCHA, not affect the Strategic Road Network (SRN).
- 7.7.23 In relation to traffic distribution, HCCHA advise that the methodology adopted was agreed by HCC officers. In relation to construction traffic, they note that the amended TA has taken on board their previous comments and they raise no objection subject to the inclusion of a planning condition requiring submission of a Construction Management Plan (CMP) which would include details of construction vehicle numbers. In relation to the various Junction Capacity Assessments undertaken, many show that the junction would continue to operate within acceptable parameters. HCCHA note that some of the junctions are starting to show

additional increases in both queues and delays. The proposals include contributions from the development which will be concentrated on promoting the LCWIP proposals (discussed below). In addition, improvements are proposed to cycle infrastructure routes and Beryl Bikes provision, a new dedicated bus service serving major interchanges and local/town centres, provision of bus season tickets for new residents, and contributions towards step-free access at Croxley Station. HCCHA consider that all of these will support more sustainable travel options for residents and visitors and the wider communities which will assist in mitigating some of the issues that have been identified within the Transport Assessment. Importantly, there would not be an unacceptable highway safety reason nor a severe road network reason to justify the recommendation of refusal of the proposals from a highways or transport perspective.

- 7.7.24 In relation to active and sustainable travel proposals, new proposed pedestrian / cycle links to the south of the site provides one set of measures. However, HCCHA previously advised that as part of this application other routes to the east need further consideration. HCCHA note that paragraphs 4.21 – 4.37 of the TA (T24544 Rev E) consider active travel routes to Croxley Station, Watford Station and Cassiobury Park via West Herts Golf Course. HCCHA note that the applicant has not proposed any major changes apart from the introduction of signage. HCCHA consider that this route is a significant asset to the development as it represents a relatively traffic free, quiet route towards the rail station and town centre facilities. The development will lead to different/greater level of use, which as all use will be active modes, use of the route should be encouraged by providing further improvements. HCCHA therefore seek a financial contribution in order that improvements to Rousebarn Lane and the public right of way between Little Green Lane and Gade Avenue can be made.
- 7.7.25 Other sustainable transport measures include:
- Contributions towards surrounding active travel links, such as the signage of routes.
 - The provision of Beryl Bikes docking stations on site. HCCHA anticipate 15 such ebikes being provided at an estimated cost of £45,000.
 - The introduction of a dedicated bus service within and surrounding the site, including to key destinations such as Rickmansworth, Watford Station, Croxley Station, and Watford Junction. The cost of the subsidy for provision of this service has been estimated at approximately £1.955 million over five years.
 - A seasonal bus pass to each dwelling on initial occupation. This item is estimated to cost up to £511,200 on the basis of providing 6 x 4-week bus passes for 600 dwellings calculated on the basis of a 4-week All-Zone Arriva ticket in Herts/Essex.
- 7.7.26 HCCHA also note that opportunities to improve active and sustainable travel in Croxley Green and the surrounding areas have been highlighted in the Watford and Three Rivers Local Cycling and Walking Infrastructure Plan (LCWIP). The plan includes upgrades and key interventions to cycle infrastructure, including to cycle priority enhancements along the A412 corridor towards Watford, known as Route 2 in the scheme. In line with the vision to ensure that the site provides everyday facilities and that movements to/from the site are undertaken as sustainably as possible, contributions to the LCWIP proposals are sought.
- 7.7.27 A Travel Plan has been provided. Whilst HCCHA consider its content appropriate at this stage in the planning process, a condition is requested requiring submission of a full Travel Plan at least 3 months prior to first occupation. HCCHA have also advised that they would also require an Evaluation and Support Fee of £1200 per year (for the residential Travel Plan which should be in place until 5 years post full occupation) index linked to RPI from March 2014. With Education Travel Plans requiring a fee of £1500 per year (linked to RPI from March 2020 for 7-year plan).
- 7.7.28 Planning Obligations: HCCHA require that the immediate/specific impacts of larger developments are mitigated via S278 obligations and / or S106 Agreements. These are described as 'Strand 1' contributions. The second strand ('Strand 2' contributions) seek to

address the cumulative impacts of all development, facilitating delivery and enhancement of the necessary active and sustainable transport networks. 'Strand 2' contributions are calculated based on a formula (set out in the Hertfordshire County Council's Guide to Developer Contributions) of £9,861 per dwelling (index linked to March 2024). The 'Strand 2' figure in this case is therefore £5,916,600.

- 7.7.29 The 'Strand 1' contributions are summarised below, these include financial contributions to secured via S106 Agreement (Table 1) and the estimated construction value of S278 works which would be required to be delivered by the developer (Table 2). The total 'Strand 1' figure is therefore £4,330,062. HCCHA advise that the 'Strand 1' total should be deducted from the 'Strand 2' figure to give the residual 'Strand 2' figure that would be sought, in this case £1,586,538. HCCHA advise that the residual figure listed is to be attached to delivering LCWIP schemes to encourage and support active travel measures serving the new occupants of the development. All Heads of Term to be secured via S106 agreement are summarised in the table at 7.20 below.

Table 1: Strand 1 Financial Contributions

Dedicated Bus Service	New half-hourly service (Watford/Rickmansworth) £1,955,000 Financial contribution Paid annually for five years (£391,000 per year)
Rousebarn Lane Upgrade	From Little Green Lane to Gade Avenue £25,000
LCWIP Contribution	Watford & Three Rivers Route 2 improvements £15,000
Beryl Bikes	Expansion and docking station provision £45,000
Travel Plan Evaluation	HCC Evaluation Fee £8,862
Travel Vouchers and Car Share	Based on TA: 6 x 4-week passes (Arriva All Zone) per unit* £511,200

Table 2: Strand 1 Developer Delivered Works (S278)

Site Access (Durrants Dr)	New priority junction, raised table, lighting & drainage. £130,000.
Site Access (Links Way)	New priority junction, visibility splays & raised table. £130,000.
Enhanced Traffic Calming	Speed calming for 20mph zone, inclusive of on-street cycling measures. £562,000.
Bus Infrastructure	4 stops (2 new, 2 upgrades) incl. shelters, RTI & Civils. £60,000.
Active Travel Signage	Wayfinding for secondary routes (Rousebarn Ln/Park). £25,000.
Vegetation Clearance (Rousebarn)	Maintenance asset. £10,000.

- 7.7.30 HCCHA also request that specific planning conditions, necessary to make the development acceptable are included. These have been discussed above and are included in the suggested conditions at section 8 below.
- 7.7.31 In conclusion, there would not be an unacceptable highway safety reason nor a severe road network reason to justify the recommendation of refusal of the proposals from a highways or transport perspective. Nevertheless, the acceptability of the proposals would be subject to the full technical approval and completion of the necessary off-site highway work and inclusion of recommended conditions and S106 obligations. It is considered that the proposed planning obligations would meet the NPPF 58 tests.

National Highways – the Highway Authority (NH)

- 7.7.32 NH is interested in whether there would be any adverse safety implications or material increase in queues and delays on the strategic road network (SRN) as a result of the proposed development, in this case on the M25 J18 and 19, and the M1 J5.
- 7.7.33 NH provided initial holding objections, requesting that further information be provided. Additional information was provided, most recently further traffic modelling information for the M1 Junction 5.
- 7.7.34 NH note that modelling undertaken has generated average queue lengths that are shorter than the M1 off-slips. A minority of the seeded runs indicate a maximum queue length that would exceed the length of the M1 southern on-slip. However, the average queue length remains within the slip road. Therefore, the model outputs indicate a potentially infrequent impact on the operation of the Strategic Road Network (SRN). On consideration there is insufficient evidence of likely occurrence related to the additional development related traffic.
- 7.7.35 NH are therefore satisfied that the development will not materially affect the safety, reliability and/or operation of the strategic road network (the tests set out in DfT Circular 01/2022, and MHCLG NPPF 2024 paragraphs 115-118) in this location and its vicinity and therefore raise no objection to the application.

Active Travel England (ATE)

- 7.7.36 ATE reviewed the application against the criteria in the updated planning assessment toolkit, national planning policy, and active travel design guidance. They noted that the proposals demonstrate strong potential to support active travel, with the site being sustainably located and offering opportunities to access surrounding services and amenities via active modes. However, they considered that certain aspects required further consideration and therefore ATE requested additional information and analysis to address these matters.
- 7.7.37 A response / additional information was prepared by the applicant and ATE were reconsulted. Following review of the additional information ATE have raised no objection to the grant of planning permission subject to conditions.
- 7.7.38 ATE had requested provision of expected trip rates for walking, wheeling and cycling and inclusion of all day trip rates for all land users, not just residential. Table 4 of the Transport Assessment (TA) has been updated to include forecasts for Active Travel trips based on TRICS data which is welcomed by ATE. ATE note that the TRICS data within Appendix F indicates more than 70 cycle trips and approximately 550 pedestrian trips per day and note that it is important to ensure that opportunities exist to support and encourage these modes as part of future development proposals. ATE have suggested that a Travel Plan be secured via planning condition.

- 7.7.39 In relation to accessibility, ATE considered that the site has reasonable levels of accessibility to surrounding services and the potential to be sustainable for the purposes of active travel. However, the distance to the nearest bus stop was identified as exceeding the recommended standard (440m). ATE note that the applicant now proposes to provide bus stops and shelters on site, together with real-time bus information where appropriate. This matter is therefore accepted by ATE, subject to securing sufficient funding to the satisfaction of the Highway Authority.
- 7.7.40 In relation to the shared footway/cycleway, ATE does not generally support shared-use paths except in limited circumstances. As discussed above, the initial favoured option was for widened footways to allow for the creation of an off-carriageway cycle facility. However, following the safety concerns raised by the Road Safety Audit, the feasibility of shared footway cycleways from the site along Canterbury Way, Dover Way and Links Way was ruled out. HCCHA have concluded that the introduction of a 20mph zone to support the current vehicle speeds, along with supporting measures, such as raised junction tables at all junctions which will prioritise pedestrians and allow cycling from the development to be safely incorporated on-carriageway would be appropriate.

Transport for London (TfL)

- 7.7.41 TfL have reviewed the application to consider the potential impacts of the proposed development on TfL services and infrastructure including Croxley station. TfL note that throughout the engagement process regarding the development proposals at this site, it has been consistently acknowledged that a financial contribution would be sought towards step-free access at Croxley Underground Station. The data provided indicates that trips generated by the development would represent an increase of 7.1 percent compared to existing usage. This figure is accepted by TfL who accordingly, seek a financial contribution of £1,065,000 towards the delivery of step-free access at Croxley Underground Station.
- 7.7.42 In addition to the consideration of Station capacity, when the preliminary report was discussed Members queried whether there would be sufficient capacity on trains to accommodate additional demand resulting from the development. TfL were asked to comment on this point and advised that they did not see crowding being an issue.

Highways, Access & Transport Impacts – Conclusion

- 7.7.43 In conclusion, as set out above HCC as Highway Authority (HCCHA) advise that there would not be an unacceptable highway safety reason nor a severe road network reason to justify the recommendation of refusal of the proposals from a highways or transport perspective subject to the full technical approval and completion of the necessary off-site highway work and inclusion of recommended conditions and S106 obligations. National Highways have also advised that they are satisfied that the development will not materially affect the safety, reliability and/or operation of the Strategic Road Network (SRN) and therefore raise no objection.
- 7.8 Vehicle Parking
- 7.8.1 Development Management Policy DM13 requires development to make provision for parking in accordance with the parking standards and zone based reductions set out in Appendix 5.
- 7.8.2 Policy 10 of the Sarratt Neighbourhood Plan (adopted 2025) relates to Car Parking and notes that the standards set by TRDC are considered a minimum level of provision.
- 7.8.3 As previously noted, this application is submitted in Outline with matters of access for consideration. As the Reserved Matters, including layout, will be considered at a later date there is no requirement for the Outline application to provide detailed parking plans. Instead, it seeks to explain the principle of parking by identifying the total number of parking spaces

required, showing their general location on the illustrative site plan, and demonstrating how the layout accommodates access and circulation. To reiterate, the site's layout would be considered at a later date as a Reserved Matter and the proposed car parking layout and provision would be dealt with at that time. However, having regard to the number of dwellings proposed on site, it is acknowledged that a significant number of car parking spaces would be required in addition to car parking for the new school and local centre.

- 7.8.4 Whilst car parking provision and layout would be dealt with at Reserved Matters stage, the submitted Transport Assessment (in association with the illustrative layout plan) considers how parking could be provided and details that for the 538 residential dwelling houses proposed, parking would be provided in accordance with Appendix 5 standards which require 1 assigned space for 1 and 2 bedroom dwellings; 2 assigned spaces for 3 bedroom dwellings; and 3 assigned spaces for dwellings with 4 bedrooms or more.
- 7.8.5 The remaining residential units (62 flats) would be located within the local centre, which would also include community uses such as retail, café and health and social care. The Transport Assessment (Table 2, page 25 of Transport Assessment Rev E) suggests that 175 car parking spaces would be provided at the local centre and suggests a split of 62 spaces for the flat (1 per dwelling) and 113 spaces for the retail, medical and community uses. The provision of 175 car parking spaces would represent a small (-13 spaces) shortfall against the existing standards but would exceed (+23 spaces) the standards set out in the emerging local plan.
- 7.8.6 Parking for the 1FE Primary School would be accommodated with the parcel of land allocated for this use.
- 7.8.7 It is also acknowledged that a package of sustainable transport initiatives is proposed, primarily focusing on encouraging alternatives to private car use to maximise the need for extensive new traffic infrastructure. It is proposed to provide Beryl Bikes docking stations on site. It is proposed to introduce a dedicated bus service within and surrounding the site, including to key destinations such as Rickmansworth, Watford Station, Croxley Station, and Watford Junction. Similarly, a seasonal bus pass would be provided to each dwelling on initial occupation.
- 7.8.8 In summary, the parking provision would form part of the consideration of any subsequent Reserved Matters application. However, it is considered that sufficient space could be accommodated within the site to provide adequate parking to serve the development in accordance with Policy CP10 of the Core Strategy (adopted October 2011) and Policy DM13 and Appendix 5 of the Development Management Policies LDD (adopted July 2013).
- 7.9 Impact on residential amenity
- 7.9.1 Paragraph 135 (f) of the NPPF advises that planning policies and decisions should ensure that developments create places that are safe, inclusive and accessible and which promote health and well-being, with a high standard of amenity for existing and future users; and where crime and disorder, and the fear of crime, do not undermine the quality of life or community cohesion and resilience.
- 7.9.2 Policy CP12 of the Core Strategy (adopted October 2011) states that the Council will expect development proposals to protect residential amenities. Design Guidelines for residential development are set out in Appendix 2 of the Development Management Policies LDD (adopted July 2013).
- 7.9.3 The application is submitted in outline, with matters of access for consideration. However, the application is accompanied by an illustrative masterplan which suggests a form of development where a buffer would be maintained between the development and the closest existing properties to the opposite side of Little Green Lane. Whilst impact on neighbouring amenity would be fully assessed at reserved matters stage, it is considered that the

illustrative masterplan demonstrates how the site could be developed to ensure no demonstrable harm to the amenity of existing residents through matters such as overshadowing, loss of light or overlooking. The impact on the amenity of future occupiers would also be assessed at reserved matters stage.

- 7.9.4 The application was accompanied by a Health Impact Assessment (RPS, December 2024, 1.0). The HIA assess the potential impacts of the proposed development during construction, operation and management phases, evaluating the potential effects of the development on the health and well-being of the local population. The HIA concludes that the development would have a mostly positive impact on the health of the community, with the potential to improve access to green space, promote active travel and enhance healthcare services. However, it does also identify potential negative impacts such as temporary disruption during construction and suggests recommendations for mitigating these potential negative impacts and maximising the potential benefits.

7.10 Pollution – Air Quality

- 7.10.1 Paragraph 187 of the NPPF advises that planning policies and decisions should contribute to and enhance the natural and local environment by amongst other considerations:

(e) Preventing new and existing development from contributing to, being put at unacceptable risk from, or being adversely affected by, unacceptable levels of soil, air, water or noise pollution or land instability. Development should, wherever possible, help to improve local environmental conditions such as air and water quality, taking into account relevant information such as river basin management plans;

- 7.10.2 The NPPG provides guidance as to when air quality would be relevant to a planning decision. In summary, it states that when deciding whether air quality is relevant to a planning application, considerations could include whether the development would, amongst other considerations:

- Significantly affect traffic in the immediate vicinity of the proposed development site or further afield.
- Introduce new point sources of air pollution e.g. furnaces.
- Give rise to potentially unacceptable impact (such as dust) during construction for nearby sensitive locations.

- 7.10.3 In relation to air quality, Policy DM9 of the Development Management Policies LDD (adopted July 2013) advises that development will not be permitted where it would:

- Have an adverse impact on air pollution levels, particularly where it would adversely affect air quality in an Air Quality Management Area and/or
- Be subject to unacceptable levels of air pollutants or disturbance from existing pollutant sources.

- 7.10.4 The application is accompanied by an Air Quality Assessment (BWB, December 2024, 233574-01-AQA) which has been review by the Environmental Protection Officer (EPO). They note that a construction phase dust assessment was undertaken to evaluate the potential impact of construction activities (including construction vehicles on public highways up to 250m from the site entrances) on local air quality. The assessment indicates that with the implementation of the recommended mitigation measures, the residual impacts from the construction phase will be not significant. The EPO notes that an operational phase road traffic emissions assessment was also undertaken to consider the impact of development generated road traffic at identified existing receptor locations. This concludes that the development is not predicted to result in any new exceedances of the air quality objectives and that the impacts of the development are considered to be negligible at all modelled receptor locations.

- 7.10.5 The EPO raises no objection subject to conditions as the impact of the proposed development on local air quality is not considered to be significant.
- 7.10.6 In summary, in view of the specialist advice received, it is concluded that subject to conditions there would be no adverse impacts with regards to air quality as a result of the development. The proposed development in this respect complies with the NPPF and Policy DM9 of the Development Management Policies LDD (adopted July 2013).
- 7.11 Pollution – Noise and Vibration
- 7.11.1 Paragraph 187 of the NPPF advises that planning policies and decisions should contribute to and enhance the natural and local environment by amongst other considerations:
- (e) Preventing new and existing development from contributing to, being put at unacceptable risk from, or being adversely affected by, unacceptable levels of soil, air, water or noise pollution or land instability. Development should, wherever possible, help to improve local environmental conditions such as air and water quality, taking into account relevant information such as river basin management plans;
- 7.11.2 Policy DM9 of the Development Management Policies LDD (adopted July 2013) sets out that planning permission will not be granted for development has an unacceptable adverse impact on the indoor and outdoor acoustic environment of existing or planned development, has an unacceptable adverse impact on countryside areas of tranquillity which are important for wildlife and countryside recreation.
- 7.11.3 The application is accompanied by a Noise Impact Assessment (BWB, December 2024, 233574_002). Environmental Health (EHO) have reviewed the submitted report and consider the main impacts associated with the application to be: (1) Increased traffic flows resulting in higher noise levels. The EHO notes that this has been considered within the report and the impact on existing residents has been deemed insignificant. The EHO does not have grounds to consider this to be inaccurate; (2) Noise associated with the school; and (3) Noise associated with the community centre and café.
- 7.11.4 The EHO raises no objections to the application on noise grounds subject to the inclusion of relevant planning conditions.
- 7.11.5 In summary, in view of the specialist advice received, it is considered that subject to conditions there would be no adverse impacts with regards to noise as a result of the development. The proposed development complies with the NPPF and Policy DM9 of the Development Management Policies LDD (adopted July 2013) in this regard.
- 7.12 Pollution – Light
- 7.12.1 Policy DM9 of the Development Management Policies LDD (adopted July 2013) sets out that development proposals which include external lighting should ensure that proposed lighting schemes are the minimum required for public safety and security, that there is no unacceptable impact on neighbouring or nearby properties or the surrounding countryside or wildlife.
- 7.12.2 As the application is in Outline, full details of lighting would be required at Reserved Matters stage or via condition if appropriate.
- 7.13 Pollution – Land Contamination
- 7.13.1 Policy DM9 of the Development Management Policies LDD (adopted July 2013) states that the Council will only grant planning permission for development on, or near to, former landfill sites or on land which is suspected to be contaminated where the Council is satisfied that there will be no threat to the health of future users or occupiers of the site or neighbouring

land, and there will be no adverse impact on the quality of local ground water or surface water quality.

7.13.2 The application is accompanied by a Phase 1 GEO-Environmental Assessment (BWB, December 2024, 233574) which has been reviewed by the Environmental Protection Officer (EPO). They note that the preliminary risk assessment undertaken has identified a number of plausible contaminant linkages that require further investigation. As such, an assessment of the potential risks associated with the site is considered necessary and the EPO therefore recommends the standard contaminated land condition be attached in the event that planning permission were to be granted.

7.13.3 In summary, in view of the specialist advice received, it is considered that subject to conditions there would be no adverse impacts with regards to contaminated land as a result of the development. The proposed development complies with the NPPF and Policy DM9 of the Development Management Policies LDD (adopted July 2013) in this regard.

7.14 Flood Risk and Drainage

7.14.1 Policy CP1 of the Core Strategy (adopted October 2011) requires all development in Three Rivers to contribute to the sustainability of the District, by minimising flood risk through the use of Sustainable Drainage Systems. Policy DM8 of the Development Management Policies LDD (adopted July 2013) refers to Flood Risk and Water Resources, and states that development will only be permitted where it would not be subject to unacceptable risk of flooding. It also states that Development in all areas should include Sustainable Drainage Systems to reduce surface water runoff.

7.14.2 The site is wholly within Flood Zone 1 as defined by the Environment Agency. Flood Zone 1 signifies areas with the lowest probability of flooding (less than a 0.1% annual probability of river or sea flooding, equating to less than 1 in 1000 chance).

7.14.3 The application was accompanied by a Flood Risk Assessment (FRA) (BWB, December 2024, 233574_FRA) and Sustainable Drainage Strategy (BWB, December 2024, 233574-SDS). These were reviewed by the Lead Local Flood Authority (LLFA) who requested additional information be provided. Additional information (BWB Ref. 233574-BWB-ZZ-XX-T-W-0005_LLFA) was received and the LLFA reconsulted.

7.14.4 Having reviewed the additional information the LLFA have advised that the submitted details are in accordance with the NPPF and local planning policy and they therefore raise no objection subject to conditions. The requested conditions relate to the provision of detailed designs of a surface water management scheme prior to or in conjunction with each reserved matters application; a SuDS phasing plan to ensure that each phase does not exceed the agreed discharge rates and that source control measures are installed; a construction phase surface water management plan; and verification report. The conditions are considered necessary to make the development acceptable in planning terms, ensuring the satisfactory management of local sources of flooding of surface water; to ensure the development achieves a high standard of sustainability; and to ensure that the construction does not result in flooding on or off site.

7.14.5 In relation to water quality, Affinity Water (AW) have advised that the proposed development site is not located within an Environment Agency defined Source Protection Zone. AW raise no objection but note that construction works should be in accordance with the relevant British Standards and Best Management Practices to minimise groundwater pollution risk. In relation to water efficiency, AW note that the site is within a water stressed area such they would expect it to include water efficient fixtures and fittings and measures such as rainwater harvesting. Whilst this level of detail would not be secured at Outline stage, it is noted that the submission (Sustainability Statement (Greengage, December 2024)) has considered water efficiency and refers to the integration of water efficient fixtures and fittings; rainwater harvesting; flow control devices; leak detection and irrigation.

- 7.14.6 Thames Water (TW) have confirmed that they have identified an inability of the existing foul water network infrastructure to accommodate the needs for the development proposal and require a condition be attached to any planning permission that does not allow the occupation of the development until all foul water network upgrades are completed or a phasing plan agreed. TW have confirmed that they have identified an inability of the existing sewage treatment works infrastructure to accommodate the needs of the development proposal and require a condition be attached to any planning permission that does not allow the occupation of the development until all sewage works upgrades required to accommodate the additional flows from the development have been completed, or a development and infrastructure phasing plan has been agreed. Officers consider this approach to be acceptable.
- 7.15 Impact on Wildlife, Biodiversity and Agriculture
- 7.15.1 Section 40 of the Natural Environment and Rural Communities Act 2006 requires Local Planning Authorities to have regard to the purpose of conserving biodiversity. This is further emphasised by regulation 3(4) of the Habitat Regulations 1994 which state that Councils must have regard to the strict protection for certain species required by the EC Habitats Directive.
- 7.15.2 Paragraph 13 of Schedule 7A of the Town and Country Planning Act 1990 sets out that every planning permission granted for the development of land in England shall be deemed to have been granted subject to the 'biodiversity gain condition' requiring development to achieve a net gain of 10% of biodiversity value.
- 7.15.3 Paragraph 187 of the NPPF advises that planning policies and decisions should contribute to and enhance the natural and local environment by:
- b) recognising the intrinsic character and beauty of the countryside, and the wider benefits from natural capital and ecosystem services – including the economic and other benefits of the best and most versatile agricultural land, and of trees and woodland;*
- d) minimising impacts on and providing net gains for biodiversity, including by establishing coherent ecological networks that are more resilient to current and future pressures and incorporating features which support priority or threatened species such as swifts, bats and hedgehogs.*
- 7.15.4 Footnote 62 states "Where significant development of agricultural land is demonstrated to be necessary, areas of poorer quality land should be preferred to those of a higher quality".
- 7.15.5 Paragraph 192 of the NPPF advises that in order to protect and enhance biodiversity and geodiversity, plans should: b) promote the conservation, restoration and enhancement of priority habitats, ecological networks and the protection and recovery of priority species; and identify and pursue opportunities for securing measurable net gains for biodiversity.
- 7.15.6 Policy CP1 of the Core Strategy (adopted October 2011) advises that; "all development in Three Rivers will contribute to the sustainability of the District. This means taking into account the need to" (amongst other things) (f) "protect and enhance our natural, built and historic environment from inappropriate development and improve the diversity of wildlife and habitats". Policy CP9 of the Core Strategy (adopted October 2011) advises that; "The Council will seek a net gain in the quality and quantity of Green Infrastructure, through the protection and enhancement of assets and provision of new green spaces".
- 7.15.7 Policy DM6 of the Development Management Policies LDD (adopted July 2013) advises that development should result in no net loss of biodiversity value across the District as a whole.

- 7.15.8 Policy 6 of the Sarratt Neighbourhood Plan (adopted 2025) relates to Biodiversity and requires all proposals to achieve a net gain in biodiversity (BNG), apply the mitigation hierarchy, and integrate ecologically beneficial planting.
- 7.15.9 As set out in the site description above, the land comprising the application site is predominantly greenfield and in agricultural use. The Government's 'A Green Future: Our 25 Year Plan to Improve the Environment' (published 2018 and last updated 2023) sets out a 25-year plan to improve the health of the environment by using natural resources more sustainably and efficiently and includes plans to protect the 'best' agricultural land.
- 7.15.10 The applicant has submitted an Agricultural Land Classification and Soil Resources Report (Reading Agricultural Consultants, July 2024) which concludes the land is Grade 3B land which is not considered best and most versatile land. The loss of existing 'good to moderate quality' agricultural land is not, therefore, considered a reason to restrict the development and its loss to the development would not be contrary to the Development Plan or the NPPF (2024).
- 7.15.11 In respect of biodiversity, the submission includes Biodiversity Calculation Metric; Biodiversity Checklist; and Ecological and Biodiversity Impact Assessment (RammSanderson, December 2024, RSE_8239_R1_V4_EclA).
- 7.15.12 Biodiversity Net Gain calculations detail that the development would result in a 34.41% increase in habitat units and 42.54% increase in hedgerow units. This net gain is owed to the creation of other neutral grassland, modified grassland, mixed scrub, allotments, bioswale, shrubs, vegetated gardens, and urban trees. Herts Ecology have advised that sufficient information has been provided to determine the application. The BNG for this site would be considered as 'significant' net gain because of the creation of medium distinctiveness habitats. Achieving the gains would be secured by the mandatory condition, S106, and alongside a requirement to provide a habitat management and monitoring plan. Subject to such provisions it is considered that the proposed development meets the requirements of Policy CP9 of the Core Strategy (2011), Policy DM6 of the Development Management Policies LDD (2013) and the NPPF (2024).
- 7.15.13 In respect of protected species, Herts Ecology have reviewed the submitted reports and do not consider that protected species would represent a fundamental ecological constraint to the proposals. Mitigation measures are proposed and these could be secured by planning condition. Initial concerns were raised regarding nesting birds, with Herts Ecology suggesting that further surveys should be carried out prior to determination. The applicants' ecologist responded noting that as construction would not be taking place for some time, they considered that it would be premature to undertake the surveys at this time as it is vital that the red kite surveys are as current as possible to accurately inform mitigation measures. Herts Ecology have reviewed their position and have confirmed that completing pre-commencement red kite surveys will be sufficient. The results of the survey can be included in the Construction Environment Management Plan (CEMP), along with any mitigation outlined by the ecologist.
- 7.15.14 In relation to habitats, Herts Ecology note that no areas of ancient woodland will be lost to the development, and that no existing trees or groups of trees on site will require removal. They note that a 30m buffer has been implemented from the areas of built development to Green Lane Wood Local Wildlife Site. In relation to Whippendell Wood Site of Special Scientific Interest (SSSI), Herts Ecology do not consider there will be any adverse impacts on this important habitat, similarly to the adjacent Dell Wood, Jacotts Hill/West Herts Golf Course, and Merlin's Wood and Newland's Spring. Herts Ecology do request appropriate condition(s) to ensure that no indirect impacts occur on the above important habitats.
- 7.15.15 Conditions requested by Herts Ecology that are considered necessary to make the development acceptable in planning terms relate to: A Construction Environmental Management Plan (CEMP); a pre-commencement Badge Survey; a Lighting Design

Dstrategy for bats; submission of a Biodiversity Enhancement Plan; Mitigation and monitoring plan relating to Green Wood Local Wildlife Site; a Habitat Management and Monitoring Plan; and pre-commencement Red Kite surveys.

7.15.16 In summary, in view of the specialist advice received, it is considered that subject to conditions, the proposed development meets the requirements of Policy CP9 of the Core Strategy, Policy DM6 of the Development Management Policies LDD and accords with the guidance in the NPPF (2024).

7.16 Landscaping and Impact on trees including Ancient Woodland and SSSI

7.16.1 As previously noted, this application is submitted in outline with landscaping a reserved matter. Nevertheless, the application has been submitted with an illustrative landscape strategy.

7.16.2 Policy DM6 of the Development Management Policies LDD (adopted July 2013) notes that proposals for new development should be submitted with landscaping proposals which seek to retain trees and other important landscape and nature conservation features. Development proposals on sites which contain existing trees and hedgerows will be expected to retain as many trees and hedgerows as possible. It also notes that planning permission will be refused for any development resulting in the loss or deterioration to protected woodland, protected trees, and hedgerows unless conditions can be imposed to secure their protection. It states that where the felling of a tree or hedgerow is permitted, a replacement tree or hedge of an appropriate species, size and in a suitable location will be required.

7.16.3 The NPPF sets out at Paragraph 193(c) that “development resulting in the loss or deterioration of irreplaceable habitats (such as ancient woodland and ancient or veteran trees) should be refused, unless there are wholly exceptional reasons and a suitable compensation strategy exists”.

7.16.4 A Tree Preservation Order (TPO) TPO935 was confirmed on the 14 October 2025. This comprises of 10 individual trees (9 x English Oak and 1 x Common Holly) and 1 group (mixed woodland) all located within the application site. Six individual trees are located to the west of Green Lane Wood (the group protected), 2 are located to the northern site boundary and 2 are located to the southern site boundary with Little Green Lane.

7.16.5 There are Ancient Woodlands adjoining (Dell Wood and Long Newlands Spring) the site to the west and north-west and within the site (Green Lane Wood). Whippendell Wood SSSI is sited to the east and north-east, separated by Rousebarn Lane.

7.16.6 As noted above, the application was accompanied by an illustrative landscape strategy, this was updated during the application (DL02 Rev G) in response to consultee comments. The minor amendments reflect the revised drainage layout SuDS basins in response to the LLFAs comments and the footpath to the western boundary with Long Newland’s Wood has been omitted in response to the conclusions of the Woodland Recreational Management Plan. The application was also accompanied by a Preliminary Arboricultural Impact Assessment (AIA) (Tyler Grange, December 2024, 11702_R02_NC Rev E). The AIA was updated during the course of the application following the confirmation of TPO935.

7.16.7 The site is predominantly an agricultural field bounded by hedgerows and trees that are proposed to be supplemented with new planting. Two small sections of hedge (adjacent to Little Green Lane) are proposed to be removed to facilitate access to the site, however, no trees, woodland or groups of trees require removal to facilitate the development proposals.

7.16.8 Natural England (NE) is a non-departmental public body whose statutory purpose is to ensure that the natural environment is conserved, enhanced, and managed for the benefit of present and future generations. NE have reviewed the application and raise no objections

subject to appropriate mitigation being secured. NE considers that without appropriate mitigation the application would damage or destroy the interest features for which Whippendell Wood Site of Special Scientific Interest have been notified. In order to mitigate these adverse effects and make the development acceptable, NE advise that the following options should be secured: Provision of 24ha green space/country park with secured management plan/maintenance for the lifetime of the development; Minimum 30m buffer zone around ancient woodland within and adjacent to the proposed development; An ancient woodland recreational management plan; Information packs for residents on sensitive use of local habitats/protected sites; and a Construction Environment Management Plan for both construction and operational measures. They consider that these mitigation measures can be secured via an appropriate planning condition or obligation attached to any planning.

- 7.16.9 As set out at 7.15 above, Herts Ecology (LPA advisors on ecology matters) note that no areas of ancient woodland will be lost to the development, and that no existing trees or groups of trees on site will require removal. They note that a 30m buffer has been implemented from the areas of built development to Green Lane Wood Local Wildlife Site. In relation to Whippendell Wood Site of Special Scientific Interest (SSSI), Herts Ecology do not consider there will be any adverse impacts on this important habitat, similarly to the adjacent Dell Wood, Jacotts Hill/West Herts Golf Course, and Merlin's Wood and Newland's Spring. Herts Ecology do request appropriate condition(s) to ensure that no indirect impacts occur on the above important habitats.
- 7.16.10 The Forestry Commission (Governments forestry experts/non-statutory consultee on developments in or within 500m of ancient woodland) have also reviewed and provided comments on the application. In relation to the Ancient Woodland Buffer they note that the Standing Advice refers to a minimum 15m buffer and that the application proposes a 30m buffer. Whilst the buffer may be sufficient to avoid direct impacts, indirect soil damage and disturbance would still be expected. They would encourage considering a mix of habitat types to create a graded edge from the existing woodland including new woodland, scrub and species rich grassland with effective management that maximises biodiversity value. They also note the inclusion of amenity public open space and footpaths within the Ancient woodland buffer, and suggest that these may be better located outside of the buffer, with the buffer itself managed as a semi natural habitat less attractive to be used as public open space. In relation to habitat fragmentation and connectivity the Forestry Commission suggest there is opportunity for increased woodland planting to improve connectivity. The planting of new trees is supported, however, the species and provenance of new trees needs to be considered to ensure resilience. Plans should also be in place to ensure long term management and maintenance. The Forestry Commission request, in the event of a grant of planning permission, that full details of any woodland protection measures, a woodland management plan, a planting plan including species selection and lighting strategy to avoid illuminating all woodlands on site and adjacent to it, be provided at the reserved matters stage. Following the submission of a Woodland Recreational Management Plan (ref. RSE_8239_R2_V2 October 2025) (discussed below) the Forestry Commission provided further advice and recommendations regarding landscaping in the event that the LPA was minded to approve the application. It is important to note that the application is in Outline with details of Access provided, but that Landscaping is a Reserved Matter for detailed consideration at a later date which would allow, for example, the applicant to explore a more "wooded" Country Park and enhanced habitat connectivity, whilst remaining within the parameters of the outline consent.
- 7.16.11 The Woodland Trust (woodland conservation charity) have reviewed the submitted application and have raised an objection on the basis of concerns regarding the deterioration of Woodland Trust sites and ancient woodlands. They raise particular concerns in relation to two sites adjacent to the development - Dell Wood ancient woodland and Newland's Spring (part ancient woodland). The Woodland Trust object on the basis that the feasibility of mitigating deterioration of ancient woodland has not been

demonstrated. They suggested that the applicant should submit additional information to demonstrate that effective mitigation could be provided.

- 7.16.12 TRDCs Tree and Landscape Officer has visited the site and reviewed the submitted details. They note that the outline plans indicate that there will be no direct impacts on trees and woodland on the site, with no trees needing to be felled or pruned, and no loss of irreplaceable habitats. In addition, no development is proposed to take place within the root protection areas of retained trees, although some short sections of existing hedgerow would need to be removed. Whilst they consider there to be no direct impacts on trees and woodlands, they note the high potential for indirect impacts. They consider the increase in population would inevitably lead to additional recreational pressures on the trees and woodland, such as the compaction of soils around important trees; the trampling of ground flora in woodland areas; erosion and widening of footpaths through woodland areas; and the disturbance of wildlife, through activities such as dog walking. To prevent any long-term deterioration of these irreplaceable habitats a suitable compensation and mitigation strategy would be required. The Landscape Officer notes that the plans indicate that buffer zones between the housing areas, and the woodlands and trees, would be created, comprising of a Country Park, formal areas of green space, and allotment sites. Whilst they consider that these will provide some mitigation, over the long term, managing visitor access and pressure to the surrounding woodland and being able to deal with antisocial behaviour issues will be key to preventing the deterioration of the trees and woodlands.
- 7.16.13 Following consideration of the points raised by consultees, the applicant submitted a Woodland Recreational Management Plan (ref. RSE_8239_R2_V2 October 2025) which outlines measures to mitigate the recreational and urban edge pressures on the surrounding Ancient Woodlands. The mitigation measures are split into two categories, on-site and off-site. On-site mitigation measures are those which can be directly controlled, funded and managed by the Applicant (or Management Company) and secured via the LPA via planning condition. Off-site mitigation measures are predominantly for the adjacent Ancient Woodlands and would require indirect funding/securing through a S106 legal agreement.
- 7.16.14 The applicants' preference (Option A) is that the ancient woodland and wider Country Park be managed by an appropriate third party with relevant expertise, funded via S106 contributions. They consider this to be the most logical and robust solution given the sensitivity of the habitats. Notwithstanding, the applicant recognises that agreement has not been reached on this approach (Option A) to date and therefore they agree that it is necessary to build in a fall-back position (Option B) in order that the LPA can be confident that delivery and long-term management are secured irrespective of whether a third-party agreement is ultimately reached.
- 7.16.15 It is proposed that a S106 is drafted to: (1) Keep open the option of transfer to a third party (provide for the woodland and part of the Country Park (and associated commuted sum) to be transferred to the agreed third-party organisation, should agreement be reached at any point up to an agreed trigger (e.g. prior to occupation of a specified number of dwellings) and require any such transfer to be accompanied by an approved Detailed Woodland Recreational Management Plan and Habitat Management and Monitoring Plan, prepared at reserved matters stage) and (2) Specify a clear fall-back to a management company (in the event that no suitable third party is willing or able to take on the land and financial contribution, the default would be for the woodland and Country Park to be retained and managed by an on-site management company, again in accordance with the approved management plans and funded via estate service charges/endowment). It is considered that this would ensure that the mitigation and management framework described in the Woodland Recreational Management Plan is still implemented and monitored over the long term. The Heads of Term to be secured via the S106 Agreement are summarised at 7.20 below and include Option B as discussed above.
- 7.16.16 Subject to appropriate mitigation as discussed above secured via a combination of S106 Agreement and conditions, including: Provision of 24ha green space/country park with

secured management plan/maintenance for the lifetime of the development; Minimum 30m buffer zone around ancient woodland within and adjacent to the proposed development; An Ancient Woodland recreational management plan (to include a planting plan including species selection; lighting strategy; details of information packs for residents on sensitive use of local habitats/protected sites); A Construction Environment Management Plan for both construction and operational measures woodland management plan, it is considered that the proposal development would accord with the NPPF, specifically Paragraph 193(c) as it would not result in the lost or deterioration of irreplaceable habitats. Similarly, the development would, subject to conditions, accord with Policy DM6 of the Development Management Policies LDD (adopted July 2013) as existing trees would be retained; enhanced landscaping would be provided (as indicated on illustrative landscaping strategy but to be secured in detail at Reserved Matters stage); and there would be no loss or deterioration to protected woodland or protected trees.

7.17 Energy Efficiency

- 7.17.1 Paragraph 161 of the NPPF states that “The planning system should support the transition to a low carbon future in a changing climate, taking full account of flood risk and coastal change. It should help to: shape places in ways that contribute to radical reductions in greenhouse gas emissions, minimise vulnerability and improve resilience; encourage the reuse of existing resources, including the conversion of existing buildings; and support renewable and low carbon energy and associated infrastructure”.
- 7.17.2 Policy CP1 of the Core Strategy requires the submission of an Energy and Sustainability Statement demonstrating the extent to which sustainability principles have been incorporated into the location, design, construction and future use of proposals and the expected carbon emissions.
- 7.17.3 Policy DM4 of the DMLDD requires applicants to demonstrate that development will produce 5% less carbon dioxide emissions than Building Regulations Part L (2013) requirements having regard to feasibility and viability. This may be achieved through a combination of energy efficiency measures, incorporation of on-site low carbon and renewable technologies, connection to a local, decentralised, renewable or low carbon energy supply. The policy states that from 2016, applicants will be required to demonstrate that new residential development will be zero carbon. However, the Government has announced that it is not pursuing zero carbon and the standard remains that development should produce 5% less carbon dioxide emissions than Building Regulations Part L (2013) requirements having regard to feasibility and viability.
- 7.17.4 Policy 12 of the Sarratt Neighbourhood Plan (adopted 2025) relates to Renewable Energy and states that development proposals are encouraged to achieve the highest standards of sustainability, decarbonisation and energy efficiency.
- 7.17.5 The application is accompanied by an Energy Statement (Greengage, December 2024). This sets out that the proposed development is predicted to exceed Part L 2021 carbon emission reduction requirements. Key aspects of the strategy include:
- Prioritisation of high-performance building fabric to significantly reduce energy demand.
 - Implementation of low-carbon heating solutions using heat pumps for all buildings within the development.
 - Adoption of an all-electric strategy, eliminating reliance on fossil fuel based systems.
 - Maximisation of onsite renewable energy generation through installation of roof mounted photovoltaic (PV) panels.
- 7.17.6 As this application does not seek approval for the appearance or layout of the proposed buildings, any future Reserved Matters submission would provide full details of the energy

efficiency of the proposed buildings and demonstrate their ability to comply with Policy DM4, however, the submitted details demonstrate that consideration has been given to sustainability, decarbonisation and energy efficiency at outline stage and illustrate how the development would exceed the requirements of Policy DM4. The Energy Statement is also considered to closely align with the Council's Climate Change and Sustainability Strategy, contributing to the target of achieving net zero carbon emissions by 2045.

7.18 Refuse and Recycling

7.18.1 Policy DM10 (Waste Management) of the DMLDD advises that the Council will ensure that there is adequate provision for the storage and recycling of waste and that these facilities are fully integrated into design proposals. New developments will only be supported where:

- i) The siting or design of waste/recycling areas would not result in any adverse impact to residential or work place amenity
- ii) Waste/recycling areas can be easily accessed (and moved) by occupiers and by local authority/private waste providers
- iii) There would be no obstruction of pedestrian, cyclists or driver site lines

7.18.2 The County Council's adopted waste planning documents reflect Government policy which seeks to ensure that all planning authorities taken responsibility for waste management. This includes ensuring that development makes sufficient provision for waste management and promotes good design to secure the integration of waste management facilities with the rest of the development and ensuring that the handling of waste arising from the construction and operation of development maximises reuse/recovery opportunities, and minimises off-site disposal.

7.18.3 HCC would therefore require a Site Waste Management Plan (SWMP) to be submitted which should aim to reduce the amount of waste produced on site. Through a S106 HCC seek a Waste Service Transfer Station Contribution towards increasing capacity at Waterdale Transfer Station and/or provision serving the development (£63,947 index linked to BCIS 1Q2024).

7.18.4 In relation to minerals, the site falls entirely within the 'Sand and Gravel Belt' as identified in HCC's Minerals Local Plan 2002 – 2016. The Sand and Gravel Belt', is a geological area that spans across the southern part of the county and contains the most concentrated deposits of sand and gravel throughout Hertfordshire.

7.18.5 The county council, as the Minerals Planning Authority, encourage the opportunistic use of these deposits within the developments, should they be found when creating the foundations/footings. Opportunistic use of minerals will reduce the need to transport sand and gravel to the site and make sustainable use of these valuable resources.

7.18.6 In respect of domestic and commercial waste, it is considered that further details regarding the storage and management of waste on site would be considered at the reserved matters stage.

7.19 Safety and Security

7.19.1 Policy CP12 of the Core Strategy advises that all development in Three Rivers will contribute to the sustainability of the District. This means taking into account the need to, for example promote buildings and public spaces that reduce opportunities for crime and anti-social behaviour. Policy CP12 also requires that development proposals design out opportunities for crime and anti-social behaviour through the incorporation of appropriate measures to minimise the risk of crime and create safe and attractive places.

7.19.2 The Designing Out Crime Officer at Hertfordshire Constabulary has confirmed that they are able to support this application as they are satisfied that security measures have been considered and will be implemented for this development.

7.20 Infrastructure Contributions

7.20.1 Policy CP8 of the Core Strategy requires development to make adequate contribution to infrastructure and services. The Three Rivers Community Infrastructure Levy (CIL) Charging Schedule sets out that the charge per sqm of residential development in this area is £180 (plus indexation).

7.20.2 In order to make the proposals acceptable, a number of Heads of Term are required to be secured via a S106 Agreement. These are set out in the relevant sections of the analysis above, however, are summarised for ease of reference in the table below:

Authority	Reason	Amount
HCC GIU	Primary Education Contribution - delivery of a new 1FE (up to 2FE land) primary school in the area and/or provision serving the development.	£5,883,141 which has a land cost of £10,530 deducted index linked to BCIS 1Q2024, and appropriate transfer of land for education provision.
HCC GIU	Secondary Education Contribution - towards the expansion of a Secondary School in the area and/or provision serving the development.	£4,376,834 index linked to BCIS 1Q2024
HCC GIU	SEND Contribution - towards new Severe Learning Difficulty (SLD) special school places (WEST) and/or provision serving the development.	£784,006 index linked to BCIS 1Q2024
HCC GIU	Children's Home.	Construction of a 5-bedroom property for children's social care and supported living (Use Class C3(b)) and associated transfer of building/land.
HCC GIU	Waste Service Transfer Station Contribution towards increasing capacity at Waterdale Transfer Station and/or	£63,947 index linked to BCIS 3Q2024

	provision serving the development.	
HCC GIU	HCC Monitoring Fees.	These will be based on the number of triggers within each legal agreement with each distinct trigger point attracting a charge of £420 (adjusted for inflation against RPI Jan 2024).
HCC Highways	Strand 1 Contributions (direct site specific)	
	Dedicated Bus Service	New half-hourly service (Watford/Rickmansworth) £1,955,000 Financial contribution Paid annually for five years (£391,000 per year)
	Rousebarn Lane Upgrade	From Little Green Lane to Gade Avenue £25,000
	LCWIP Contribution	Watford & Three Rivers Route 2 improvements £15,000
	Beryl Bikes	Expansion and docking station provision £45,000
	Travel Plan Evaluation	HCC Evaluation Fee £8,862
	Travel Vouchers and Car Share	Based on TA: 6 x 4-week passes (Arriva All Zone) per unit* £511,200
HCC Highways	Strand 2 Contributions (cumulative impacts)	£1,586,538 – Figure attached to LCWIP schemes supporting active travel links to the development to facilitate delivery and enhancement of necessary active and sustainable travel networks and improving the walking and cycling network. Note: works including the delivery of 20mph speed limit, inclusive of on-street cycling measures, bus stop upgrades/installation, site access and vegetation clearance are likely developer funded/delivered works to be secured by S278 agreement.
HWW ICB	Medical Centre (to address the impact of the new development on Grand Union PCN).	Medical Centre built to 'shell' and financial contribution of £1.85 million towards 'fit out'.
HWW ICB	Mental Health costs (to address the impact of new development, and the additional residents on mental healthcare)	600 dwellings x £338.92 per dwelling = £203,352.
HWW ICB	Community Healthcare costs (to address the	600 dwellings x £352.68 per dwelling = £211,608.

	impact of new development, and the additional residents on community healthcare)	
TfL	A financial contribution towards the delivery of step-free access at Croxley Underground Station.	A financial contribution of £1,065,000 towards the delivery of step-free access at Croxley Underground Station.
TRDC	Affordable Housing	A total of 50% (up to 300) dwellings to be provided as affordable housing, comprising 70% for Rent (of which 70% should be for Social Rent and 30% for Affordable Rent) and 30% Affordable Home Ownership.
TRDC	Affordable Housing – Monitoring Fee	£673 (full monitoring fee)
TRDC	Biodiversity Net Gain (BNG)	Securing significant on-site BNG enhancements.
TRDC	BNG – Monitoring Fee	£11,610
TRDC	Sports Provision – contribution towards indoor and outdoor provision within the area that is necessary as a consequence of the development.	Natural Grass Pitches £217,169 Adult Football £52,381 Youth Football £70,447 Mini Soccer £20,951 Rugby Union £10,767 Cricket £62,624 Artificial Grass Pitches 3G £117,438 Tennis £21,226 Indoor Swimming Pools £330,488 Sports Halls £273,328 (Not required if minimum specification is included within S106)
TRDC	Sports Provision – minimum specification for sports hall (not required if financial contribution included within S106).	“A community hall building with a minimum of 695 sq. metres (external) floorspace for the community hall building and the minimum internal dimensions for the community hall floorspace of 18x10 metres and an internal clearance height of at least 3.5 metres together with an activity studio with a minimum size of 12x9.1 metres and a minimum clearance height of 3.5 metres. The design of the flooring, walls, windows, ceiling, lighting, and ventilation for both the community hall and activity studio, as well as the provision of ancillary toilets and storage facilities, shall accord with Sport England’s Village and Community Halls Design guidance <a 455="" 561="" 933="" 955"="" data-label="Page-Footer" href="https://www.sportengland.org/guidance-and-support/facilities-and-planning/design-and-cost-guidance/sports-halls.”</p> </td></tr> <tr> <td>TRDC</td><td>Sports Provision – Monitoring Fee</td><td> <p>£380 / 2 = £190</p> <p>(NB. Where an obligation secures more than one category of works, a fee is payable for each category. The full monitoring fee is payable</p> </td></tr> </table> </div> <div data-bbox="> Page 61

		for the largest fee category, and 50% of the monitoring fee for any subsequent categories).
TRDC	Country Park and Woodland Management	(1) Keep open the option of transfer to a third party (provide for the woodland and part of the Country Park (and associated commuted sum) to be transferred to the agreed third-party organisation, should agreement be reached at any point up to an agreed trigger (e.g. prior to occupation of a specified number of dwellings) and require any such transfer to be accompanied by an approved Detailed Woodland Recreational Management Plan and Habitat Management and Monitoring Plan, prepared at reserved matters stage) <u>and</u> (2) Specify a clear fall-back to a management company (in the event that no suitable third party is willing or able to take on the land and financial contribution, the default would be for the woodland and Country Park to be retained and managed by an on-site management company, again in accordance with the approved management plans and funded via estate service charges/endowment).
TRDC	Country Park and Woodland Management – Monitoring Fee	£380 / 2 = £190 (NB. Where an obligation secures more than one category of works, a fee is payable for each category. The full monitoring fee is payable for the largest fee category, and 50% of the monitoring fee for any subsequent categories).

7.20.3 The applicant raises no objection to these requirements and a NPPF 58 complaint S106 agreement to secure the contributions will be progressed.

7.21 Referral to Secretary of State

7.21.1 The Town and Country Planning (Consultation) (England) Direction 2024 requires Local Planning Authorities to consult the Secretary of State before granting planning permission for certain types of development. The purpose of the Direction is to give the Secretary of State an opportunity to consider using the power to call in an application under section 77 of the Town and Country Planning Act 1990. If a planning application is called in, the decision on whether or not to grant planning permission will be taken by the Secretary of State.

7.21.2 Applications required to be referred to the Secretary of State include inappropriate developments in the Green Belt that by reason of their scale or nature or location would have a significant impact on the openness of the Green Belt. Whilst officers consider the site to be Grey Belt and therefore not inappropriate in the Green Belt, in the event that Members conclude that the development subject of this application is acceptable although contrary to the Development Plan, or that very special circumstances exist which are considered to outweigh the harm to the Green Belt by inappropriateness and any other harm, it would be necessary for the LPA to consult the Secretary of State prior to a decision being issued.

7.21.3 It is also noted that the Town and Country Planning (Consultation) (England) Direction 2024 (published January 2024) requires Local Planning Authorities in England to consult the Secretary of State before granting planning permission for certain types of development,

including development that affects ancient woodland where the Local Planning Authority considers that the potential adverse impacts cannot be mitigated. As set out above at 7.16 officers consider that any adverse impacts can be mitigated and are therefore not recommending referral on this basis.

7.22 Planning Balances: Issues for consideration

7.22.1 As part of the decision making process, there are various planning balances that must be undertaken by the decision maker.

7.22.2 Very special circumstances: As set out in the analysis above, officers consider that the site is Grey Belt and accords with clauses (a) – (d) of Paragraph 155 of the NPPF. As such, it is considered that the development is an appropriate form of development in the Green Belt. However, if members consider that the site is not located within the Grey Belt and/or doesn't comply with clauses (a) – (d) of Paragraph 155 and therefore is inappropriate development, then regard must be had to Paragraph 153 of the NPPF which states the following:

Inappropriate development is, by definition, harmful to the Green Belt and should not be approved except in very special circumstances. 'Very special circumstances' will not exist unless the potential harm to the Green Belt by reason of inappropriateness, and any other harm resulting from the proposal, is clearly outweighed by other considerations.

7.22.3 Members would therefore need to consider whether there are very special circumstances which outweigh the harm to the Green Belt and any other identified harm.

7.22.4 Heritage Public Benefits test: The proposal is considered to result in less than substantial harm (low – mid level and low level respectively) to the setting of the Grade II Listed Durrants House and the Grade II Registered Cassiobury Park. The NPPF advises that where a development proposal will lead to less than substantial harm to the significance of a designated heritage asset, this harm should be weighed against the public benefits of the proposal. When considering the impact of a proposed development on the significance of a designated heritage asset, great weight should be given to the asset's conservation, irrespective of whether any potential harm amounts to substantial harm, total loss or less than substantial harm to its significance.

7.22.5 Other harm: There would be localised harm to the landscape as set out at 7.2 above, contrary to policy, however, harmful effects would diminish over time as landscaping becomes established.

7.22.6 The harm to the significance of designated heritage assets must also be weighed against the public benefits of the proposal, with great weight given to the asset's conservation.

7.22.7 Whilst the site has been found to be Grey Belt and compliant with NPPF Paragraphs 155-156, as other harm (landscape harm) has been identified, regard must be had to the tilted balance. In respect of the tilted balance, the Council can only demonstrate a 1.7 year housing land supply. As a result, the policies that are most important for determining the application are deemed to be 'out of date' and the tilted balance at Paragraph 11 of the NPPF applies:

7.22.8 For decision-taking this means:

d) where there are no relevant development plan policies, or the policies which are most important for determining the application are out-of-date, granting permission unless:

i. the application of policies in this Framework that protect areas or assets of particular importance provides a strong reason for refusing the development proposed; or

ii. any adverse impacts of doing so would significantly and demonstrably outweigh the benefits, when assessed against the policies in this Framework taken as a whole, having particular regard to key policies for directing development to sustainable locations, making effective use of land, securing well-designed places and providing affordable homes, individually or in combination.

7.22.9 The following material planning considerations would need to be considered. Officers have noted the weight they consider should be attached to each consideration, either Significant, Moderate or Limited.

7.22.10 The need for Housing: The Council is unable to demonstrate a five year land housing supply and is only able to demonstrate a 1.7 year housing land supply. As such, there is a significant need for housing within the district. The scheme would deliver up to 600 residential dwellings and therefore would contribute to the housing supply. As noted by colleagues within the Planning Policy Team; *"The delivery of up to 600 dwellings would make a significant and positive contribution to much needed housing provision within the District"*.

7.22.11 The significant need for housing in the District has been afforded significant weight in recent appeals. For example, in allowing the appeal for the erection of 83 new dwellings and 9 dwellings at Church Lane in Sarratt (LPA refs. 22/0601/OUT and 22/0602/OUT), the Inspector made the following comments in respect of the need for housing:

94. The current five year housing supply situation is pressing and acute. The very great need for housing is persistently going unmet. The existing development plan is simply not delivering anywhere near the requisite amount of housing of all types. The Council accepts that the need cannot be purely met within the existing settlement boundaries and that significant Green Belt land will need to be built on to meet this unmet need. These circumstances mean inevitable adverse consequences for the openness of the Green Belt, its purposes and in terms of landscape and visual effects. I consider a plan led approach to development is certainly desirable, but in this instance, there seems little prospect of a timely plan led remedy. The overwhelming deficiency in the five year housing supply needs to be addressed as a matter of urgency rather than waiting for the adoption of a new local plan.....

100. However, the Council cannot demonstrate a five year supply of housing, and so the most important development policies are deemed out of date. It is quite clear that the strict application of these policies, especially 'place-shaping' or spatial policies such as Policy PSP4, as well as Policy CP4 on affordable housing, is not leading to sufficient housing of all types being provided in accordance with the Framework, and are restricting development. The overwhelming lack of supply diminishes the weight that can be attached to any conflict with these policies. The demonstration of very special circumstances amounts to powerful material considerations justifying departing from the development plan.

101. The severe housing shortfall attracts very substantial weight in favour of granting permissions for the proposals, unless any adverse impacts of doing so would significantly and demonstrably outweigh the benefits, when assessed against the policies in this Framework taken as a whole. I am satisfied that none of the reasons put forward for opposing these proposals establishes that the harm would significantly and demonstrably outweigh the benefits. Therefore, notwithstanding any conflict with development plan policies, it follows that both appeals should succeed, subject to conditions. I deal with the conditions below.

7.22.12 Furthermore, in determining an appeal for Alpine Press, Station Road, Kings Langley for 36 flats (LPA ref. 22/2025/FUL), the Inspector found that there would be harm to the character

of the area but considered that significant weight should be afforded to the need for housing stating:

17. The proposed development would cause harm to the street scene resulting in conflict with the development plan as a whole. However, I give moderate weight to this conflict as set out above.

18. The Council is not currently able to demonstrate a five-year supply of deliverable housing sites with its Housing Supply Update (2022) identifying that the Council had a supply of 1.9 years, and a Housing Delivery Test figure (2022) of 46%. The plan-led system is embedded in planning law, with the Framework placing great emphasis on the engagement of communities in shaping development plans. This is intended to provide certainty. However, it also means that to meet community requirements for homes, jobs and other facilities, development plans must be up to date. In situations such as this, where future housing needs are not being met, the Framework sets out that the policies which are most important for determining the application, in this case Policy CP 12 of the CS and Policy DM1 and Appendix 2 of the DMP, are out of date. Specifically, this means that the presumption in favour of sustainable development set out in paragraph 11d) of the Framework is engaged.

19. The government places considerable importance on making effective use of land to boost the supply of housing, including specifically on previously developed land and in locations with good access to services and facilities, such as the appeal site, which is immediately adjacent to the railway station.

20. Cumulatively, these benefits would significantly and demonstrably outweigh the modest adverse impacts on the street scene. Therefore, the presumption in favour of sustainable development applies and paragraph 11 d) indicates that permission should be granted. There are no other material considerations to override this finding.

- 7.22.13 As such it is considered by officers that the need for housing within Three Rivers should be afforded **Significant Weight** in the decision-making process.
- 7.22.14 The need for Affordable Housing: The proposed development would deliver 50% affordable housing. There is a pressing need for affordable housing within the District. The affordable housing would comprise 300 dwellings, with 70% for Rent (of which 70% is Social Rent and 30% is Affordable Rent) and 30% Affordable Home Ownership (eg. Shared Ownership).
- 7.22.15 The proposed development would exceed the requirements of Policy CP4 of the Core Strategy (adopted October 2011) and Policy 5.1 of the Sarratt Neighbourhood Plan (adopted 2025) in terms of the overall percentage of affordable housing provided, providing an additional 30 affordable units over that required by Policy CP4. The affordable housing would all be provided on site and would be tenure blind. The tenure mix would not strictly accord with these policies, with the inclusion of an element of Affordable Rent. However, overall, 70% (210 units) would be provided as a Rented product with an additional 30% (63 units) as Affordable Home Ownership (eg. Shared Ownership) in accordance with the Emerging Local Plan and the tenure mix is supported by TRDC Housing Services.
- 7.22.16 It is considered by officers that the need for affordable housing within Three Rivers should be afforded **Significant Weight** in the decision-making process.
- 7.22.17 Compliance with the 'Golden Rules': Paragraph 158 of the NPPF sets out that 'a development which complies with the Golden Rules should be given significant weight in favour of the grant of permission'. As set out above (paragraph 7.1.40 – 7.1.45), it is considered that the development would comply with the 'Golden Rules'.
- 7.22.18 As per Paragraph 158 of the NPPF, officers consider that compliance with the Golden Rules should be afforded **Significant Weight** in the decision-making process.

- 7.22.19 Provision of Supported Living for Vulnerable Children: The application includes a 5 bedroom property to be built for children's social care. HCC welcome and supports the inclusion of a children's home on the site.
- 7.22.20 Whilst the need for supported living is recognised, in view of the fact that the proposal would include 1 property for this purpose, officers consider that provision of supported living for vulnerable children should be afforded **Moderate Weight** in the decision-making process.
- 7.22.21 A New 1FE Primary School with expansion land for 2FE: The proposed development includes provision of land for a new one form entry primary school in partnership with HCC with capacity for future expansion land if required.
- 7.22.22 HCC are supportive of the proposals. The proposed 1FE primary school is intended to serve the new development directly, ensuring that the pupil yield generated by the site is met without placing additional pressure on existing schools. The proposed expansion land for 2FE would also assist in accommodating future growth.
- 7.22.23 It is considered by officers that the provision of a new 1FE Primary School with expansion land for 2FE should be afforded **Significant Weight** in the decision-making process.
- 7.22.24 Provision for NHS health and social care services: The application includes provision for NHS health and social care services (Use Class E(e)). The Hertfordshire and West Essex Integrated Care Board (HWE ICB) recognise that there is a clear need to address primary healthcare provision in Croxley Green. They comment that a new medical facility within this development would allow the co-location of New Road, Baldwins Lane and Sarratt branch surgery to a new, purpose-built premises in line with the needs of a modern General Practice. The HWE ICB are therefore supportive in principle to a new medical centre. The HWE ICB note that the applicant has agreed to build the 'shell' of the medical facility, with the 'fit out' funded by a combination of a financial contribution from the developer (£1.85 million) and CIL. The HWE ICB is also seeking financial contributions for community (£211,608) and mental healthcare (£203,352). It is considered by officers that provision for NHS health and social care services should be afforded **Significant Weight** in the decision-making process.
- 7.22.25 Provision of Local Centre (Retail, Café and Community Building): The proposed development provides floorspace for a community hub and local centre facilities across Use Classes E(a), E(b), E(e) and F2(b). The Local Centre Capacity Statement concludes that the proposed local centre seeks to meet the needs that arise from the proposed development and the wider local area.
- 7.22.26 It is considered by officers that the provision of Local Centre (Retail, Café and Community Building) to serve the proposed development and wider local area should be afforded **Moderate Weight** in the decision-making process.
- 7.22.27 Provision of Sports Facilities and Play: The proposed development will deliver a range of multifunctional green spaces, providing opportunities for children's play, recreation paths and biodiversity enhancement. Equipped play areas are incorporated into the scheme with other informal open spaces around the site designed to allow for informal play and exploration.
- 7.22.28 The level of provision would exceed that required to serve the development itself and it is considered by officers that such provision should be afforded **Moderate Weight** in the decision-making process.
- 7.22.29 Low Carbon Development: Through a range of measures including sustainable design and construction, the development will seek to maximise energy efficiency in order to reduce energy consumption and achieve high levels of sustainability. The proposals will include air source heat pumps to all new homes and will reduce carbon dioxide emissions by 78kg per

year which demonstrates a 37% reduction, significantly exceeding the Councils target of 5%.

- 7.22.30 It is considered by officers that low carbon development should be afforded **Moderate Weight** in the decision-making process.
- 7.22.31 New Public Open Space and Country Park: The current site is privately owned with limited public access restricted to one public right of way. The proposals would retain the existing public right of way across the site, maintaining an east to west connection, however, would open up a large proportion (approximately 60%) of the site as green infrastructure and publicly accessible open space. This would significantly exceed the 10% policy requirement.
- 7.22.32 It is considered by officers that the provision of new Public Open Space and Country Park should be afforded **Significant Weight** in the decision-making process.
- 7.22.33 Biodiversity Net Gain (BNG): The development would result in a 34.41% increase in habitat units and 42.54% increase in hedgerow units. There is a legal requirement for a minimum BNG of 10%. It is considered by officers that the exceedance of 10% BNG should be afforded **Moderate Weight** in the decision-making process.
- 7.22.34 Delivery of Sustainable and Active Travel Options and a New Bus Service: A package of sustainable transport initiatives is proposed, primarily focussing on encouraging alternatives to private car use to maximise the need for extensive new traffic infrastructure. It is proposed to provide Beryl Bikes docking stations on site. It is proposed to introduce a dedicated bus service within and surrounding the site, including to key destinations such as Rickmansworth, Watford Station, Croxley Station, and Watford Junction. Similarly, a seasonal bus pass would be provided to each dwelling on initial occupation.
- 7.22.35 It is considered by officers that delivery of Sustainable and Active Travel Options and a New Bus Service should be afforded **Moderate Weight** in the decision-making process.
- 7.22.36 Economic Benefits: The applicant has advised that the development would result in the creation of 930 FTE jobs during the construction period. After occupation, new residents (with an estimated spending power of £17.7 million per annum) will support the vitality of the economy, generating demand and support for the range of services within Croxley Green. There will also be increased revenues for the Local Authority.
- 7.22.37 Officers acknowledge that the development would generate economic benefits both short term during the construction phase and during the lifetime of the scheme as it would create investment locally. It is officers view that this should be afforded **Moderate Weight** in the decision-making process.
- 7.22.38 Summary of Benefits: The identified benefits and their weight are summarised in the table below.

<u>Benefit</u>	<u>Weight in Support</u>
The need for Housing	Significant
The need for Affordable Housing	Significant
Compliance with the 'Golden Rules'	Significant
A New 1FE Primary School with expansion land for 2FE	Significant
New Public Open Space and Country Park	Significant
Provision for NHS health and social care services:	Significant

Provision of Supported Living for Vulnerable Children	Moderate
Provision of Local Centre (Retail, Café and Community Building):	Moderate
Provision of Sports Facilities and Play	Moderate
Low Carbon Development	Moderate
Biodiversity Net Gain (BNG):	Moderate
Delivery of Sustainable and Active Travel Options and a New Bus Service	Moderate
Economic Benefits	Moderate

7.22.39 **Conclusion:** The substantial public benefits of the proposal are considered to outweigh the less than substantial harm to the heritage asset. Similarly, having regard to the tilted balance, any adverse impacts of the development are significantly and demonstrably outweighed by the benefits identified above.

7.22.40 Whilst officers consider the site Grey Belt and accords with clauses (a) – (d) of Paragraph 155 of the NPPF, having regard to the above, it is the view of officers that all the above considerations would amount to very special circumstances which would outweigh any harm identified to the Green Belt and any other harm.

8 Recommendation

8.1 The APPLICATION BE DELEGATED TO THE HEAD OF REGULATORY SERVICES TO GRANT PLANNING PERMISSION 24/2073/OUT following the completion of a S106 Agreement to secure the Heads of Term set out at section 7.20 and subject to the conditions set out below:

C1 Reserved Matters – Details (TRDC)

Details of the appearance, landscaping, layout, and scale, (hereinafter called "the reserved matters") shall be submitted to and approved in writing by the Local Planning Authority before any development begins and the development shall be carried out as approved.

Reason: To prevent the accumulation of unimplemented planning permissions, to enable the Local Planning Authority to review the suitability of the development in the light of altered circumstances and to comply with the provisions of Section 92(2) of the Town and Country Planning Act 1990 as amended by the Planning and Compulsory Purchase Act 2004.

C2 Time Limit – Submission of Reserved Matters (TRDC)

Any application for approval of the reserved matters shall be made to the Local Planning Authority before the expiration of three years from the date of this permission.

Reason: In pursuance of Section 92(2) of the Town and Country Planning Act 1990 and as amended by the Planning and Compulsory Purchase Act 2004.

C3 Time Limit – Commencement (TRDC)

The development hereby permitted shall commence before the expiration of two years from the date of approval of the last of the reserved matters to be approved.

Reason: In pursuance of Section 92(2) of the Town and Country Planning Act 1990 and as amended by the Planning and Compulsory Purchase Act 2004.

C4 Plans – Detailed Element (TRDC)

The accesses hereby permitted shall be carried out in accordance with the following approved plans: T24544.001 Rev E, T24544.002 Rev D, T24544.003 Rev F, T24544.004 Rev B, T24544.005 Rev C.

Reason: In the interests of highway safety in accordance with Policies CP1, CP10 and CP12 of the Core Strategy (adopted October 2011).

C5 Parameter Plans (TRDC)

The reserved matters application(s) pursuant to this permission shall be made in general accordance with the approved plans and supporting documents as listed below:

Land Use Parameter Plan (P24-1200_DE_0014_S1_Rev F)
Indicative Building Heights (P24-1200_DE_0016_S1_Rev B)
Indicative Street Hierarchy (P24-1200_DE_0023_S1)
Indicative Placemaking (P24-1200_DE_0024_S1)

Reason: In the interests of the visual amenities of the Green Belt and locality in accordance with Policies CP1, CP2, CP3, CP4, CP6, CP7, CP8, CP9, CP10, CP11 and CP12 of the Core Strategy (adopted October 2011), Policies DM1, DM2, DM3, DM4, DM6, DM7, DM8, DM9, DM10, DM11, DM12 and DM13 and Appendices 2 and 5 of the Development Management Policies LDD (adopted July 2013) and Policies 2, 4, 5, 6, 7, 8, 9, 10 and 12 of the Sarratt Neighbourhood Plan (adopted 2025).

C6 Design Code (TRDC)

The reserved matters application(s) pursuant to this permission shall be made in strict accordance with the Design Code (Revision C, October 2025).

Reason: In the interests of the visual amenities of the Green Belt and locality in accordance with Policies CP1, CP2, CP3, CP4, CP6, CP7, CP8, CP9, CP10, CP11 and CP12 of the Core Strategy (adopted October 2011), Policies DM1, DM2, DM3, DM4, DM6, DM7, DM8, DM9, DM10, DM11, DM12 and DM13 and Appendices 2 and 5 of the Development Management Policies LDD (adopted July 2013) and Policies 2, 4, 5, 6, 7, 8, 9, 10 and 12 of the Sarratt Neighbourhood Plan (adopted 2025).

Pre-commencement conditions

C7 Standard Estate Road Condition (HCC Highways)

No development shall commence until full details have been submitted to and approved in writing by the Local Planning Authority in relation to the proposed arrangements for future management and maintenance of the proposed streets within the development. The streets shall thereafter be maintained in accordance with the approved management and maintenance details until such time as an agreement has been entered into under Section 38 of the Highways Act 1980 or a Private Management and Maintenance Company has been established.

Reason: To ensure satisfactory development and to ensure estate roads are managed and maintained thereafter to a suitable and safe standard in accordance with Policies 5 and 22 of Hertfordshire's Local Transport Plan (adopted 2018) and Policy CP10 of the Core Strategy (adopted October 2011).

C8 Standard Highway Condition (HCC Highways)

No development shall commence until full details (in the form of scaled plans and / or written specifications) have been submitted to and approved in writing by the Local Planning Authority to illustrate the following:

- i) Roads, footways.
- ii) Cycleways.
- iii) Foul and surface water drainage.
- iv) Visibility splays.
- v) Access arrangements.
- vi) Parking provision in accordance with adopted standard.
- vii) Loading areas.
- viii) Turning areas.

The development shall thereafter be constructed in accordance with the approved details.

Reason: To ensure suitable, safe and satisfactory planning and development of the site in accordance with Policy 5 of Hertfordshire's Local Transport Plan (adopted 2018) and Policy CP10 of the Core Strategy (adopted October 2011).

C9 Construction Management Plan (HCC Highways)

No development shall commence until a Construction Management Plan (or Construction Method Statement) has been submitted to and approved in writing by the Local Planning Authority. Thereafter the construction of the development shall only be carried out in accordance with the approved Plan. The Construction Management Plan / Statement shall include details of

- a. Construction vehicle numbers, type, routing;
- b. Access arrangements to the site;
- c. Traffic management requirements;
- d. Construction and storage compounds (including areas designated for car parking, loading / unloading and turning areas);
- e. Siting and details of wheel washing facilities;
- f. Cleaning of site entrances, site tracks and the adjacent public highway;
- g. Timing of construction activities (including delivery times and removal of waste) and to avoid school pick up/drop off times;
- h. Provision of sufficient on-site parking prior to commencement of construction activities;
- i. Post construction restoration/reinstatement of the working areas and temporary access to the public highway;
- j. where works cannot be contained wholly within the site a plan should be submitted showing the site layout on the highway including extent of hoarding, pedestrian routes and remaining road width for vehicle movements.

Reason: In order to protect highway safety and the amenity of other users of the public highway and rights of way in accordance with Policies 5, 12, 17 and 22 of Hertfordshire's Local Transport Plan (adopted 2018) and Policy CP10 of the Core Strategy (adopted October 2011).

C10 Infrastructure (Active Travel England)

No development shall commence until general arrangement plan(s) to a scale of 1:200 showing details of the walking / cycling infrastructure including works to the adopted highway have been submitted to and approved in writing by the Local Planning Authority. The details shall be submitted in accordance with guidance contained in LTN 1/20 on Cycle Infrastructure Design and Manual for Streets and where applicable indicate proposals for:

- Existing levels of the finished highway tying into building threshold levels

- Alterations to waiting restrictions or other Traffic Regulation Orders to enable the works
- Signing, street furniture, street trees and pits
- Structures on or adjacent to the highway
- Extent of any stopping up, diversion or dedication of new highway (including all public rights of way shown on the definitive map and statement)

The development or any phase of the development, whichever is the sooner, shall not be occupied until the walking and cycling infrastructure for the development or phase of development has been constructed and completed in accordance with the approved details.

Reason: To comply with Policy CP10 of the Core Strategy (adopted October 2011) and the guidance in LTN 1/20 on Cycle Infrastructure Design and in Manual for Streets.

C11 Dust Management Plan (Watford Environmental Health)

Prior to the commencement of the development hereby permitted, a Dust Management Plan shall be submitted for the written approval of the Local Planning Authority. The Dust Management Plan shall include best practicable means to be incorporated to minimise dust caused by the permitted operations and to prevent the emission of dust from the site and should incorporate the mitigation measures presented in Section 5.14 of the Air Quality Assessment ((BWB, December 2024, 233574-01-AQA). The management of dust emissions shall thereafter be carried out in accordance with the approved plan.

Reason: This is a pre-commencement condition in the interests of the amenities of surrounding occupiers during the construction of the development and to meet the requirements of Policy CP12 of the Core Strategy (adopted October 2011) and Policy DM9 of the Development Management Policies LDD (adopted July 2013).

C12 Contamination – Remediation (Watford Environmental Health)

Prior to the commencement of development approved by this planning permission, the following components of a scheme to deal with the risks associated with contamination of the site shall each be submitted to and approved, in writing, by the Local Planning Authority:

- i) A preliminary risk assessment which has identified:
 - all previous uses
 - potential contaminants associated with those uses
 - a conceptual model of the site indicating sources, pathways and receptors
 - potentially unacceptable risks arising from contamination at the site.
- ii) A site investigation scheme, based on (i) to provide information for a detailed assessment of the risk to all receptors that may be affected, including those off site.
- iii) The site investigation results and the detailed risk assessment (ii) and, based on these, an options appraisal and remediation strategy giving full details of the remediation measures required and how they are to be undertaken.
- iv) A verification plan providing details of the data that will be collected in order to demonstrate that the works set out in (iii) are complete and identifying any requirements for longer term monitoring of pollutant linkages, maintenance and arrangements for contingency action.

The scheme shall be implemented as approved.

Reason: To ensure that risks from land contamination to the future users of the land and neighbouring land are minimised, together with those to controlled waters, property and ecological systems, and to ensure that the development can be carried out safely without unacceptable risks to workers, neighbours and other offsite receptors and to meet the requirements of Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM9 of the Development Management Policies LDD (adopted July 2013).

C13 Active Design Principles (Sport England)

For each parcel/phase of development for which Outline permission is granted, no development in relation to that parcel/phase shall commence until details have been submitted and approved in writing by the Local Planning Authority to demonstrate how Active Design principles have been met.

Reason: To promote healthy lifestyles through physical activity and to accord with Policies DM11 and DM12 of the Development Management Policies LDD (adopted July 2013) and Chapter 8 of the NPPF (2024).

C14 Construction Phase Surface Water Management Plan (LLFA)

No development shall take place until a detailed construction phase surface water management plan for the site has been submitted to and approved in writing by the Local Planning Authority. The scheme shall subsequently be carried out in accordance with the approved details.

Reason: To ensure that the construction of the site does not result in any flooding both on and off site and that all Surface water Drainage features are adequately protected and to meet the requirements of Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM8 of the Development Management Policies LDD (adopted July 2013).

C15 Site Waste Management Plan (SWMP) (HCC)

No development shall take place until a Site Waste Management Plan (SWMP) for the site has been submitted to and approved in writing by the Local Planning Authority. The SWMP should aim to reduce the amount of waste produced on site and should contain information including estimated types and quantities of waste to arise from construction and waste management actions for each waste type. The development shall be carried out in accordance with the approved SWMP.

Reason: To promote the sustainable management of waste arisings and contribution towards resource efficiency, in accordance with Policy 12 of the Hertfordshire Waste Core Strategy, Policies CP1 and CP12 of the Core Strategy (adopted October 2011) and Policy DM10 of the Development Management Policies LDD (adopted July 2013).

C16 Archaeological Written Scheme of Investigation (HCC Historic Environment)

(A) No demolition/development shall take place/commence until an Archaeological Written Scheme of Investigation has been submitted to and approved by the local planning authority in writing. The scheme shall include an assessment of archaeological significance and research questions; and:

1. The programme and methodology of site investigation and recording
2. The programme and methodology of site investigation and recording as required by the evaluation
3. The programme for post investigation assessment
4. Provision to be made for analysis of the site investigation and recording

5. Provision to be made for publication and dissemination of the analysis and records of the site investigation
6. Provision to be made for archive deposition of the analysis and records of the site investigation
7. Nomination of a competent person or persons/organisation to undertake the works set out within the Archaeological Written Scheme of Investigation.

(B) The demolition/development shall take place/commence in accordance with the programme of archaeological works set out in the Written Scheme of Investigation approved under condition (A)

(C) The development shall not be occupied/used until the site investigation and post investigation assessment has been completed in accordance with the programme set out in the Written Scheme of Investigation approved under condition (A) and the provision made for analysis and publication where appropriate.

Reason: This condition is a pre commencement condition to define, in advance of any development commencing, the details of evaluation/mitigation necessary to protect any archaeological remains present within the development site. The significance of heritage assets with archaeological interest can be harmed/destroyed by development. This is in accordance with NPPF guidance, Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM3 of the Development Management Policies LDD (adopted July 2013).

C17 Construction Environment Management Plan (CEMP) (Hertfordshire Ecology & Natural England)

No development shall take place (including demolition, ground works, vegetation clearance) until a Construction Environmental Management Plan (CEMP: Biodiversity) has been submitted to and approved in writing by the Local Planning Authority. The CEMP (Biodiversity) shall include the following.

- Risk assessment of potentially damaging construction activities.
- Buffer zones to be implemented to protect onsite and adjacent habitats.
- All mitigation recommended in the ecology report (RammSanderson, December 2024) for local wildlife sites and habitats (Section 4 to 4.6 in the report).
- Identification of "biodiversity protection zones".
- Practical measures (both physical measures and sensitive working practices) to avoid or reduce impacts during construction (may be provided as a set of method statements).
- The location and timing of sensitive works to avoid harm to biodiversity features.
- The times during construction when specialist ecologists need to be present on site to oversee works.
- Responsible persons and lines of communication.
- The role and responsibilities on site of an ecological clerk of works (ECoW) or similarly competent person.
- Use of protective fences, exclusion barriers and warning signs.

The CEMP shall also include the mitigation in the ecology report for the protected species listed below:

- Reptiles (s4.7 of the report).
- Bats (s4.8 of the report).
- Nesting birds (subsequent to mitigation informed by the red kite breeding surveys).
- Badgers (s4.11; iv precautionary work measures).

The approved CEMP shall be adhered to and implemented throughout the construction period strictly in accordance with the approved details.

Reason: This condition is a pre commencement condition to ensure to ensure that any protected species and habitats are safeguarded and to meet the requirements of Policies CP1, CP9 and CP12 of the Core Strategy (adopted October 2011) and Policy DM6 of the Development Management Policies LDD (adopted July 2013).

C18 Biodiversity Enhancement Plan (Hertfordshire Ecology)

Prior to the commencement of development, a Biodiversity Enhancement Plan shall be submitted to and approved in writing by the Local Planning Authority. The Biodiversity Enhancement Plan shall include the following:

- Installation of one integrated swift brick per dwelling (north facing).
- Installation of one integrated bat box per dwelling (south facing).
- Bat and bird boxes on retained trees.
- Hedgehog highways – one hedgehog hole per garden fence.

The enhancements shall thereafter be implemented in accordance with the approved details prior to the first occupation of the development.

Reason: This condition is a pre commencement condition to maintain wildlife habitat and to meet the requirements of Policies CP1, CP9 and CP12 of the Core Strategy (adopted October 2011) and Policy DM6 of the Development Management Policies LDD (adopted July 2013).

C19 Habitat Management & Monitoring Plan (Herts Ecology)

Prior to the commencement of development hereby permitted, an Overall Habitat Management and Monitoring Plan (“the HMMP”), prepared in accordance with the approved Overall Biodiversity Net Gain Plan, shall be submitted to and approved in writing by the Local Planning Authority. This shall demonstrate how the habitat enhancement and creation, and subsequent target habitat conditions on-site will be created, enhanced, and monitored over 30 years following the completion of the capital works required to create them.

The created and enhanced habitat shall thereafter be managed in accordance with the approved HMMP.

Reason: This is a pre-commencement condition to ensure that the net gain for biodiversity on site is delivered, maintained and managed in the interests of local biodiversity in accordance Schedule 7A of the Town and Country Planning Act 1990 and Policy DM6 of the Development Management Policies LDD (adopted July 2013) and for the purposes of para 9(2) and 9(3) of Schedule 7A of the Town and Country Planning Act 1990.

C20 Badger Survey (Hertfordshire Ecology)

A pre-commencement survey for badgers shall be undertaken prior to the commencement of the development. This survey shall determine whether the current outlier setts are still active and thus require closure, or if any additional setts have been excavated. The results of this badger survey should be submitted to the Local Planning Authority for approval and shall include any mitigation and/or compensation measures required. The development shall be carried out in strict accordance with the approved details.

Reason: This condition is a pre commencement condition to ensure to ensure that protected species are safeguarded and to meet the requirements of Policies CP1,

CP9 and CP12 of the Core Strategy (adopted October 2011) and Policy DM6 of the Development Management Policies LDD (adopted July 2013).

C21 Red Kite Surveys (Hertfordshire Ecology)

Prior to the commencement of development, including vegetation clearance, a nesting bird survey for Red Kites shall be carried out by a suitably qualified and experienced ecologist. A written report shall be produced by the ecologist and submitted to the Local Planning Authority stating whether or not it is likely that Red Kites would be adversely affected by the development proposals hereby permitted.

If the report indicates that Red Kites would be adversely affected, appropriate mitigation measures to safeguard them shall be submitted to and approved in writing by the Local Planning Authority prior to the commencement of any development.

The mitigation measures shall be implemented as approved in accordance with an agreed timetable.

Reason: This is a pre commencement condition in the interests of safeguarding protected species and to meet the requirements of Policies CP1 and CP9 of the Core Strategy (adopted October 2011) and Policy DM6 of the Development Management Policies LDD (adopted July 2013).

C22 Management Plan – Country Park & On-site Ancient Woodland (Green Lane Wood LWS) (TRDC, Landscape Officer, Herts Ecology)

Prior to the commencement of development, a Management Plan for the Country Park and on-site Ancient Woodland for the lifetime of the development, shall be submitted to and approved in writing by the Local Planning Authority. The Management Plan shall outline mitigation measures, monitoring methodology and time frame and the bodies responsibilities for its implementation and any remedial action required. The Management Plan shall include:

- Minimum 30m buffer zone around the Ancient Woodland;
- Ancient Woodland recreation Management Plan;
- Planting plan;
- Lighting plan;
- Details of Information Packs for residents on sensitive use of local habitats/protected sites.

The Country Park and on-site Ancient Woodland shall thereafter be managed in accordance with the approved Management Plan.

Reason: To prevent a reduction in the existing condition of Green Lane Wood LWS and to meet the requirements of Policies CP1 and CP9 of the Core Strategy (adopted October 2011) and Policy DM6 of the Development Management Policies LDD (adopted July 2013).

Prior to any works above slab level

C23 Highway Works to Durrants Drive, Canterbury Way, Dover Way and Links Way – Off-Site (Design Approval, Implementation & Construction) (HCC Highways)

(A) Notwithstanding the details indicated on the submitted drawings no on-site works above slab level shall commence until a detailed scheme for the offsite highway improvement works as indicated by a system of traffic calming measures as identified in Appendix B of the Transport Assessment Addendum Report dated 10/12/2025

including any associated Traffic Regulation Orders required to deliver 20mph speed limit have been submitted to and approved in writing by the Local Planning Authority.

(B) Prior to the first occupation of the development hereby permitted the offsite highway improvement works referred to in Part A of this condition shall be completed in accordance with the approved details.

Reason: To ensure construction of a satisfactory development and that the highway improvement works are designed to an appropriate standard in the interest of highway safety and amenity and in accordance with Policy 5, 13 and 21 of Hertfordshire's Local Transport Plan (adopted 2018) and Policy CP10 of the Core Strategy (adopted October 2011).

C24 New Access – Design Approval / Construction (HCC Highways)

(A) Notwithstanding the details indicated on the submitted drawings no on-site works above slab level shall commence until a detailed scheme for the access and off-site highway improvement works as indicated by Drg No 001 Rev E, Drg No 002 Rev D, Drg 004 Rev B including any associated Traffic Regulation Orders have been submitted to and approved in writing by the Local Planning Authority.

(B) Prior to the first occupation of the development hereby permitted the New Access referred to in Part A of this condition shall be completed in accordance with the approved details.

Reason: To ensure construction of a satisfactory development and that the highway improvement works are designed to an appropriate standard in the interest of highway safety and amenity and in accordance with Policy 5, 13 and 21 of Hertfordshire's Local Transport Plan (adopted 2018) and Policy CP10 of the Core Strategy (adopted October 2011).

Prior to/or in conjunction with Reserved Matters application(s)

C25 Surface Water Drainage – Detailed Design (LLFA)

Prior to or in conjunction with the submission of each reserved matters application, in accordance with the submitted FRA (Flood Risk Assessment, prepared by BWB, 17 December 2024, REF 233574-BWB-ZZ-XX-T-W-0002_FRA REV P04) and Drainage Strategy (Sustainable Drainage Statement, prepared by BWB, 11 December 2024, REF 233574-BWB-ZZ-XX-T-W-0001_SDS REV P01), detailed designs of a surface water drainage scheme incorporating the following measures shall be submitted to and agreed with the Local Planning Authority. The approved scheme will be implemented prior to the first occupation of the development. The scheme shall address the following matters:

- i. Detailed infiltration testing in accordance with BRE Digest 365 (or equivalent) along the length and proposed depth of the proposed infiltration feature/s.
- or
- i. If infiltration is proven to be unfavourable, then Greenfield runoff rates for the site shall be agreed with the Lead Local Flood Authority. The post development runoff rates will be attenuated to the equivalent Greenfield rate for all rainfall events up to and including the 1% Annual Exceedance Probability (AEP). The discharge location for surface water runoff will be confirmed to connect with the wider watercourse network.

- ii. Provision of surface water attenuation storage, sized and designed to accommodate the volume of water generated in all rainfall events up to and including the critical storm duration for the 3.33% AEP (1 in 30 year) and 1% AEP (1 in 100) rainfall events (both including allowances for climate change).
- iii. Detailed designs, modelling calculations and plans of the of the drainage conveyance network in the:
 - 3.33% AEP (1 in 30 year) critical rainfall event plus climate change to show no flooding outside the drainage features on any part of the site.
 - 1% AEP (1 in 100 year) critical rainfall plus climate change event to show, if any, the depth, volume and storage location of any flooding outside the drainage features, ensuring that flooding does not occur in any part of a building or any utility plant susceptible to water (e.g. pumping station or electricity substation) within the development. It will also show that no runoff during this event will leave the site uncontrolled.
- iv. The design of the infiltration basin will incorporate an emergency spillway and any drainage structures include appropriate freeboard allowances. Plans to be submitted showing the routes for the management of exceedance surface water flow routes that minimise the risk to people and property during rainfall events in excess of 1% AEP (1 in 100) rainfall event plus climate change allowance.
- v. Details of how all surface water management features to be designed in accordance with The SuDS Manual (CIRIA C753, 2015), including appropriate treatment stages for water quality prior to discharge.
- vi. A maintenance and management plan detailing the activities required and details of who will adopt and maintain the all the surface water drainage features for the lifetime of the development.

Reason: To prevent flooding in accordance with National Planning Policy Framework paragraphs 181,182 and 187 by ensuring the satisfactory management of local sources of flooding surface water flow paths, storage and disposal of surface water from the site in a range of rainfall events and ensuring the SuDS proposed operates as designed for the lifetime of the development and to meet the requirements of Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM8 of the Development Management Policies LDD (adopted July 2013).

C26 SuDS Phasing Plan (LLFA)

Prior to or in conjunction with the submission of each Reserved Matters application a detailed Site SuDS Phase plan which aligns with the site phasing plan shall be submitted to and approved in writing by the Local Planning Authority. This SuDS Phasing plan shall ensure that each phase does not exceed the agreed discharge rates for that phase and that source control measures are installed within each phase to adequately address the phases own surface water runoff. The plan shall ensure that each SuDS component is adequately protected throughout the development of the scheme. The plan shall show all exceedance routes throughout the site clearance and construction of the scheme ensuring flood risk is not increased elsewhere or to the site itself and that the site remains safe for all exceedance event flow routes for the lifetime of the development during rainfall (i.e. greater than design events or during blockage) and how property on and off site will be protected.

Reason: To ensure that the development achieves a high standard of sustainability and ensure the flood risk is adequately addressed for each new dwelling and not increased in accordance with the NPPF and Policy CP1 of the Core Strategy (adopted

October 2011) and Policy DM8 of the Development Management Policies LDD (adopted July 2013).

C27 GenActive Track (Sport England)

Details of the design of the NewGen Active track, and timetables for the implementation of the facility shall be submitted to the Local Planning Authority for approval with or before the submission of any reserved matters application(s). No development shall commence until those schemes have been approved in writing by the Local Planning Authority, and the facility shall then be delivered in accordance with the approved schemes and thereafter retained.

Reason: To secure well managed safe NewGen Active Track to ensure sufficient benefit to the development of sport and to accord with the Applicants Sports Strategy, Policies DM11 and DM12 of the Development Management Policies LDD (adopted July 2013) and Chapter 8 of the NPPF (2024).

Prior to occupation

C28 Travel Plan (HCC Highways, Active Travel England)

At least 3 months prior to the first occupation / use of the approved development a detailed Travel Plan for the site, based upon the Hertfordshire Council document 'Hertfordshire's Travel Plan Guidance', shall be submitted and approved in writing by the Local Planning Authority. The approved Travel Plan shall be implemented at all times.

Reason: To ensure that sustainable travel options associated with the development are promoted and maximised to be in accordance with Policies 3, 5, 7, 8, 9 and 10 of Hertfordshire's Local Transport Plan (adopted 2018) and Policies CP1, CP10 and CP12 of the Core Strategy (adopted October 2011).

C29 Verification Report - Contamination (Watford Environmental Health)

Following completion of measures identified in the approved remediation scheme and prior to the first use or occupation of the development, a verification report that demonstrates the effectiveness of the remediation carried out must be produced together with any necessary monitoring and maintenance programme and copies of any waste transfer notes relating to exported and imported soils shall be submitted to the Local Planning Authority for approval. The approved monitoring and maintenance programme shall be implemented.

Reason: To ensure that risks from land contamination to the future users of the land and neighbouring land are minimised, together with those to controlled waters, property and ecological systems, and to ensure that the development can be carried out safely without unacceptable risks to workers, neighbours and other offsite receptors and to meet the requirements of Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM9 of the Development Management Policies LDD (adopted July 2013).

C30 Verification Report - Drainage (LLFA)

Prior to first use of each phase of the development a detailed verification report, (appended with substantiating evidence demonstrating the approved construction details and specifications have been implemented in accordance with the surface water drainage scheme), shall be submitted to and approved in writing by the Local Planning Authority.

The verification report shall include a full set of “as built” drawings plus photographs of excavations (including soil profiles/horizons), any installation of any surface water drainage structures and control mechanisms.

Reason: To ensure that the development achieves a high standard of sustainability and ensure the flood risk is adequately addressed for each new dwelling and not increased in accordance with the NPPF and to meet the requirements of Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM9 of the Development Management Policies LDD (adopted July 2013).

C31 Foul Water Network Upgrades (Thames Water)

The development shall not be occupied until confirmation has been provided that either:-

1. All foul water network upgrades required to accommodate the additional flows from the development have been completed; or-
2. A development and infrastructure phasing plan has been agreed with the Local Authority in consultation with Thames Water to allow the development to be occupied.

Where a development and infrastructure phasing plan is agreed, no occupation shall take place other than in accordance with the agreed development and infrastructure phasing plan.

Reason: Network reinforcement works are likely to be required to accommodate the proposed development. Any reinforcement works identified will be necessary in order to avoid sewage flooding and/or potential pollution incidents in accordance with Policy DM9 of the Development Management Policies LDD (adopted July 2013).

C32 Sewage Works Upgrades (Thames Water)

No development shall be occupied until confirmation has been provided that either:-

1. All sewage works upgrades required to accommodate the additional flows from the development have been completed; or
2. A development and infrastructure phasing plan has been agreed with the Local Authority in consultation with Thames Water to allow the development to be occupied.

Where a development and infrastructure phasing plan is agreed no occupation shall take place other than in accordance with the agreed development and infrastructure phasing plan.

Reason: Sewage Treatment Upgrades are likely to be required to accommodate the proposed development. Any upgrade works identified will be necessary in order to avoid sewage flooding and/or potential pollution incidents in accordance with Policy DM9 of the Development Management Policies LDD (adopted July 2013).

C33 Lighting Design Strategy - Bats (Hertfordshire Ecology)

Prior to occupation, a lighting design strategy for bats shall be submitted to and approved in writing by the Local Planning Authority. This should accurately identify the features/areas of interest, describe levels of illumination prior to, during, and post-development, and should be shown in suitable contour plans and charts so that it can be clearly demonstrated that that lit areas will not compromise existing use.

Proposed lighting should accord with best practice (Bats and artificial lighting in the UK, (BCT & ILP) and maintained accordingly. No further external lighting should be added unless agreed with the Local Planning Authority. These proposals should also be accompanied by a statement by an ecologist on how it achieves these goals.

Reason: In the interests of biodiversity and to meet the requirements of Policy CP9 of the Core Strategy (adopted October 2011) and Policy DM6 of the Development Management Policies LDD (adopted July 2013).

Other

C34 Reporting of Unexpected Contamination (Watford Environmental Health)

In the event that contamination is found at any time when carrying out the approved development that was not previously identified it must be reported in writing immediately to the Local Planning Authority. An investigation and risk assessment must be undertaken in accordance with the requirements of Condition 29, and where remediation is necessary a remediation scheme must be prepared in accordance with the requirements of Condition 29, which is subject to the approval in writing of the Local Planning Authority. Following completion of measures identified in the approved remediation scheme a verification report must be prepared, which is subject to the approval in writing of the Local Planning Authority in accordance with Condition 29.

Reason: To ensure that risks from land contamination to the future users of the land and neighbouring land are minimised, together with those to controlled waters, property and ecological systems, and to ensure that the development can be carried out safely without unacceptable risks to workers, neighbours and other offsite receptors and to meet the requirements of Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM9 of the Development Management Policies LDD (adopted July 2013).

C35 Notification that Habitat Management & Monitoring Plan has been implemented (TRDC)

Notice in writing shall be given to the Local Planning Authority when the agreed Habitat Management and Monitoring Plan ("the HMMP") as secured by Condition 19, has been implemented.

Reason: This is to ensure that the Local Planning Authority have knowledge when the habitat enhancement and creation works have been implemented to enable effective monitoring in accordance with Schedule 7A of the Town and Country Planning Act 1990 and Policy DM6 of the Development Management Policies LDD (adopted July 2013).

C36 Compliance – Maintenance of the Habitat Management & Monitoring Plan (TRDC)

The created and / or enhanced habitat specified in the approved HMMP (as secured by Condition 19), shall be managed and maintained in accordance with the approved HMMP for 30 years from the date of first operation of the development.

Reason: To ensure that the created and enhanced habitat is maintained for 30 years from the first operation of the development and can be monitored and enforced by the Local Planning Authority, in accordance with Policy DM6 of the Development Management Policies LDD (adopted July 2013) and for the purposes of para 9(2) and 9(3) of Schedule 7A of the Town and Country Planning Act 1990.

8.2 Informatives:

11 Standard Advice: With regard to implementing this permission, the applicant is advised as follows:

All relevant planning conditions must be discharged prior to the commencement of work. Requests to discharge conditions must be made by formal application which includes a fee.

There may be a requirement for the approved development to comply with the Building Regulations. Please contact Hertfordshire Building Control (HBC) on 01438 879990 or at buildingcontrol@hertfordshirebc.co.uk who will be happy to advise you on building control matters and will protect your interests throughout your build project by leading the compliance process. Further information is available at www.hertfordshirebc.co.uk.

Community Infrastructure Levy (CIL) - Your development may be liable for CIL payments and you are advised to contact the CIL Officer for clarification with regard to this (cil@threerivers.gov.uk). If your development is CIL liable, even if you have been granted exemption from the levy, please be advised that before commencement of any works it is a requirement under Regulation 67 of The Community Infrastructure Levy Regulations 2010 (As Amended) that CIL form 6 (Commencement Notice) must be completed, returned and acknowledged by Three Rivers District Council before building works start. Failure to do so will mean you lose the right to payment by instalments (where applicable), and a surcharge will be imposed. However, please note that a Commencement Notice is not required for residential extensions IF relief has been granted.

Following the grant of planning permission by the Local Planning Authority it is accepted that new issues may arise post determination, which require modification of the approved plans. Please note that regardless of the reason for these changes, where these modifications are fundamental or substantial, a new planning application will need to be submitted. Where less substantial changes are proposed, the following options are available to applicants:

{\b (a)} Making a Non-Material Amendment

{\b (b)} Amending the conditions attached to the planning permission, including seeking to make minor material amendments (otherwise known as a section 73 application).

It is important that any modifications to a planning permission are formalised before works commence otherwise your planning permission may be unlawful and therefore could be subject to enforcement action. In addition, please be aware that changes to a development previously granted by the LPA may affect any previous Community Infrastructure Levy (CIL) owed or exemption granted by the Council. If you are in any doubt whether the new/amended development is now liable for CIL you are advised to contact the Community Infrastructure Levy Officer (01923 776611) for clarification. Information regarding CIL can be found on the Three Rivers website (<https://www.threerivers.gov.uk/services/planning/community-infrastructure-levy>).

Care should be taken during the building works hereby approved to ensure no damage occurs to the verge or footpaths during construction. Vehicles delivering materials to this development shall not override or cause damage to the public footway. Any damage will require to be made good to the satisfaction of the Council and at the applicant's expense.

Where possible, energy saving and water harvesting measures should be incorporated. Any external changes to the building which may be subsequently required should be discussed with the Council's Development Management Section prior to the commencement of work. Further information on how to incorporate changes to reduce your energy and water use is available at: <https://www.threerivers.gov.uk/services/environment-climate-emergency/home-energy-efficiency-sustainable-living#Greening%20your%20home>.

- 12 Hours of Work: The applicant is reminded that the Control of Pollution Act 1974 allows local authorities to restrict construction activity (where work is audible at the site boundary). In Three Rivers such work audible at the site boundary, including deliveries to the site and running of equipment such as generators, should be restricted to 0800 to 1800 Monday to Friday, 0900 to 1300 on Saturdays and not at all on Sundays and Bank Holidays.
- 13 Positive & Proactive: The applicant is reminded that this planning permission is subject to either a unilateral undertaking or an agreement made under the provisions of Section 106 of the Town and Country Planning Act 1990. It is extremely important that the applicant is aware of the stipulations, covenants and obligations set out within any legal agreements tied to the planning permission. This may include the requirement to notify the Council prior to commencement of the development (as defined within the legal agreement) if certain obligations are required to be paid, for example, an affordable housing contribution including indexation.
- 14 Biodiversity Net Gain (BNG): The effect of paragraph 13 of Schedule 7A to the Town and Country Planning Act 1990 is that planning permission granted for the development of land in England is deemed to have been granted subject to the condition "(the biodiversity gain condition)" that development may not begin unless:
- a) a Biodiversity Gain Plan has been submitted to the planning authority, and
 - b) the planning authority has approved the plan.

The planning authority, for the purposes of determining whether to approve a Biodiversity Gain Plan if one is required in respect of this permission would be Three Rivers District Council.

Based on the information available, this permission is considered to be one which will require the approval of a biodiversity gain plan before development is begun because none of the statutory exemptions or transitional arrangements are considered to apply.

Where the local planning authority considers that the permission falls within paragraph 19 of Schedule 7A to the Town and Country Planning Act 1990, the permission which has been granted has the effect of requiring or permitting the development to proceed in phases. The modifications in respect of the biodiversity gain condition which are set out in Part 2 of the Biodiversity Gain (Town and Country Planning) (Modifications and Amendments) (England) Regulations 2024 apply.

Biodiversity gain plans are required to be submitted to, and approved by, the planning authority before development may be begun, and, if subject to phased development, before each phase of development may be begun (Phase Plans).

If the onsite habitat includes irreplaceable habitat (within the meaning of the Biodiversity Gain Requirements (Irreplaceable Habitat) Regulations 2024) there are additional requirements for the content and approval of Biodiversity Gain Plans. The Biodiversity Gain Plan must include, in addition to information about steps taken or to be taken to minimise any adverse effect of the development on the habitat, information on arrangements for compensation for any impact the development has on the biodiversity of the irreplaceable habitat.

The planning authority can only approve a Biodiversity Gain Plan if satisfied that the adverse effect of the development on the biodiversity of the irreplaceable habitat is minimised and appropriate arrangements have been made for the purpose of compensating for any impact which do not include the use of biodiversity credits.

More information can be found in the Planning Practice Guidance online at <https://www.gov.uk/guidance/biodiversity-net-gain>.

- 15 Site Notice Removal: The applicant is hereby advised to remove all site notices on or near the site that were displayed pursuant to the application.
- 16 Sport England Advice 1: Consideration should be given to using the Active Design checklist in Sport England's Active Design Guidance to assess reserved matters planning applications.
- 17 Sport England Advice 2: The applicant is advised that the design and layout of the active track should comply with the relevant industry Technical Design Guidance, including guidance published by Sport England, National Governing Bodies for Sport. Particular attention is drawn to: England Athletics NewGen Tracks guidance.
- 18 Cadent Gas: Cadent Gas Ltd own and operate the gas infrastructure within the area of your development. There may be a legal interest (easements and other rights) in the land that restrict activity in proximity to Cadent assets in private land. The applicant must ensure that the proposed works do not infringe on legal rights of access and or restrictive covenants that exist.

If buildings or structures are proposed directly above the apparatus the development may only take place following diversion of the apparatus. The applicant should apply online to have apparatus diverted in advance of any works, by visiting cadentgas.com/diversions

Prior to carrying out works, including the construction of access points, please register on www.linsearchbeforeudig.co.uk to submit details of the planned works for review, ensuring requirements are adhered to.

- 19 S106 Agreement: The applicant is reminded that this planning permission is subject to either a unilateral undertaking or an agreement made under the provisions of Section 106 of the Town and Country Planning Act 1990. It is extremely important that the applicant is aware of the stipulations, covenants and obligations set out within any legal agreements tied to the planning permission. This may include the requirement to notify the Council prior to commencement of the development (as defined within the legal agreement) if certain obligations are required to be paid, for example, an affordable housing contribution including indexation.

9 Appendix 1 – Consultee Responses

9.1 Active Travel England: [No objection subject to conditions]

9.1.1 Initial comments 11.2.25 [Deferral, further information requested]

1.0 Background

Active Travel England (ATE) welcomes the opportunity to comment on this outline planning application. This is ATE's first involvement with the proposal site; however, it is noted that standing advice was issued in response to a pre-application engagement request, as ATE does not currently provide detailed advice at the pre-application stage.

It is understood that the site is not allocated within the current Local Plan (2011); however, it has been considered as part of evidence gathering for the preparation of a new Local Plan.

2.0 Summary

ATE has reviewed the application against the criteria in the updated planning assessment toolkit, national planning policy, and active travel design guidance.

The proposals demonstrate strong potential to support active travel, with the site being sustainably located and offering opportunities to access surrounding services and amenities via active modes. However, certain aspects require further consideration, leading to a deferral response. ATE requests additional information and analysis to address these matters, detailed below.

3.0 Areas of Concern

1. Trip Generation and Travel Plan Targets

Trip Generation:

Expected trip rates for walking, wheeling, and cycling journeys are not clearly provided in the Transport Assessment (TA) and appear to focus solely on vehicle trips. Trip rates should be provided for active modes as all-day trips rather than being restricted to peak hours. The trip generation for active modes should consider all onsite uses, not just residential elements.

Travel Plan:

The Travel Plan lacks targets for active modes and instead relies on 2011 Census Journey to Work (JTW) data to establish a baseline modal split, intending to update this with surveys post-occupation. This approach is disappointing, given the site's high potential for active travel. Reliance on outdated census data results in a less ambitious starting point. Recognising the limitations of the 2021 Census, adopting a vision-led approach and incorporating alternative data sources, such as the National Travel Survey, could help establish robust, forward-looking targets in line with the updated NPPF.

2. Active Travel Route Audit

Section 4.0 of the TA assesses the distances to local facilities and opportunities for sustainable and active travel. While it identifies several destinations accessible on foot or by cycle, it does not include maps to illustrate key routes. The assessment provides photographs and commentary on walking routes but lacks a cycling audit, unlike the walking audit.

While the walking audit identifies some areas for improvement, a more critical evaluation is required, considering:

- National Design Guide
- Inclusive Mobility Guidance
- The five core design principles of LTN 1/20, which apply to both cycling and walking routes

The Watford and Three Rivers Local Cycling and Walking Infrastructure Plan (LCWIP), attached in Appendix A of the TA, applies similar principles. It would be beneficial for the applicant to provide a comparable level of assessment with maps.

3. Accessibility

Walking and Cycling – Access to Services:

The development site is well located for accessing services, as confirmed in Table 3 – Distance to Local Facilities of the TA. However, when assessing accessibility, it is essential to evaluate the quality of routes. As noted, the route audit should be expanded to cover a broader range of facilities. While proposed commercial and educational facilities will improve accessibility, residents will likely need access beyond the site boundary.

Access to Public Transport:

Public transport journeys typically start and end with active travel. Ideally, developments should be within:

- 400m of a high-frequency bus stop
- 800m of a rail station

The TA states the nearest bus stop is 750m away at Durrants Drive/Baldwins Lane. The nearest underground station (Croxley) is 1.8km away, and the closest National Rail station is a 15-17 minute cycle ride, making it inaccessible by foot to most users.

While the site is generally well served by public transport, the distance to the nearest bus stop exceeds the recommended standard. The proposed new bus service within the site could improve access, but further details on funding, frequency, routes, and operating hours are needed.

4. Off-Site Infrastructure Improvements

Access Arrangements:

Two vehicular accesses via Links Way and Durrants Drive are proposed. While these allow logical, direct routes into the site, improvements are needed to facilitate east-west pedestrian and cycle connections along Little Green Lane in terms of materials and crossings. The Design and Access Statement (DAS) illustration (p.146) suggests this, but the detailed drawings do not reflect it.

Further Improvements:

- New Pedestrian & Cycle Links:
 - o A shared footway/cycleway connecting the site to Croxley Danes School and Baldwins Lane.
 - o Pedestrian/cycle priority at junctions along this route.

While the principle of off-carriageway walking and cycling infrastructure is welcome, ATE does not generally support shared-use paths unless they meet limited exceptions in LTN 1/20. The proposed route interacts with driveways, creating potential conflicts with both vehicles and pedestrians and ultimately amounts to conversion of a footpath. Moreover, it appears pavement parking is prevalent along this route, however no detail on how this will be managed is provided. Alternative measures should be considered, including managing pavement parking, enhancing placemaking and introducing traffic calming which reduces conflicts, to ensure this route is attractive to all users.

- Upgrades to Public Rights of Way (PRoW):
 - o Footpath 17 improvements towards West Hertfordshire Golf Course.
 - o Enhancements to PRoWs 63 and 18 to improve connectivity.
- Cycle Route Integration with LCWIP:
 - o Contributions to the cycleway along The Green.
 - o Cycle priority improvements along the A412 corridor towards Watford.

Discussions with the PRoW and Highway Authority are needed to determine appropriate contributions. It is considered that there is a significant opportunity to benefit from the proximity of the site to existing PRoW network.

5. Permeability and Placemaking

The proposals are currently in outline form, which typically limits the level of detail available for comment on permeability and placemaking. However, the submitted road layouts provide an opportunity to influence design at this stage.

Permeability

Detailed comments on internal permeability will be provided at an appropriate time. It is disappointing that the submitted Land Use Parameter Plan only reserves land for vehicular access.

The DAS includes an Indicative Pedestrian and Movement Strategy, but it is concerning that while this plan identifies several potential access/egress points for cyclists and pedestrians, it does not seek to secure them. While it is recognised that the layout is not fixed, it is crucial to guarantee a minimum number of dedicated access points for cyclists and pedestrians. Additional opportunities to secure links include:

- Southwest corner – to create a dedicated link to Little Green Junior School.
- Southeastern corner – to facilitate a link to Rousebarn Lane and onward to Croxley Danes School.
- Northeastern corner – to connect towards footpaths 017 and 031 leading to Watford.

The boundary along Little Green Lane should remain open to prevent disconnection from the built-up area to the south. Walking and cycling links into the site should be abundant to ensure the development remains integrated, especially given the number of proposed services on-site and paying regard to NPPF 96a.

Shared Use

It is understood that the Boulevard will feature a 3m-wide foot/cycleway. As previously discussed, ATE does not support shared-use facilities, particularly in residential areas where pedestrian flows are high. While it is acknowledged that vehicle traffic will generally be low-speed and low-volume, shared-use paths can lead to conflicts between cyclists and pedestrians.

Consideration should be given to:

- Providing segregated facilities on both sides of the highway; and/or
- Enhancing placemaking by reducing carriageway widths.
- Restricting on-street parking to create a safer and more accessible environment for active travel.

These measures would help prioritise safe and inclusive movement throughout the development.

6. Cycle Parking

- It is understood that cycle parking provision will comply with local standards. Thought should also be given LTN 1/20 standards. Parking should be as convenient as car parking with unobstructed access to secure facilities provided by the developer.
- The need for further cycle parking provision should be explored at Croyley Underground Station.
- The expansion of Beryl Bikes is welcomed.

4.0 Next Steps

ATE acknowledges the strong potential of this development to support active travel but requests further information and amendments to trip generation analysis, infrastructure design, permeability, and public transport integration before providing full support.

ATE requests that the Local Planning Authority share this response with the applicant's agent. Additional details and amendments in line with the above comments would be welcomed, with a view to providing further feedback and appropriate wording for conditions as required.

9.1.2 Further comments 28.07.25 [No objection subject to conditions]

Notice is hereby given that Active Travel England's formal recommendation is as follows:

Conditional approval: ATE recommends approval of the application, subject to the agreement and implementation of planning conditions and/or obligations as set out in this response.

1.0 Background

Active Travel England (ATE) welcomes the opportunity to provide comments on this further consultation. ATE previously submitted a response dated 11 February 2025, recommending that the application be deferred pending the provision of additional information. That previous response should be read in conjunction with this updated consultation response.

ATE notes that the application has since been amended, with revised plans and supporting documentation now submitted.

Following a review of the revised proposals, ATE is issuing a conditional approval. Further context for this decision is set out below, with reference to the specific issues previously raised.

2.0 Summary

1. Trip Generation and Travel Plan Targets

- **Trip Generation:**

ATE requested the following:

Provision of expected trip rates for walking, wheeling and cycling, not solely vehicle trips.
Inclusion of all-day trip rates for all land uses (not just residential).

Table 4 of the updated Transport Assessment (TA) now includes forecasts for Active Travel trips based on TRICS data. This is welcomed. However, ATE requested that the applicant provide an analysis of all-day trips rather than only peak-hour trips within the TA. As many trips are unrelated to commuting, it is essential that an all-day analysis is undertaken. It is noted, however, that TRICS data has been provided throughout the day in Appendix F. This data indicates more than 70 cycle trips and approximately 550 pedestrian trips, significantly higher than those reported in the TA. It will therefore be important to ensure that opportunities exist to support and encourage these modes as part of the development proposals.

Provision of trip rate data for other on-site uses is also welcomed.

• **Travel Plan:**

ATE requested the following:

Inclusion of targets for active modes.

Adoption of a vision-led approach using alternative data to set ambitious, forward-looking targets.

It is disappointing that the applicant has not provided figures for annual monitoring targets or for an increase in active travel. A 15% reduction in private vehicle trips is welcomed, and it is noted that this has been recommended by the Highway Authority. However, it is unclear how this 15% reduction will be reallocated among other modes. Notwithstanding this, the applicant has identified various active travel improvements that will help to support this reduction. A planning condition has been suggested should the Local Planning Authority (LPA) be minded to approve the proposals.

2. Active Travel Route Audit

ATE requested that the applicant undertake a more detailed Active Travel Route Audit, including an assessment of key routes from the site to surrounding destinations. The applicant has now undertaken a detailed assessment, including maps and photo analysis. The applicant has also applied the principles within the ATE Route Audit Tool and the Cycling Level of Service (CLOs), reflecting the core principles of LTN 1/20. Overall, it is considered that this assessment is sufficient and this matter has been addressed.

3. Accessibility

In general, it was considered that the site has reasonable levels of accessibility to surrounding services and the potential to be sustainable for the purposes of active travel. However, the distance to the nearest bus stop was identified as exceeding the recommended standard (440m). It is understood that the applicant now proposes to provide bus stops and shelters on site, together with real-time bus information where appropriate. This matter is therefore accepted, subject to securing sufficient funding to the satisfaction of the Highway Authority.

4. Off-Site Infrastructure Improvements

ATE does not wish to raise any further concerns regarding site access via Links Way and Durrants Drive.

New shared footway/cycleway:

ATE does not generally support shared-use paths except in limited circumstances set out in LTN 1/20. The applicant has sought to justify the proposed shared footway/cycleway on the basis of anticipated pedestrian flows of fewer than 300 per hour. However, this misinterprets the guidance and overlooks the fact that shared use is only acceptable in specific situations, as listed in LTN 1/20 paragraph 6.5.6, none of which apply in this case.

The assertion that pavement parking will not be an issue because properties along the route have adequate off-street parking is not considered justified. Pavement parking is clearly evident in Google Street View imagery dating back to 2008. Without a Traffic Regulation Order, it seems unlikely that the applicant will be able to resolve this issue.

A facility incorporating a physical buffer between the carriageway and the shared-use path, together with provision for driveway access, would effectively mitigate the risk of pavement parking. This could include physical build-outs to formalise parking bays, replacing the current unrestricted arrangement. Notwithstanding these points, the principle is accepted, and it is considered that this matter can be addressed through detailed design. The proposed facility may offer some utility for less experienced cyclists and children, while on-carriageway cycling is feasible on lightly trafficked streets where vehicle speeds are low.

See build-out examples and buffer examples. Also see '*Streets for All*' within *Building for a Healthy Life* for detailed design guidance.

PRoW Upgrades:

ATE identified the following:

Improve Footpath 17 and PRoWs 63 and 18.

Coordinate with the PRoW/Highway Authority regarding contributions.

5. Permeability and Placemaking

ATE does not wish to make any further comments on this matter at this stage and is generally content with the design approach.

6. Cycle Parking

ATE does not wish to make further comments on this matter.

3.0 Recommended Planning Conditions

Travel Plan submit:

Condition: Prior to occupation or use commenced, evidence that the preoccupation elements of the approved Travel Plan have been put in place shall be prepared, submitted to and approved in writing by the Local Planning Authority. The developer shall then enable the Highways Authority to implement, monitor and review the approved Travel Plan to the satisfaction of Local Planning Authority unless agreed in writing by the Local Planning Authority.

Reason: To support sustainable transport objectives including a reduction in private vehicular journeys and the increased use of public transport, walking, wheeling and cycling.

Infrastructure:

No development shall commence until general arrangement plan(s) to a scale of 1:200 showing details of the walking / cycling infrastructure including works to the adopted highway have been submitted to and approved in writing by the Local Planning Authority.

The details shall be submitted in accordance with guidance contained in LTN 1/20 on Cycle Infrastructure Design and Manual for Streets and where applicable indicate proposals for:

- Existing levels of the finished highway tying into building threshold levels
- Alterations to waiting restrictions or other Traffic Regulation Orders to enable the works
- Signing, street furniture, street trees and pits
- Structures on or adjacent to the highway
- Extent of any stopping up, diversion or dedication of new highway (including all public rights of way shown on the definitive map and statement)

The development or any phase of the development, whichever is the sooner, shall not be occupied until the walking and cycling infrastructure for the development or phase of development has been constructed and completed in accordance with the approved details.

Reason: To comply with CP10: Transport and Travel of the Three Rivers Local Development Framework Core Strategy Development Plan Document (DPD) 2011 and the guidance in LTN 1/20 on Cycle Infrastructure Design and in Manual for Streets.

4.0 Next Steps

ATE requests that the Local Planning Authority share this response with the applicant's agent.

9.2 Affinity Water: [No objection]

Thank you for notification of the above planning application. Planning applications are referred to us where our input on issues relating to water quality or quantity may be required.

Water quality

We have reviewed the planning application documents and we can confirm that the site is **not located** within an Environment Agency defined groundwater Source Protection Zone (SPZ) or close to our abstractions.

The construction works and operation of the proposed development site should be done in accordance with the relevant British Standards and Best Management Practices, thereby significantly reducing the groundwater pollution risk. It should be noted that the construction works may exacerbate any existing pollution. If any pollution is found at the site then the appropriate monitoring and remediation methods will need to be undertaken.

For any works involving excavations below the chalk groundwater table (for example, piling or the implementation of a geothermal open/closed loop system), a ground investigation should first be carried out to identify appropriate techniques and to avoid displacing any shallow contamination to a greater depth, which could impact the chalk aquifer.

For further information we refer you to CIRIA Publication C532 "Control of water pollution from construction - guidance for consultants and contractors".

Water efficiency

Being within a water stressed area, we expect that the development includes water efficient fixtures and fittings. Measures such as rainwater harvesting and grey water recycling help the environment by reducing pressure for abstractions. They also minimise potable water use by reducing the amount of potable water used for washing, cleaning and watering gardens. This in turn reduces the carbon emissions associated with treating this water to a standard suitable for drinking and will help in our efforts to get emissions down in the borough.

We currently offer a discount to the infrastructure charge for each new development where evidence of a water efficiency design to a standard of 110litres (or less) per person per day is expected. The discount value for the charging period 2023/24 is £258. For more information visit Water efficiency credits (affinitywater.co.uk).

Infrastructure connections and diversions

There are potentially water mains running through or near to part of proposed development site. If the development goes ahead as proposed, the applicant/developer will need to get in contact with our Developer Services Team to discuss asset protection or diversionary measures. This can be done through the My Developments Portal (<https://affinitywater.custhelp.com/>) or aw_developerservices@custhelp.com. Due to its location, Affinity Water will supply drinking water to the development in the event that it is constructed. Should planning permission be granted, the applicant is also advised to contact Developer Services as soon as possible regarding supply matters due to the increased demand for water in the area resulting from this development.

To apply for a new or upgraded connection, please contact our Developer Services Team by going through their My Developments Portal (<https://affinitywater.custhelp.com/>) or aw_developerservices@custhelp.com. The Team also handle C3 and C4 requests to cost potential water mains diversions. If a water mains plan is required, this can also be obtained by emailing maps@affinitywater.co.uk. Please note that charges may apply.

9.3 British Pipeline Agency: [No comments on application]

Having reviewed the information provided, the BPA pipeline(s) is not affected by these proposals, and therefore BPA does not wish to make any comments on this application.

However, if any details of the works or location should change, please advise us of the amendments and we will again review this application.

Whilst we try to ensure the information we provided is accurate, the information is provided Without Prejudice and we accept no liability for claims arising from any inaccuracy, omissions or errors contained herein.

9.4 Chiltern Conservation Board (CCB): [No objection]

9.4.1 Thank you for consulting the Chilterns Conservation Board (CCB). Our duties and responsibilities are set out in the Countryside and Rights of Way Act 2000, at section 87, and we have confined our scrutiny of this application to ensuring it falls within this duty.

The statutory boundary of the Chilterns AONB/National Landscape is set away from the application site and lies some 2.4 to 2.6km to the west of the submitted red line. The landscape within and surrounding the application site shares several characteristics with the Chilterns landscape, notably narrow and partly sunken lanes, dry chalk valley features, and a chalk plateau landscape. The River Gade, a Chilterns Chalk stream and valley landscape, is located approximately 2-3 km to the east of the application site. This flows from within a source within the National Landscape.

It is material that in the Spring of 2025, Natural England ceased work on the Chilterns boundary extension review, along with other candidate projects. The distance and intervening topography to the east of this application site result in a very marginal impact upon the setting of the Chilterns, and we accept that this would not harm the special qualities following an appraisal of visual impacts alone.

In taking a more holistic view of the impacts upon the Chilterns, we would seek assurances that the River Gade's ecology is not impacted. The applicants within their submitted

landscape and visual impact assessment and/or ecological assessment are welcome to comment on the wider implications upon the River Gade and the recreational impacts upon footpaths and green infrastructure more generally. We would welcome an addendum to the landscape assessment with a Chilterns perspective.

To assist all parties, we have recently produced the Chilterns Chalk Streams Planning Guidance (in collaboration with Land Use Consultants), which was released a few weeks ago. This specifically sets out development management policies, and we welcome assurances that the Gade is unaffected.

This new guidance may be accessed at
<https://www.chilterns.org.uk/news/new-planning-guidance-launched-to-protect-fragile-chalk-streams/>

9.4.2 The covering email from CCB stated;

We can confirm, as in the attached letter, that there would be no physical impact upon the visual setting of the NL/AONB (following the Landscape Institute's approach).

9.4.3 Further comment 21.10.25 following review of Woodland Management Plan:

Updated Comment. Thank you for the LPA's further consultation on the applicant's submission of a Woodland Recreation Management Plan, in which Appendix 4 deals with the previous CCB comments on the River Gade. We have noted this, but we have no further comments to make on this matter. The applicants are not offering anything tangible, as far as the River Gade's habitat is concerned. They note the benefits of further dialogue with the CCB.

9.5 Croxley Green Parish Council: [Objection]

9.5.1 Initial comments 21.2.25 [Objection]

Introduction

We object to the application for the following reasons:

The site is open farmland and part of the protected green belt currently enjoyed by thousands of residents. It can be seen from all the roads and footpaths adjoining and approaching it. The loss of amenity resulting from its removal would affect the well being of all those who currently enjoy it. It is not and does not meet the test of grey belt.

The proposed design, layout and density are out of keeping with the existing patterns in the environs. Insufficient parking is provided.

Existing services: sewerage, water supply and electricity supply are not adequate to support the proposed development.

Traffic in the area will be adversely affected by the proposed development, and a sustainable transport plan has not been demonstrated.

Green Belt, Planning & Heritage

Green Belt Protection – The land is currently protected Green Belt. It should not be developed unless there are exceptional circumstances, which have not been demonstrated. This is not “Grey Belt”.

This land is not previously developed, so it falls into the category of ‘other land.’ It is required for the purposes of a, b and d in NPPF (page 73), therefore it is not Grey Belt.

The Croxley Green Neighbourhood Plan (CGNP, adopted 2018) identifies the extent of the Green Belt surrounding Croxley Green and its importance to residents.

For example, in CGNP at 2.1.3:

“Croxley Green is surrounded by countryside and greenery – fields, woodlands and marshy floodplain, mostly designated as Green Belt. Some of these areas lie within the parish, but most of them lie in adjoining parishes, to the south, west and north. These green areas provide a physical and visual buffer and help define the exclusive “village” feeling as well as being highly valued by the majority of residents. The main characteristic is of two storey houses set in residential roads many with glimpses of the open countryside which lies on all sides.”

TRDC commissioned a strategic analysis of the Green Belt in August 2017. It concluded that the Green Belt fulfils its purpose.

A further study in 2019 ranked 152 parcels of land on a 7-point scale of very high, high, moderate-high, moderate, low-moderate, low and very low. This proposal site was ranked as moderate-high harm. Logically the sites identified as being moderate to very low harm should be brought forward first.

As a result of the recently revised NPPF, TRDC has to undertake a new Green Belt Review.

Therefore, this application is premature and a decision should be deferred until Three Rivers District Council has completed its review.

Neighbourhood plan: This application should be revised to take account of the Croxley Green Neighbourhood Plan

Heritage Statement: The development of the site will adversely affect the prospect of listed Durrants House and its iconic tower when viewed from footpath 17. A corridor between 4 storey buildings along the proposed ‘Durrants View’ will severely restrict the view of Durrants House. The development will not preserve the setting.

Density, Design and topography

Density of Housing: The proposed density is markedly tighter than the existing adjacent housing, Front gardens of 2m (cf 5m nearby in Croxley), back gardens of 10m (cf 20m nearby in Croxley).

Design code: This advocates three storey buildings across most of the site, with many four storey buildings. This is out of character with the adjacent housing in Croxley Green. The code shows inappropriate examples of buildings taken from central London as design examples. Four storey Georgian buildings for example.

Topography: The whole assessment of the site seems to ignore topography. Parts of the site are comparatively level, others are quite steeply sloped. The site is visible from a number of directions, the proposed built form should be 3D modelled to show the visual impact.

Well being, sports & environment

Protected species such as skylarks will be affected as noted by the applicant. The applicant also states that they have not carried out a study to find out which protected species exist across the site. Surely that must be done before an application is made.

Street trees and road noise. The proposed new cycle way along Links Way requires the inappropriate removal of many street trees. This will destroy existing residents' green amenities, which with the stated 5dB increase in road noise from traffic will reduce their quality of life.

Sports facilities: The report states that football and cricket fields in particular are under increasing strain. It also identifies significant overuse of grass pitches, with rising youth and female participation creating "urgent demand". No new pitch or court sports facilities are proposed. The expectation is that residents travel elsewhere in the area to participate in sports, creating additional car journeys.

Community Facilities: Falling school rolls and Hertfordshire County Councils five years projections suggest there is no need for a new school. The space allocated for a doctor's surgery is not large enough to take the expanded facility that is required, nor is there sufficient parking provided. There are already 8 halls available for community use in Croxley, so the need for a new one is not demonstrated. There are two local shopping centres within 15 minutes walk of the site, so the viability of two new retail units is not proved.

Infrastructure

Foul drainage: The sewerage system is at capacity and cannot take any further discharge from this proposed site. As Thames Water asserted in their consultee comment, the development should not be approved until it is confirmed that the system's capacity can be suitably enlarged.

Drainage strategy: This says that the new roads themselves will take the excess surface water, presumably becoming a river over the road. We have seen instances in nearby Millside Grange where the unadopted roads have not been built to sufficient standards and gullies are raised not allowing water to escape into them.

Net Zero: There is no overall assessment of the energy demands associated with creating the buildings on site, the embedded carbon, or the energy requirements for the life of the buildings, to demonstrate how the proposed development will comply with net zero targets.

Transport, Roads & Parking

The Transport Assessment and Travel Plan does not consider the impact of construction traffic (or of providing for workers on site) or heavy vehicle movements on local roads. Baldwins Lane is already showing signs of structural deterioration and may require extensive reconstruction if it is used as part of the site access route for construction vehicles. The transport assessment fails to take account of the development of Breakspeare School or the proposed redevelopment of Croxley House as a nursery.

The network analysis is deficient in only considering local network effects and impacts outside Croxley Green but not the impact on the main road network within Croxley Green.

The Transport Assessment contains inaccuracies and errors. The obvious ones give no confidence that the more technical parts are correct or appropriate.

We note that Highways England recommend refusal based on the information provided to date.

The Travel Plan is not sustainable. The site is a significant distance on foot from local facilities and public transport.

We note that Active Travel England can not support the proposal for these reasons.

The outline proposal is to bring a bus route to the site, but there is no evidence about the practicability in terms of diverting local services, the quality of local services, existing patronage, or the desired destinations from the new development.

Parking: The 2021 census shows that residents near the proposed site had approximately 170 vehicles (cars and vans) per 100 addresses. The local area is currently highly dependent on cars and vans for travel and transport. The proposed parking provision is inadequate. The 'centre' has too few spaces. The residential areas have too few spaces. One only has to look at Durrants estate and Millside Grange to see that cars are parked on pavements because there is nowhere else to park.

Therefore, the sustainability aspects of the travel plan and the transport assessment lack the substance required to be credible.

Conclusion

There have been over 650 objections from the local community to this proposal. It is clear there is strong resistance on planning grounds.

The site is open farmland and part of the protected green belt currently enjoyed by thousands of residents. It is not and does not meet the test of grey belt.

Traffic in the area will be adversely affected by the proposed development, and a sustainable transport plan has not been demonstrated.

Existing services: sewerage, water supply and electricity supply are not adequate to support the proposed development.

The proposed design, layout and density are out of keeping with the existing patterns in the area. Insufficient parking is provided.

There is no need for the proposed new school, NHS facility, community hall or retail units.

We therefore confirm our objection to the application.

If the officer is minded to approve, we request 'call in.'

9.5.2 Further comments 13.11.25 following review of Planning Statement Addendum:

In summary:

- Addendum references Sarratt Neighbourhood Plan not Croxley Green Neighbourhood Plan.
- Disagree with application of Sarratt Neighbourhood Plan policies.
- Proposal does not protect setting of or improve views of Durrants House.
- Do not agree that the land is grey belt.
- Query highways trip figures.
- Off site sports provision not sustainable.
- Space allocated for GP surgery is insufficient.

9.6 Forestry Commission: [Concerns, condition(s) if minded to approve]

9.6.1 Initial comments 11.2.25 [Concerns, condition(s) if minded to approve]

We have been notified of this application and would like to submit comments.

As the Government's forestry experts, we endeavour to provide as much relevant information to enable the project to reduce any impact on irreplaceable habitat such as

Ancient semi natural Woodland as well as other woodland. We are particularly concerned about any impact on Ancient Semi natural Woodland and will expect to see careful consideration of any impact when assessing the site.

The site is directly adjacent to Dell Wood and Long Newland's Spring Ancient Semi Natural Woodlands, with Green Lane Ancient Semi Natural Woodland within the site.

Ancient Woodland:

Ancient woodlands are an irreplaceable habitat. They have great value because they have a long history of woodland cover, being continuously wooded since at least 1600AD with many features remaining undisturbed.

Decisions should be made in line with paragraph 193 (c) of the National Planning Policy Framework (Dec 2024), which states:

“Development resulting in the loss or deterioration of irreplaceable habitats (such as ancient woodland and ancient or veteran trees) should be refused, unless there are wholly exceptional reasons and a suitable compensation strategy exists”

As Ancient woodland, ancient trees and veteran trees are irreplaceable, you should not consider proposed compensation measures as part of your assessment of the merits of the development proposal.

We particularly refer you to further technical information set out in Natural England and Forestry Commission's [Standing Advice on Ancient Woodland](#) – plus supporting [Assessment Guide](#) and [“Keepers of Time” – Ancient and Native Woodland and Trees Policy in England](#).

The Joint NE/FC Standing Advice states that both the direct and indirect effects of development should be considered for both the construction and operational phases of the proposed development.

Not just including the potential for actual construction to impact on soils, trees and tree roots. But also the potential for effects when the residential development is in use.

Other impacts to the ancient woodland, for example reducing the resilience of the woodland and making it more vulnerable to change. Increasing the amount of dust, light, air and soil pollution and increasing disturbance to wildlife, also trampling of plants, erosion of soil and noise from additional people, traffic and domestic pets.

Ancient Woodland Buffer:

The Standing Advice also states that proposals should have a buffer zone of **at least** 15m from the boundary of ancient woodlands to avoid root damage which can result in loss or deterioration of the woodland. Where assessment shows impacts are likely to extend beyond this distance, you're likely to need a larger buffer zone. For example, the effect of air pollution from development that can result from a significant increase in traffic.

Whilst we note plans for a 30m buffer for the ancient woodlands, and plans for thorny shrub planting in the buffer zone, the application may still have the potential to cause deterioration to the ancient woodland. Although the buffer may be sufficient to avoid direct soil compaction during construction, indirect soil damage and disturbance would still be expected due to the extent of the proposed development. Impacts from machinery, movement of the workforce and from new residents would be expected to cause a deterioration.

We would encourage considering a mix of habitat types to create a graded edge from the existing woodland including new woodland, scrub and species rich grassland with effective management that maximises biodiversity value. We also note the inclusion of amenity public open space and footpaths within the Ancient woodland buffer, these may be better located outside of the buffer, with the buffer itself managed as a semi natural habitat less attractive to be used as public open space.

Priority Habitat:

Both Dell Wood and Green Lane Wood are also listed as mixed deciduous woodlands on the National Forest Inventory and the Priority Habitat Inventory (England).

They were recognized under the UK Biodiversity Action Plan as being the most threatened, requiring conservation action. The UK Biodiversity Action Plan has now been superseded but this priority status remains under the Natural Environment & Rural Communities Act 2006. (NERC) Sect 40 “Duty to conserve and enhance biodiversity” and Sect 41 – “List of habitats and species of principle importance in England”.

Paragraph 187b of the NPPF states:

“Planning policies and decisions should contribute to and enhance the natural environment recognising the intrinsic character and beauty of the countryside, and the wider benefits from natural capital and ecosystem services – including the economic and other benefits of the best and most versatile agricultural land, and of trees and woodland.”

Habitat Fragmentation and Connectivity:

Fragmentation is one of the greatest threats to mixed deciduous woodland and especially ancient woodland. Woodlands can suffer loss or deterioration from nearby development through damage to soils, roots and vegetation and changes to drainage and air pollution from an increase in traffic and dust, particularly during the construction phase of a development.

The proposed development will not improve habitat connectivity between Dell Wood, Long Newland’s Spring and Green Lane Wood. In fact, it could sever it completely. With Green Lane Wood becoming completely isolated in its landscape. While managed grassland and play areas are to be provided, there is a greater opportunity to provide habitat connectivity between Green Lane Wood and Dell Wood in particular.

With current plans, there would be very limited movement of species (flora and fauna) between habitat areas and therefore the species quality and diversity in the smaller, isolated woodland would likely decline and would be unlikely to improve (especially without appropriate management) and would further impact the woodland’s resilience to future threats including climate change. The measures taken by the application to offset the proposal do not appear to take account for habitat connectivity or continuity.

Whilst we understand that all trees and woodlands on site will be retained, there is an opportunity for increased woodland planting between the two woodlands to improve connectivity across the whole landscape.

Hedgerows, individual trees and woodlands within a development site should be considered in terms of their overall connectivity between woodlands affected by the development. Perhaps with the creation of some larger woodland blocks and hedgerow/hedgerow trees between the existing woodland blocks on site, to link them and ensure maximum gains to increase habitat connectivity, to make woodlands more resilient and to benefit biodiversity across the whole site

Canopy Cover and Woodland Management:

With the Government aspiration to increase tree and canopy cover to 16.5% of land area in England by 2050, The Forestry Commission is seeking to ensure that tree planting is a consideration in every development not just as compensation for loss.

The species and provenance of new trees and woodland needs to be considered to ensure a resilient treescape which can cope with the full implications of a changing climate. The biosecurity of all planting stock also needs to be considered to avoid the introduction of pests and diseases, particularly in areas near ancient woodlands.

Plans should also be in place to ensure the long term management and maintenance of new and existing woodland, including deer management and would recommend the creation of a UK Forestry Standard compliant management plan, access also needs to be considered for future management.

Active management of woodlands, especially ancient woodlands, is essential for a host of reasons but crucially to create and maintain the valuable biodiversity element of these habitats. This diversity leads to greater resilience and productivity along with environmental benefits. The diversity and benefit of woodlands will be lost over time if they are neglected. These interventions are also crucial in the face of climate change where active management is needed to help woodlands adapt.

If the Local Authority is minded to approve this application, we would recommend that full details of any woodland protection measures, a woodland management plan, a planting plan including species selection and lighting strategy to avoid illuminating all woodlands on site and adjacent to it, be provided at the reserved matters stage.

We hope these comments have been useful to you. If you require any further information, please do not hesitate to contact me.

9.6.2 Further comments 10.06.25 following notification of increased separation between SuDS and woodland:

Thank you for contacting us regarding changes to the application. While any separation between the suds and the woodland is to be welcomed, we have rather more concerns regarding the potential increase in recreational pressures on the ancient woodlands within and adjacent to the site. The minimum suggested buffer mentioned in the Natural England/Forestry Commission Standing advice is more suited to a single dwelling, rather than a large development of up to 600 dwellings. With the associated direct and indirect impacts of both development, traffic, people and domestic pets.

Larger planted buffers, better connectivity between woodlands, provision of alternative recreational space and appropriate woodland management may go some way to mitigate these effects. However an assessment of the impacts of the development on the woodland habitats as a whole should be undertaken before appropriate mitigation can be proposed.

It is however worth noting that The Town and Country Planning (Consultation) (England) Direction 2024 (published January 2024) requires local planning authorities in England to consult the Secretary of State before granting planning permission for certain types of development, including development that affects ancient woodland: [The Town and Country Planning \(Consultation\) \(England\) Direction 2024 - GOV.UK \(www.gov.uk\)](https://www.gov.uk/government/consultations/town-and-country-planning-consultation-england-direction-2024)

Strategic tree planning can also be used to assist with minimising flood risk on some sites and should also be a consideration.

9.6.3 Further comments 29.10.2025 following notification of woodland management plan:

We have concerns regarding fencing the Ancient Woodland within the site, this will isolate the woodland further creating more negative impact. Negative impacts on irreplaceable habitat can't be justified on the basis that the woodlands are surrounded and isolated by agricultural land, that is entirely irrelevant.

We have concerns regarding the lack of evidence for wholly exceptional reasons as per NPPF Para 193 (c) as the information appears to confirm that loss or deterioration of the ancient woodlands is to be envisaged. In which case, the application should be referred to the Secretary of State for a decision as per my previous email.

If the country park were to be much more wooded, with the creation of a scrubby mosaic with grass and trees with spinneys, to reflect the importance of Ancient Semi Natural Woodland in the landscape, thus providing more enhanced connectivity between all of the Ancient Woodlands, it would be more preferable.

It would also be advisable that a Woodland Condition Assessment is undertaken for all the on site ancient woodlands, which can be used as a basis of an ongoing management plan. Ongoing condition could also then be monitored to inform decisions about potential impacts going forwards.

Of course education of residents regarding the scarcity and importance of ancient woodlands is also a good thing, however that shouldn't be used as a mitigation measure.

9.6.4 Further comments 16.12.2025:

Following discussions both internally and with the developer, we would like to reiterate some points regarding this application:

The Forestry Commission is a non-statutory consultee on developments in or within 500m of ancient woodland. As a Government department we can neither support nor object to planning applications but endeavour to supply the necessary information to help inform your decision on the application. Ultimately the decision whether to approve or not, lies with the Local Authority, we can only provide advice.

Please consider all the points made in our previous consultation responses as still valid. Concerns remain about the long term effects on all of the Ancient Woodlands affected by this development.

Full assessment of the potential effects on each Ancient woodland habitat has not been undertaken, therefore it is difficult to assess whether a 30m buffer is appropriate and what the effects of new development including dust, noise, people and pets etc would have.

Whilst an application should be considered on its merits, in the case of ancient woodland as irreplaceable habitats, the integrity of the woodland should take priority except when the exceptional reasons test applies.

Due to the irreplaceable nature of ancient woodland and ancient and veteran trees, most temporary effects will result in irreplaceable damage.

If the Local Authority is minded to approve this application, we have made some recommendations regarding the landscape plan, (attached) which we feel may help mitigate some of our concerns.

This includes increased woodland planting in the country park area to ensure that functional connectivity between the Ancient Woodlands is enhanced and that wildlife has a greater 'refuge area'. (It might be argued that the creation of a country park would provide more connectivity than at present but this should be weighed against the increase in disturbance

from people, pets, noise, light and in unvegetated open space versus the existing connectivity via filed margins, hedges and fallow land at present.) A restriction in access through to the Ancient Woodlands in the northern area by the erection of chestnut paling fences to minimise disturbance and anti-social behaviour from people and dogs, plus a much larger buffer zone between the ancient woodland within the site and the housing development.

9.7 HCC Footpath Section: No response received.

9.8 HCC Growth and Infrastructure Unit: [No objection, contributions requested]

9.8.1 Initial comments 14.2.25 [No objection, contributions requested]

Thank you for your recent consultation. I am writing regarding the additional planning obligations that are sought for this outline planning application. HCC acknowledges that the site falls within the district council's CIL charging area. However, to mitigate the impact of the proposed development of 600 dwellings on education provisions (primary education, secondary education and SEND education) and waste facilities, it is essential that appropriate mitigation measures be secured through a Section 106 legal agreement.

HOUSES		
Number of Bedrooms	A) Open Market & Shared Ownership	B) Affordable Rent
1		
2	15	8
3	153	59
4+	56	8
Total	224	75

FLATS		
Number of Bedrooms	A) Open Market & Shared Ownership	B) Affordable Rent
1	51	46
2	115	89
3		
4+		
Total	166	135

Trajectory						
Year	2026	2027	2028	2029	2030	2031
Units	50	100	150	150	150	

PLEASE NOTE: If the tenure or mix of dwellings changes, please notify us immediately as this may alter the contributions sought.

Children's Homes

HCC welcomes and supports the inclusion of a children's home on the site. We look forward to engaging with the applicant regarding the appropriate location and design as plans progress. Additionally, we anticipate starting discussions related to the potential operation of the home and any necessary land or building transfers, as deemed appropriate.

Primary Education Contribution

In 2018, HCC responded to Three Rivers District Council Regulation 18 local plan consultation. In paragraph 17.4, our response set out that primary school sites may need to be identified in all settlements to meet pupil yield from new housing developments, depending on the number of sites and level of growth chosen. We acknowledge that the applicant has proposed a new 1FE (up to 2FE land) primary school on-site to accommodate the needs arising from their scheme. Therefore, the contribution sought towards the delivery of a new 1FE (up to 2FE land) primary school in the area and/or provision serving the development would be (£5,335,853 index linked to BCIS 1Q2022).

Secondary Education Contribution towards the expansion of a Secondary School in the area and/or provision serving the development (£4,534,908 index linked to BCIS 1Q2022).

Special Educational Needs and Disabilities (SEND) Contribution towards new Severe Learning Difficulty (SLD) special school places (WEST) and/or provision serving the development (£498,652 index linked to BCIS 1Q2022).

Waste Service Transfer Station Contribution towards increasing capacity at Waterdale Transfer Station and/or provision serving the development (£35,316 index linked to BCIS 3Q2022).

Monitoring Fees – HCC will charge monitoring fees. These will be based on the number of triggers within each legal agreement with each distinct trigger point attracting a charge of £340 (adjusted for inflation against RPI July 2021). For further information on monitoring fees please see section 5.5 of the Guide to Developer Infrastructure Contributions.

The CIL Regulations discourage the use of formulae to calculate contributions however, the County Council is not able to adopt a CIL charge itself. Accordingly, in areas where a CIL charge has not been introduced to date, planning obligations in their restricted form are the only route to address the impact of a development. In instances where a development is not large enough to require on site provision but is large enough to generate an impact on a particular service, an evidenced mechanism is needed to form the basis of any planning obligation sought. HCC views the calculations and figures set out within the Guide to Developer Infrastructure Contributions as an appropriate methodology for the obligations sought in this instance.

The county council methodology provides the certainty of identified contribution figures based on either a known or estimated dwelling mix, the latter of which might be agreed with the local planning authority based on expected types and tenures set out as part of the local plan evidence base. This ensures the contributions are appropriate to the development and thereby meet the third test of Regulation 122 of the Community Infrastructure Levy Regulations 2010 (amended 2019): “fairly and reasonably relates in scale and kind to the development”.

OUTLINE ONLY: Outline applications will require the ability for an applicant to recalculate contributions at the point of a reserved matters application and as such a calculation Table will be provided as part of the S106 drafting process. This approach provides the certainty of identified contribution figures with the flexibility for an applicant/developer to amend the dwelling mix at a later stage and the financial contribution to be calculated accordingly.

Please note that current service information for the local area may change over time and projects to improve capacity may evolve. This may potentially mean a contribution towards other services could be required at the time any application is received in respect of this site.

Justification

The above figures have been calculated using the amounts and approach set out within the Guide to Developer Infrastructure Contributions (Hertfordshire County Council's requirements) document, which was approved by Hertfordshire County Council's Cabinet 12 July 2021 and is available via the following link:

[HCC Guide to Developer Infrastructure Contributions](#)

In respect of Regulation 122 of the CIL Regulations 2010 (amended 2019), the planning obligations sought from this proposal are:

(i) Necessary to make the development acceptable in planning terms.

Recognition that contributions should be made to mitigate the impact of development are set out in planning related policy documents. The NPPF states “Local planning authorities should consider whether otherwise unacceptable development could be made acceptable through the use of conditions or planning obligations.” Conditions cannot be used cover the payment of financial contributions to mitigate the impact of a development The NPPG states “No payment of money or other consideration can be positively required when granting planning permission.” The development plan background supports the provision of planning contributions. The provision of community facilities is a matter that is relevant to planning. The contributions sought will ensure that additional needs brought on by the development are met.

(ii) Directly related to the development.

The occupiers of new residential developments will have an additional impact upon local services. The financial contributions sought towards the above services are based on the size, type and tenure of the individual dwellings comprising this development following consultation with the Service providers and will only be used towards services and facilities serving the locality of the proposed development and therefore, for the benefit of the development's occupants.

(iii) Fairly and reasonably related in scale and kind to the development.

The above financial contributions have been calculated according to the size, type and tenure of each individual dwelling comprising the proposed development (based on the person yield).

PLEASE NOTE THE FOLLOWING:

Consult the Hertfordshire Fire and Rescue Service Water Officer directly at water@hertfordshire.gov.uk, who may request the provision of fire hydrants through a planning condition.

I would be grateful if you would keep me informed about the progress of this application so that either instruction for a planning obligation can be given promptly if your authority is minded to grant consent or, in the event of an appeal, information can be submitted in support of the requested financial contributions and provisions. Should you require any further information please contact the Growth & Infrastructure Unit.

9.8.2 Further comments 7.8.25 [providing clarification following consideration by TRDC Planning Committee of Preliminary Report]

We acknowledge the concerns raised by members and other stakeholders regarding the need for an additional 1FE primary school in Croxley Green. I hope the following provides further clarity on both the short-term demand and the longer-term strategic rationale behind HCC's request for a 1FE school site. Please note that this response is limited to school planning matters; other infrastructure contributions are outside the scope of this note.

Following discussions with our School Planning colleagues, we understand that as of 16 July 2025, all three primary schools in Croxley Green with Reception class intakes were full. This includes Malvern Way Infant School, which is due to reduce its Published Admission Number (PAN) from September 2025, with a corresponding reduction at its linked junior school in 2028/29. Despite these planned reductions, current forecasts indicate that demand continues to match available capacity.

Given the situation above, it is of School Planning perspective that the proposed 1FE primary school is intended to serve the new development directly, ensuring that the pupil

yield generated by the site is met without placing additional pressure on existing schools. This self-sufficient approach supports the strategic goal of delivering infrastructure that is proportionate and responsive to the specific impact of development.

It is also important to highlight that the case for a new school on this site is not solely based on current capacity. The request is equally informed by principles of placemaking and sustainable development. Schools delivered in this context are intended to meet the needs of the development in isolation, enabling children to walk or wheel to school in a safe, healthy environment and contribute towards the creation of a new community. The intention is not to attract pupils from other parts of the settlement who would need to travel by car. This approach aligns with policy ambitions of chapter 8 of the NPPF.

9.8.3 Further comments 12.11.2025 [amendments to contributions requested following update to HCC guidance on Developer Infrastructure Contributions]

Thank you for your recent consultation. I am writing regarding the additional planning obligations that are sought for this outline planning application. HCC acknowledges that the site falls within the district council's CIL charging area. However, to mitigate the impact of the proposed development of 600 dwellings on education provisions (primary education, secondary education and SEND education) and waste facilities, it is essential that appropriate mitigation measures be secured through a Section 106 legal agreement.

HOUSES			FLATS		
Number of Bedrooms	A) Open Market & Shared Ownership	B) Affordable Rent	Number of Bedrooms	A) Open Market & Shared Ownership	B) Affordable Rent
1			1	51	46
2	15	8	2	115	89
3	153	59	3		
4+	56	8	4+		
Total	224	75	Total	166	135

Trajectory						
Year	2027	2028	2029	2030	2031	2032
Units	50	100	150	150	150	

Children's Homes

HCC welcomes and supports the inclusion of a children's home on the site. We look forward to engaging with the applicant regarding the appropriate location and design as plans progress. Additionally, we anticipate starting discussions related to the potential operation of the home and any necessary land or building transfers, as deemed appropriate.

Primary Education Contribution towards the delivery of a new 1fe primary school (up to 2fe land) in the area and/or provision serving the development (£5,883,141 which has a land cost of £10,530 deducted index linked to BCIS 1Q2024)

Secondary Education Contribution towards the expansion of a Secondary School in the area and/or provision serving the development (£4,376,834 index linked to BCIS 1Q2024).

Special Educational Needs and Disabilities (SEND) Contribution towards new Severe Learning Difficulty (SLD) special school places (WEST) and/or provision serving the development (£784,006 index linked to BCIS 1Q2024).

Waste Service Transfer Station Contribution towards increasing capacity at Waterdale Transfer Station and/or provision serving the development (£63,947 index linked to BCIS

1Q2024).

Monitoring Fees – HCC will charge monitoring fees. These will be based on the number of triggers within each legal agreement with each distinct trigger point attracting a charge of £420 (adjusted for inflation against RPI Jan 2024). For further information on monitoring fees please see section 5.5 of the Guide to Developer Infrastructure Contributions.

The CIL Regulations discourage the use of formulae to calculate contributions however, the County Council is not able to adopt a CIL charge itself. Accordingly, in areas where a CIL charge has not been introduced to date, planning obligations in their restricted form are the only route to address the impact of a development. In instances where a development is not large enough to require on site provision but is large enough to generate an impact on a particular service, an evidenced mechanism is needed to form the basis of any planning obligation sought. HCC views the calculations and figures set out within the Guide to Developer Infrastructure Contributions as an appropriate methodology for the obligations sought in this instance.

The county council methodology provides the certainty of identified contribution figures based on either a known or estimated dwelling mix, the latter of which might be agreed with the local planning authority based on expected types and tenures set out as part of the local plan evidence base. This ensures the contributions are appropriate to the development and thereby meet the third test of Regulation 122 of the Community Infrastructure Levy Regulations 2010 (amended 2019): “fairly and reasonably relates in scale and kind to the development”.

Outline applications will require the ability for an applicant to recalculate contributions at the point of a reserved matters application and as such a calculation Table will be provided as part of the S106 drafting process. This approach provides the certainty of identified contribution figures with the flexibility for an applicant/developer to amend the dwelling mix at a later stage and the financial contribution to be calculated accordingly.

Please note that current service information for the local area may change over time and projects to improve capacity may evolve. This may potentially mean a contribution towards other services could be required at the time any application is received in respect of this site.

Justification

The above figures have been calculated using the amounts and approach set out within the Guide to Developer Infrastructure Contributions (Hertfordshire County Council's requirements) document, which was approved by Hertfordshire County Council's Cabinet 12 July 2021 and is available via the following link: [Planning obligations and developer infrastructure contributions | Hertfordshire County Council](#)

In respect of Regulation 122 of the CIL Regulations 2010 (amended 2019), the planning obligations sought from this proposal are:

(i) Necessary to make the development acceptable in planning terms.

Recognition that contributions should be made to mitigate the impact of development are set out in planning related policy documents. The NPPF states “Local planning authorities should consider whether otherwise unacceptable development could be made acceptable through the use of conditions or planning obligations.” Conditions cannot be used cover the payment of financial contributions to mitigate the impact of a development The NPPG states “No payment of money or other consideration can be positively required when granting planning permission.” The development plan background supports the provision of planning contributions. The provision of community facilities is a matter that is relevant to planning.

The contributions sought will ensure that additional needs brought on by the development are met.

(ii) Directly related to the development.

The occupiers of new residential developments will have an additional impact upon local services. The financial contributions sought towards the above services are based on the size, type and tenure of the individual dwellings comprising this development following consultation with the Service providers and will only be used towards services and facilities serving the locality of the proposed development and therefore, for the benefit of the development's occupants.

(iii) Fairly and reasonably related in scale and kind to the development.

The above financial contributions have been calculated according to the size, type and tenure of each individual dwelling comprising the proposed development (based on the person yield).

9.9 HCC Healthy Places: No objection.

Thank you for the opportunity to comment on the submitted HIA report for this development proposal.

HCC Public Health are pleased to see that a comprehensive HIA has been carried out for the above proposal. The Health Impact Assessment has been quality assessed using the WHIASU Quality Assurance Review Framework (2017). The findings are detailed in this section. They have been broken down into four headings:

1. Clarifications required; 2. Strengths; 3. Weaknesses; and 4. Revisions required

1. Clarifications required

None

2. Strengths

- The HIA report acknowledges the positive, negative, and neutral impacts of the proposed development and the magnitude of the impact. It clearly considers sensitivity of receptors and the significance of effect.
- The HIA provides clear recommendations to reduce or mitigate negative impacts.
- The HIA was carried out at an early stage which means its recommendations has informed the masterplan of the scheme.
- The type of HIA is appropriate and proportionate to the scale and nature of the proposed development.
- HCC Public Health was consulted on the scope of the HIA.
- The HIA includes aims and objectives.
- The HIA report identifies key stakeholders and consultation data has been included in the report.
- The HIA refers to HCC's Health Impact Assessment Position Statement.
- The HIA considers the wider determinants of human health and is informed by other technical reports submitted as part of the planning application.
- The HIA includes a description of the proposed development and information on the surrounding area. This includes access to existing services and amenities from the site, including schools, shops and public transport.
- The HIA had been assessed used the WHIASU Quality Assurance Framework.
- The WHO definition of health has been used in the HIA.

- The HIA has considered the health of the existing population of the surrounding areas and has identified vulnerable groups. The HIA distinguishes between the general population and vulnerable people in the community to identify impacts.
- The HIA report references National Planning Policy Framework, National Planning Practice Guidance, Three Rivers Local Plan, Community Strategy for Three Rivers and the Hertfordshire Health and wellbeing Strategy.
- The report includes a section which provides a local health profile for Three Rivers.
- Cumulative impacts have been considered in the HIA.
- The HIA considers the construction and operational impacts from the proposed scheme.
- Report is clearly structured with subheadings.
- The HIA report includes assumptions and limitations.

3. Weaknesses

- No monitoring is proposed to ensure that recommendations are implemented and key health and wellbeing impacts will not be further monitored.

The points included under 'weaknesses' have been included in our feedback for your consideration, which the applicant may wish to address.

Thank you again for consulting HCC Public Health on the HIA for this proposal. We are pleased with the outcome of this report and that recommendations have influenced the masterplan of the scheme.

9.10 HCC Lead Local Flood Authority: [No objection subject to conditions]

9.10.1 Initial comments 7.2.25 [Objection]

Thank you for your consultation on the above site, received on 21 January 2025. We have reviewed the application as submitted and wish to make the following comments.

This is an Outline Application for up to 600 residential dwellings, a social care / assisted living facility and a medical centre.

We are concerned that calculations have not been provided for all rainfall return periods up to and including the 1% AEP plus appropriate climate change allowance event. This should include the correct parameters (FEH2013 / FEH22, CV value of 1, 10% urban creep and correct climate change allowance on the 3.33% AEP and 1% AEP events). Additionally, we are concerned that the level of detail on the masterplan drawing is not sufficient. Currently, the swales do not appear to connect into the drainage system and there is no outfall (infiltration rate) for the basin.

We **object** to this planning application in the absence of an acceptable Drainage Strategy relating to:

- The proposed SuDS are likely to increase the risk of flooding elsewhere.
- The development is not in accordance with NPPF, PPG or local policies.
 - Three Rivers SFRA Level 2

Reason

To prevent flooding in accordance with National Planning Policy Framework paragraphs 181, 182 and 187 by ensuring the satisfactory management of local flood risk, surface water flow paths, storage and disposal of surface water from the site in a range of rainfall events and ensuring the SuDS proposed operates as designed for the lifetime of the development.

We will consider reviewing this objection if the issues highlighted on the accompanying Planning Application Technical Response document are adequately addressed.

Informative

Both FEH13 and FEH22 are currently accepted to support drainage modelling calculations. For the avoidance of doubt the use of FSR and FEH1999 data has been superseded and therefore, use in rainfall simulations are not accepted.

Please note if, you the Local Planning Authority review the application and decide to grant planning permission, notify the us (the Lead Local Flood Authority), by email at FRMConsultations@hertfordshire.gov.uk.

9.10.2 Further comments 15.5.25 [No objection subject to conditions]

Thank you for your consultation on the above site, received on 06 May 2025. We have reviewed the application as submitted and wish to make the following comments.

This is an Outline Application for up to 600 residential dwellings, a social care / assisted living facility and a medical centre.

We have reviewed the updated documentation as submitted (Response to the LLFA – prepared by BWB, 08 April 2025, REF 233574-BWB-ZZ-XX-T-W-0005_LLFA) and have the following comments to make.

The applicant has provided a Flood Risk Addendum and additional information, as listed in the Annex). These are to account for the local flood risk issues and surface water drainage at this location. Following a review of the submitted documents, the details are in accordance with NPPF and local planning policy Three Rivers SFRA Level 2.

We have **no objection subject to conditions being attached to any consent** if this application is approved. We suggest the following wording.

Condition 1:

Prior to or in conjunction with the submission of each reserved matters application, in accordance with the submitted FRA (Flood Risk Assessment, prepared by BWB, 17 December 2024, REF 233574-BWB-ZZ-XX-T-W-0002_FRA REV P04) and Drainage Strategy (Sustainable Drainage Statement, prepared by BWB, 11 December 2024, REF 233574-BWB-ZZ -XX-T-W-0001_ SDS REV P01), detailed designs of a surface water drainage scheme incorporating the following measures shall be submitted to and agreed with the Local Planning Authority. The approved scheme will be implemented prior to the first occupation of the development. The scheme shall address the following matters:

- ii. Detailed infiltration testing in accordance with BRE Digest 365 (or equivalent) along the length and proposed depth of the proposed infiltration feature/s.

or

- vii. If infiltration is proven to be unfavourable, then Greenfield runoff rates for the site shall be agreed with the Lead Local Flood Authority. The post development runoff rates will be attenuated to the equivalent Greenfield rate for all rainfall events up to and including the 1% Annual Exceedance Probability (AEP). The discharge location for surface water runoff will be confirmed to connect with the wider watercourse network.

- viii. Provision of surface water attenuation storage, sized and designed to accommodate the volume of water generated in all rainfall events up to and including the critical storm duration for the 3.33% AEP (1 in 30 year) and 1% AEP (1 in 100) rainfall events (both including allowances for climate change).
- ix. Detailed designs, modelling calculations and plans of the of the drainage conveyance network in the:
 - 3.33% AEP (1 in 30 year) critical rainfall event plus climate change to show no flooding outside the drainage features on any part of the site.
 - 1% AEP (1 in 100 year) critical rainfall plus climate change event to show, if any, the depth, volume and storage location of any flooding outside the drainage features, ensuring that flooding does not occur in any part of a building or any utility plant susceptible to water (e.g. pumping station or electricity substation) within the development. It will also show that no runoff during this event will leave the site uncontrolled.
- x. The design of the infiltration basin will incorporate an emergency spillway and any drainage structures include appropriate freeboard allowances. Plans to be submitted showing the routes for the management of exceedance surface water flow routes that minimise the risk to people and property during rainfall events in excess of 1% AEP (1 in 100) rainfall event plus climate change allowance.
- xi. Details of how all surface water management features to be designed in accordance with The SuDS Manual (CIRIA C753, 2015), including appropriate treatment stages for water quality prior to discharge.
- xii. A maintenance and management plan detailing the activities required and details of who will adopt and maintain the all the surface water drainage features for the lifetime of the development.

Reason: To prevent flooding in accordance with National Planning Policy Framework paragraphs 181,182 and 187 by ensuring the satisfactory management of local sources of flooding surface water flow paths, storage and disposal of surface water from the site in a range of rainfall events and ensuring the SuDS proposed operates as designed for the lifetime of the development.

Condition 2:

Prior to or in conjunction with the submission of each Reserved Matters application a detailed Site SuDS Phase plan which aligns with the site phasing plan shall be submitted to and approved in writing by the Local Planning Authority. This SuDS Phasing plan shall ensure that each phase does not exceed the agreed discharge rates for that phase and that source control measures are installed within each phase to adequately address the phases own surface water runoff. The plan shall ensure that each SuDS component is adequately protected throughout the development of the scheme. The plan shall show all exceedance routes throughout the site clearance and construction of the scheme ensuring flood risk is not increased elsewhere or to the site itself and that the site remains safe for all exceedance event flow routes for the lifetime of the development during rainfall (i.e. greater than design events or during blockage) and how property on and off site will be protected.

Reason: To ensure that the development achieves a high standard of sustainability and ensure the flood risk is adequately addressed for each new dwelling and not increased in accordance with NPPF and Policies of Three Rivers District Council.

Condition 3:

Construction shall not begin until a detailed construction phase surface water management plan for the site has been submitted to and approved in writing by the Local Planning Authority. The scheme shall subsequently be carried out in accordance with the approved details.

Reason: To ensure that the construction of the site does not result in any flooding both on and off site and that all Surface water Drainage features are adequately protected.

Condition 4:

Prior to first use of each phase of the development a detailed verification report, (appended with substantiating evidence demonstrating the approved construction details and specifications have been implemented in accordance with the surface water drainage scheme), has been submitted to and approved (in writing) by the Local Planning Authority.

The verification report shall include a full set of “as built” drawings plus photographs of excavations (including soil profiles/horizons), any installation of any surface water drainage structures and control mechanisms.

Reason: To ensure that the development achieves a high standard of sustainability and ensure the flood risk is adequately addressed for each new dwelling and not increased in accordance with NPPF and Policies of Three Rivers District Council.

9.11 HCC Waste and Minerals Team: [No objection subject to condition(s)]

Minerals

In relation to minerals, the site falls entirely within the ‘Sand and Gravel Belt’ as identified in Hertfordshire County Council’s adopted Minerals Local Plan 2002 – 2016. The Sand and Gravel Belt is a geological area that spans across the southern part of the county and contains the most concentrated deposits of sand and gravel throughout Hertfordshire. British Geological Survey (BGS) data also identifies potential superficial sand/gravel deposits in the west of the application site.

The Minerals Planning Authority identifies the entirety of the Sand and Gravel Belt together with the identified resource blocks, as Mineral Consultation Areas.

Planning applications submitted to the District and Borough Councils for non-minerals development that fall within a Mineral Consultation Area (other than applications which meet the ‘excluded development’ criteria), may not be determined until the county council has been given the opportunity to comment on whether the proposal would unacceptably sterilise mineral resources.

In accordance with paragraph 225 of the NPPF (Dec 2024) development proposals in Mineral Safeguarding Areas that might constrain potential future use for mineral working should not normally be permitted.

After reviewing the application, the Minerals Planning Authority does not consider that the proposal would have the potential to unacceptably sterilise mineral resources. It is not necessary to investigate the potential for the prior extraction of mineral resources at this site.

Whilst prior extraction is not necessary, there may still be opportunities to utilise sand and gravel resources that are found during site preparation works, should any deposits be uncovered that are of a suitable quality.

Opportunistic extraction refers to cases where preparation of a site for built development, such as excavating the foundations and footings or landscaping works, may result in suitable material being uncovered that could be extracted and processed for use on site as part of the development.

The Minerals Planning Authority would like to encourage the opportunistic extraction and subsequent use of sand and gravel deposits within developments wherever possible. Opportunistic use of minerals will reduce the need to import sand and gravel to the site and make sustainable use of these valuable resources.

Waste

Government policy seeks to ensure that all planning authorities take responsibility for waste management. This is reflected in the County Council's adopted waste Development Plan Documents (DPDs). In particular, these documents seek to promote the sustainable management of waste in the county and encourage Local Planning Authorities to have regard to the potential for minimising waste generated by development.

The National Planning Policy for Waste (October 2014) sets out the following:

'When determining planning applications for non-waste development, local planning authorities should, to the extent appropriate to their responsibilities, ensure that:

- the likely impact of proposed, non- waste related development on existing waste management facilities, and on sites and areas allocated for waste management, is acceptable and does not prejudice the implementation of the waste hierarchy and/or the efficient operation of such facilities;
- new, non-waste development makes sufficient provision for waste management and promotes good design to secure the integration of waste management facilities with the rest of the development and, in less developed areas, with the local landscape. This includes providing adequate storage facilities at residential premises, for example by ensuring that there is sufficient and discrete provision for bins, to facilitate a high quality, comprehensive and frequent household collection service;
- the handling of waste arising from the construction and operation of development maximises reuse/recovery opportunities, and minimises off-site disposal.'

Section 7.35 of Planning Statement makes reference to the Waste Core Strategy and Development Management Policies DPD (2012). The policies in the adopted DPD (2012) that relate to this proposal, and which must be considered by the Local Planning Authority in determining the application, include Policy 1: Strategy for the Provision for Waste Management Facilities (namely the penultimate paragraph of the policy) and Policy 12: Sustainable Design, Construction and Demolition.

Many of the policy requirements can be met through the imposition of planning conditions.

As a general point, built development should have regard to the overall infrastructure required to support it, including where appropriate a sufficient number of waste storage areas that should be integrated accordingly and facilitate the separate storage of recyclable wastes.

Waste Policy 12: Sustainable Design, Construction and Demolition requires all relevant construction projects to be supported by a Site Waste Management Plan (SWMP). Section D of the 'Three Rivers District Council Adopted Screening Opinion' for 24/1220/EIA included within the Planning Statement makes reference to the production of a SWMP as part of the planning application, which the county council encourages.

The Waste Planning Authority would expect to see a SWMP prepared to support this application. The SWMP must be prepared and agreed in consultation with the Waste Planning Authority prior to commencement of the project. The SWMP must be implemented throughout the duration of the project, from initial site preparation works to final completion of the construction phase.

By preparing a SWMP prior to commencement, early decisions can be made relating to the management of waste arisings and building supplies made from recycled and secondary materials can be sourced, to help alleviate the demand for primary materials such as virgin sand and gravel. Early planning for waste arisings will help to establish what types of containers/skips are required for the project and when segregation would be best implemented for various waste streams. It will also help in determining the costs of removing waste from the site.

As a minimum, the SWMP should include the following:

Project and People

- Identification of the client
- Identification of the Principal Contractor
- Identification of the person who drafted the SWMP
- Location of the site
- An estimated cost of the project
- Declaration that the client and contractor will comply with the requirements of Duty of care that materials will be handled efficiently and waste managed appropriately (Section 34 of Environmental Protection Act 1990 and Environmental Protection (Duty of Care) Regs 1991)

Estimating Waste

- A description of the types of waste that are expected to arise on site (recorded through the use of 6-digit European Waste Catalogue codes) and an estimated quantity for each of the types (in tonnes)
- Waste management actions for each waste type (i.e., will the waste be re-used or recycled (on-site or off-site?), recovered or disposed of)

Space for Later Recordings

- Space for the recording of actual figures against the estimated figures
- Space for the recording and identification of those responsible for removing the waste from site and details of the sites they will be taking it to
- Space to record explanations for any deviations from what has been set out in the SWMP, including explanations for differences in actual waste arisings compared to the estimates

As a SWMP has not been produced at the planning application stage, the Waste Planning Authority request the following pre-commencement condition be attached to any approved planning application:

Condition: No development shall take place until a Site Waste Management Plan (SWMP) for the site has been submitted to the Local Planning Authority and approved in consultation with the Waste Planning Authority. The SWMP should aim to reduce the amount of waste produced on site and should contain information including estimated types and quantities of waste to arise from construction and waste management actions for each waste type. The development shall be carried out in accordance with the approved SWMP.

Reason: To promote the sustainable management of waste arisings and contribution towards resource efficiency, in accordance with Policy 12 of the Hertfordshire Waste Core Strategy and Development Management Policies Development Plan Document (2012).

Hertfordshire Fire and Rescue Service (Hydrants only) have no formal comments at this time but should the project go forward, we would seek a condition that any Fire Hydrants Required are at no cost to the service.

9.13 Hertfordshire Archaeology: [No objection subject to conditions]

No heritage assets of archaeological interest are known from within the proposed development site. However, as noted in the Heritage Assessment report submitted with the planning application, there is an underlying potential for prehistoric activity, which would be of regional significance. The site has not been subject to significant development or other disturbance, and according to the same Heritage Assessment, cartographic evidence shows the development site has remained largely untouched since at least 1766. As a result, it is likely that if any archaeological remains are present on the remainder of the site, they are well preserved.

A Geophysical Survey carried out in September of 2024 revealed a number of anomalies within the site. Although none of these anomalies could be confidently identified as archaeological in origin, there were anomalies where archaeological origin could not be ruled out either. In particular, a group of anomalies were identified in Area 2, which form rectangular patterns that may relate to buildings or other structures. Given that maps from the post-medieval period show no indication of buildings within the site, these anomalies could potentially date to the a much earlier period, if found to be archaeological in nature.

Therefore, I believe that given the size and scope of the proposed development, it should be regarded as having the potential to have an impact on heritage assets of archaeological interest, and I recommend that the following provisions be made, should you be minded to grant consent:

1. the archaeological field evaluation of the proposed development area, via trial trenching, prior to development commencing;
2. such appropriate mitigation measures indicated as necessary by that evaluation.
These may include:
 - a. the preservation of any remains *in situ*, if warranted,
 - b. appropriate archaeological excavation of any remains before any development commences on the site, with provisions for subsequent analysis and publication of results,
 - c. archaeological monitoring of the groundworks of the development (also including a contingency for the preservation or further investigation of any remains then encountered),
 - d. such other provisions as may be necessary to protect the archaeological interests of the site;
3. the analysis of the results of the archaeological work with provision for the subsequent production of a report and an archive, and the publication of the results;
4. such other provisions as may be necessary to protect the archaeological interests of the site;

I believe that these recommendations are both reasonable and necessary to provide properly for the likely archaeological implications of this development proposal. I further believe that these recommendations closely follow the policies included within Policy 16 (para. 218, etc.) of the National Planning Policy Framework, and relevant guidance contained in the National Planning Practice Guidance, and in the Historic Environment Good Practice Advice in Planning Note 2: Managing Significance in Decision-Taking in the Historic Environment (Historic England, 2015).

In this case three appropriately worded conditions on any planning consent would be sufficient to provide for the level of investigation that this proposal warrants. I suggest the following wording:

A No demolition/development shall take place/commence until an Archaeological Written Scheme of Investigation has been submitted to and approved by the local planning authority in writing. The scheme shall include an assessment of archaeological significance and research questions; and:

- 8. The programme and methodology of site investigation and recording***
- 9. The programme and methodology of site investigation and recording as required by the evaluation***
- 10. The programme for post investigation assessment***
- 11. Provision to be made for analysis of the site investigation and recording***
- 12. Provision to be made for publication and dissemination of the analysis and records of the site investigation***
- 13. Provision to be made for archive deposition of the analysis and records of the site investigation***
- 14. Nomination of a competent person or persons/organisation to undertake the works set out within the Archaeological Written Scheme of Investigation.***

B The demolition/development shall take place/commence in accordance with the programme of archaeological works set out in the Written Scheme of Investigation approved under condition (A)

C The development shall not be occupied/used until the site investigation and post investigation assessment has been completed in accordance with the programme set out in the Written Scheme of Investigation approved under condition (A) and the provision made for analysis and publication where appropriate.

If planning consent is granted, I will be able to provide detailed advice concerning the requirements for the investigations, and to provide information on professionally accredited archaeological contractors who may be able to carry out the necessary work.

I hope that you will be able to accommodate the above recommendations.

9.14 Hertfordshire and West Essex ICB: [No objection subject to S106 contributions]

9.14.1 Initial comments 18.2.25 [No objection, on site provision or contributions requested]

Thank you for consulting the Hertfordshire and West Essex Integrated Care Board (HWE ICB) on the above-mentioned planning application.

Please accept this letter as the HWE ICB's position on primary healthcare capacity and need arising from this planning application and the health financial contribution sought if TRDC is minded to grant planning permission.

The HWE ICB became a statutory body on 1 July 2022 and is the health commissioner responsible for delivering joined up health and social health care to a population of c1.5m. in Hertfordshire and west Essex.

The HWE ICB works in partnership with health providers, local authorities, and other organisations to:

- improve the general health and wellbeing of Hertfordshire and west Essex residents and improve health care services in the area.

- tackle the inequalities which affect people's physical and mental health, such as their ability to get the health services they need, and the quality of those services help tackle health and wider inequalities.
- get the most out of local health and care services and make sure that they are good value for money.
- help the NHS support social and economic development in Hertfordshire and west Essex.

A strategic aim of the NHS HWE ICB is the improvement of primary, community and mental health care outside of hospitals. To achieve this, the NHS commissions a number of services from general practices in addition to their "core" activity. On the ground this means more joined up care, for example, primary and community healthcare hubs with co-ordinated multidisciplinary professionals/ teams. Therefore, a doctors' general practitioners' surgery may also include an ancillary pharmacy and ancillary facilities for treatments provided by general practitioners, nurses and other healthcare professionals to provide care to residents.

Primary Care Networks (PCNs)

Within the HWE ICB there are 35 PCNs across the 14 localities, each covering a population of between circa 27,000 and 68,000 patients. PCNs are expected to deliver services at scale for its registered population whilst working collaboratively with acute, community, voluntary and social care services to ensure an integrated approach to patient care.

Patients are at liberty to choose which GP practice to register with, providing they live within the practice boundary. However, most patients choose to register with the surgery closest and/or most easily accessible to their home for the following reasons: walking distance, quickest journey time, accessibility by public transport, parking provision.

Despite premises constraints GP Practices are not allowed to close their lists to new registrations without consultation with, and permission from the HWE ICB. Even when surgeries are significantly constrained, the NHS will seek to avoid a situation where a patient is denied access to their nearest GP surgery, with patient lists only closed in exceptional circumstances.

The HWE ICB keeps up to date PCN patient lists and closely monitors the current and future capacity of GP surgeries against Local Plan allocations/ housing trajectories.

The HWE ICB also ranks PCNs using existing premises data and known development data. This will identify and rank hotspots across the PCN patch where there is a need to explore projects to increase capacity, for example, by either re-configuring, extending or relocating GP practices to provide sufficient space to increase resources and clinical services to keep patient lists open.

Assessment of impact on existing Healthcare Provision

The HWE ICB has assessed the impact of the proposed development on existing primary health care provision in and around the vicinity of Croxley Green. This scheme is expected to deliver 600 homes, which based on an average occupancy of 2.4 will create circa 1,440 new patients.

These new residents will impact on Grand Union PCN, which is formed of 2 GP practices and has a combined patient list of 26,388 as of 1 January 2025.

In terms of premises need and priority, Grand Union PCN is ranked 4th out of 35 PCNs in the HWE ICB. To illustrate their current capacity, individually as well as collectively - on PCN as well as settlement level please see the table below:

			Settlement level				PCN level		
Surgery Name	Settlement/ Area	PCN	Number of patients capacity/ constraint relative to 18 per m2	Number of patients capacity/ constraint	Total NIA capacity/ shortfall	Capital impact of existing capacity/ shortfall	Number of patients capacity/ constraint	Total NIA capacity/ shortfall	Capital impact of existing shortfall
Bridgewater House Surgeries (Meriden)	North Watford/ Garston	Bridgewater	-825	-9,836	-546	£3,825,224			
Bridgewater House Surgeries (North)		Bridgewater	-1,815						
Garston Medical Centre	Croxley	Grand Union	-7,697	-3,711	-206	£1,443,034	-11,407	-634	£4,436,118
Baldwins Lane Surgery		Grand Union	-152						
New Road Surgery		Grand Union	-3,113						
Church Lane Surgery		Grand Union	-446						
Bridgewater House Surgeries	West Watford	Bridgewater	594	-1,378	-77	£0			
Holywell Surgery		Attenborough	-1,972						

*For the purposes of capacity assessment, we have adopted an alternative calculation to the NHS England "Principles of Best Practice" (referred to below) based on 18 patients per m2, which has regard to national GMS space guidelines but also considers opportunities for economies of scale.

This table demonstrates that both practices – New Road Surgery, including its branch surgeries and Garston Medical Centre - are already constrained and their ability to accept additional patients is limited. The closest practice to the proposed development is New Road Surgery and its branch on Baldwins Lane. Both surgeries are operating out of converted residential buildings which do not meet the needs of the modern General Practice or NHS building guidelines.

In reviewing the PCN data and as explained above, New Road Surgery and its branches will be unable to accommodate the additional patient numbers arising from this development, and indeed potential future housing growth in and around the vicinity of Croxley Green. In reviewing all options, the HWE ICB has concluded that new health infrastructure in the form of on-site provision for a new medical facility will be needed to accommodate additional patient numbers arising from this development.

In the light of the HWE ICB's response to this outline planning application, it would be sensible for the HWE ICB to meet with the Council and the applicant to discuss in more detail the NHS' site and primary and community healthcare requirements, and the draft Heads of Terms.

NHS GP premises and funding

By way of context, GP Practices are independent contractors that deliver NHS services - in most cases through General Medical Services (GMS) contract. In line with their contract, they receive payments for the delivery of GMS services as well as reimbursements of their premises costs.

According to the terms of their GMS contract, GP contractors receive rent from NHS for using their premises (which they either own or lease) to provide NHS services from. In line with NHS Premises Costs Directions 2024, for the premises that the GP's own, NHS pays

Current Market Rent (i.e. fair and reasonable rent as determined by the District Valuer). For leased premises, NHS reimburses the lease rent that they pay to their landlord (also as verified by the District Valuer). In addition, NHS reimburses business rates and water rates.

If new and/or extended surgery buildings are required, these can be funded in various ways:

- NHS capital investment in the building works – GP practice will sign a Grant Agreement and as a result, their rent reimbursement is abated proportionately to reflect the amount of capital invested for a specified time period in line with NHS Premises Costs Directions 2024.
- S106/CIL investment in the building works – as above, treated in the same way as NHS capital investment.
- Capital investment by the practice.
- Capital investment by the landlord/third party developer.

In the latter two cases, where there is no NHS capital investment, yet the NHS receives the benefit of an increased and/or improved building, there is an increase in either the Current Market Rent (GP owned) or the lease rent (leased building) and the NHS commissioner will be liable for that additional revenue consequence. It should be noted that because all GMS contracts are contracts in perpetuity, the NHS will be liable for these costs indefinitely.

Please note, all NHS health infrastructure improvement projects are subject to the HWE ICB's own governance and scrutiny processes and are assessed against viability, affordability, deliverability and the ability to be future proofed for any future housing growth, given that new medical facilities present a significant cost pressure to the NHS.

Therefore, in terms of the HWE ICB's formal commitment to the proposal for a new on-site medical facility at **Land north of Little Green Lane, Croxley Green**, at this stage the following points must be considered:

- All projects are subject to Full Business Case approval by the ICB and NHS England.
- A commercial arrangement has to be agreed between the landowner, developer and end user based on a compliant design specification and demonstrate value for money.
- A project identified and costed in response to the planning application may not meet the objectives of NHS current strategies or could have significantly increased in cost, especially if there has been any significant time lapse from the date of the response to the date of implementation of the planning consent.

In the event the HWE ICB cannot support the delivery of a new medical centre at this location for viability, affordability and deliverability reasons, the HWE ICB will seek a financial contribution as calculated below.

Cost calculation of additional primary care healthcare services arising from the development proposal

The financial contribution for health infrastructure that the HWE ICB is seeking, to mitigate the health impacts from this development has been calculated using a formula based on the number of units proposed and does not take into account any existing deficiencies or shortfalls in Croxley Green and its vicinity, or other development proposals in the area.

The proposed development would deliver 600 dwellings, which based on an average occupancy of 2.4 occupants per dwelling will create circa **1,440 new patient registrations**.

1,440 new patient registrations/2000 = 0.72 of a GP

*GP based on ratio of 2,000 patients per 1 GP and 199m² as set out in the NHS England "Premises Principles of Best Practice Part 1 Procurement & Development"

0.72 x 199 m² = 143.28 m² of additional space required

143.28 m² x £7,000* per m² = £1,002,960 (*Build cost; includes fit out and fees)
£1,002,960 / 600 = £1,671.60 per dwelling (rounded up to £1,672 per dwelling)

Total GMS contribution requested: 600 dwellings x £1,672 per dwelling = £1,003,200
(indexed from the date of the planning permission)

If planning permission is granted, and in the event the HWE ICB cannot support the delivery of a new medical centre at this location for viability, affordability and deliverability reasons, the HWE ICB propose to focus Section 106 monies on the relocation of New Road Surgery which explores options for a new medical facility within the locality to accommodate additional patient numbers arising from this development and future housing growth in and around Croxley Green.

It is also vital to consider the impact of new development, and the additional residents on community and mental healthcare, as occupiers of the development will also access a variety of healthcare. Based on recent cost impact forecasting calculations, the cost impact on community and mental healthcare is as follows:

Mental Health costs:

600 dwellings x £338.92 per dwelling = £203,352

Community Healthcare costs:

600 dwellings x £352.68 per dwelling = £211,608

Section 106 contributions towards these services support for the Croxley Green area will be focused on the proposed integrated Health Hub at Watford Town Hall Quarter, which is planned to include reprovision of the Avenue Clinic (current building is to be demolished). Contributions would be allocated to the Community Services provider Hertfordshire Community NHS Trust and the Mental Health Services provider Hertfordshire Partnership NHS Foundation Trust.

The HWE ICB therefore requests that these sums are secured through a planning obligation attached to any grant of planning permission.

A trigger point of payment on occupancy of the 1st Dwelling is requested for GMS and community and mental healthcare planning obligations. Please note, the developer contribution figure(s) referred to in this response are a calculation only and that the final payment will be based on the actual dwelling unit mix and the inclusion of indexation.

Subject to securing the healthcare infrastructure and/or the developer contributions, as set out above, to mitigate the health service impacts arising from this development, the HWE ICB does not raise an objection to the proposed development.

The HWE ICB looks forward to working with the Council and the applicant to address the matters raised in this consultation response and would appreciate acknowledgement of receipt of this letter.

9.14.2 Further comments 15.12.25 [No objection subject to S106 contributions]

Thank you for consulting the Hertfordshire and West Essex Integrated Care Board (HWE ICB) on the above-mentioned planning application. Please accept this letter as the HWE ICB's updated position on primary and community and mental healthcare capacity and need arising from this planning application and the health infrastructure and financial contributions sought if the Council is minded to grant planning permission.

The HWE ICB, as the health commissioner responsible for delivering health and social health care to a population of c1.5m, works closely with all 13 Local Planning Authorities

within Hertfordshire and west Essex to ensure patients have access to good health infrastructure, for both existing and new residents.

This proposed scheme is expected to deliver 600 homes, which based on an average occupancy of 2.4 will create circa **1,440 new patients**. These new residents will impact on Grand Union PCN, which is formed of two GP practices. New Road Surgery in Croxley Green with its two branch surgeries forms a part of Grand Union PCN together with Garston Medical Centre and its branch surgery in Garston Clinic. The latter two are based in Garston, i.e. on the opposite side of Watford town, thus sharing capacity and resources is not always practical.

New Road Surgery, including its branch surgeries and Garston Medical Centre are already constrained and their ability to accept additional patients is limited. The closest practice to the proposed development is New Road Surgery and its branch on Baldwins Lane. Both surgeries are operating out of converted residential buildings which do not meet the needs of modern General Practice or NHS building guidelines.

The HWE ICB fully recognises, substantiated by a primary care capacity assessment, that there is a clear need to address primary healthcare provision in Croxley Green. A new medical facility, within this development would allow the co-location of New Road, Baldwins Lane and Sarratt branch surgery to a new, purpose-built premises in line with the needs of a modern General Practice.

The HWE ICB can therefore confirm its support 'in principle' to a new medical centre at land north of Little Green Lane, Croxley Green, subject to the approval of a full business case by the HWE ICB's Primary Care Commissioning Committee (PCCC).

To confirm, the developer Richborough Estates has agreed to build the 'shell' of the medical facility on the ground floor of a residential building, with the 'fit out' funded by a combination of a financial contribution from the developer of **£1.85m** and CIL (Community Infrastructure Levy) of **£850k**. For your information, the HWE ICB will be submitting a CIL bid to the Council in January 2026 for its consideration.

In the new year the HWE ICB will continue to liaise closely with New Road Surgery and the developer, but in the meantime requests our immediate engagement in the draft Section 106 Agreement/ Heads of Terms.

In the new year the HWE ICB will continue to liaise closely with New Road Surgery and the developer, but in the meantime requests our immediate engagement in the draft Section 106 Agreement/ Heads of Terms.

As per the HWE ICB's consultation response dated 18th February 2025, the HWE ICB is also seeking financial contributions for community and mental healthcare. Based on recent cost impact forecasting calculations, the cost impact on community and mental healthcare is as follows:

Mental Health costs:

600 dwellings x £338.92 per dwelling = £203,352

Community Healthcare costs:

600 dwellings x £352.68 per dwelling = £211,608

Section 106 contributions towards these services, which will support the Croxley Green area, will be focused on the proposed integrated Health Hub at Watford Town Hall Quarter, which is planned to include re-provision of the Avenue Clinic (current building is to be demolished). Contributions would be allocated to the Community Services provider

Hertfordshire Community NHS Trust and the Mental Health Services provider Hertfordshire Partnership NHS Foundation Trust.

The HWE ICB therefore requests that these sums are secured through a planning obligation attached to any grant of planning permission.

A trigger point of payment on occupancy of the 50th Dwelling is requested for GMS and community and mental healthcare planning obligations. Please note, the developer contribution figure(s) referred to in this response are a calculation only and that the final payment will be based on the actual dwelling unit mix and the inclusion of indexation.

Subject to securing the healthcare infrastructure and the developer contributions, as set out above, to mitigate the health service impacts arising from this development, the HWE ICB does not raise an objection to the proposed development.

9.15 Hertfordshire Constabulary: No objection

9.15.1 Initial comments 28.07.25 [Concerns]

My comments are from a crime prevention and security perspective only.

I do have concerns regarding security for this development, although it has been mentioned in the Design and Access statement (creating a safer place to live, 6.170, page 110). "The design proposals for the site are based on an understanding of best practice guidance and reference has been made to the relevant documents including "Safer Places: The Planning System" and "Manual for Streets as well as ACPO "New Homes" guidance."

Regarding a development of this size with 70% affordable housing, 25% first homes and 5% shared ownership I would expect to see far more detail and information relating to crime prevention and security. Experience has shown that if this is not considered at the outset, the development will become a place where no one wants to live. The houses and local area become run down, an increase in the fear of crime affecting residents' wellbeing, also it decreases sustainability as people move out, there is a rise in crime and therefore a greater demand on the police.

I would ask if this application were granted I will have the opportunity to discuss security with the client and architects.

9.15.2 Further comments 22.09.25 [No objection]

I am now able to support this application as I am content that security measures have been considered and will be implemented for this development.

9.16 Hertfordshire Ecology: [No objection subject to conditions]

9.16.1 Initial comments 10.2.25 [Further information prior to determination]

Overall Recommendation:

☒ Further information/amendments required prior to determination.

Summary of Advice:

- Further information required in relation to Schedule 1 birds – Red kite breeding surveys should be undertaken.
- Condition 1 – CEMP.
- Condition 2 – Pre-commencement badger survey.

- Condition 3 – Lighting Design Strategy for bats.
- Condition 4 – Biodiversity Enhancement Plan.
- Condition 5 – Mitigation and Monitoring Plan for Green Lane Wood LWS (irreplaceable habitat).
- BNG sufficient for determination – Significant BNG requiring HMMP Condition (Condition 6).

Supporting documents:

- Ecological Impact Assessment and Biodiversity Impact Assessment (RammSanderson, December 2024).
- Biodiversity Metric.

Comments:

The site is situated in an area of high ecological importance, with multiple Local Wildlife Sites (LWS) adjacent to the site boundaries including Jacotts Hill/West Herts Golf Course, Dell Wood, and Merlin's Wood and Newland's Spring. Whippendell Wood SSSI is also adjacent at the northern boundary. The site itself is dominated by cropland, however an area of ancient woodland is present at the east of the site, which is classified as an irreplaceable habitat. This area of on-site ancient woodland is designated as Green Lane Wood LWS. Other habitats on-site comprise rural trees, native hedgerows with trees, and native hedgerow.

An Ecological Impact Assessment and Biodiversity Impact Assessment document has been submitted (RammSanderson, December 2024) whereby the site was assessed for its potential to host protected/notable species. We have no fundamental objections to the proposals, however the below regarding nesting birds will need addressing prior to determination.

Protected species:

Bats: Walked Bat Transect Surveys and Static Bat Detector Surveys were undertaken across the site between May and September 2024. The site was confirmed to be utilised by nine species of bat – common pipistrelle, soprano pipistrelle, Nathusius pipistrelle, noctule, Leisler's, serotine, Natterer's, brown long-eared, and barbastelle. However, most of the bat activity was owed to common and soprano pipistrelles, and noctules. The bat activity on site was assessed to be of nature conservation importance at the local level.

A Ground Level Tree Assessment (GLTA) for bats was undertaken, with results indicating that eight trees on-site either had potential for individual roosting bats, or multiple roosting bats. It should be noted that the trees within the ancient woodland will also have value for roosting bats, however given the proximity of the woodland to the proposed houses, I do not consider further assessment for these trees is required.

The eight trees with potential for roosting bats are situated in close proximity to the built development, with what looks to be driveways adjacent to the one of the trees identified to have roosting features. No lighting proposals have been included as part of the application.

GCN and reptiles: The site was deemed unsuitable for great crested newts given the lack of ponds in vicinity, and the lack of terrestrial habitat on-site, which I do not dispute. Most of the site was deemed to be of sub-optimal for reptiles, however the boundary features could provide opportunities for a small number of reptiles. Further surveys were not deemed proportionate.

Badgers: Two single-hole outlier sets were found within the site boundary, along with other signs of badgers such as footprints, latrines, and snuffle holes. A live badger was also

identified during the survey. The ecologist has noted that further sett excavation can occur prior to construction, therefore a pre-commencement badger survey is required.

Birds: A total of 22 bird species were recorded within the site, four of which are red listed (greenfinch, mistle thrush, common swift, and skylark). A large portion of birds were assessed to be “possibly breeding”, and this includes red kite which is listed as a schedule 1 species. Schedule 1 birds are afforded additional protection during the nesting period whereby it is an offence to disturb them or their young while they’re nesting, building a nest, in or near a nest that contains their young.

The ecologist has recommended that nesting bird surveys specifically for red kites should be carried out. If breeding is therefore confirmed onsite, further mitigation should be implemented which is listed in s4.10.2 of the ecology report. Given the size of the development and significant disturbance it would cause, **I advise that the nesting bird surveys for red kites should be carried out prior to determination.** The results should then be included in a report, with any appropriate mitigation measures included in the below CEMP to ensure no schedule 1 species are disturbed during the works.

Habitats:

No areas of ancient woodland will be lost to the development, and no existing trees or groups of trees on site will require removal. The EcIA has noted that a 30m buffer has been implemented from the areas of built development to Green Lane Wood LWS.

Given the proximity of the built development to the Whippendale Wood SSSI, I do not consider there will be any adverse impacts on this important habitat, similarly to the adjacent Dell Wood, Jacotts Hill/West Herts Golf Course, and Merlin’s Wood and Newland’s Spring. However, the below Condition will ensure that no indirect impacts occur on the above important habitats.

Biodiversity Net Gain: The baseline habitat units stand at 82.25BU. Given the presence of an irreplaceable habitat onsite, the woodland does not count towards the baseline. No bespoke compensation is required since this woodland is to be retained. The total net unit change for habitats is 28.30BU which equates to a biodiversity net gain of 34.41%. This net gain is owed to the creation of other neutral grassland, modified grassland, mixed scrub, allotments, bioswale, shrubs, vegetated gardens, and urban trees. The landscape plan shows that an orchard will be created, albeit the size of this orchard will be very small. This has not been included in the metric calculation for habitat creation, however since BNG is a pre-commencement matter, this is not a constraint at this stage.

The country park proposals have not fully maximised opportunities for ecological enhancements. All the area north of the bridleway, which itself should be bordered by a hedge on at least its north side, should be a priority for biodiversity and be managed as such. Currently this does not seem to be proposed, although access here is proposed to be limited which is welcome. This area could support areas of wood pasture/parkland creation with some scattered trees. This would provide a better-quality buffer zone of the landscape between the development and the important habitats adjacent to the site. Again, this is not a constraint at this stage, however the BNG proposals should ideally be revisited to maximise potential for biodiversity.

The baseline hedgerow units stand at 14.62BU. The total net change for this group is 4.36BU, which equates to a biodiversity net gain of 42.54%. Some hedgerows will be retained, and further native hedgerows will be created.

I consider the proposed BNG is sufficient to advise determination of the application. The biodiversity gain condition will apply to this application, whereby a biodiversity gain plan will be submitted as part of this condition.

The claims for BNG for this site would be considered as 'significant' net gain. This is because of the creation of medium distinctiveness habitats. In this instance the LPA are advised to secure this significant net gain for the respective habitat units via legal agreement whether through an S106 agreement or conservation covenant.

Conditions

Condition 1: Given the presence of multiple wildlife sites both within the redline boundary, and adjacent, **I advise that a Construction Environmental Management Plan (CEMP) should be submitted as a Condition of approval.**

No development shall take place (including demolition, ground works, vegetation clearance) until a Construction Environmental Management Plan (CEMP: Biodiversity) has been submitted to and approved in writing by the local planning authority. The CEMP (Biodiversity) shall include the following.

- *Risk assessment of potentially damaging construction activities.*
- *Buffer zones to be implemented to protect onsite and adjacent habitats.*
- *All mitigation recommended in the ecology report (RammSanderson, December 2024) for local wildlife sites and habitats (Section 4 to 4.6 in the report).*
- *Identification of "biodiversity protection zones".*
- *Practical measures (both physical measures and sensitive working practices) to avoid or reduce impacts during construction (may be provided as a set of method statements).*
- *The location and timing of sensitive works to avoid harm to biodiversity features.*
- *The times during construction when specialist ecologists need to be present on site to oversee works.*
- *Responsible persons and lines of communication.*
- *The role and responsibilities on site of an ecological clerk of works (ECoW) or similarly competent person.*
- *Use of protective fences, exclusion barriers and warning signs.*

The CEMP shall also include the mitigation in the ecology report for the protected species listed below:

- *Reptiles (s4.7 of the report).*
- *Bats (s4.8 of the report).*
- *Nesting birds (subsequent to mitigation informed by the red kite breeding surveys).*
- *Badgers (s4.11; iv precautionary work measures).*

The approved CEMP shall be adhered to and implemented throughout the construction period strictly in accordance with the approved details, unless otherwise agreed in writing by the local planning authority.

Condition 2: Given the known presence of badgers onsite, **a pre-commencement badger survey should be submitted as a Condition of approval.**

A pre-commencement survey for badgers shall be undertaken prior to the commencement of the development. This survey shall determine whether the current outlier setts are still active and thus require closure, or if any additional setts have been excavated. The results of this badger survey should be submitted to the LPA for approval.

Condition 3: Given the presence of bats making use of the site for foraging and commuting, **I advise that a Lighting Design Strategy for bats should be submitted as a Condition of approval.**

Prior to occupation, a lighting design strategy for bats shall be submitted to and approved in writing by the LPA. This should accurately identify the features/areas of interest, describe levels of illumination prior to, during, and post-development, and should be shown in suitable contour plans and charts so that it can be clearly demonstrated that lit areas will not compromise existing use.

Proposed lighting should accord with best practice (Bats and artificial lighting in the UK, (BCT & ILP) and maintained accordingly. No further external lighting should be added unless agreed with the LPA. These proposals should also be accompanied by a statement by an ecologist on how it achieves these goals.

Condition 4: Biodiversity enhancements have been recommended in the ecology report (s4.13). **I advise that these should be incorporated into the development plan and outlined in a Biodiversity Enhancement Plan, secured by Condition.**

A Biodiversity Enhancement Plan shall be submitted to the LPA as a Condition of approval. The Biodiversity Enhancement Plan shall include the following:

- *Installation of one integrated swift brick per dwelling (north facing).*
- *Installation of one integrated bat box per dwelling (south facing).*
- *Bat and bird boxes on retained trees.*
- *Hedgehog highways – one hedgehog hole per garden fence.*

Condition 5: Taking into account the presence of an irreplaceable habitat onsite (Green Lane Wood LWS), I advise that mitigation should be in place to ensure the habitat is maintained in its current condition and to allow for further measures if impacts are shown to be having a negative effect. Since this habitat is being retained and not enhanced, it is not included in the biodiversity metric calculations, therefore monitoring outside of the BNG process should be in place.

To prevent a reduction in the existing condition of Green Lane Wood LWS, a mitigation and monitoring plan shall be submitted as a Condition of approval. This plan shall outline mitigation measures, monitoring methodology and time frame and the bodies responsibilities for its implementation and any remedial action required.

Condition 6: Given that BNG for this site is significant, if the LPA were minded granting permission, a Habitat Management and Monitoring Plan (HMMP) should be added as a Condition of approval.

This shall demonstrate how the habitat enhancement and creation, and subsequent target habitat conditions on-site will be created, enhanced, and monitored over 30 years following the completion of the capital works required to create them. It is recommended that the HMMP should be in line with the HMMP template produced by DEFRA. Considerations should also be given within any legal agreement to secure resources to allow adequate monitoring over the 30-year period.

9.16.2 Officer comment: Further comments were received from the applicants' ecologist in relation to red kite surveys. In summary, as construction would not be taking place for some time, they considered that it would be premature to undertake the surveys at this time as it is vital that the red kite surveys are as current as possible to accurately inform mitigation measures. Therefore they suggested the detail of the pre-commencement survey requirements and associated mitigation measures should be secured by planning condition.

9.16.3 Further comments 27.2.25 [No objection subject to conditions]

As per the recommendation from the ecologist, I can confirm that completing pre-commencement red kite surveys will be sufficient. The results of the survey can be included in the already conditioned CEMP, along with any mitigation outlined by the ecologist.

9.17 Hertfordshire Highways: [No objection, conditions and S106 contributions requested]

9.17.1 Initial comments 28.2.25 [Objection – insufficient information]

Recommendation

Notice is given under article 22 of the Town and Country Planning (Development Management Procedure) (England) Order 2015 that Hertfordshire County Council as Highway Authority recommends that permission be refused for the following reasons:

There is insufficient information supplied with this application to enable the Highway Authority to reach a recommendation. In the absence of the necessary information, the Highway Authority recommends refusal due to doubt over possible implications for the free and safe flow of public highway users.

Access Comments

Durrants Drive - Little Green Lane junction there is clear evidence of vehicles over-running the grass verge, the proposed design will need to consider this issue in terms of the geometrical design and construction i.e the footway / cycleway will need to have suitable loading capacity for HGV's. Section of Durrants Drive from Dover Way to Little Green Lane more heavily parked due to housing layout and several properties not having driveway provision. This creates a situation with vehicles parking on the footways, traffic movement through this section will be problematic with development traffic creating congestion.

The proposed footpath / cycleway along Canterbury Way as it passes over Little Green Lane will require further design consideration, currently the proposal shows the route crossing the existing road we are assuming that the levels are the same as the existing footway so a raised table would be required at this junction.

Dover Way between the junction of Canterbury Way and Links Way narrower than both Durrants Drive and Links Way noticeable parking occurring on footways. If the road is narrowed to introduce a pedestrian / cycle link this issue will need to be considered. Also, at the junction of Canterbury Way / Dover Way the northern kerblin on the western side of the junction would also need to be realigned with some hatching provided otherwise vehicles travelling in an eastbound direction will be swerving by the junction as they try to avoid the footpath/cycleway build out.

We require a Stage 1 Safety Audit for the access options.

Cycle Route Comments

The proposed shared footway/cycleway will be located along the northeastern side of Canterbury Way, the existing width is approximately 3.0m wide some minor widening works may be required subject to detailed design. This section has the lighting columns set at the back of the footway which assists in providing a continuous width for pedestrians and cyclists, there are two highway trees near to the junction with Dover Way that will need to be removed. The route then joins onto Dover Way this section of the route will be located on northern side, the route will require the widening to provide a shared footway/cycleway. The lighting columns set at the back of the footway however three trees are located in the footway these will need to be removed. Cyclists will then cross Dover Way near to the junction with Links Way using the proposed raised table and the head along Links Way. This section of the route will be located on the western side of the road, the route will require

the widening to provide a shared footway/cycleway. There are telegraph poles and lighting columns located at the front of the existing footway that will obstruct the proposed route once the widening occurs. This infrastructure should be relocated to the back of the footway. Two trees are located along the route these will need to be removed.

We require a Stage 1 Safety Audit for the cycle out options.

TA – General Comments

Traffic Data

Paragraph – 3.14 and 3.15 lists the location of the classified turning counts and 3.16 states that these along with the queuing data are included in Appendix B. Some of the counts are missing and there is no queuing data included for any of the junctions listed. Also, the baseline flows listed as Figures 3.1 to 3.4 in paragraph 3.9 have also not been included. Without this information we are unable to review any of the modelling outputs or check the flow diagrams for baseline and future year scenarios.

Accident Data

Paragraph 3.20 refers to the review of Personal Injury Accidents along the site frontage and in the vicinity of the site with locations identified in Appendix D. It appears that several locations identified on the image in Appendix D have not been referred to in Table 1. An example is along Rousebarn Lane and the link to north of Croxley Danes School where it appears that three slight accidents and one severe accident has occurred. Also, the image shows a fatal accident along Sarrat Road, please explain why these locations have not been included and if other locations have been discounted, please provide a list and an explanation of why. The route along Rousebarn Lane could be well used by both pedestrians and cyclists so we wish to see this area included.

Accessibility by Foot / Walking Audits

This proposed development needs to promote as many options as possible in terms of providing alternative modes of travel beyond site boundary. The new proposed pedestrian / cycle links to the south of the site provides one set of measures. However, as part of this application other routes to the east need further consideration.

indicative active travel image as set out on page 147 of the Design Access Statement Design Code shows internal footpath/cycleways connecting onto footpath Sarratt 017 which connects onto Watford Borough 031 this provides a route through Cassiobury Park to Watford Railway Station this route is approximately 2.8km. It has not been included in the Walking Audit but provides another opportunity of promoting connectivity to the site.

This proposed development needs to promote as many options as possible in terms of providing alternative modes of travel to residents and as such we would be seeking improvements to these routes. The Transport Consultant should firstly audit the route via Sarratt 017 / Watford Borough 031 via Cassiobury Park and identify where improvements could be made and costing provided.

With regards to the alternative route to Watford Station via Rousebarn Lane this route is the shortest route to the railway station, there are opportunities to improve this route. The Transport Consultant should provide a series of measures to enhance this route for both walking and cycling and provide costings.

Accessibility by Bus

Paragraph 4.50 of the Transport Assessment indicates that to enhance the appeal of using public transport from the proposed development, it is proposed to bring a service into the site to serve Watford and important transport hubs along with major destinations between the site and Watford.

We have noted that there is no information regarding the anticipated service provision, or which existing route will be diverted into the site. Or is the bus route a new service that will serve the destinations described above? Will any additional stops be provided along Durrants Drive to serve this existing residential catchment for this service?

Secondly there is no evidence that any dialogue has taken place with bus operators. The introduction of a bus service into the site, is one of many measures to assist in promoting sustainable travel options for residents, as it is imperative that a bus service is provided and therefore, we will require further evidence that this is supported by the bus operators along with costings for the service. So this can be incorporated into the Section 106 agreement.

Paragraph 4.77 states that bus stops and shelters will be on site along with real time bus information.

Chapter 5 set out details of the development proposals with reference to the site access strategy paragraph 5.4 indicates that existing width of Durrant Drive will be maintained, with buses entering the site from Durrants Drive completing a loop around the primary street network and exiting the site along Durrants Drive. Durrants Drive will have priority over Little Green Lane for motor vehicles, cycles and pedestrians.

Accessibility by Rail

It is noted that as part of this proposed development it will provide a suitable contribution towards the implementation of step-free access at Croxley Underground station. This will need to be finalised so it can be secured via S106 contribution if the application is considered for approval at a later date.

Car Parking

Paragraph 5.10 states that "Sufficient car parking for the site will be provided in accordance with Three Rivers and Hertfordshire County Councils Parking standards to provide on plot parking spaces and secure cycle storage for residents of the development site, and to provide suitable levels of parking for staff at the school and at the local centre". Firstly, Hertfordshire County Council do not have any parking policy this is set by the LPA.

Paragraph 5.14 and 5.15 sets out reduced levels of parking for the local centre. The proposed level of parking is 126 spaces, with the emerging LP requirement listed as requiring 166 spaces, thus a 40-space shortfall is being delivered. Paragraph 5.17 states the following "*The main purpose of the provision of the local centre on the proposal site is to serve the needs of the development. Any such trips to the local centre from the development will predominantly be undertaken by walk or cycle and, therefore, typical parking standards will not apply*". However, a significant proportion of the shortfall relates to the residential element of the scheme, people living in this location are not travelling in from the wider development, so this rational would apply to this land use. If the local centre is going to be viewed as having reduced parking provision, then some form of parking controls will be required so parking is not abused by residents, and it is available to all visitors to the local centre.

It is unclear how the figure of 187 spaces quoted in paragraph 5.22 has been derived and what relevance it has to the parking provision quoted in paragraph 5.14 and 5.15.

Paragraph 5.23 states that "*community parking in Durrants Square (42 spaces) and close to the school (16 spaces), will not be assigned to any particular use. This proposal offers the ability of users to efficiently share parking and therefore minimise the amount of space taken up by parking in the development*". Refer to point above regarding the residential element of the scheme and the risk of overspill parking from this land use into this area.

Traffic Generations

We have reviewed the trip rates, and we have some concerns with the affordable housing trip rate that has been used. We appreciate that TRICS has limited sites available but after further reviewing the selected site it has come to our attention that site EX-03-B-01 has low levels of parking when compared to the other selected sites which is lowering the trips rates

This site should be deselected, and the trip rate calculations and all the supporting information should be updated to reflect the revised flows.

Traffic Impact and Assessment

The following points have been previously mentioned we have repeated them again under this section as they are fundamental to the review of the traffic impacts.

Figures 3.1 and 3.2 are missing so we unable to review the baseline flows and compare the information to the surveyed data. These figures should also include the PCU conversion factors so we can undertake checks. Subsequently we cannot confirm the future year flows as these use the baseline data as part of calculation process. This issue will also affect our ability to check the traffic matrices in the modelling outputs.

Appendix B includes junction location imagery and the manual classified turning counts, we have noted that some of counts are missing these should be provided.

Queue length survey information has not been included, this is referenced in the TA as some of junction modelling has been calibrated, please provide this information. Queue length surveys should have undertaken for several days to provide an accurate representation of current levels of queuing.

Junction Modelling

Appendix H - Site Access Junction – Little Green Lane (NE)/ Durrants Drive/ Little Green Lane (SW)

- Minor Arm visibilities have been set to 0m for two of the inputs we would expect any proposed access to provide adequate visibility provision to meet safety audit requirements, as two of the visibility inputs relate to visibility splays passing into the site from the minor arms this can be improved.
- Major Arm carriageway width is incorrectly inputted refer to the proposed junction design that has been submitted as part of this application.
- HGV matrix has all movements at zero baseline traffic data shows HGV's therefore this matrix should be updated.

Appendix I - Little Green Lane (NE) / Links Way / Little Green Lane (SW)

The submitted outputs relate to the junction of Baldwins Lane / Links Way these have been submitted in the wrong appendices.

- The major arm carriageway width has been incorrectly inputted.
- The minor arm has no flare, and the splitter island reduces the minor arm widths.
- HGV matrix has all movements at zero baseline traffic data shows HGV's therefore this matrix should be updated.
- Please provide a drawing showing the geometry measurements, we have concerns in relation to the inputs.
- The interaction of the Winton Drive junction which located 30m east of Links Way has the potential to create additional delays along Baldwin Lane, the road markings along the major arm have been modified so that the Winton Drive has a longer right turn storage capacity at the junction. The assessment should model the junctions as a staggered crossroad and the pedestrian crossing by the school should be included in the assessment, as this will create delays along major road especially in the AM Peak. New traffic survey and pedestrian counts will be required for this updated analysis. to address this point.

Appendix J - Baldwins Lane (W) / Links Way / Baldwins Lane (E)

The submitted outputs relate to the junction of Little Green Lane (NE) / Links Way / Little Green Lane (SW) these have been submitted in the wrong appendices. The following comments relate to the outputs within Appendix J for the junction of Little Green Lane (NE) / Links Way / Little Green Lane (SW)

- Minor Arm visibilities have been set to 0m for three of the inputs we would expect any proposed access to provide adequate visibility provision to meet safety audit requirements, as two of the visibility inputs relate to visibility splays passing into the site from the minor arms this can be improved.
- Major Arm carriageway width incorrectly inputted.
- HGV matrix has all movements at zero baseline traffic data shows HGV's therefore this matrix should be updated.

Appendix K – A412 Watford Road (W) / New Road / A412 Watford Road (E)

- The minor arm lane width of 2.2m is incorrect.
- Please provide a drawing showing the geometry measurements, we have concerns in relation to the inputs
- HGV matrix has all movements at zero baseline traffic data shows HGV's therefore this matrix should be updated.

Appendix L – Winton Drive / A412 Watford Road

- Please confirm the Major Arm carriageway width it is difficult to read the pdf document that has been submitted.
- HGV matrix has all movements at zero baseline traffic data shows HGV's therefore this matrix should be updated.

The modelling for the junction of A412 Watford Road and Winton Approach has been submitted in Appendix L by mistake.

Appendix M – Winton Approach / Watford Road

- Please provide a drawing showing the geometry measurements, we have concerns in relation to the inputs, the mainline carriageway has advisory cycle lanes along so it's unclear how the major arm width has been calculated.
- HGV matrix has all movements at zero baseline traffic data shows HGV's therefore this matrix should be updated.

Appendix N – Manor Way / Baldwins Lane / Repton Way

- Please provide a drawing showing the geometry measurements, we have concerns in relation to the inputs, for example Arm A has a flare of 3.3m it's clear that this arms approach onto the mini roundabout is relatively straight and no radius is provided until after the give way point so it's not possible to have a flare length of over 3m. This would apply to the other arms as well. Also, the distances to the next arm and entry corner kerb line distances raise some concerns.
- HGV matrix has all movements at zero baseline traffic data shows HGV's therefore this matrix should be updated.

Appendix O – A412 Watford Road (E) / Sea Cadets / A412 Watford Road (S) / Baldwins Lane / Car Panet.

- Please provide a drawing showing the geometry measurements, we have concerns in relation to the inputs, for example Arm D has an entry width of 5.4m however this approach has a two-lane entry, the existing lane widths are not 2.7m. Also, google imagery shows parking occurring after the bridge which starves the nearside lane capacity, the geometry input shows arm D as having a flare of 22m it's unclear how this has been calculated and what assumptions are being made to the parking issue. The inscribed circle diameter for Arm E is 32m this also appears to be incorrect.
- HGV matrix has all movements at zero baseline traffic data shows HGV's therefore this matrix should be updated.

Appendix P – A412 Rickmansworth Road / Ascot Round Roundabout

- We have noted that within the TA reference is made to calibration being used for this junction. No information has been provided with the Transport Assessment in relation to queue length surveys.
- Please provide a drawing showing the geometry measurements, the entry width for arm A appears to be less than what has been inputted. Also, the radii for the arms appears to be incorrect.
- HGV matrix has all movements at zero baseline traffic data shows HGV's therefore this matrix should be updated.
- As this roundabout is so close to the Whippendell Road / Ascot Road roundabout they should be assessed as linked roundabouts, due to the lane configurations the modelling should consider lane simulation mode in ARCADY. The results show queues of between 25 - 41 vehicles in future year scenarios this level of queuing would block back onto the Whippendell Road / Ascot Road roundabout which is another reason why modelling the roundabouts as linked junctions may provide a more accurate assessment of the impacts.

Appendix Q – Raven Close / Whippendell Road / Ascot Road

- We have noted that within the TA reference is made to calibration being used for this junction. No information has been provided with the Transport Assessment in relation to queue length surveys.
- Please provide a drawing showing the geometry measurements, we have concerns in relation to the inputs, for example Arm A has the half width as 3.0m this is incorrect as Raven Close is narrower. Also, the flare length for Arm D appears to be incorrect. For Arm E the half width is shown as 10.0m and the entry width as 11.4 with a flare length of 10m, and the entry radius is shown as 25m. These inputted geometries are incorrect.
- HGV matrix has all movements at zero baseline traffic data shows HGV's therefore this matrix should be updated.
- As this roundabout is so close to the A412 Rickmansworth Road / Ascot Roundabout they should be assessed as linked roundabouts.
- Along Whippendell Road / Ascot Road there is a Premier Inn and Health Centre along with other land use and bus stops all of which could generate a reasonable level of pedestrian movements. Therefore, the pedestrian crossing facilities should have been surveyed and included in the ARCADY analysis as they could create delays that may result in queuing occurring onto the roundabout due to the close proximity.

Appendix Q – Durrants Drive / Baldwins Lane

- We have noted that within the TA reference is made to calibration being used for this junction. No information has been provided with the Transport Assessment in relation to queue length surveys.
- Please provide a drawing showing the geometry measurements, we have concerns in relation to the inputs, for example Arm C has a flare of 3.4m it's clear that this arms approach onto the mini roundabout is relatively straight and no radius is provided until after the give way point so it's not possible to have a flare length of over 3m. This would apply to the other arms as well. Also, the distances to the next arm and entry corner kerb line distances raises some concerns.
- HGV matrix has all movements at zero baseline traffic data shows HGV's therefore this matrix should be updated.

Design and Access Statement – comments

The indicative pedestrian cycle and movement strategy appears to have some discrepancies between the image and the key, this relates to the green routes where they appear to be described the wrong way around.

The plan shows two potential access/egress for cyclists and pedestrians only onto Little Green Lane these are identified with yellow arrows, the issue with the access located opposite Durant House is the narrowing of the footway on the southern side of Little Green Lane, if pedestrians exit at this location and wish to head towards Lincoln Drive they are

forced to work in the road especially if they have a child's buggy. By adding another connection west of the proposed access point would resolve this issue.

Travel Plan Review

General comments:

There is potential for this site to be sustainable, if adequate infrastructure and services are provided. If the site can be included in the Beryl Bikes scheme with a docking station on site this would help to encourage active travel, and a bus service diversion is proposed but no details given – this is required to make bus use more attractive as current bus stops are well over the recommended 400m away. According to the Travel Plan, contributions have been requested by TfL towards lifts at Croxley Underground station which would improve accessibility of the station for site residents and visitors.

This Travel Plan requires significant amendment in a number of key areas before we can approve, in particular in relation to the inclusion of clearly stated aims and objectives, Travel Plan Co-Ordinator duties and plan management, a wider range of measures, revised targets, monitoring method and travel plan duration.

As the Travel Plan is intended to cover the whole site, which is mixed use, the plan is a Framework Travel Plan. Individual Travel Plans will be required to be produced prior to occupation for land uses on site which meet the criteria set out in Appendix A of our Travel Plan Guidance (www.hertfordshire.gov.uk/travelplans). The primary school will also be required to produce an Education Travel Plan. The individual Travel Plans will be expected to be in general alignment with the Framework Travel Plan but with measures tailored to the land use in question.

Detailed comments are as follows:

Site details/introduction:

- The site location plan is provided as a figure in the appendix only and does not show the boundary of the site – usually a smaller version of the location plan is integrated into the main text at the relevant point which helps understanding of the geographical context and the site given a red line boundary to clearly illustrate its extent (as in the separate Location Plan provided as part of the application but not part of the Travel Plan).

Outcome objectives:

- There should be clearly stated aims and objectives for the Travel Plan in a dedicated section. The Travel Plan objective is not in Section 3 as stated, and whilst paragraph 5.1 comes close to being an objective it is not stated as such, nor are paragraphs 6.1-6.3 which also cover relevant ground, and obviously these paragraphs are not even together. There should be objectives around positive impacts on health/environment and reducing traffic impacts, levels of awareness of the Travel Plan, reducing the need to travel in the first place as well as reduction in single occupancy vehicle use mentioned in 5.1.

Travel Plan Management:

- Travel Plan Co-Ordinator contact details should be provided on appointment along with those of a secondary contact in case of personnel changes. Frequency on site and time allocated to the role should be provided once known and a list of expected duties is required now. These are all indicators for us that the role has been understood and sufficient resource (in terms of both people and funding) will be provided to undertake the role effectively.
- We require a statement of commitment to the robust implementation of the Travel Plan from a suitable member of developers' senior management prior to occupation – this is to demonstrate senior level commitment to the effective implementation of the plan.
- More detail should be given as to how the Travel Plan will be managed. As a Framework Travel Plan, with individual Travel Plans for land uses on site sitting beneath this, the Travel

Plan Co-Ordinator will be required to liaise between representatives of the different land uses and gather feedback on the effectiveness of measures and progress towards the overall objectives and targets within the Framework Plan. A Steering Group or similar which meets regularly and is formed of relevant stakeholders should be considered – this can improve levels of engagement and target initiatives more effectively.

Measures:

- Measures are generally appropriate although given the scale of the site, we would usually expect a wider range. Suitable additional measures include promotion of HCC cycle training, provision of cycle repair equipment, Dr Bike sessions, active travel events, promotion of local cycle hubs/cycling groups, showers/lockers/changing facilities in land uses other than residential, Bicycle User Group, information provision re local walking groups, walking/cycling buddy scheme, promotion of national active travel events, promotion of Intalink website for bus/rail information (<https://www.intalink.org.uk/>).
- Again given the scale of development, provision of a car club car on site should be considered not just promotion of Liftshare and EV charge points. People may be more willing to share with people living close-by that they know.
- There is no detail on car parking provision which can affect the relative attractiveness of sustainable modes of transport, not just total no's but inclusion of car share spaces and provision for electric vehicles.

Targets, monitoring and action plan:

- Targets proposed lack ambition. We seek a minimum 10-15% mode shift for a 5 year plan – this being based on experience of what is realistic and achievable. Whilst single occupancy vehicle use indicated by the Census data is relatively low, this is only for commuting trips and actual baseline figures for the site may well be higher and given the length of travel plan required for the residential element, greater levels of modal shift should be aspired to.
- Travel surveys are proposed, but little detail given as to exactly what this means – for a site of this scale, we require TRICS SAM standard (or equivalent) multi-modal counts as well as questionnaires. This ensures adequate data is obtained, both qualitative and quantitative. This helps give a more complete picture of travel patterns and why people are travelling the way they are which can inform revisions to the Travel Plan after each monitoring period.
- Paragraph 7.12 suggests an annual survey for a period of 3 years – we require annual monitoring until 5 years post full occupation of residential element, for 7 years for the Education Travel Plan and for 5 years from first occupation for commercial land uses with an individual Travel Plan.

Evaluation and Support Fees:

- We require an Evaluation and Support Fee of £1200 per year (for the residential Travel Plan which should be in place until 5 years post full occupation) index linked to RPI from March 2014. Education Travel Plans require a fee of £1500 per year (linked to RPI from March 2020 for 7-year plan) and business/workplace Full Travel Plans a fee of £1200 per year (for a -year plan).

Plan approved? No

9.17.2 Further comments 22.8.25 [Objection – insufficient information]

Recommendation

Notice is given under article 22 of the Town and Country Planning (Development Management Procedure) (England) Order 2015 that Hertfordshire County Council as Highway Authority recommends that permission be refused for the following reasons:

There is insufficient information supplied with this application to enable the Highway Authority to reach a recommendation. In the absence of the necessary information, the

Highway Authority recommends refusal due to doubt over possible implications for the free and safe flow of public highway users.

The following response relates to the amended Transport Assessment and supporting documents that have been submitted to address our previous comments dated the 28th February 2025.

Site Accesses / Cycle Route Options.

In our previous response we requested Safety Audits for both the proposed site accesses and the shared pedestrian / cycle route that is proposed between the site and Baldwins Lane. We have yet to receive the safety audits.

The proposals will require further design considerations to determine if they can be delivered in accordance the criteria set out in LTN 1/20. We will be undertaking an internal review of the proposals once we receive the safety audit.

TA – General Comments

Accident Data

The amended Transport Assessment has included additional locations as requested. In summary most of the junctions within the study area have fewer than 5 accidents recorded. Some of larger junctions have higher levels but this would be expected as the volume of traffic passing through these junctions would be higher and the majority of the accidents are most likely to be rear end shunts. Two fatal accidents have been recorded one on Sarratt Road which involved a vehicle and cyclist and the other on Hempstead Road which involved a van and pedestrian. Though these incidents are unfortunate there is no evidence that traffic generations from this proposed development would adversely affect highway safety.

Active Travel and Sustainable Travel Proposals

I refer to the Active Travel Route Audit and the applicant's paragraph,

4.41 We investigate traffic impacts at various junctions along the A412 corridor where the LCWIP interventions are planned. As will be seen later in this report, highway improvements are not planned as part of the development proposals, but, in line with the vision to ensure that the site provides everyday facilities and that movements to/from the site are undertaken as sustainably as possible, contributions to the LCWIP proposals will be provided.

Planning Obligation (further financial contributions)

Our Guide to Developer Contributions Policy sets out further information in relation to planning obligations. This can be viewed on the link below.

<https://www.hertfordshire.gov.uk/media-library/documents/environment-and-planning/planning/developer-infrastructure-contributions-guide/technical-appendix-1-transport.pdf>

It should be noted that immediate and specific impacts of larger developments are established via a TA and mitigated via S278 obligation, or funded via CIL/S106 agreement in the conventional way. We consider this to first strand of possible transport contributions. The second strand should address facilitating delivery and enhancement of the necessary active and sustainable transport networks, such as the LCWIP interventions identified within Active Travel Audit and/or for example, improvements to Rousebarn Lane. The need for second strand contributions will be balanced against the level of first strand contributions.

Therefore, to establish the balance (therefore, value of strand 2 contribution) we need to understand the value of 'stand 1' supporting infrastructure and services. Is it possible for the applicant to list all supporting (off-site) infrastructure and services (e.g. cycling infrastructure, controlled crossings, proposed bus services, etc) alongside an approximate

value of each item. As you can appreciate it is important that all figures agreed at the planning stage allow us to understand how the overall planning vision can be delivered.

Car Parking

Table 2 sets out the latest parking provision for the development square this now provides higher levels of parking for the residential elements of the scheme and parking levels are in line with the emerging LP requirements. Paragraph 4.54 states that parking for the community hub will not be assigned to any particular use, this will allow this area to be used during the day if the retail parking areas becomes busy. It is anticipated that the community hub will be busier during the evenings when parking demand for the other land uses will be lower. This approach is rational and will allow flexibility across the development square uses.

Traffic Generations

The amended Transport Assessment has adopted a new approach to the trip rate calculations which provides multi modal trip rates for the development site. They have selected mixed private/affordable dwellings (Class 3M) subcategory within TRICS. The vehicle trip rates and numbers are set out in Table 3. This shows an increase in vehicle trips compared to the previous TA approach. The assessment has also included active travel trips rates in line with the comments received from ATE. Table 4 sets out the trip rates and anticipated walking and cycling movements that the site could generate.

Following on from comments received from National Highways the amended Transport Assessment has also considered the other proposed site uses the assessment has demonstrated that the school land use will only generate 9 external car movements and most of the school related trips will be internal to the development. With regards to the other land uses within the local centre we agree that these uses will be primarily internal trips with only small proportion of external movements occurring and these would be fairly local and not affect the SRN.

Construction Traffic

The information provided in Table 8 for the construction related activity is confusing, it is unclear how the correlation between total people light vehicle per day and resultant trips has been derived. Is light vehicle movements LGV's or does this include staff car trips? Also, when you review Phase 1 section of the table for the respective elements of the build the labourer columns differ, i.e. Medical Centre Labourers = 10 people = 10 light vehicles per day = 20 resultant trips. However, the same number of labourers for the Local Centre = 6.7 light vehicles per day and = 13.3 resultant trips. The school Building also provides a completely different number of resultant trips as well. It is unclear why these variations are occurring. We require further information on the construction related section of this amended Transport Assessment.

Traffic Impact and Assessment

We have noted that the surveyed flows shown on Figures 3.1 and 3.2 have two sets of numbers shown along with a percentage figures, the numbers shown in blue include all vehicle types excluding cars, this has then been used to create the HGV %'s for the modelling assessments. This calculation is incorrect as the figure in blue also includes the LGV values these shouldn't be included in the HGV percentage calculations.

The flows shown on Figures 3.1 and 3.2 are incorrect at the junction of Baldwins Lane / Links Way and Winton Drive, the LGV values that were recorded in the traffic surveys have not been accounted for. This equates to approximately 100 vehicles in the AM Peak and 110 vehicles in the PM Peak which have not been included in modelling assessments.

The flows presented on Figures 3.1 and 3.2 have been used in the baseline modelling scenarios for each junction. As mentioned above the LGV values have been included in the HGV percentage calculations it also appears that these values have been included in the

PCU conversions with a factor of 2.0 being applied. DfT guidance states that LGV values should not have PCU factors applied to them. The PCU values shown on Figures 3.3 and 3.4 are incorrect.

Figure 5.2 shows the development trip assignment in the PM Peak along Baldwins Lane in the westbound direction 57% of the trips assigned along this link however at the roundabout with the A412 only 33% of the inbound trips are assigned at the junction, 14% of the inbound trips are missing. This error will affect the development traffic flows which have been provided on Figure 5.8

Figure 5.7 shows the development traffic in the AM peak the departures are split between Durrants Drive and Links way with 45 vehicles departing via Durrants Drive these vehicles will pass through the Links Way / Baldwins Lane junction these vehicles have not been included this error flows through into the Future Year Flow diagrams.

The issues that we have identified in relation to the baseline data and the development traffic assignments will impact the junction modelling therefore we are unable to accept the results that have been reported in this amended Transport Assessment.

9.17.3 Further comments 06.01.26 [No objection – conditions and S106 contributions requested]

Decision

Notice is given under article 18 of the Town and Country Planning (Development Management Procedure) (England) Order 2015 that the Hertfordshire County Council as Highway Authority does not wish to restrict the grant of permission subject to the following planning conditions and obligations:

Background

Extensive dialogue has occurred between the applicant's transport consultant and the highway authority. The following comments provide an update on the relevant aspects of the Transport Assessment and the submitted documentation.

Development Access Designs and 20mph Zone (Little Green Lane, Canterbury Way, Dover Way and Links Way)

One of the key issues for this proposal is how it connects to the surrounding highway network. As you would expect, routes to the south, Durrants Drive, Canterbury Way and Links Way have been discussed in detail. A proposal of this scale, in this location, will lead to these roads having to accommodate additional pedestrians, cyclists, buses and vehicles.


The applicant has investigated a variety of options to ensure sustainable travel modes are prioritised and residual traffic speed remains in the region of 20mph (or less) to support active travel.

The initial favoured option was for widened footways to allow for off carriageway cycle facility. However, following the safety concerns raised by road safety audit, the feasibility of shared footway cycleways from the site along Canterbury Way, Dover Way and Links Way was ruled out.


We have concluded that the introduction of a 20mph zone to support the current vehicle speeds, along with supporting measures, such as raised junction tables at all junctions will prioritise pedestrians and allow cycling from the development to be safely incorporated on-carriageway. The transport addendum document dated 10/12/2025 sets out the extents of

a supporting 20mph zone and provides examples of the typical measures that may be introduced.

Appendix B sets out the extents of the initial 20mph zone and typical measures.



However, throughout the planning application's consultation period, HCC's county wide 20mph programme has been reviewed and subsequently accelerated. This section of Croxley Green is listed on our reserve list 'awaiting funding' but covers a larger area (the adjoining residential area to the west).



(extract from HCC's 20mph zone programme – grey shading represents a scheme awaiting funding))

After further review of speed data, the average speeds along Little Green Lane, Canterbury Way, Dover Way, Ludlow Way, Richmond Way and Warwick Way all have speeds that are within acceptable parameters where speed cushions may not be required but entry treatments at all junctions such as raised junction tables would be acceptable to promote/support a 20mph limit. The upper section of Links Way between Dove Way and Little Green Lane and Rousebarn Lane may require some additional speed management

treatments which should be designed to enhance the street scene with combined benefit of retaining low vehicle speeds and improving pedestrian environment.

If a 20mph zone is to be promoted to support the development (in conjunction with the network of junction tables) it will have to cover the wider area. The 'wider area' is unlikely to require similar traffic calming measures, instead, the wider scheme is likely to rely purely on lines and signs. But there is still a cost which will need to be provided to bring the scheme forward. The cost is based on similar schemes elsewhere in the County.

The final design of the overall 20mph zone and specific measures (junction tables) in Durrants Drive and Canterbury and Links Way can be addressed via a planning condition/obligation. Therefore, delivered by the developer. The wider 20mph scheme will require financial contribution from the development.

Planning Condition

Highway Works to Durrants Drive, Canterbury Way, Dover Way and Links Way – Off-Site (Design Approval)

Notwithstanding the details indicated on the submitted drawings no on-site works above slab level shall commence until a detailed scheme for the offsite highway improvement works as indicated by a system of traffic calming measures as identified in Appendix B of the Transport Assessment Addendum Report dated 10/12/2025 including any associated Traffic Regulation Orders required to deliver 20mph speed limit have been submitted to and approved in writing by the Local Planning Authority.

Reason: To ensure construction of a satisfactory development and that the highway improvement works are designed to an appropriate standard in the interest of highway safety and amenity and in accordance with Policy 5, 13 and 21 of Hertfordshire's Local Transport Plan (adopted 2018).

Highway Works to Durrants Drive, Canterbury Way, Dover Way and Links Way – Off-Site (Implementation / Construction)

Prior to the first occupation of the development hereby permitted the offsite highway improvement works referred to in Part A of this condition shall be completed in accordance with the approved details.

Reason: To ensure construction of a satisfactory development and that the highway improvement works are designed to an appropriate standard in the interest of highway safety and amenity and in accordance with Policy 5, 13 and 21 of Hertfordshire's Local Transport Plan (adopted 2018).

Planning Obligation



A proportion of the residual Strand 2 financial contribution towards improving walking and cycling environment will be used for the delivery of wider 20mph speed limit covering residential area to west of site. The contribution to be used to design, consult and implement Croxley Green 20mph zone.

Site Access

Drg No 005 Rev B formed part of submission for the Stage 1 safety audit this shows new parking areas along Durrants Drive these have been introduced to ease parking pressure along the road which will be one of main access routes to the development. The amended TA has included a revision to DRG No 005 Rev C this shows the parking area configured differently. A revised safety audit will need to be submitted this ideally should be concluded

prior to any decision notice being issued by the LPA so drawings can be updated if required. Alternatively, this point can be resolved during the S278 process however this could result in changes occurring that may prove problematic as residents may feel that they have not been fully informed of the changes that are proposed to highway layout.

DRG No 006 shows the site access designs, the visibility spays and the method for calculating the x-distance position along Little Green Lane has been raised as point of concern in safety audit. The introduction of stop lines has been included as part of amendments to resolve the safety audit comments. We request that the length of raised tables along Little Green Lane is reduced so the ramp hump is closer to the stop line we would recommend 1.5 -2.0m. This will create a situation where drivers will slow down on the approach the hump and look and then approach the stop line and again check to see if both cars and pedestrians are nearby before proceeding on to the raised table. Drawing numbers 001 Rev E, 002 Rev D and 004 Rev B show the proposed access arrangements to the development.



Planning Condition

New Access

Design Approval

Notwithstanding the details indicated on the submitted drawings no on-site works above slab level shall commence until a detailed scheme for the access and off-site highway improvement works as indicated by Drg No 001 Rev E, Drg No 002 Rev D, Drg 004 Rev B including any associated Traffic Regulation Orders have been submitted to and approved in writing by the Local Planning Authority.

Reason: To ensure construction of a satisfactory development and that the highway improvement works are designed to an appropriate standard in the interest of highway safety and amenity and in accordance with Policy 5, 13 and 21 of Hertfordshire's Local Transport Plan (adopted 2018).

Access Construction

Prior to the first occupation of the development hereby permitted the New Access referred to in Part A of this condition shall be completed in accordance with the approved details.

Reason: To ensure construction of a satisfactory development and that the highway improvement works are designed to an appropriate standard in the interest of highway safety and amenity and in accordance with Policy 5, 13 and 21 of Hertfordshire's Local Transport Plan (adopted 2018).

TA – General Comments

Traffic Data – Baseline

We previously identified some errors in relation to the baseline traffic data which related to HGV % calculations and LGV values that this affected the surveyed flows shown on Figures 3.1 and 3.2. The TA has since been updated with the traffic flows being revised along with junction capacity modelling.

Traffic Data – Development Traffic

We also identified some errors in relation to Figure 5.2 and 5.7 which would also then affect the future year flows. The TA has since been updated with the traffic flows being revised along with junction capacity modelling.

Accident Data

The amended Transport Assessment has included additional locations as requested. In summary most of the junctions within the study area have fewer than 5 accidents recorded. Some of larger junctions have higher levels but this would be expected as the volume of traffic passing through these junctions would be higher and the majority of the accidents are most likely to be rear end shunts. Two fatal accidents have been recorded one on Sarratt Road which involved a vehicle and cyclist and the other on Hempstead Road which involved a van and pedestrian. Though these incidents are unfortunate there is no evidence that traffic generations from this proposed development would adversely affect highway safety.

Active and Sustainable Travel Proposals

Paragraphs 4.21 – 4.37 covers active travel routes to Croxley Station, Watford Station and Cassiobury Park via West Hertfordshire Golf. The applicant has not proposed any major

changes apart from the introduction of signage. However, this route is a significant asset to the development. It represents a relatively traffic free, quiet route towards the rail station and town centre facilities. The development will lead to different/greater level of use, which as all use will be active modes, use of the route should be encouraged by providing further improvements. During the application process we have discovered a potentially complicated ownership/classification issues exist. But the overarching classification will not prevent major maintenance regime to be carried out which will provide immediate improvements and lead to greater use. Therefore, as the improvements can be directly related to the additional demand, a financial contribution for this purpose has been agreed with the applicant.

Planning Obligation

Prior to occupation pay the local highway authority to be used to make improvements to Rousebarn Lane and public right of way between Little Green Lane and Gade Avenue.

Active travel (LCWIP) Interventions

Opportunities to improve active and sustainable travel in Croxley Green and the surrounding areas have been highlighted in the Watford and Three Rivers Local Cycling and Walking Infrastructure Plan (LCWIP). The plan includes upgrades and key interventions to cycle infrastructure, including to cycle priority enhancements along the A412 corridor towards Watford, known as Route 2 in the scheme.

A brief summary of the potential interventions includes:

- Various junctions on the A412 between Whippendell Road and Watford cycle routes 6 and 17 to give safe continuation of the cycle track over the mouth of each junction.
- Two-way cycle track on the north side of the A412 between Gade Avenue and Cassio Road.
- Improvement of A412/Metropolitan Station Approach/Hagden Lane signals to give additional priority to peds/cycles.
- Additional signalled crossings at A412/Ascot Road roundabout.
- Crossings along the Baldwins Lane/Watford Road roundabout should demand require this improvement.
- Two-way cycle track on the south side of the A412 between Baldwins Lane and Ascot Road roundabouts and to continue westwards along the A412 past Croxley Station and The Green.
- Upgrade of crossing of A412 at Winton Approach to a signal crossing with further crossings of the A412 and priority over side roads.
- A priority crossing along the A412 Watford Rd where the A412 Watford Rd meets Frankland Road, near Croxley Station.

Paragraph 4.41 of the amended TA states that “The TA has considered traffic impacts at various junctions along the A412 corridor where the LCWIP interventions are planned. As will be seen later in this report, highway improvements are not planned as part of the development proposals, however, in line with the vision to ensure that the site provides everyday facilities and that movements to/from the site are undertaken as sustainably as possible, contributions to the LCWIP proposals will be provided.

Creating a cleaner, greener, healthier Hertfordshire

As described by Hertfordshire County Council’s Guide to Developer Contributions, HCC seek immediate and specific impacts of larger developments to be mitigated via S278 obligation or funded via CIL/S106 agreement in the conventional way. This is the first strand of possible transport contributions. The second strand should address the cumulative impacts of all development, large and small, facilitating delivery and enhancement of the necessary active and sustainable transport networks. These local sustainable networks must be provided in their entirety to provide the sustainable connections to the key trip

generators, as such contributions will be pooled to fund these networks within the local area (subject to any legislative restrictions), as supported by the NPPF. This second strand contribution is intended to help implement broader transport measures in the catchments of new development from which contributions are secured. The need for second strand contributions will be balanced against the level of first strand contributions and any other relevant planning matters.

Contribution per dwelling based on forecasted residential development proportion required to meet Active Travel funding gap (cost per dwelling): Indexed to March 2024 = £9,861. Therefore, as a guide, total cost of supporting active travel infrastructure will be in the region 600(units) x £9,861. £5.9m.

As described in HCC's Guide to Developer Contributions, the active travel funding gap figure is considered to be the total cost/value. Various Strand 1 measures are listed in Paragraph 4.44 which sets out further support that will be included to support the LCWIP's objectives by delivering clear, effective connections that promote active and sustainable travel choices for both future residents and the wider community. All of which can be theoretically subtracted from the total £5.9m figure, clarification of the process has been provided by the applicant which I have included as **Appendix 1** (Transport Mitigation Valuation (Strand 1 vs Strand 2 (6/1/2026))). The residual figure listed is to be attached to delivering LCWIP schemes to encourage and support active travel measures serving the new occupants of the development.

Contributions to be made from the developer are set to include the following.

- Contributions towards surrounding active travel links, such as the signage of routes
- The provision of Beryl Bikes docking stations on site. We anticipate 15 such ebikes being provided at an estimated cost of £45K, as per the provision at Croxley Green. At paragraph 2.15 of the Policy and Resources Committee on 4th Dec 2023 we note;
"The capital cost of this pilot project for expansion of the scheme with 15 ebikes into Croxley Green would be £45k. There is no revenue requirement. All revenue arising from the scheme would be utilised for bike maintenance and further project development".
- The introduction of a dedicated bus service within and surrounding the site, including to key destinations such as Rickmansworth, Watford Station, Croxley Station, and Watford Junction. The cost of the subsidy for provision of this service has been estimated at approximately £1.955M over five years.
- Offer of a seasonal bus pass to each dwelling on initial occupation. This item is estimated to cost up to £511,200 on the basis of providing 6 x 4-week bus passes for 600 dwellings calculated on the basis of a 4-week All-Zone Arriva ticket in Herts/Essex.
- Potential contribution to planned step-free access at Croxley station. We are currently in discussion with TfL as to the appropriate level of contribution.
- Designated car-pooling parking provision.

As indicated, certain costings and details of contributions are still under discussion with the transport authorities

Planning Obligations

All above items to be listed and secured via s.106.

The applicant has provided a summary table listing all financial and developer provided infrastructure supporting the proposal which I have included as Appendix 1 (Transport Mitigation Valuation (Strand 1 vs Strand 2 (6/1/2026))). Although various triggers for payments and completions are included, timescales did not allow further discussion to take place, which means triggers are not agreed with HCC. Further debate about what item is required, and when, will be for discussion/agreement further down the line.

Car Parking

Table 2 sets out the latest parking provision for the development square this now provides higher levels of parking for the residential elements of the scheme and parking levels are in line with the emerging LP requirements. Paragraph 4.54 states that parking for the community hub will not be assigned to any particular use, this will allow this area to be used during the day if the retail parking areas becomes busy. It is anticipated that the community hub will be busier during the evenings when parking demand for the other land uses will be lower. This approach is rational and will allow flexibility across the development square uses.

Traffic Generations - Trip rates

The amended Transport Assessment has adopted a new approach to the trip rate calculations which provides multi modal trip rates for the development site. They have selected mixed private/affordable dwellings (Class 3M) subcategory within TRICS. The vehicle trip rates and numbers are set out in Table 3. This shows an increase in vehicle trips compared to the previous TA approach. The assessment has also included active travel trips rates in line with the comments received from ATE. Table 4 sets out the trip rates and anticipated walking and cycling movements that the site could generate.

Following on from comments received from National Highways the amended Transport Assessment has also considered the other proposed site uses the assessment has demonstrated that the school land use will only generate 9 external car movements and most of the school related trips will be internal to the development. With regards to the other land uses within the local centre we agree that these uses will be primarily internal trips with only small proportion of external movements occurring and these would be fairly local and not affect the SRN.

Traffic Distributions

The methodology adopted within the TA was agreed by HCC Officers

Construction Traffic

The amended TA has taken onboard our previous comments relating to the construction traffic numbers reported in Table 8. These are estimates and an appropriate planning condition will be included which will need to be discharged (see general Planning Conditions below).

Junction Capacity Assessments

Table 10 – Site Access Junction – Little Green Lane (NE) /Durrants Drive/ Little Green Lane (SW) PICADY

The assessment demonstrates that in the future 2030 the Base + Committed + Development scenario the junction operates within acceptable parameters.

Table 11 – Site Access Junction – Little Green Lane (NE) / Links Way / Little Green Lane (SW) PICADY

The assessment demonstrates that in the future 2030 the Base + Committed + Development scenario the junction operates within acceptable parameters.

Table 12 – Links Way/Baldwins Lane(E) /Winton Drive/Baldwins Lane (W) PICADY

The assessments shows that Winton Drive RT and Baldwins Lane (E) movements shows an increase in the RFC values and queues when comparing the 2030 base + Committed assessment to the 2030 Base + Committed + Development assessment. The RFC values and queues are still within acceptable limits.

Table 13 – A412 Watford Road (W)/New Road/ A412 Watford Road (E) PICADY

The assessment demonstrates that in the future 2030 the Base + Committed + Development scenario the junction operates within acceptable

Table 14 – Winton Drive/A412 Watford Road PICADY parameters.

The assessment demonstrates that in the future 2030 the Base + Committed + Development scenario the junction operates within acceptable

Table 15 – Winton Approach/A412 Watford Road PICADY Analysis

The assessment demonstrates that in the future 2030 the Base + Committed + Development scenario the junction operates within acceptable

Table 16 – Manor Way/ Baldwins Lane/ Repton Way Mini Roundabout– ARCADY Analysis

The assessments shows that Baldwins Lane (W) movement in the AM Peak shows an increase in the RFC values and queues when comparing the 2030 base + Committed assessment to the 2030 Base + Committed + Development assessment. Also, the Baldwins Lane (E) movement shows an increase in the RFC values and queues for the similar assessment periods. It is considered that the cumulative traffic impact at this junction is relatively modest and certainly not severe, and the development proposal will not have an unacceptable impact on safety.

Table 17 – A412(E)/Sea Cadets/ A412(S)/Baldwins Lane/ Car Planet Roundabout– ARCADY Analysis

The assessments shows that A412 Watford Road (S) and Baldwins Lane movements in the AM Peak shows an increase in the RFC values and queues when comparing the 2030 base + Committed assessment to the 2030 Base + Committed + Development assessment. Also, A412 Watford Road (E) and A412 Watford Road (S) movements shows an increase in the RFC values and queues for the similar assessment periods.

Table 18 – A412 Rickmansworth Road Linked Ascot Road Roundabout – ARCADY Analysis

The assessments shows that Whippendell Road is operating over capacity in the 2024 baseline conditions and when the 2030 Base + Committed + Development flows are assessed the assessment indicates increases to both queues and vehicle delays.

Table 19 – Durrants Drive/Baldwins Lane Roundabout – ARCADY Analysis

The assessments shows that Baldwins Lane (W) movement in the AM Peak shows an increase in the RFC values and queues when comparing the 2030 base + Committed assessment to the 2030 Base + Committed + Development assessment. It is considered that the cumulative traffic impact at this junction is relatively modest and certainly not severe, and the development proposal will not have an unacceptable impact on safety.

We note that several of the junctions are starting to show additional increases in both queues and delays. The proposals include contributions from the development which will be concentrated on promoting the LCWIP proposals. In addition, improvements are proposed to cycle infrastructure routes and Beryl Bikes provision, a new dedicated bus service serving major interchanges and local/town centres, provision of bus season tickets for new residents, and contributions towards step-free access at Croxley Station. All of which will support more sustainable travel options for residents and visitors and the wider communities which will assist in mitigating some of the issues that have been identified within the Transport Assessment.

Travel Plan Review

General comments:

A commitment is made to the provision of a Beryl Bikes docking station on site and discussions appear to be ongoing with TfL regarding a contribution towards lifts at Croxley station. More detail is given as to proposed bus service improvements, with the proposed route included in Appendix D. These elements will all improve access to and the attractiveness of sustainable transport for site users.

There is a commitment to individual land use Travel Plans (paragraph 3.16) as required by our Travel Plan guidance, which should be in general alignment with the Framework Travel Plan but with measures tailored to the land use in question.

Objectives have been included, as have expected Travel Plan Co-Ordinator duties, there's mention of a steering group and adequate reference to expected operation of the Framework Travel Plan in relation to the land use specific Travel Plans.

A wider range of measures are included as requested – these will need to be further tailored to the land use in question when individual Travel Plans are developed.

An interim mode shift target has been included that is more in line with our requirements. Targets and measures can be amended as part of annual Travel Plan review following results of the baseline monitoring and should be responsive to opportunities on site and feedback from site users.

Paragraph 7.17 quotes previous comments made about requirements in terms of Travel Plan duration but then goes on to say surveys will be undertaken on an annual basis to meet the proposed monitoring period '...for a period of five years for the residential and local centre components of the site and seven years for the school....' - just to reiterate, the requirement for the residential Travel Plan is that it should be in place until 5 years post full occupation (the build out period is not stated in the Travel Plan but with larger sites such as this, this often means the Travel Plan is required to be in place for rather longer than 5 years), for 7 years for the Education Travel Plan and for 5 years from first occupation for commercial land uses with an individual Travel Plan. As long as this is the intention, this is acceptable.

Planning Condition

Travel Plan – Requested Prior to Use

At least 3 months prior to the first occupation / use of the approved development a detailed Travel Plan for the site, based upon the Hertfordshire Council document 'Hertfordshire's Travel Plan Guidance', shall be submitted and approved in writing by the Local Planning Authority. The approved Travel Plan shall be implemented at all times.

Reason: To ensure that sustainable travel options associated with the development are promoted and maximised to be in accordance with Policies 3, 5, 7, 8, 9 and 10 of Hertfordshire's Local Transport Plan (adopted 2018).

Planning Obligation

Evaluation and Support Fees:

We require an Evaluation and Support Fee of £1200 per year (for the residential Travel Plan which should be in place until 5 years post full occupation) index linked to RPI from March 2014. Education Travel Plans require a fee of £1500 per year (linked to RPI from March 2020 for 7-year plan)

Other Recommended Standard Highway Planning Conditions

Standard Estate Road Condition

No development shall commence until full details have been submitted to and approved in writing by the Local Planning Authority in relation to the proposed arrangements for future management and maintenance of the proposed streets within the development. (The streets shall thereafter be maintained in accordance with the approved management and maintenance details until such time as an agreement has been entered into under Section 38 of the Highways Act 1980 or a Private Management and Maintenance Company has been established).

Reason: To ensure satisfactory development and to ensure estate roads are managed and maintained thereafter to a suitable and safe standard in accordance with Policies 5 and 22 of Hertfordshire's Local Transport Plan (adopted 2018).

Standard Highway Condition

No development shall commence until full details (in the form of scaled plans and / or written specifications) have been submitted to and approved in writing by the Local Planning Authority to illustrate the following:

- i) Roads, footways.
- ii) Cycleways.
- iii) Foul and surface water drainage.
- iv) Visibility splays.
- v) Access arrangements.
- vi) Parking provision in accordance with adopted standard.
- vii) Loading areas.
- viii) Turning areas.

Reason: To ensure suitable, safe and satisfactory planning and development of the site in accordance with Policy 5 of Hertfordshire's Local Transport Plan (adopted 2018).

Construction Management Plan

No development shall commence until a Construction Management Plan (or Construction Method Statement) has been submitted to and approved in writing by the Local Planning Authority. Thereafter the construction of the development shall only be carried out in accordance with the approved Plan. The Construction Management Plan / Statement shall include details of

- a. Construction vehicle numbers, type, routing;
- b. Access arrangements to the site;
- c. Traffic management requirements
- d. Construction and storage compounds (including areas designated for car parking, loading / unloading and turning areas);
- e. Siting and details of wheel washing facilities;
Creating a cleaner, greener, healthier Hertfordshire
- f. Cleaning of site entrances, site tracks and the adjacent public highway;
- g. Timing of construction activities (including delivery times and removal of waste) and to avoid school pick up/drop off times;
- h. Provision of sufficient on-site parking prior to commencement of construction activities;
- i. Post construction restoration/reinstatement of the working areas and temporary access to the public highway;
- j. where works cannot be contained wholly within the site a plan should be submitted showing the site layout on the highway including extent of hoarding, pedestrian routes and remaining road width for vehicle movements.

Reason: In order to protect highway safety and the amenity of other users of the public highway and rights of way in accordance with Policies 5, 12, 17 and 22 of Hertfordshire's Local Transport Plan (adopted 2018).

APPENDIX 1

Transport Mitigation Valuation (Strand 1 vs Strand 2)

Croxley Green (600 Dwellings). Ref. 24/2073/OUT Date: 06.01.2026

Methodology: In accordance with Hertfordshire's Guide to Developer Contributions, the total transport mitigation package is balanced between Strand 1 (direct site-specific impacts) and Strand 2 (cumulative impacts). The Applicant proposes that the

value of direct delivery works (S278) and specific site mitigations (Strand 1) be deducted from the headline Strand 2 liability to determine the residual financial contribution.

Strand 2 Liability

- Metric: Three Rivers Benchmark (£9,861 per dwelling)
- Scheme Size: 600 dwellings
- Total Strand 2 Liability: £5,916,600

Strand 1 Valuation (Deductions)

Part A: Financial Contributions

Item	Description	Value / Costs	Trigger / Notes
Dedicated Bus Service	New half-hourly service (Watford/Rickmansworth)	£1,955,000	Financial contribution Paid annually for five years (£391,000 per year)
Step-Free Access	Contribution to TfL for lifts at Croxley Station	£1,065,000	Financial contribution Delivery prior to 50% occupation
Rousebarn Lane Upgrade	From Little Green Lane to Gade Avenue	£25,000	Financial contribution Delivery prior to occupation
LCWIP Contribution	Watford & Three Rivers Route 2 improvements	£15,000	Financial contribution Delivery prior to 50% occupation
Beryl Bikes	Expansion and docking station provision	£45,000	Financial contribution Delivery prior to 50% occupation
Travel Plan Evaluation	HCC Evaluation Fee	£8,862	Financial contribution
Travel Vouchers and Car Share	Based on TA: 6 x 4-week passes (Arriva All Zone) per unit*	£511,200	Financial contribution
Sub-Total (Part A)		£3,625,062	

* Estimated based on standard Hertfordshire sustainable travel packs and 600 dwellings

Part B: Developer-Delivered Works (S278 / Condition)

Estimated construction values for works delivered directly by the Developer. Estimates based on standard civil engineering rates including preliminaries and fees.

Item	Description	Estimated Value	
Site Access (Durrants Dr)	New priority junction, raised table, lighting & drainage.	£130,000	S278 Works (Delivered via Developer/Planning Condition) Delivery prior to occupation
Site Access (Links Way)	New priority junction, visibility splays & raised table.	£130,000	S278 Works (Delivered via Developer/Planning Condition) Delivery prior to occupation
Enhanced Traffic Calming	Speed calming for 20mph zone, inclusive of on-street cycling measures**	£562,500	S278 Works (Delivered via Developer/Planning Condition) Delivery prior to occupation
Bus Infrastructure	4 stops (2 new, 2 upgrades) incl. shelters, RTI & Civils. (Est. £15k per stop)	£60,000	S278 Works (Delivered via Developer/Planning Condition) Delivery prior to 50% occupation
Active Travel Signage	Wayfinding for secondary routes (Rousebarn Ln/Park).	£25,000	S278 Works (Delivered via Developer/Planning Condition) Delivery prior to 50% occupation
Vegetation Clearance (Rousebarn)	Maintenance asset	£10,000	S278 Works (Delivered via Developer/Planning Condition) Delivery prior to 50% occupation
Sub-Total (Part B)		£705,000	

** HCC preference for on-street cycling and traffic calming integration. As per schedule at Appendix A.

Final Balance Calculation

Description	Amount
Total Strand 2 Liability	£5,916,600
Less Part A (Contributions)	(£3,625,062)
Less Part B (Delivered Works)	(£705,000)
Residual Strand 2 Contribution	£1,586,538

These draft Heads of Terms are provided on a 'Without Prejudice' basis and represent an indicative framework for the proposed mitigation. While the current figures outline anticipated financial contributions, all terms remain subject to further refinement following a review by both parties. It is acknowledged that the final quantum for highway contributions will be confirmed via a technical audit and formally secured through the Section 106 agreement pursuant to any grant of planning permission. Furthermore, the detailed design, specification, and delivery of any physical highway works remain strictly subject to the Section 278 technical approval process. Consequently, these draft terms are intended to

establish principle only, with comprehensive costings and final engineering specifications to be agreed during the formal legal drafting stage.

9.18 London Underground Limited: [No comments on application]

I can confirm that London Underground/DLR Infrastructure Protection has no comment to make on this planning application.

My colleagues in Spatial Planning will respond separately with comments, if any.

9.19 National Grid: [No objection]

Your planning application – No objection, informative note required

We have received a notification from the LinesearchbeforeUdig (LSBUD) platform regarding a planning application that has been submitted which is in close proximity to our medium and low pressure assets. We have no objection to this proposal from a planning perspective, however we need you to take the following action.

What you need to do

To prevent damage to our assets or interference with our rights, please add the following Informative Note into the Decision Notice:

Cadent Gas Ltd own and operate the gas infrastructure within the area of your development. There may be a legal interest (easements and other rights) in the land that restrict activity in proximity to Cadent assets in private land. The applicant must ensure that the proposed works do not infringe on legal rights of access and or restrictive covenants that exist. If buildings or structures are proposed directly above the apparatus the development may only take place following diversion of the apparatus. The applicant should apply online to have apparatus diverted in advance of any works, by visiting cadentgas.com/diversions. Prior to carrying out works, including the construction of access points, please register on www.linesearchbeforeudig.co.uk to submit details of the planned works for review, ensuring requirements are adhered to.

Your responsibilities and obligations

Cadent may have a Deed of Easement on the pipeline, which provides us with a right of access for a number of functions and prevents change to existing ground levels, storage of materials. It also prevents the erection of permanent/temporary buildings, or structures. If necessary Cadent will take action to legally enforce the terms of the easement.

This letter does not constitute any formal agreement or consent for any proposed development work either generally or related to Cadent's easements or other rights, or any planning or building regulations applications.

Cadent Gas Ltd or their agents, servants or contractors do not accept any liability for any losses arising under or in connection with this information. This limit on liability applies to all and any claims in contract, tort (including negligence), misrepresentation (excluding fraudulent misrepresentation), breach of statutory duty or otherwise. This limit on liability does not exclude or restrict liability where prohibited by the law nor does it supersede the express terms of any related agreements.

If you need any further information or have any questions about the outcome, please contact us at plantprotection@cadentgas.com or on 0800 688 588 quoting your reference at the top of this letter.

9.20 National Highways: [No objection]

9.20.1 Initial comments 10.2.25 [Holding objection]

National Highways Ref: NH/25/09637

Referring to the consultation on a planning application dated 21 January 2025 referenced above, in the vicinity of the M25, J18 and 19, the M1 J5 that forms part of the Strategic Road Network, notice is hereby given that National Highways' formal recommendation is that we:

c) recommend that planning permission not be granted for a specified period (see reasons at Annex A);

This represents National Highways' formal recommendation and is copied to the Department for Transport as per the terms of our Licence.

Should the Local Planning Authority propose not to determine the application in accordance with this recommendation they are required to consult the Secretary of State for Transport, as set out in the Town and Country Planning (Development Affecting Trunk Roads) Direction 2018, via transportplanning@dft.gov.uk and may not determine the application until the consultation process is complete.

The Local Planning Authority must also copy any consultation under the 2018 Direction to PlanningSE@nationalhighways.co.uk.

This response and all comments outlined herein are made in respect of planning matters only in National Highways' position as a statutory planning consultee, and does not confer any proprietary rights nor amount to the giving or refusal of consent, assent, approval, or awareness of or by National Highways in or of any other aspects or matters (including, but not limited to, the use of property belonging to National Highways). If anyone wishes for National Highways to consider any aspects which do not relate to planning submissions, they should call our contact centre on 0300 123 5000.

Annex A National Highways' assessment of the proposed development

National Highways was appointed by the Secretary of State for Transport as a strategic highway company under the provisions of the Infrastructure Act 2015 and is the highway authority, traffic authority and street authority for the Strategic Road Network (SRN). The SRN is a critical national asset and as such we work to ensure that it operates and is managed in the public interest, both in respect of current activities and needs as well as in providing effective stewardship of its long-term operation and integrity.

National Highways is interested whether there would be any adverse safety implications or material increase in queues and delays on the SRN as a result of the proposed development, in this case on the M25 J18 and 19, and the M1 J5.

Proposed Development

The proposed development includes construction of up to 600 dwellings and a 5-bedroom property for children's social care and supported living. Two vehicular access points from Little Green Lane are proposed, as well as further pedestrian and cycleway access points. A one form entry primary school, plus expansion land for a two form entry primary school are also proposed alongside a mixed use local centre with provision for NHS health and social care services, a community building, retail units and café provision. A country park and areas for play and recreation, allotments, community orchard and landscaping with associated infrastructure including SuDS are also included in the development proposals.

A bus service is also proposed to be secured via s106 contribution to serve the site, and the development will provide a suitable contribution towards the implementation of step-free access at Croxley Underground Station.

We have reviewed the Transport Assessment (TA) provided as part of the planning submission, written by Hub Transport Planning Ltd.

Trip Generation

Table 7 in Section 6 of the TA sets out the total trip generation expected from the residential aspect of the proposed development, including both market and affordable dwellings. The proposed development is expected to generate 254 two-way vehicle trips in the AM peak period, and 267 two-way vehicle trips in the PM peak period. In both periods, this equates to just over 4 additional vehicles per minute. Following an internal replication of the selection parameters provided using TRICS, National Highways are satisfied that the expected trip generation is accurate.

The trip generation provided in the TA does not include any other aspect of the proposed development, including the expected trips generated from the primary school use, or the mixed use local centre with NHS health and social care facilities, retail and café provision, or the country park and outdoor play / recreation areas. Paragraph 6.9 states that it was previously agreed with Hertfordshire County Council (HCC) that the “great majority of movements to/from school will be local in nature and that traffic movements associated with the school will be limited”. Paragraph 6.10 similarly states that “the majority of traffic movements to/from the local centre are likely to be undertaken by those from the development or from residents just to the south of the development, and likely to be undertaken by active travel modes. Therefore, no additional traffic has been added for these development proposals”.

National Highways accept that this is an outline application and the trip impact from the non-residential uses of the proposed development on the SRN are likely to be minor. However, as the anticipated trips from the residential uses alone are already relatively high, we require this additional information to understand the full potential traffic impact of the proposed development, particularly given the proposed country park and play space uses may generate a significant number of external vehicle trips. **We request that the additional information is provided, including the anticipated trips generated from the non-residential uses of the proposed development with internalisation factors applied, and justification for the proposed internalisation factors.**

Trip Distribution and Assignment

Figure 7.5 and Figure 7.6 illustrate the total anticipated traffic flows on the local highway network including the 2030 Future Year Base Flows, committed development traffic flows and the proposed development traffic for the AM and PM peak periods. The impact of the proposed development on the SRN has not been considered as part of the TA despite there being several connections to the SRN from the proposed development site, namely via the M25 J18 and 19, and the M1 J5. Due to the relatively high number of trips predicted to be generated from the proposed development, in addition to the trips generated from committed development in the surrounding area, **National Highways request that the trip distribution/assignment exercise is extended to the nearby SRN junctions and provided for review before further comments are made. This should be presented as turning movements for the sensitive weekday AM and PM peak hours.**

Junction Capacity Assessments

Section 7 of the TA sets out the traffic impacts, growth rates and the outputs of the junction capacity assessments. Junctions with the SRN are not included in these assessments. Due

to the relatively high volume of anticipated vehicle trips from the proposed development, it is possible that further junction capacity assessments may be required to assess the impact on the SRN. This will be determined following the provision of the additional information requested above, including the trip distribution/assignment at the SRN junctions.

Sustainable Transport

We have reviewed the Framework Travel Plan supplied and relevant sections of the TA relating to sustainable transport. Section 4 of the TA (replicated in the Travel Plan) outlines the accessibility of local facilities, i.e. education, retail and health care services, by foot, cycle and public transport, demonstrating that the proposed site is readily accessible by a variety of transport modes that have the potential to reduce reliance on the private car.

The active and sustainable transport proposals set out in Paragraphs 4.72 to 4.90 suggest that new pedestrian and cyclist access routes and links are proposed and there is potential to expand the Beryl cycle hire scheme with a bike station on site. Proposals also include a bus service into the site via Durrants Drive to serve Watford and major destinations between Watford and the proposed site, as well as important transport hubs.

National Highways welcomes sustainable transport measures being the primary means to off-set any severe / significant development impacts on the SRN, although for us to take these measures into account, these would need to be worked up to a position where we can understand the likely mode shift benefits they could provide.

National Highways agree that in principle the measures proposed will help reduce travel demand by private vehicle on the SRN, particularly the proposed provision of a bus service providing connections to important transport hubs and Watford. **The applicant should provide further information regarding the proposed routing and service frequency etc of this bus service for us to review.**

Construction Traffic

National Highways request that a construction traffic impact assessment is carried out and provided for review, to allow us to understand the potential impact of construction HGVs and workforce traffic on our network, particularly during the peak construction period.

A Framework Construction Traffic Management Plan (FCTMP) should also be provided to mitigate any potential impacts identified.

Recommended Non-Approval

Given the above, it is currently not possible to determine whether the application would have an unacceptable impact on the safety, reliability and/or operational efficiency of the SRN (the tests set out in DfT Circular 01/2022 and MHCLG NPPF2024 [particularly paras 115 to 118]). This response details the steps that need to be taken in order to resolve this issue.

In light of the above, National Highways currently recommends that planning permission not be granted (other than a refusal if the Council so wishes) for a period of three months from the date of this response to allow the applicant to resolve the outstanding matters.

This recommendation can be replaced, renewed, or reviewed during the three-month period, or at its end, dependent on progress made with regards to the outstanding matters.'

It is recommended that the application should not be approved until 11 April 2025.

Standing advice to the local planning authority

The Climate Change Committee's 2022 Report to Parliament notes that for the UK to achieve net zero carbon status by 2050, action is needed to support a modal shift away from car travel. The NPPF supports this position, with paragraphs 77 and 110 prescribing that significant development should offer a genuine choice of transport modes, while paragraphs 109 and 115 advise that appropriate opportunities to promote walking, cycling and public transport should be taken up as part of a vision-led approach.

Moreover, the carbon reduction hierarchy (avoid-switch-improve) as set out in clause 4.3 of PAS2080:2023 promotes approaches and measures to minimise resource consumption and thereby reduce carbon emissions.

These considerations should be weighed alongside any relevant Local Plan policies to ensure that planning decisions are in line with the necessary transition to net zero carbon.

9.20.2 Further comments 07.05.25 [Holding objection maintained]

National Highways Ref: NH/25/09637

Referring to the consultation on a planning application dated 21 January 2025 referenced above, in the vicinity of the M25, J18 and 19, the M1 J5 that forms part of the Strategic Road Network, notice is hereby given that National Highways' formal recommendation is that we:

c) recommend that planning permission not be granted for a specified period (see reasons at Annex A);

This represents National Highways' formal recommendation and is copied to the Department for Transport as per the terms of our Licence.

Should the Local Planning Authority propose not to determine the application in accordance with this recommendation they are required to consult the Secretary of State for Transport, as set out in the Town and Country Planning (Development Affecting Trunk Roads) Direction 2018, via transportplanning@dft.gov.uk and may not determine the application until the consultation process is complete.

The Local Planning Authority must also copy any consultation under the 2018 Direction to PlanningSE@nationalhighways.co.uk.

This response and all comments outlined herein are made in respect of planning matters only in National Highways' position as a statutory planning consultee, and does not confer any proprietary rights nor amount to the giving or refusal of consent, assent, approval, or awareness of or by National Highways in or of any other aspects or matters (including, but not limited to, the use of property belonging to National Highways). If anyone wishes for National Highways to consider any aspects which do not relate to planning submissions, they should call our contact centre on 0300 123 5000.

Annex A National Highways' assessment of the proposed development

National Highways was appointed by the Secretary of State for Transport as a strategic highway company under the provisions of the Infrastructure Act 2015 and is the highway authority, traffic authority and street authority for the Strategic Road Network (SRN). The SRN is a critical national asset and as such we work to ensure that it operates and is managed in the public interest, both in respect of current activities and needs as well as in providing effective stewardship of its long-term operation and integrity.

National Highways is interested whether there would be any adverse safety implications or material increase in queues and delays on the SRN as a result of the proposed development, in this case on the M25 J18 and 19, and the M1 J5.

Our previous NHPR response of 7 February stated the following

Proposed Development

The proposed development includes construction of up to 600 dwellings and a 5-bedroom property for children's social care and supported living. Two vehicular access points from Little Green Lane are proposed, as well as further pedestrian and cycleway access points. A one form entry primary school, plus expansion land for a two form entry primary school are also proposed alongside a mixed use local centre with provision for NHS health and social care services, a community building, retail units and café provision. A country park and areas for play and recreation, allotments, community orchard and landscaping with associated infrastructure including SuDS are also included in the development proposals.

A bus service is also proposed to be secured via s106 contribution to serve the site, and the development will provide a suitable contribution towards the implementation of step-free access at Croxley Underground Station.

We have reviewed the Transport Assessment (TA) provided as part of the planning submission, written by Hub Transport Planning Ltd.

Trip Generation

Table 7 in Section 6 of the TA sets out the total trip generation expected from the residential aspect of the proposed development, including both market and affordable dwellings. The proposed development is expected to generate 254 two-way vehicle trips in the AM peak period, and 267 two-way vehicle trips in the PM peak period. In both periods, this equates to just over 4 additional vehicles per minute. Following an internal replication of the selection parameters provided using TRICS, National Highways are satisfied that the expected trip generation is accurate.

The trip generation provided in the TA does not include any other aspect of the proposed development, including the expected trips generated from the primary school use, or the mixed use local centre with NHS health and social care facilities, retail and café provision, or the country park and outdoor play / recreation areas. Paragraph 6.9 states that it was previously agreed with Hertfordshire County Council (HCC) that the "great majority of movements to/from school will be local in nature and that traffic movements associated with the school will be limited". Paragraph 6.10 similarly states that "the majority of traffic movements to/from the local centre are likely to be undertaken by those from the development or from residents just to the south of the development, and likely to be undertaken by active travel modes. Therefore, no additional traffic has been added for these development proposals".

National Highways accept that this is an outline application and the trip impact from the non-residential uses of the proposed development on the SRN are likely to be minor. However, as the anticipated trips from the residential uses alone are already relatively high, we require this additional information to understand the full potential traffic impact of the proposed development, particularly given the proposed country park and play space uses may generate a significant number of external vehicle trips. We request that the additional information is provided, including the anticipated trips generated from the non-residential uses of the proposed development with internalisation factors applied, and justification for the proposed internalisation factors.

Trip Distribution and Assignment

Figure 7.5 and Figure 7.6 illustrate the total anticipated traffic flows on the local highway network including the 2030 Future Year Base Flows, committed development traffic flows and the proposed development traffic for the AM and PM peak periods. The impact of the proposed development on the SRN has not been considered as part of the TA despite there being several connections to the SRN from the proposed development site, namely via the M25 J18 and 19, and the M1 J5. Due to the relatively high number of trips predicted to be generated from the proposed development, in addition to the trips generated from committed development in the surrounding area, National Highways request that the trip distribution/assignment exercise is extended to the nearby SRN junctions and provided for review before further comments are made. This should be presented as turning movements for the sensitive weekday AM and PM peak hours.

Junction Capacity Assessments

Section 7 of the TA sets out the traffic impacts, growth rates and the outputs of the junction capacity assessments. Junctions with the SRN are not included in these assessments. Due to the relatively high volume of anticipated vehicle trips from the proposed development, it is possible that further junction capacity assessments may be required to assess the impact on the SRN. This will be determined following the provision of the additional information requested above, including the trip distribution/assignment at the SRN junctions.

Sustainable Transport

We have reviewed the Framework Travel Plan supplied and relevant sections of the TA relating to sustainable transport. Section 4 of the TA (replicated in the Travel Plan) outlines the accessibility of local facilities, i.e. education, retail and health care services, by foot, cycle and public transport, demonstrating that the proposed site is readily accessible by a variety of transport modes that have the potential to reduce reliance on the private car.

The active and sustainable transport proposals set out in Paragraphs 4.72 to 4.90 suggest that new pedestrian and cyclist access routes and links are proposed and there is potential to expand the Beryl cycle hire scheme with a bike station on site. Proposals also include a bus service into the site via Durrants Drive to serve Watford and major destinations between Watford and the proposed site, as well as important transport hubs.

National Highways welcomes sustainable transport measures being the primary means to off-set any severe / significant development impacts on the SRN, although for us to take these measures into account, these would need to be worked up to a position where we can understand the likely mode shift benefits they could provide.

National Highways agree that in principle the measures proposed will help reduce travel demand by private vehicle on the SRN, particularly the proposed provision of a bus service providing connections to important transport hubs and Watford. The applicant should provide further information regarding the proposed routing and service frequency etc of this bus service for us to review.

Construction Traffic

National Highways request that a construction traffic impact assessment is carried out and provided for review, to allow us to understand the potential impact of construction HGVs and workforce traffic on our network, particularly during the peak construction period.

A Framework Construction Traffic Management Plan (FCTMP) should also be provided to mitigate any potential impacts identified.

Since our previous NHPR we have had confirmation from the applicant's consultants that the above requirements for further information can be supplied and further assessment work undertaken if necessary. A meeting was held on 25th March to discuss requirements.

We are awaiting the further information requested to enable us to determine the application with more certainty in relation to impacts on the SRN.

Recommended Non-Approval

Given the above, it is currently not possible to determine whether the application would have an unacceptable impact on the safety, reliability and/or operational efficiency of the SRN (the tests set out in DfT Circular 01/2022 and MHCLG NPPF2024 [particularly paras 115 to 118]). This response details the steps that need to be taken in order to resolve this issue.

In light of the above, National Highways currently recommends that planning permission not be granted (other than a refusal if the Council so wishes) for a period of three months from the date of this response to allow the applicant to resolve the outstanding matters.

This recommendation can be replaced, renewed, or reviewed during the three-month period, or at its end, dependent on progress made with regards to the outstanding matters.'

It is recommended that the application should not be approved until 7th August 2025.

Standing advice to the local planning authority

The Climate Change Committee's 2022 Report to Parliament notes that for the UK to achieve net zero carbon status by 2050, action is needed to support a modal shift away from car travel. The NPPF supports this position, with paragraphs 77 and 110 prescribing that significant development should offer a genuine choice of transport modes, while paragraphs 109 and 115 advise that appropriate opportunities to promote walking, cycling and public transport should be taken up as part of a vision-led approach.

Moreover, the carbon reduction hierarchy (avoid-switch-improve) as set out in clause 4.3 of PAS2080:2023 promotes approaches and measures to minimise resource consumption and thereby reduce carbon emissions.

These considerations should be weighed alongside any relevant Local Plan policies to ensure that planning decisions are in line with the necessary transition to net zero carbon.

9.20.3 Further comments 30.07.25 [Holding objection maintained]

National Highways Ref: NH/25/09637

Referring to the consultation on a planning application dated 21 January 2025 referenced above, in the vicinity of the M25, J18 and 19 and the M1 J5 that forms part of the Strategic Road Network, notice is hereby given that National Highways' formal recommendation is that we:

recommend that planning permission not be granted for a specified period (see reasons at Annex A);

This represents National Highways' formal recommendation and is copied to the Department for Transport as per the terms of our Licence.

Should the Local Planning Authority propose not to determine the application in accordance with this recommendation they are required to consult the Secretary of State for Transport, as set out in the Town and Country Planning (Development Affecting Trunk Roads) Direction 2018, via transportplanning@dft.gov.uk and may not determine the application until the consultation process is complete.

The Local Planning Authority must also copy any consultation under the 2018 Direction to PlanningSE@nationalhighways.co.uk.

This response and all comments outlined herein are made in respect of planning matters only in National Highways' position as a statutory planning consultee, and does not confer any proprietary rights nor amount to the giving or refusal of consent, assent, approval, or awareness of or by National Highways in or of any other aspects or matters (including, but not limited to, the use of property belonging to National Highways). If anyone wishes for National Highways to consider any aspects which do not relate to planning submissions, they should call our contact centre on 0300 123 5000.

Annex A National Highways' assessment of the proposed development

National Highways was appointed by the Secretary of State for Transport as a strategic highway company under the provisions of the Infrastructure Act 2015 and is the highway authority, traffic authority and street authority for the Strategic Road Network (SRN). The SRN is a critical national asset and as such we work to ensure that it operates and is managed in the public interest, both in respect of current activities and needs as well as in providing effective stewardship of its long-term operation and integrity.

National Highways is interested whether there would be any adverse safety implications or material increase in queues and delays on the SRN as a result of the proposed development, in this case on the M25, J18 and 20, and the M1 J5.

We have reviewed the Amended Transport Assessment (ATA), Amended Travel Plan (ATP) and associated appendices provided as part of the planning submission update, written by Hub Transport Planning Ltd.

Trip Generation

We note that HCC requested the exclusion of a site surveyed due to low levels of parking and potential low levels of vehicle trip rates. As only one affordable site remained, we agree with the approach to use Land Use 3M within TRICS.

The AM peak period (08:00-09:00) is estimated to generate 315 two-way vehicle trips and the PM peak period (17:00-18:00) is expected to generate 304 two-way vehicle movements. Following the completion of internal comparison checks using TRICS, we are satisfied that the trip generation presented in Table 3 of the ATA is accurate.

We note that the ATA includes the requested trip generation for the primary school use and mixed local centre. We agree with the methodology used to establish the educational trips to the proposed development and are satisfied that the car-based arrivals to the site will travel via the local highway network. We also accept the reasoning behind the exclusion of the local centre and health centre use vehicle trips and are satisfied that those trips are unlikely to use the SRN.

Trip Distribution

We note that the ATA includes the traffic distribution for the SRN junctions as requested. We have reviewed the traffic distribution information provided in Appendix H and summarised in Table 7 of the ATA.

Travelling inbound in the AM peak period (08:00-09:00) and the PM peak period (17:00-18:00) the M25 J18 NB is expected to see an increase of 5 additional vehicles. At the same junction travelling outbound, the AM peak is expected to see an increase of 16 vehicles and the PM peak is estimated to see an additional 15 vehicles.

The highest volume of inbound traffic assigned to the SRN is 34 additional vehicles travelling SB on the M25 J18 in the AM peak and 33 additional vehicles travelling in the PM peak at the same junction. Travelling outbound, the M25 J18 SB is expected to see an increase of 50 vehicles in the AM peak hour and 49 additional vehicles in the PM peak hour. In the AM peak, typical traffic at the M25 J18 shows slow moving vehicles on Rickmansworth Road (A404) due to the signalised junction with the M25 J18 slip roads. The additional inbound vehicles at the SB off-slip are likely to cause further queuing on the off-slip due to the slow-moving vehicles at the signalised junction. The additional outbound vehicles have the potential to add to the congestion build up on the A404 and cause further queuing which may have implications for the SB on-slip.

An additional 15 inbound vehicles are expected at the M1 J5 NB in the AM peak period and an additional 27 inbound vehicles are expected in the PM peak. An additional 15 vehicles are expected to travel outbound at this junction during both peak periods. Travelling SB at the M1 J5, there are estimated to be an additional 15 inbound vehicles in the AM peak and an additional 16 inbound vehicles in the PM peak. Travelling outbound, an additional 29 vehicles are expected in the AM peak and an additional 28 vehicles are expected in the PM peak.

The M1 J5 SB off slip entering the Berrygrove Interchange experiences slow moving traffic during both peak hours. The inbound SB traffic at this junction has the potential to exacerbate this issue further and cause blocking back on the SB off-slip.

Traffic Impact

Section 6 of the TA sets out the traffic impacts, growth rates and the outputs of the junction capacity assessments carried out for local highway junctions surrounding the proposed development site.

Development proposals can be considered unacceptable by virtue of a severe impact if they increase demand for use of a section of the network that is already operating near or over capacity, or where the additional traffic cannot be safely accommodated on the SRN unless mitigation is agreed. National Highways considers that any development trips adding to a junction off-slip which then results in mainline queuing, extends a mainline queue, and / or increases the frequency at which mainline queuing occurs to be an unacceptable safety impact.

Both the M1 J5 and M25 J18 are observed to have significant existing off-slip queues which extend back towards their respective mainline carriageway in the AM and/or PM peak, such that any increases in flow on these off-slips may result in mainline queueing. Following a review of the trip distribution and the levels of existing congestion at each of the affected SRN junctions, **we request that the junction capacity assessments are extended to include the SRN junctions, particularly the M25 J18 and the M1 J5.** This will allow us to assess the full traffic impact of the proposal on the safety and operation of the SRN. Until this work is undertaken National Highways cannot satisfactorily consider the impact of the development on its network.

Sustainable Transport

We have reviewed the Amended Travel Plan provided which outlines the accessibility of local facilities, i.e. education, retail and health care services, by foot, cycle and public

transport, demonstrating that the proposed site is readily accessible by a variety of transport modes that have the potential to reduce reliance on the private car.

Section 5 sets out the Travel Plan Targets which states that the developer is confident that a 15% reduction in single-occupancy car use can be achieved based on the journey to work modal split indicated by the census data. This would reduce car driver trips by 8.2% to 42% from 55.2%. The drivers for this change are expected to be the provision of local facilities on site, reducing the need to travel by car and encouraging more active travel, the proposed shared-use walking/cycling facility, the inclusion of a Beryl Bikes facility on site, the enhancement of the existing local bus service (service 22) providing sustainable access to off-site facilities, bus taster tickets for each household and the inclusion of a car club on site which has the potential to reduce private car ownership. These measures are further explored in Section 6 of the amended Travel Plan.

National Highways welcomes sustainable transport measures being the primary means to off-set any severe / significant development impacts on the SRN. We are satisfied that the measures proposed will help reduce travel demand by private vehicle on the SRN, particularly the proposed provision of a bus service providing connections to important transport hubs and Watford.

Construction Traffic

Table 8 of the ATA outlines the anticipated construction traffic from the proposed development and Table 9 shows the maximum daily construction traffic trip generation. It is estimated that the proposed development will generate a maximum of 63 two-way daily vehicle movements. It is expected that 12 of these daily movements will be two-way HGV movements.

We note that the FCTMP requested in our previous response will be conditioned as part of formal planning permission being granted for the proposal.

Recommended Non-Approval

Given the above, it is currently not possible to determine whether the application would have an unacceptable impact on the safety, reliability and/or operational efficiency of the SRN (the tests set out in DfT Circular 01/2022 and MHCLG NPPF2024 [particularly paras 115 to 118]). This response details the steps that need to be taken in order to resolve this issue.

In light of the above, National Highways currently recommends that planning permission not be granted (other than a refusal if the Council so wishes) for a period of three months from the date of this response to allow the applicant to resolve the outstanding matters.

This recommendation can be replaced, renewed, or reviewed during the three-month period, or at its end, dependent on progress made with regards to the outstanding matters.'

It is recommended that the application should not be approved until 30 October.

Standing advice to the local planning authority

The Climate Change Committee's 2022 Report to Parliament notes that for the UK to achieve net zero carbon status by 2050, action is needed to support a modal shift away from car travel. The NPPF supports this position, with paragraphs 77 and 110 prescribing that significant development should offer a genuine choice of transport modes, while paragraphs 109 and 115 advise that appropriate opportunities to promote walking, cycling and public transport should be taken up as part of a vision-led approach.

Moreover, the carbon reduction hierarchy (avoid-switch-improve) as set out in clause 4.3 of PAS2080:2023 promotes approaches and measures to minimise resource consumption and thereby reduce carbon emissions.

These considerations should be weighed alongside any relevant Local Plan policies to ensure that planning decisions are in line with the necessary transition to net zero carbon.

9.20.4 Further comments 10.09.25:

Thank you for your email dated 20 August providing the additional information requested in the previous National Highways response dated July 2025.

We have reviewed the Technical Note (TN) produced by Hub Transport Planning dated 18 August 2025 and have outlined our comments below.

The TN sets out a review of existing traffic modelling for the SRN junctions including the M1 J5 and M25 J18 from nearby development applications. For the M1 J5, the traffic impact has been derived using related planning applications (24/1283/OUTEI and 23/1035/OUTEI) which have traffic turning counts at M1 J5 and VISSIM microsimulation modelling and forecasting at the junction for employment development proposals of up to 45,000sqm. The traffic impact for M25 J18 is based on application 24/0538/OUT which includes traffic data at the SRN junction for 2019. The 2019 flows have been used to derive the impact analysis carried out for the Little Green Lane proposal.

In view of the additional review undertaken, the current operation of M25 J18 and the levels of development traffic proposed, we accept that no further assessment is required of the impact of the development on this junction.

However, we do not accept the findings of the high level assessment the applicant has undertaken for M1 J5, and continue to expect that a junction capacity assessment will be required. National Highways does not accept findings based on percentage impact for the SRN, particularly at already congested junctions such as M1 J5. Given the high volumes of traffic using our network, even a very small percentage impact could represent a significant/severe effect. M1 Junction 5 is already experiencing significant queues and delays during weekday peak hours, with vehicle queues extending off the M1 southbound off-slip during the AM peak hour.

The applicant references two applications, both of which used VISSIM modelling to test their impacts with similar levels of development trip numbers to this development at M1 J5. These were ultimately approved, subject to mitigation for M1 J5, which was tested through modelling and are now classed as committed schemes.

As a reminder, development proposals can be considered unacceptable by virtue of a severe impact if they increase demand for use of a section of the network that is already operating near or over capacity, or where the additional traffic cannot be safely accommodated on the SRN unless mitigation is agreed. National Highways considers that any development trips adding to a junction off-slip which then results in mainline queuing, extends a mainline queue, and / or increases the frequency at which mainline queuing occurs to be an unacceptable safety impact.

As a next step, we recommend the applicant gets in touch with us to discuss requirements for a modelling assessment at M1 J5.

Thank you for consulting National Highways and we look forward to continuing to participate in future consultations and discussions. In the meantime, if you have any questions with

regards to the comments made in this response, please do not hesitate to contact us at planningse@nationalhighways.co.uk.

9.20.5 Further comments 23.10.25 [Holding objection maintained]

Referring to the consultation on a planning application dated 21 January 2025 referenced above, in the vicinity of the M25, J18 and 19 and the M1 J5 that forms part of the Strategic Road Network, notice is hereby given that National Highways' formal recommendation is that we:

c) recommend that planning permission not be granted for a specified period (see reasons at Annex A);

Annex A National Highways' assessment of the proposed development

National Highways was appointed by the Secretary of State for Transport as a strategic highway company under the provisions of the Infrastructure Act 2015 and is the highway authority, traffic authority and street authority for the Strategic Road Network (SRN). The SRN is a critical national asset and as such we work to ensure that it operates and is managed in the public interest, both in respect of current activities and needs as well as in providing effective stewardship of its long-term operation and integrity.

National Highways is interested whether there would be any adverse safety implications or material increase in queues and delays on the SRN as a result of the proposed development, in this case on the M25, J18 and 20, and the M1 J5.

Previous NHPR of 30 July 2025

In our previous NHPR of 30 July 2025 we stated the following

We have reviewed the Amended Transport Assessment (ATA), Amended Travel Plan (ATP) and associated appendices provided as part of the planning submission update, written by Hub Transport Planning Ltd.

Trip Generation

We note that HCC requested the exclusion of a site surveyed due to low levels of parking and potential low levels of vehicle trip rates. As only one affordable site remained, we agree with the approach to use Land Use 3M within TRICS.

The AM peak period (08:00-09:00) is estimated to generate 315 two-way vehicle trips and the PM peak period (17:00-18:00) is expected to generate 304 two-way vehicle movements. Following the completion of internal comparison checks using TRICS, we are satisfied that the trip generation presented in Table 3 of the ATA is accurate.

We note that the ATA includes the requested trip generation for the primary school use and mixed local centre. We agree with the methodology used to establish the educational trips to the proposed development and are satisfied that the car-based arrivals to the site will travel via the local highway network. We also accept the reasoning behind the exclusion of the local centre and health centre use vehicle trips and are satisfied that those trips are unlikely to use the SRN.

Trip Distribution

We note that the ATA includes the traffic distribution for the SRN junctions as requested. We have reviewed the traffic distribution information provided in Appendix H and summarised in Table 7 of the ATA.

Travelling inbound in the AM peak period (08:00-09:00) and the PM peak period (17:00-18:00) the M25 J18 NB is expected to see an increase of 5 additional vehicles. At the same junction travelling outbound, the AM peak is expected to see an increase of 16 vehicles and the PM peak is estimated to see an additional 15 vehicles.

The highest volume of inbound traffic assigned to the SRN is 34 additional vehicles travelling SB on the M25 J18 in the AM peak and 33 additional vehicles travelling in the PM peak at the same junction. Travelling outbound, the M25 J18 SB is expected to see an increase of 50 vehicles in the AM peak hour and 49 additional vehicles in the PM peak hour. In the AM peak, typical traffic at the M25 J18 shows slow moving vehicles on Rickmansworth Road (A404) due to the signalised junction with the M25 J18 slip roads. The additional inbound vehicles at the SB off-slip are likely to cause further queuing on the off-slip due to the slow-moving vehicles at the signalised junction. The additional outbound vehicles have the potential to add to the congestion build up on the A404 and cause further queuing which may have implications for the SB on-slip.

An additional 15 inbound vehicles are expected at the M1 J5 NB in the AM peak period and an additional 27 inbound vehicles are expected in the PM peak. An additional 15 vehicles are expected to travel outbound at this junction during both peak periods. Travelling SB at the M1 J5, there are estimated to be an additional 15 inbound vehicles in the AM peak and an additional 16 inbound vehicles in the PM peak. Travelling outbound, an additional 29 vehicles are expected in the AM peak and an additional 28 vehicles are expected in the PM peak.

The M1 J5 SB off slip entering the Berrygrove Interchange experiences slow moving traffic during both peak hours. The inbound SB traffic at this junction has the potential to exacerbate this issue further and cause blocking back on the SB off-slip.

Traffic Impact

Section 6 of the TA sets out the traffic impacts, growth rates and the outputs of the junction capacity assessments carried out for local highway junctions surrounding the proposed development site.

Development proposals can be considered unacceptable by virtue of a severe impact if they increase demand for use of a section of the network that is already operating near or over capacity, or where the additional traffic cannot be safely accommodated on the SRN unless mitigation is agreed. National Highways considers that any development trips adding to a junction off-slip which then results in mainline queuing, extends a mainline queue, and / or increases the frequency at which mainline queuing occurs to be an unacceptable safety impact.

Both the M1 J5 and M25 J18 are observed to have significant existing off-slip queues which extend back towards their respective mainline carriageway in the AM and/or PM peak, such that any increases in flow on these off-slips may result in mainline queueing. Following a review of the trip distribution and the levels of existing congestion at each of the affected SRN junctions, **we request that the junction capacity assessments are extended to include the SRN junctions, particularly the M25 J18 and the M1 J5.** This will allow us to assess the full traffic impact of the proposal on the safety and operation of the SRN. Until this work is undertaken National Highways cannot satisfactorily consider the impact of the development on its network.

Sustainable Transport

We have reviewed the Amended Travel Plan provided which outlines the accessibility of local facilities, i.e. education, retail and health care services, by foot, cycle and public

transport, demonstrating that the proposed site is readily accessible by a variety of transport modes that have the potential to reduce reliance on the private car.

Section 5 sets out the Travel Plan Targets which states that the developer is confident that a 15% reduction in single-occupancy car use can be achieved based on the journey to work modal split indicated by the census data. This would reduce car driver trips by 8.2% to 42% from 55.2%. The drivers for this change are expected to be the provision of local facilities on site, reducing the need to travel by car and encouraging more active travel, the proposed shared-use walking/cycling facility, the inclusion of a Beryl Bikes facility on site, the enhancement of the existing local bus service (service 22) providing sustainable access to off-site facilities, bus taster tickets for each household and the inclusion of a car club on site which has the potential to reduce private car ownership. These measures are further explored in Section 6 of the amended Travel Plan.

National Highways welcomes sustainable transport measures being the primary means to off-set any severe / significant development impacts on the SRN. We are satisfied that the measures proposed will help reduce travel demand by private vehicle on the SRN, particularly the proposed provision of a bus service providing connections to important transport hubs and Watford.

Construction Traffic

Table 8 of the ATA outlines the anticipated construction traffic from the proposed development and Table 9 shows the maximum daily construction traffic trip generation. It is estimated that the proposed development will generate a maximum of 63 two-way daily vehicle movements. It is expected that 12 of these daily movements will be two way HGV movements.

We note that the FCTMP requested in our previous response will be conditioned as part of formal planning permission being granted for the proposal.

Position of 23 October 2025

Since issuing our previous NHPR response we have been in correspondence with the applicant's transport consultants to assist with the transport modelling requirements. From your consultation of 20 August we responded on 10 September and were able to discount the requirement for transport modelling at M1 Junction 18.

We have exchanged emails about modelling requirements with the above consultants and understand that the modelling for M1 Junction 5 is being undertaken at the present time.

Recommended Non-Approval

Given the above, it is currently not possible to determine whether the application would have an unacceptable impact on the safety, reliability and/or operational efficiency of the SRN (the tests set out in DfT Circular 01/2022 and MHCLG NPPF2024 [particularly paras 115 to 118]). This response details the steps that need to be taken to resolve this issue.

Considering the above, National Highways currently recommends that planning permission not be granted (other than a refusal if the Council so wishes) for a period of three months from the date of this response to allow the applicant to resolve the outstanding matters.

This recommendation can be replaced, renewed, or reviewed during the three-month period, or at its end, dependent on progress made with regards to the outstanding matters.'

It is recommended that the application should not be approved until 23 January 2026.

Standing advice to the local planning authority

The Climate Change Committee's [2022 Report to Parliament](#) notes that for the UK to achieve net zero carbon status by 2050, action is needed to support a modal shift away from car travel. The NPPF supports this position, with paragraphs 77 and 110 prescribing that significant development should offer a genuine choice of transport modes, while paragraphs 109 and 115 advise that appropriate opportunities to promote walking, cycling and public transport should be taken up as part of a visionled approach.

Moreover, the carbon reduction hierarchy (avoid-switch-improve) as set out in clause 4.3 of PAS2080:2023 promotes approaches and measures to minimise resource consumption and thereby reduce carbon emissions.

These considerations should be weighed alongside any relevant Local Plan policies to ensure that planning decisions are in line with the necessary transition to net zero carbon.

9.20.6 Further comments 4.12.25:

Thank you for your consultation of 14 November on the planning application referenced above.

National Highways has been appointed by the Secretary of State for Transport as a strategic highway company under the provisions of the Infrastructure Act 2015 and is the highway authority, traffic authority and street authority for the Strategic Road Network (SRN). The SRN is a critical national asset and as such we work to ensure that it operates and is managed in the public interest, both in respect of current activities and needs as well as in providing effective stewardship of its long-term operation and integrity.

National Highways are interested as to whether there would be any adverse safety implications or material increase in queues and delays on the SRN as a result of the proposed development, in this case on the M1 Junction 5.

Our transport modelling consultants have reviewed the report that you have submitted on to your planning portal. We have additionally asked the applicant's consultants for the actual transport models that have since been supplied to us for examination.

The modelling and reporting, as presented by WSP on behalf of the applicant, for the M1 J5 indicates that the proposed development may have an impact on the SRN. The length of the M1 J5 southbound on-slip is approximately 450m from the signalised stop line to the start of the diverge, the maximum queue recorded on this link in the 2025 Do Something model is approx. 700m in the AM peak, as shown in Table 5.6. We note that the maximum queue lengths set out in Table 5.6 of the technical note do not align with Figures 5.1 and 5.2 as Figure 5.1 is captioned as the maximum queue length for the M1 northbound but appears to illustrate the maximum queue length for M1S from Table 5.6. We have assumed for the purpose of this review that table 5.6 is correct and that Figure 5.1 correlates to the M1 J5southbound queue lengths despite its caption.

The maximum queue for the M1 J5 southbound (Figure 5.1) occurs in 1 run of the 9 carried out. The technical note states that run 1 is an outlier and should be removed from the results. However, to ensure there is not an issue with the model, we request that queue length data is provided for 20 runs of the model to fully demonstrate that the long queue length shown in run 1 is an anomaly.

As you are aware our current holding recommendation expires on 23 January 2026. This should give sufficient time for the applicant's consultants to respond. We are aware that you may wish to determine this application before this date and we would recommend that the

requested modelling is undertaken as soon as possible to enable us sufficient time to review with the intention of providing a final response should all issues be resolved.

9.20.7 Further comments 07.01.26 [No objection]

Referring to the consultation on a planning application dated 21 January 2025 referenced above, in the vicinity of the M25, J18 and 19 and the M1 J5 that forms part of the Strategic Road Network, notice is hereby given that National Highways' formal recommendation is that we:

a) offer no objection (see reasons at Annex A);

This represents National Highways' formal recommendation and is copied to the Department for Transport as per the terms of our Licence.

Should the Local Planning Authority propose not to determine the application in accordance with this recommendation they are required to consult the Secretary of State for Transport, as set out in the Town and Country Planning (Development Affecting Trunk Roads) Direction 2018, via transportplanning@ddt.gov.uk and may not determine the application until the consultation process is complete.

The Local Planning Authority must also copy any consultation under the 2018 Direction to PlanningSE@nationalhighways.co.uk.

This response and all comments outlined herein are made in respect of planning matters only in National Highways' position as a statutory planning consultee, and does not confer any proprietary rights nor amount to the giving or refusal of consent, assent, approval, or awareness of or by National Highways in or of any other aspects or matters (including, but not limited to, the use of property belonging to National Highways). If anyone wishes for National Highways to consider any aspects which do not relate to planning submissions, they should call our contact centre on 0300 123 5000.

Annex A National Highways' assessment of the proposed development

National Highways was appointed by the Secretary of State for Transport as a strategic highway company under the provisions of the Infrastructure Act 2015 and is the highway authority, traffic authority and street authority for the Strategic Road Network (SRN). The SRN is a critical national asset and as such we work to ensure that it operates and is managed in the public interest, both in respect of current activities and needs as well as in providing effective stewardship of its long-term operation and integrity.

National Highways is interested whether there would be any adverse safety implications or material increase in queues and delays on the SRN as a result of the proposed development, in this case on the M25, J18 and 20, and the M1 J5.

Previous NHPR of 30 July 2025

In our previous NHPR of 30 July 2025 we stated the following

We have reviewed the Amended Transport Assessment (ATA), Amended Travel Plan (ATP) and associated appendices provided as part of the planning submission update, written by Hub Transport Planning Ltd.

Trip Generation

We note that HCC requested the exclusion of a site surveyed due to low levels of parking and potential low levels of vehicle trip rates. As only one affordable site remained, we agree with the approach to use Land Use 3M within TRICS.

The AM peak period (08:00-09:00) is estimated to generate 315 two-way vehicle trips and the PM peak period (17:00-18:00) is expected to generate 304 two-way vehicle movements. Following the completion of internal comparison checks using TRICS, we are satisfied that the trip generation presented in Table 3 of the ATA is accurate.

We note that the ATA includes the requested trip generation for the primary school use and mixed local centre. We agree with the methodology used to establish the educational trips to the proposed development and are satisfied that the car-based arrivals to the site will travel via the local highway network. We also accept the reasoning behind the exclusion of the local centre and health centre use vehicle trips and are satisfied that those trips are unlikely to use the SRN.

Trip Distribution

We note that the ATA includes the traffic distribution for the SRN junctions as requested. We have reviewed the traffic distribution information provided in Appendix H and summarised in Table 7 of the ATA.

Travelling inbound in the AM peak period (08:00-09:00) and the PM peak period (17:00-18:00) the M25 J18 NB is expected to see an increase of 5 additional vehicles. At the same junction travelling outbound, the AM peak is expected to see an increase of 16 vehicles and the PM peak is estimated to see an additional 15 vehicles.

The highest volume of inbound traffic assigned to the SRN is 34 additional vehicles travelling SB on the M25 J18 in the AM peak and 33 additional vehicles travelling in the PM peak at the same junction. Travelling outbound, the M25 J18 SB is expected to see an increase of 50 vehicles in the AM peak hour and 49 additional vehicles in the PM peak hour. In the AM peak, typical traffic at the M25 J18 shows slow moving vehicles on Rickmansworth Road (A404) due to the signalised junction with the M25 J18 slip roads. The additional inbound vehicles at the SB off-slip are likely to cause further queuing on the off-slip due to the slow-moving vehicles at the signalised junction. The additional outbound vehicles have the potential to add to the congestion build up on the A404 and cause further queuing which may have implications for the SB on-slip.

An additional 15 inbound vehicles are expected at the M1 J5 NB in the AM peak period and an additional 27 inbound vehicles are expected in the PM peak. An additional 15 vehicles are expected to travel outbound at this junction during both peak periods. Travelling SB at the M1 J5, there are estimated to be an additional 15 inbound vehicles in the AM peak and an additional 16 inbound vehicles in the PM peak. Travelling outbound, an additional 29 vehicles are expected in the AM peak and an additional 28 vehicles are expected in the PM peak.

The M1 J5 SB off slip entering the Berrygrove Interchange experiences slow moving traffic during both peak hours. The inbound SB traffic at this junction has the potential to exacerbate this issue further and cause blocking back on the SB off-slip.

Traffic Impact

Section 6 of the TA sets out the traffic impacts, growth rates and the outputs of the junction capacity assessments carried out for local highway junctions surrounding the proposed development site.

Development proposals can be considered unacceptable by virtue of a severe impact if they increase demand for use of a section of the network that is already operating near or over capacity, or where the additional traffic cannot be safely accommodated on the SRN unless mitigation is agreed. National Highways considers that any development trips adding to a junction off-slip which then results in mainline queuing, extends a mainline queue, and / or increases the frequency at which mainline queuing occurs to be an unacceptable safety impact.

*Both the M1 J5 and M25 J18 are observed to have significant existing off-slip queues which extend back towards their respective mainline carriageway in the AM and/or PM peak, such that any increases in flow on these off-slips may result in mainline queueing. Following a review of the trip distribution and the levels of existing congestion at each of the affected SRN junctions, **we request that the junction capacity assessments are extended to include the SRN junctions, particularly the M25 J18 and the M1 J5.** This will allow us to assess the full traffic impact of the proposal on the safety and operation of the SRN. Until this work is undertaken National Highways cannot satisfactorily consider the impact of the development on its network.*

Sustainable Transport

We have reviewed the Amended Travel Plan provided which outlines the accessibility of local facilities, i.e. education, retail and health care services, by foot, cycle and public transport, demonstrating that the proposed site is readily accessible by a variety of transport modes that have the potential to reduce reliance on the private car.

Section 5 sets out the Travel Plan Targets which states that the developer is confident that a 15% reduction in single-occupancy car use can be achieved based on the journey to work modal split indicated by the census data. This would reduce car driver trips by 8.2% to 42% from 55.2%. The drivers for this change are expected to be the provision of local facilities on site, reducing the need to travel by car and encouraging more active travel, the proposed shared-use walking/cycling facility, the inclusion of a Beryl Bikes facility on site, the enhancement of the existing local bus service (service 22) providing sustainable access to off-site facilities, bus taster tickets for each household and the inclusion of a car club on site which has the potential to reduce private car ownership. These measures are further explored in Section 6 of the amended Travel Plan.

National Highways welcomes sustainable transport measures being the primary means to off-set any severe / significant development impacts on the SRN. We are satisfied that the measures proposed will help reduce travel demand by private vehicle on the SRN, particularly the proposed provision of a bus service providing connections to important transport hubs and Watford.

Construction Traffic

Table 8 of the ATA outlines the anticipated construction traffic from the proposed development and Table 9 shows the maximum daily construction traffic trip generation. It is estimated that the proposed development will generate a maximum of 63 two-way daily vehicle movements. It is expected that 12 of these daily movements will be two-way HGV movements.

We note that the FCTMP requested in our previous response will be conditioned as part of formal planning permission being granted for the proposal.

Position of 23 October 2025

Since issuing our previous NHPR response we have been in correspondence with the applicant's transport consultants to assist with the transport modelling requirements. From

your consultation of 20 August we responded on 10 September and were able to discount the requirement for transport modelling at M1 Junction 18.

We have exchanged emails about modelling requirements with the above consultants and understand that the modelling for M1 Junction 5 is being undertaken at the present time.

Position of 7 January 2026

Further traffic modelling information for M1 Junction 5 was received on 15 December 2025. Following our review we have the following comments.

The VISSIM modelling undertaken has generated average queue lengths that are shorter than the M1 off-slips. A minority of the seeded runs indicate a maximum queue length that would exceed the length of the M1 southern on-slip. However, the average queue length remains within the slip road. Therefore, the model outputs indicate a potentially infrequent impact on the operation of the Strategic Road Network (SRN). On consideration there is insufficient evidence of likely occurrence related to the additional development related traffic.

Regarding the operation of the model, the base network has been calibrated with traffic using two lanes to exit junction 5 to the M1 southbound. The circulating carriageway of junction 5 has been relined since the calibration of the base model to mark a single lane exit. As such, the base model may overestimate the capacity of junction 5 at this location and the preceding signal stoplines. The calibration should be revisited prior to any future application of the model.

Recommended No Objection

Given the above, we are satisfied that the development will not materially affect the safety, reliability and/or operation of the strategic road network (the tests set out in DfT Circular 01/2022, and MHCLG NPPF 2024 paragraphs 115-118) in this location and its vicinity.

Standing advice to the local planning authority

The Climate Change Committee's 2022 Report to Parliament notes that for the UK to achieve net zero carbon status by 2050, action is needed to support a modal shift away from car travel. The NPPF supports this position, with paragraphs 77 and 110 prescribing that significant development should offer a genuine choice of transport modes, while paragraphs 109 and 115 advise that appropriate opportunities to promote walking, cycling and public transport should be taken up as part of a vision-led approach.

Moreover, the carbon reduction hierarchy (avoid-switch-improve) as set out in clause 4.3 of PAS2080:2023 promotes approaches and measures to minimise resource consumption and thereby reduce carbon emissions.

These considerations should be weighed alongside any relevant Local Plan policies to ensure that planning decisions are in line with the necessary transition to net zero carbon.

9.21 Natural England: [No objection subject to conditions]

Thank you for your consultation on the above dated 22 January 2025 which was received by Natural England on the same date.

Natural England is a non-departmental public body. Our statutory purpose is to ensure that the natural environment is conserved, enhanced, and managed for the benefit of present and future generations, thereby contributing to sustainable development.

SUMMARY OF NATURAL ENGLAND'S ADVICE

NO OBJECTION - SUBJECT TO APPROPRIATE MITIGATION BEING SECURED

Natural England considers that without appropriate mitigation the application would:

- damage or destroy the interest features for which Whippendell Wood Site of Special Scientific Interest and Croxley Common Moor Site of Special Scientific Interest have been notified.

In order to mitigate these adverse effects and make the development acceptable, the following options should be secured:

- Provision of 24ha green space/country park with secured management plan/maintenance for the lifetime of the development
- Minimum 30m buffer zone around ancient woodland within and adjacent to the proposed development
- An ancient woodland recreational management plan
- Information packs for residents on sensitive use of local habitats/protected sites
- A Construction Environment Management Plan for both construction and operational measures

We advise that an appropriate planning condition or obligation is attached to any planning permission to secure these measures.

A lack of objection does not mean that there are no significant environmental impacts. Natural England advises that all environmental impacts and opportunities are fully considered and relevant local bodies are consulted.

Natural England's further advice on designated sites/landscapes and advice on other natural environment issues is set out below.

Further advice on mitigation

The proposed development falls within the Impact Risk Zones (IRZs) for Whippendell Wood SSSI and Croxley Common Moor SSSI and, without appropriate mitigation, has the potential to impact the sites' interest features. Natural England are satisfied that subject to securing of the below measures, the development will have minimal impact on the above designated sites. We have come to this conclusion after review of the following documents:

- Planning statement MNP-00124.C8622 December 2024
- Ecological Impact Assessment and Biodiversity Impact Assessment RSE_8239_R1_V 4_E cIA December 2024
- Agricultural Land Classification and Soil Resources July 2024
- Landscape & Visual Impact Assessment and Green Belt Assessment I000010_DL100_E December 2024

Protected sites - Open Green space design

Having reviewed the provided landscape mitigation plan Natural England are satisfied that subject to implementation of the open Green Space design set out within the planning statement and illustrative masterplan, adverse impacts on Whippendell Wood SSSI and Croxley Common Moor SSSI can be avoided/mitigated. In order to provide an alternative to these highly sensitive protected sites, it is important that the development delivers, at the appropriate phasing, a suitable scale and quality of Green Space, ideally in accordance of Natural England's Green Infrastructure Framework: Principles and Standards, and particularly the ANGst guidelines. Ideally this should include:

- Circular walk of at least 2.3km
- Provision for dogs along SANG guidelines e.g. off lead areas, dog waste bins
- Signage and interpretation of PRoW/paths
- On-site maintenance and management of greenspace/country park secured in perpetuity

Due to the location of the proposed development within the Area of Search for the Chilterns National Landscape we recommend liaising with the Chilterns Conservation Board to inform such designs, ensuring they are sympathetic to the landscape character.

Please note that if your authority is minded to grant planning permission contrary to the advice in this letter, you are required under Section 28I (6) of the Wildlife and Countryside Act 1981 (as amended) to notify Natural England of the permission, the terms on which it is proposed to grant it and how, if at all, your authority has taken account of Natural England's advice. You must also allow a further period of 21 days before the operation can commence.

Protected Landscapes – Chilterns National Landscape

The proposed development is located partly within/ within a proposed area of search which Natural England is considering as a possible boundary variation to the Chilterns Area of Outstanding Natural Beauty (AONB, known as National Landscape). Whilst this assessment process does not confer any additional planning protection, the impact of the proposal on the natural beauty of this area may be a material consideration in the determination of the proposal. Natural England considers the Chilterns to be a valued landscape in line with paragraph 180 of the National Planning Policy Framework (NPPF). Furthermore, paragraph 182 of the NPPF states that development in the settings of AONBs should be sensitively located and designed to avoid or minimise impacts on the designated areas. An assessment of the landscape and visual impacts of the proposal on this area should therefore be undertaken, with opportunities taken to avoid or minimise impacts on the landscape and secure enhancement opportunities. Any development should reflect or enhance the intrinsic character and natural beauty of the area and be in line with relevant development plan policies. In addition, Section 245 (Protected Landscapes) of the Levelling Up and Regeneration Act 2023 places a duty on relevant authorities to seek to further the statutory purposes of the area in carrying out their functions in relation to, or so as to affect, land in an AONB.

We expect consultation with the appropriate statutory body, in this case, the Chilterns Conservation Board to inform design and mitigation measures associated with this development.

An extension to an existing AONB is formally designated once a variation Order, made by Natural England, is confirmed by the Defra Secretary of State. Following the issuing of the designation Order by Natural England, but prior to confirmation by the Secretary of State, any area that is subject to a variation Order would carry great weight as a material consideration in planning decisions.

Ancient woodland, ancient and veteran trees

The proposed site contains ancient woodland both within and adjacent to the red line boundary. Natural England acknowledges and welcomes provision of the aforementioned Green Infrastructure and a minimum 30m buffer zone for all ancient woodland within the site.

We strongly recommend liaising with the Forestry Commission as the statutory body for woodland habitats to inform a management plan and appropriate mitigation.

The local planning authority should consider any impacts on ancient woodland and ancient and veteran trees in line with paragraph 186 of the NPPF. The Natural England Access to Evidence - Ancient woodlands Map can help to identify ancient woodland. Natural England and the Forestry Commission have produced Ancient woodland, ancient trees and veteran trees: advice for making planning decisions - GOV.UK (www.gov.uk) (standing advice) for planning authorities. It should be considered when determining relevant planning applications.

The following should be secured:

- An Ancient woodland recreational management plan
- A minimum 30m buffer around ancient woodland and woodland habitats, with associated root protected zone in design plans.

Other advice

Best and Most Versatile Agricultural Land or Minerals and Waste reclamation

Local planning authorities are responsible for ensuring that they have sufficient detailed agricultural land classification (ALC) information to apply NPPF policies (Paragraphs 180 and 181). This is the case regardless of whether the proposed development is sufficiently large to consult Natural England. Further information is contained in the Guide to assessing development proposals on agricultural land - GOV.UK (www.gov.uk). Find open data - data.gov.uk on Agricultural Land Classification or use the information available on MAGIC (defra.gov.uk).

The Defra Construction Code of Practice for the Sustainable Use of Soils on Construction Sites (publishing.service.gov.uk) provides guidance on soil protection, and we recommend its use in the design and construction of development, including any planning conditions. For mineral working landfilling, we refer you to Reclaim minerals extraction and landfill sites to agriculture - GOV.UK (www.gov.uk), which provides guidance on soil protection for site restoration and aftercare. The Soils Guidance (quarrying.org) provides detailed guidance on soil handling for mineral sites.

Should the development proceed, we advise that the developer uses an appropriately experienced soil specialist to advise on, and supervise soil handling, including identifying when soils are dry enough to be handled and how to make the best use of soils on site.

Further general advice on consideration of protected species and other natural environment issues is provided at Annex A.

Should the developer wish to discuss the detail of measures to mitigate the effects described above with Natural England, we recommend that they seek advice through our Discretionary Advice Service.

If you have any queries relating to the advice in this letter, please contact me on consultations@naturalengland.org.uk.

We would be pleased to provide advice on the discharge of planning conditions or obligations attached to any planning permission to address the issues above.

Should the proposal change, please consult us again.

9.22 Ramblers: [Advisory comments]

As the local representative of The Ramblers, my sole interest in this application is the effect on the public right of way, FP17, which crosses the site. Therefore I would request that before any more serious planning is carried out on this proposal that you contact me so that

we can come to an amicable agreement over rights of way across the site, in order to avoid any disputes later in the process. I hope that footpath 17 will be preserved as far as practicable along its present route. Also, I would hope that at least one further right of way can be created from Little Green Lane, connecting up with FP17.

As you probable are aware, The Ramblers are a statutory organisation for receiving any planning proposals that affect rights of way.

Officer comment: Whilst The Ramblers have been notified of the application, they are not a statutory consultee. This has been acknowledged by their local representative.

9.23 Sarratt Parish Council: [Objection]

SPC object to this application for the reasons set out below. If the officers are minded to approve this application we request that it is brought into the planning committee.

We recognise this application whilst in Sarratt Parish boundaries, would have a more significant impact on Croxley Green and its residents.

Our primary objection is that this application is overdevelopment on Green Belt land with insufficient case to apply very special circumstances.

The purpose of Green Belt is to prevent urban sprawl by protecting separation between developed areas and to protect rural setting (NPPF Paragraphs 142 & 143). This application in our opinion would go against this policy including impacting the purpose of this land as separation between Croxley Green and Chandlers Cross, as well as providing rural setting to the north of Croxley Green. We reject the applicant's submitted assessment that this plot is classed as 'Grey Belt' as this statement does not correctly consider the full context and does not provide external references or evidence, to substantiate this self-assessed position.

We welcome the applicant adhering to the affordable housing policies with this application, however the housing need (including affordable provision) for Sarratt Parish as outlined in the Housing Needs. Assessment has already been satisfied by recent approved development applications. This and any other applications would exceed the housing need for the Parish.

Sarratt is a rural parish with concerning strains on its transport and services infrastructure. An application of this size is not sustainable in Sarratt Parish.

The neighbouring Croxley Green as a larger settlement has the theoretical potential to provide infrastructure for this size of development. However, the applicants own submitted expert reports identify many existing significant issues with transport infrastructure and services such as sewage capacity. Neither Sarratt Parish nor Croxley Green would be able to accommodate a development of this size which means this is an unsustainable location.

The indicative designs in the application include four story buildings. This height of building is not in keeping with Sarratt Parish buildings and is also not typical in Croxley Green. The effect of this aspect on the views and separation from settlements is a concern.

The need for the additional facilities outlined in this application has not been properly tested. One of these facilities, the NHS health and social care services duplicates provision in another already approved application in Sarratt Parish, so there is no defined need for this provision in this application.

We note the very large number of local public objections submitted on this application so far and also note the significant objections submitted by HCC highways and the local flood authority.

In conclusion we recognise the need for housing at the national, district and local level. SPC has in recent times supported new developments in our Parish where they are in appropriate locations. However, this application is for an unsustainable location on Green Belt land.

9.24 Sport England: [No objection subject to conditions/S106 contributions]

9.24.1 Initial comments 7.2.25 [Objection]

Thank you for consulting Sport England on the above application.

Sport England's Position

Community Sports Provision

Due to the need for more detail to be provided about the proposals for outdoor and indoor community sports provision, an **objection** is made to the planning application in its current form. However, I would be willing to withdraw this objection in due course if the advice in this response is considered and positive proposals are made to address the matters raised through the planning application and/or planning obligation/condition requirements.

Primary School

It is **requested** that any planning permission makes provision for securing a formal community use agreement on the primary school site.

Active Design

A planning condition is **requested** requiring details to be submitted and approved which demonstrate how Active Design principles have been considered in the design and layout of reserved matters applications.

Sport England – Non Statutory Role and Policy

The Government, within their Planning Practice Guidance (Open Space, Sports and Recreation Facilities Section) advises Local Planning Authorities to consult Sport England on a wide range of applications. <https://www.gov.uk/guidance/open-space-sports-and-recreation-facilities-public-rights-of-way-and-local-green-space>. This application falls within the scope of the above guidance as it relates to a development of more than 300 dwellings.

Sport England assesses this type of application in line with its planning objectives and with the National Planning Policy Framework (NPPF). Sport England's planning objectives are to PROTECT existing facilities, ENHANCE the quality, accessibility and management of existing facilities, and to PROVIDE new facilities to meet demand.

Sport England's Planning for Sport guidance can be found here:

<https://www.sportengland.org/facilities-and-planning/planning-for-sport/planning-for-sport-guidance/>

The Proposal and Assessment against Sport England's Objectives and the NPPF

Community Sports Facility Provision

Introduction

The proposal is an outline planning application for a mixed use residential led development of up to 600 dwellings on land to the north of Little Green Lane in Croxley Green. The population of the proposed development is estimated to be 1,380 based on the applicant's estimate set out in paragraph 6.10 of the Sport and Leisure Strategy. This additional population will generate additional demand for sports facilities. If this demand is not adequately met, it may place additional pressure on existing sports facilities, thereby creating or exacerbating deficiencies in facility provision. In accordance with the NPPF, Sport England seeks to ensure that the development meets any new community sports facility needs arising as a result of the development. In this context, I would wish to make the following comments on the community sports provision aspects of the planning application.

Evidence Base and Policy Context

The evidence base and local planning policy context for community sport can be summarised as follows:

□ Policy DM11 of the adopted Development Management Policies Local Development Document (2013) advises that when granting planning permission for new residential development of 25 or more dwellings, the Council will expect developer contributions to the provision or enhancement of local sports facilities where a need is demonstrated to have arisen from the development concerned and there are inadequate local facilities

□ Three Rivers District Council's Playing Pitch Strategy (2019) identifies deficiencies in outdoor sports provision (especially football pitches, 3G artificial grass pitches and rugby union pitches) and accounts for future population needs.

□ Three Rivers District Council's Leisure Facilities Strategy (2019) covers indoor sports facilities and identifies deficiencies in facilities such as health & fitness and gymnastics centres and accounts for future population needs.

In view of the local planning policy and evidence base context, it is considered that in accordance with Government policy in paragraph 103 of the NPPF, a robust local basis exists for justifying the provision of outdoor and indoor community sports facility provision to be made by this development.

Proposed Sports Facility Provision

The Sport and Leisure Strategy (prepared by Sports Planning Consultants) that has been submitted in support of the application has assessed sports facility needs in detail and the findings and conclusions are considered to be robust. This strategy was prepared in consultation with Sport England and the sports governing bodies at the pre-application stage.

In relation to outdoor sports, in response to the strategy identifying deficiencies in football and cricket pitch provision, the strategy advises that the applicant explored the potential for on-site provision at pre-application stage but concluded that this was not feasible due to topographical, landscape and highways considerations. Instead, the strategy concluded that off-site provision options should be progressed involving financial contributions being secured towards off-site natural turf football pitches, 3G artificial grass pitches, rugby union pitches, cricket pitches and tennis courts.

In response to the Council's Playing Pitch Strategy advising new development to consider integrating opportunities for athletics within wider open spaces, as set out in paragraph 6.43 of the Sport and Leisure Strategy, consideration is being given to the provision of an informal Newgen active track <https://www.englandathletics.org/clubs-and-facilities/facilities/newgen->

tracks/ within the proposed on-site country park. Paragraph 6.38 of the strategy also suggests that a community use agreement is pursued for the proposed primary school to secure community access to the school's outdoor sports facilities although the limitations of primary school facilities in meeting community needs have been set out in the strategy.

In relation to indoor sports facility provision, the strategy concludes that there is no justification for on-site indoor sports provision but that qualitative improvements may be required to sports halls and swimming pools to ensure existing facilities continue to meet demand due to their age/condition. The strategy also identified that while the Council's Leisure Facilities Strategy identified a quantitative deficit in health & fitness provision there is no evidence that demand from the development cannot be met by existing local provision. In relation to community halls, consultation has identified that there have been ongoing increases in community demand and a local community venue has closed. The strategy has indicated that an on-site community hall could integrate a health and fitness facility into its design. Furthermore, as set out above a community use agreement has been recommended for the proposed primary school's facilities which would be expected to include a school hall which may have community use potential.

The recommendations in the applicant's Sport and Leisure Strategy for meeting the additional sports facility needs generated by the development are broadly welcomed. However, before Sport England could confirm its support for the proposals the following matters would need to be addressed:

- **Financial Contributions:** Reference is made in paragraph 12.11 of the Planning Statement to appropriate and proportionate contributions towards sports being agreed following discussions with the District Council. Tables 6.1/6.2 and paragraph 6.22 of the Sport and Leisure Strategy set out what the capital costs would be of meeting the additional demand for the facilities generated by the development. These costings have been informed by the use of Sport England's Playing Pitch Calculator and Sports Facility Calculators, the use of which is endorsed for this purpose by the Council's Playing Pitch Strategy and Leisure Facilities Strategy.

However, despite these references there are no confirmed proposals at this stage in relation to the scope of the contributions and the amounts for the different sports facility types. Sport England would need certainty that appropriate contributions towards outdoor and indoor sports provision would be offered in practice before supporting the applicant's strategy for sports provision. This is necessary because if no contributions or inadequate contributions were proposed by the applicant and agreed by the District Council at a later stage of the determination process this would be unacceptable because the development's sports needs would not be met. A planning obligation would need to identify the projects that the contributions would be used towards and the trigger points for the contribution payments to be made. Confirmation is therefore requested of the scope and level of the financial contributions proposed.

- **NewGen Active Track.** While the reference in the Sport and Leisure Strategy to a NewGen Active Track being considered in the proposed country park is welcomed, no reference is made to this in the country park proposals set out in the Planning Statement or the Design & Access Statement. If an Active Track is to be provided within the country park, the track would need to be proposed as part of the application and its provision secured as part of a planning obligation. Without it being secured there would be no certainty that an Active Track which met England Athletics' guidance would be provided at the reserved matters stage as there would be no requirement to provide it in any outline planning permission. Clarity is therefore requested of whether an Active Track is proposed to be provided within the country park and how its delivery would be secured through any planning permission.

- **Community Hall:** As indicated, some indoor facility needs such as health & fitness can be met through multi-purpose community facilities such as community halls. Sport England's

Village and Community Halls design guidance <https://www.sportengland.org/how-we-can-help/facilities-and-planning/design-and-cost-guidance/sports-halls> may be helpful in this regard. Consideration should therefore be given to whether the community centre proposed could be designed so that it could provide for formal sports use as well as other community uses. For example, community halls can be designed so that they are suitable for badminton, dance, fitness and martial arts while activity studios and fitness suites can be provided as part of community halls. This could potentially negate the extent of financial contributions that would be expected towards off-site projects. If this option is pursued, further advice from Sport England should be sought as a minimum specification for such a community hall would need to be included in a planning obligation in order to ensure that a facility is suitable for indoor sport in practice.

Conclusion

As there is further information requested about the proposals for meeting the development community sports facility needs, an **objection** is made to the planning application in its current form. However, I would be willing to withdraw this objection in due course if further information is provided as set out above.

Primary School

As indicated in the applicant's Sport and Leisure Strategy, the proposed primary school would be expected to provide some sport and recreation facilities for meeting educational needs that could also be used by the community outside of school hours such as the playing field and the school hall. While these facilities are principally for school use and would be designed for primary school aged children and should not be considered as a substitute for dedicated community facilities, they would offer potential to complement on and off-site provision made for dedicated community sports facility provision. While there is limited detail of what would be provided on the school site, to ensure that the school's facilities are secured for community use in practice, I would **request** that any planning permission makes provision for securing the community use of the sports facilities provided on the school site. A formal community use agreement would be the appropriate mechanism for securing community use. This has also been suggested by the applicant in paragraph 12.20 of the Planning Statement. Without a formal community use agreement being secured there would be no certainty that the facilities would be accessible to the community in practice after they have been built. Condition 16 from our model planning conditions schedule https://www.sportengland.org/guidance-and-support/facilities-and-planning/planning-sport?section=playing_fields_policy should be used as a basis for securing this through a planning permission.

Active Design

Sport England, with support from Active Travel England and OHID, has produced 'Active Design' <https://www.sportengland.org/guidance-and-support/facilities-and-planning/design-and-cost-guidance/active-design> a guide to planning new developments that create the right environment to help people get more active. The guidance sets out ten key principles for ensuring developments incorporate opportunities for people to take part in sport and physical activity. The Active Design principles are aimed at contributing towards the Government's desire for the planning system to promote healthy communities through good urban design which is consistent with paragraphs 96 and 129 of the NPPF. Sport England commends the use of the guidance in the master planning process for new residential developments. It should be noted that the Active Design guidance has also been advocated by Hertfordshire County Council's Healthy Places Team (who Sport England works closely with) in their response to this planning application.

The conceptual development proposals offer opportunities for incorporating the active design principles such as the proposed walking and cycling routes, the co-location of the

community facilities, the country park and the other multi-functional open spaces. This potential for this has also been recognised in the applicant's Sport and Leisure Strategy and Health Impact Assessment. As the planning application is in outline form it would be inappropriate to provide detailed comments at this stage because the submitted parameter plans are conceptual. The Active Design guidance includes a checklist that can be applied to developments and it is recommended that the checklist is used in the preparation of subsequent reserved matters planning applications if the application is permitted to ensure that opportunities for encouraging active lifestyles have been fully explored in the detailed planning and design of the development. It is therefore **requested** that a planning condition be imposed requiring the submission and approval of details to demonstrate how the reserved matters applications have considered Active Design principles. Sport England would welcome discussions with the applicant in due course to provide further advice on how Active Design can be considered in the detailed proposals.

A suggested planning condition is as follows:

"For each parcel/phase of development for which Outline permission is granted, no development in relation to that parcel/phase shall commence until details have been submitted and approved in writing by the Local Planning Authority to demonstrate how Active Design principles have been met.

Reason: To promote healthy lifestyles through physical activity and to accord with Development Plan policy.

Informative: Consideration should be given to using the Active Design checklist in Sport England's Active Design Guidance to assess reserved matters planning applications"

I hope that these comments can be given full consideration when a decision is made. I would be happy to discuss the response with the local planning authority and/or the applicant as the determination of the application progresses. Please contact me if you have any queries.

If this application is to be presented to a Planning Committee, we would like to be notified in advance of the publication of any committee agendas, report(s) and committee date(s). We would be grateful if you would advise us of the outcome of the application by sending us a copy of the decision notice.

9.24.2 Further comments 28.5.25 [No objection subject to conditions/S106 contributions]

Thank you for consulting Sport England on the amended plans/information relating to the above application. The applicant's agent's letter dated 22nd May 2025 responds to the comments made in our initial formal response dated 7th February 2025. I am now in a position to review our position on the planning application and would wish to comment on the following matters:

Sport England's Position

Community Sports Provision

The objection in the previous response is withdrawn subject to the following matters being addressed as set out in this response:

- Financial contributions being secured through a section 106 agreement towards off-site outdoor and indoor sports facility provision in accordance with the capital costings set out in this response. The projects that the contributions would be used towards and the trigger points for the contribution payments to be made would need to be addressed as part of the preparation of a section 106 agreement.

- A minimum specification for the community hall building being secured through a section 106 agreement.
- A planning condition being imposed to address the design and implementation of the NewGen Active Track.

Primary School

The previous request to secure a community use agreement for the primary school's sports facilities through the imposition of a planning condition is withdrawn.

Active Design

A planning condition is requested requiring details to be submitted and approved which demonstrate how Active Design principles have been considered in the design and layout of reserved matters applications.

Community Sports Facility Provision

Financial Contributions: Off-Site Outdoor and Indoor Sports Provision

As set out in the agent's letter, if planning permission is forthcoming, the applicant is proposing to enter into a section 106 agreement with the District Council to secure financial contributions towards off-site outdoor and indoor sports facility provision in accordance with Table 1 in their letter (copied below). Financial contributions would address the majority of the additional demand for sports facilities generated by the proposed residential development.

Facility Type	Impact of New Development (Number of Pitches / size / courts)	Capital Cost
<i>Natural Grass Pitches</i>	2.12	£217,169
<i>Adult Football</i>	0.46	£52,381
<i>Youth Football</i>	0.75	£70,447
<i>Mini Soccer</i>	0.67	£20,951
<i>Rugby Union</i>	0.06	£10,767
<i>Cricket</i>	0.17	£62,624
<i>Artificial Grass Pitches</i>		
<i>3G</i>	0.10	£117,438
<i>Tennis</i>	0.18 courts	£21,226
<i>Indoor</i>		
<i>Swimming Pools</i>	14.9 sqm (0.07 pools)	£330,488
<i>Sports Halls*</i>	0.35 courts – equivalent to 0.09 halls	£273,238

The capital cost figures in the above table align with the costs associated with meeting the additional demand set out in the applicant's Sport and Leisure Strategy document which is based on Sport England's Playing Pitch Calculator and Sport Facility Calculator outputs. The above figures are therefore supported if secured as financial contributions through a section 106 agreement.

If the above contributions were secured through a section 106 agreement, Sport England's objection to the lack of confirmed proposals for financial contributions for meeting the demands arising from development would be **withdrawn subject** to a section 106 agreement identifying the projects that the contributions would be used towards and the trigger points for the contribution payments to be made. These matters can be addressed

as part of the preparation of a section 106 agreement following determination of the planning application.

It is noted from the agent's letter that the principal terms of a section 106 agreement are yet to be agreed with the District Council and that updated evidence or viability factors may influence the terms of a section 106 agreement that are agreed. In the event that the above financial contributions (in part or in full) do not form part of the terms of a section 106 agreement that is subsequently agreed between the District Council and the applicant, the Council is requested to re-consult Sport England so that our position on this matter can be reviewed if necessary.

As set out below, if a minimum specification for the on-site community hall was agreed as part of a section 106 agreement and if this was subsequently delivered it would not be necessary to secure an off-site financial contribution towards sports hall provision as well.

Community Hall

As set out in the agent's letter, the applicant has agreed as the default proposal for meeting the additional sports hall and health & fitness facility needs generated by the development to deliver a community hall that would be suitable for indoor sports and an activity studio. The specification proposed in the letter is based on Sport England's advice and would be considered appropriate for providing an indoor hall that could be used for activities such as dance, fitness and martial arts and a suitable activity studio. In the event that a community hall designed in accordance with this specification is not feasible, the contingency proposal of a financial contribution being secured towards off-site indoor sports hall provision would be considered acceptable and should be included in a section 106 agreement as suggested in the letter.

I can therefore advise that Sport England's objection to the lack of confirmed proposals for the specification of the community hall is **withdrawn subject** to the following minimum specification for the community hall being included in a section 106 agreement:

"A community hall building with a minimum of 695 sq. metres (external) floorspace for the community hall building and the minimum internal dimensions for the community hall floorspace of 18x10 metres and an internal clearance height of at least 3.5 metres together with an activity studio with a minimum size of 12x9.1 metres and a minimum clearance height of 3.5 metres. The design of the flooring, walls, windows, ceiling, lighting, and ventilation for both the community hall and activity studio, as well as the provision of ancillary toilets and storage facilities, shall accord with Sport England's Village and Community Halls Design guidance <https://www.sportengland.org/guidance-and-support/facilities-and-planning/design-and-cost-guidance/sports-halls>."

NewGen Active Track

As set out in the agent's letter, the applicant has proposed a planning condition requiring details of the design and implementation of the proposed NewGen Active Track to be submitted and approved. The wording of the condition and informative proposed by the applicant is considered to be acceptable for securing this. The condition would address the request for certainty to be provided in a planning permission that a suitably designed Active Track would be delivered as part of the development for meeting the demand for athletics generated by the proposal.

I can therefore advise that Sport England's objection to the lack of confirmed proposals for securing a suitably designed Active Track in the development is **withdrawn subject** to the condition suggested by

“Details of the design of the NewGen Active track, and timetables for the implementation of the facility shall be submitted to the local planning authority for approval with or before the submission of reserved matters application(s). No development shall commence until those schemes have been approved in writing by the local planning authority, and the facility shall then be delivered in accordance with the approved schemes and thereafter retained.

Reason: To secure well managed safe NewGen Active Track to ensure sufficient benefit to the development of sport and to accord with the Applicants Sports Strategy, Three Rivers Core Strategy, Three Rivers Development Management Policies Local Development Plan Document Policy DM11 and DM12 and Chapter 8 of the National Planning Policy Framework.

Informative: The applicant is advised that the design and layout of the active track should comply with the relevant industry Technical Design Guidance, including guidance published by Sport England, National Governing Bodies for Sport. Particular attention is drawn to: England Athletics NewGen Tracks guidance”

Primary School

While the applicant is amenable to a planning condition being imposed to secure a community use agreement for the facilities in the proposed primary school, it is understood that it has been advised by Hertfordshire County Council (as Local Education Authority) that such a condition should not be imposed at this stage until the operator of the school is identified due to the uncertainty about whether the operator would be willing and able to deliver community use in practice. As the school facilities were not proposed for meeting the community sports facility needs generated by the development on this occasion it would not be necessary for such a condition to be imposed on any outline planning permission. Sport England would be happy to revisit this matter at a future date when a reserved matters application for the primary school is submitted by which time the operator of the school may be known. I can therefore confirm that the previous request for a planning condition to be imposed requiring a community use agreement to be submitted and approved for the primary school is **withdrawn**.

Active Design

As set out in the agent’s letter, the applicant has accepted a planning condition requiring reserved matters applications to submit details for approval to demonstrate how Active Design principles have been met. The wording of the condition is as set out in our previous response (repeated below):

“For each parcel/phase of development for which Outline permission is granted, no development in relation to that parcel/phase shall commence until details have been submitted and approved in writing by the Local Planning Authority to demonstrate how Active Design principles have been met.

Reason: To promote healthy lifestyles through physical activity and to accord with the Three Rivers Core Strategy, Three Rivers Development Management Policies Local Development Plan Document Policy DM11 and DM12 and Chapter 8 of the National Planning Policy Framework.

Informative: Consideration should be given to using the Active Design checklist in Sport England’s Active Design Guidance to assess reserved matters planning applications.”

It is therefore **requested** that the above condition is imposed if planning permission is forthcoming.

I would be happy to discuss the response with the local planning authority and/or the applicant as the determination of the application progresses. Please contact me if you have any queries.

If this application is to be presented to a Planning Committee, we would like to be notified in advance of the publication of any committee agendas, report(s) and committee date(s).

We would be grateful if you would advise us of the outcome of the application by sending us a copy of the decision notice.

9.25 Thames Water: [No objection subject to conditions]

Waste Comments

Following initial investigations, Thames Water has identified an inability of the existing FOUL WATER network infrastructure to accommodate the needs of this development proposal. As such Thames Water request that the following condition be added to any planning permission.

"The development shall not be occupied until confirmation has been provided that either:-
1. All foul water network upgrades required to accommodate the additional flows from the development have been completed; or- 2. A development and infrastructure phasing plan has been agreed with the Local Authority in consultation with Thames Water to allow development to be occupied. Where a development and infrastructure phasing plan is agreed, no occupation shall take place other than in accordance with the agreed development and infrastructure phasing plan."

Reason - Network reinforcement works are likely to be required to accommodate the proposed development. Any reinforcement works identified will be necessary in order to avoid sewage flooding and/or potential pollution incidents.

The developer can request information to support the discharge of this condition by visiting the Thames Water website at thameswater.co.uk/preplanning. Should the Local Planning Authority consider the above recommendation inappropriate or are unable to include it in the decision notice, it is important that the Local Planning Authority liaises with Thames Water Development Planning Department (e-mail: devcon.team@thameswater.co.uk) prior to the planning application approval.

Thames Water recognises this catchment is subject to high infiltration flows during certain groundwater conditions. The scale of the proposed development doesn't materially affect the sewer network and as such we have no objection, however care needs to be taken when designing new networks to ensure they don't surcharge and cause flooding. In the longer term Thames Water, along with other partners, are working on a strategy to reduce groundwater entering the sewer networks.

Thames Water recognises this catchment is subject to high infiltration flows during certain groundwater conditions. The developer should liaise with the LLFA to agree an appropriate sustainable surface water strategy following the sequential approach before considering connection to the public sewer network. The scale of the proposed development doesn't materially affect the sewer network and as such we have no objection, however care needs to be taken when designing new networks to ensure they don't surcharge and cause flooding. In the longer term Thames Water, along with other partners, are working on a strategy to reduce groundwater entering the sewer network.

Following initial investigations, Thames Water has identified an inability of the existing SEWAGE TREATMENT WORKS infrastructure to accommodate the needs of this

development proposal. As such Thames Water request the following condition be added to any planning permission.

“No development shall be occupied until confirmation has been provided that either:- all sewage works upgrades required to accommodate the additional flows from the development have been completed; or - a development and infrastructure phasing plan has been agreed with the Local Authority in consultation with Thames Water to allow development to be occupied. Where a development and infrastructure phasing plan is agreed no occupation shall take place other than in accordance with the agreed development and infrastructure phasing plan.

Reason – Sewage Treatment Upgrades are likely to be required to accommodate the proposed development. Any upgrade works identified will be necessary in order to avoid sewage flooding and/or potential pollution incidents.”

The developer can request information to support the discharge of this condition by visiting the Thames Water website at Development Planning Department (telephone 0203 577 9998) prior to the planning application approval. Should the Local Planning Authority consider the above recommendation inappropriate or are unable to include it in the decision notice, it is important that the Local Planning Authority liaises with Thames Water Development Planning Department (e-mail: devcon.team@thameswater.co.uk) prior to the planning application approval.

The application indicates that SURFACE WATER will NOT be discharged to the public network and as such Thames Water has no objection, however approval should be sought from the Lead Local Flood Authority. Should the applicant subsequently seek a connection to discharge surface water into the public network in the future then we would consider this to be a material change to the proposal, which would require an amendment to the application at which point we would need to review our position.

Water Comments

With regard to water supply, this comes within the area covered by the Affinity Water Company. For your information the address to write to is - Affinity Water Company The Hub, Tamblin Way, Hatfield, Herts, AL10 9EZ - Tel - 0845 782 3333.

Supplementary Comments

STW capacity constraints with Maple Lodge STW being upgraded to ensure a higher quality of treated effluent, reducing phosphorus levels entering the river to below an average level of 0.25mg/l*. We'll also increase the capacity of the storm tanks. This will reduce the need for untreated sewage discharges during storm conditions. We plan to complete this work in 2030.

9.26 Transport for London: [No objection subject to S106 contribution]

9.26.1 Initial comments 4.3.25 [Objection – further information required]

Thank you for consulting Transport for London (TfL) on this application for up to 600 residential dwellings, a children's social care and supported living property, a one form entry primary school, a mixed-use local centre, a community building, retail and café provision and a country park.

We provided comments for this site at pre-application stage. It appears that some of our comments have not been taken into consideration by the applicant. We are happy to discuss this further if required.

As per the pre-application comments, we encourage the applicant to aim to maximise travel by sustainable modes, including improved access to Croxley Underground station on the Metropolitan Line. Station access improvements should include a funding contribution towards the potential provision of step-free access at the station as well as measures to improve active travel routes, cycle parking and bus links from the development site.

As part of the Transport Assessment (TA), the applicant must consider the potential impacts of the proposed development on TfL services and infrastructure including Croxley station. A full station capacity assessment should be carried out using approved TfL data sources.

The TA submitted does assess the route from the development to Croxley station, however no improvements seem to be proposed. We welcome point 4.80 that does confirm the applicant is willing to make an appropriate contribution to the proposed station access improvements at Croxley station. However, the impact assessment submitted currently only reviews the development's impact on the road network and as stated above a full station capacity assessment is required to be submitted.

Furthermore, could information be provided regarding the mode splits and trip rates that have been used to generate the impact assessment analysis.

In conclusion, further information is required to be submitted by the applicant prior to any decision being made on this application.

9.26.2 Further comments 11.8.25 [Further information required]

As stated within the initial comments, as part of the Transport Assessment (TA) the applicant must consider the potential impacts of the proposed development on TfL services and infrastructure including Croxley station. Within the TA submitted, a full multi-modal trip assessment has not been undertaken. The applicant must submit a multi-modal trip assessment that demonstrates the number of trips they estimate to travel by all modes to and from the site. Currently, the applicant has only demonstrated analysis of vehicular trips, cycling and walking trips and educational public transport trips.

To provide our expected contribution, this number needs to be calculated and agreed. If you would like to discuss this further then let me know.

9.26.3 Further comments 8.10.25 [Further information required]

I have completed a review of the TN3 submitted by the applicant. I have the following comments.

- I agree with the methodology presented using the census data. However, I think the rail and underground trips should be merged so the modal split would be 20 per cent rather than the 17 presented currently.
- Further evidence should be provided as to why it is considered that it will be a 50% exact split between the stations. From my analysis of the information submitted, the bus route would reach Croxley station first so it is likely that a higher percentage of trips would be via that station.
- The step free access scheme at Croxley is going to cost in the region of £15m. A contribution from this site will be sought once the above trip generation is finalised. The contribution would be commensurate with the size of this development.

9.26.4 Further comments 13.11.25 [No objection subject to S106 contribution]

Thank you for consulting Transport for London (TfL) on this application. We provided initial comments in March 2025, and the applicant has since submitted further information. The following comments are based on that additional material.

Throughout the engagement process regarding the development proposals at this site, it has been consistently acknowledged that a financial contribution would be sought towards step-free access at Croxley Underground Station.

The applicant has considered the potential impacts of the proposed development on Croxley Underground Station. Whilst a full station capacity assessment, as requested, has not been undertaken, we are prepared to accept the data provided to date. This indicates that trips generated by the development would represent an increase of 7.1 percent compared to existing usage.

Accordingly, TfL seeks a financial contribution of £1,065,000 towards the delivery of step-free access at Croxley Underground Station.

9.26.5 Further comments 19.11.25 following request for clarification regarding train capacity:

Our NUMBAT23 model shows current demand on the trains between each station on a line by 15 minutes.

Looking both at trains coming into and leaving Croxley, the max demand I see is 281 people, on trains heading south from Croxley at 7:30. I believe a Met line train has a capacity of over 1,000 people and that 281 will be spread over multiple trains, since that's the total over 15 minutes. I don't see crowding being an issue.

9.27 TRDC Environmental Health Officer (Residential): [No objection subject to conditions]

After reviewing the acoustic report for this application, it seems that not all the potential impacts have been assessed. However, I believe that these concerns can be overcome via condition.

The main impacts that are likely to be associated with this application are as follows.

- Increased traffic flows resulting in higher noise levels. This has been considered within the report and the impact on existing residents has been deemed insignificant. I do not have any grounds to consider this to be inaccurate.
- Noise associated with the school.
- Noise associated with the community centre and café. Odour and smoke associated with cooking could also have a negative impact.

School.

The report confirms that the precise location of the school is not yet known. This new facility is going to have an impact on existing and future residents. There will also be an impact on the school from the surrounding environment.

Whilst the precise location is not yet known, I am wary of confirming that this aspect of the application is completely acceptable. Therefore, a condition that requires revised calculations to be provided once the exact location is known would assist in overcoming this concern. These calculations also need to confirm that the internal noise level specified within section 5.9 of the report are achieved. There also needs to be consideration on how the school facilities might be used out of hours, for example, evening events or clubs such as football and how this impact will affect nearby residents and outline suitable controls, for example time limits or additional mitigation.

Community centre.

There are inadequate details on this new facility. These types of venues can have a substantial impact on residents from noise. The full impacts have not been considered. However, this new building can be subject to its own planning application where suitable controls can be set out. There also needs to be consideration on the control of impacts associated with food preparation.

Café.

There are no details provided on this. Some of the impacts are going to be similar to the centre, for example, deliveries and cooking. This also needs to be subject to a separate application.

Plant.

The precise detail of new plant is not yet known. Therefore, a condition requiring a separate planning application is needed to protect amenity.

Ventilation and glazing specification.

As per 5.8 of the acoustic report, the final glazing and ventilation scheme details need to be provided by an acoustic consultant or equally competent person. I am of the view that some properties will need mechanical ventilation systems that negate the need to open windows, particularly those close to the school and community centre. If there were any future complaints that required local authority investigation, assessments from properties fitted with an appropriate mechanical ventilation system would be made with the windows shut and the mechanical ventilation operating. A full mechanical ventilation with heat recovery would be appropriate.

Based upon the acoustic report, the application as it currently stands is only acceptable if the above conditions can be incorporated into the final decision. If that is not possible, the application ought to be refused until the required information is provided.

9.28 TRDC Environmental Protection: [Advisory comments regarding resources required]

Waste Services is nearing saturation point in terms of the amount of waste it can collect with the resources it currently has at its disposal. In order to enable the additional properties to be integrated into the service it would require two more refuse collection vehicles with associated running costs including two LGV drivers and 4 refuse collection loaders. The current Operators Licence allows for a maximum of 33 vehicles to be operated from the depot in Harefield Road. The depot is full to capacity and the additional two vehicles would lead to it being overfull and therefore an alternative site should be considered. Providing the above resources required would enable the service to absorb planned growth for the next few years

9.29 TRDC Heritage Officer: [Objection – less than substantial harm]

The application site comprises a parcel of agricultural land c. 40ha and includes an area of ancient woodland. A public right of way crosses the site (east-west) to the north of Dell Wood. The site is surrounded by hedged boundaries. The scheme would be a mixed-use development and include a country park along the northern and eastern fringes, a green corridor through the Site running north-south and other landscaped areas.

A nearby major housing development at Killingdown Farm c. 150m west of the site, was initially refused planning permission but allowed on appeal under PINS reference (APP/P1940/W/21/3280443).

This application follows EIA Screening Request (Ref:24/1220/EIA). The screening decision issued by the Council found that the EIA would not be required.

The current application has been accompanied by a Heritage Assessment (HA). This identified Durrants House (Listed Building Grade II, NHLE 1403581) and Cassiobury Park (Registered Park Grade II, NHLE 1000219) as heritage assets which could be affected by the proposals through change within their settings. This approach is considered appropriate by the Conservation Officer.

The stepped approach described in the Historic England Guidance document, The Setting of Heritage Assets (GPA3, 2017), has informed the accompanying Heritage Statement and the below advice. The four relevant steps are as follows:

1. Identify which heritage assets and their settings are affected.
2. Assess the degree to which these settings and views make a contribution to the significance of the heritage asset(s) or allow significance to be appreciated.
3. Assess the effects of the proposed development, whether beneficial or harmful, on the significance or on the ability to appreciate it. This may include effects which may not solely be visual.
4. Explore ways to maximise enhancement and avoid or minimise harm.

Durrants House is directly opposite the Site boundary on Little Green Lane. It is a Tudor/ Jacobean revival-style country house built in 1866-7, with an asymmetrical plan consisting of a rectangular, south-facing range; a north-east wing consisting of the ballroom, clock tower, and a rear service courtyard. It contains architectural interest including its exterior use of the Tudor/ Jacobean revival style to create varied elevational interest. It also contains historical interest due to its association with Thomas Hoade Woods, a local businessman.

The house was formerly set within 91 Ha of parkland all to the south but is now surrounded by modern development to the south and was itself subdivided into nineteen dwellings under planning reference 12/0221/RSP.

There is no known association between Durrants House and the Site either at the present time or historically. However, the Site has formed an agrarian backdrop to the house since its construction. There is strong intervisibility between the prominent northern elevation of Durrants and the Site when moving along Little Green Lane, particularly on the footway elevated above road level just to the west of Durrants House. There are also longer views south from Public Right of Way Sarratt 017, which runs east-west across the north of the Site.

Therefore, the Site forms an important part of the setting of Durrants House as a surviving remnant of its historic landscape context.

The introduction of a major housing scheme in this location would harmfully impact the appreciation of Durrants House within its historic agricultural setting. The submission recognises that there would be a harmful impact and has provided mitigation of a green corridor called 'Durrants View' on the master plan to retain views from the rear of Durrants house towards Whippendell Wood in the north.

This is shown to be approximately 50m in width at its southern end nearer Durrants House, then narrowing in the centre before widening out again. Although primarily a green pedestrian area, it would include two Primary Streets crossing from east-west, including one to towards the south of the Site and a LEAP and hard landscaped areas at the southern end. In addition, the Design Code document indicates that the green corridor would be fronted by higher density outward facing gateway/ perimeter blocks, up to a height of up to 4 storeys, designed to create a sense of enclosure.

The green corridor would provide some degree of mitigation of harm to the setting of Durrants House. However, while this is the rear of Durrants House, the Site forms its main surviving open setting and provides an appreciation of the building's historic landscape

setting and its significance as a once isolated, rural dwelling. The view out from Durrants House looking north would be harmfully impacted by the built development and the complete change in the character of the landscape and the land use. Views from PRoW 017 looking south towards Durrants House would also be harmed. This would be exacerbated by the scale of development along the edge of the green corridor and the built form within the green corridor.

This would result in less than substantial harm to the setting of Durrants House. The degree of less than substantial harm would be at a low-mid level. The degree of harm could be mitigated to some extent by increasing the width of the green corridor, reducing the height of development along the corridor and moving formal elements including hard landscaping, LEAP and main road to more distant areas. However, due to the scale of the proposal and the fundamental change in land use and character, the harm would not be removed.

Cassiobury Park is a Grade II listed Registered Park and Garden, which includes elements dating from the sixteenth to eighteenth centuries. It now contains a public park and a golf course to the western side, which is separated from the Site by a thick tree belt which ends at Rousebarn Lane.

There is no historic link between the RPG and the Site, but the Site does form part of the agricultural setting that contributes to the significance of the RPG. There is a thick tree buffer on the western edge of the RPG meaning there would be no views into the development from the RPG, although there is a degree of intervisibility between the two along Rousebarn Lane. In addition, the existing Ancient Woodland within the Site would be retained, and a wetland area and country park would sit on the eastern boundary of the Site adjacent to the RPG, providing a clear green buffer. **This would mitigate the harm to the setting of the RPG to the extent that it would result in less than substantial harm at the lowest end of this spectrum.**

It is considered that the proposal would cause harm to the setting of the designated heritage assets, particularly Durrants House, contrary to Section 66 (1) of the Planning (Listed Buildings and Conservation Areas) Act 1990. National Planning Policy Framework (NPPF) paragraph 212 requires great weight to be given to the asset's conservation. In NPPF terms the degree of harm would be less than substantial and as per paragraph 215 this harm should be weighed against the public benefits of the proposal.

9.30 TRDC Housing Officer: [No objection]

9.30.1 Initial comments 21.01.2025: [No objection]

Policy CP4 of the Adopted Core Strategy requires that 45% of new housing should be provided as Affordable Housing, unless it can be clearly demonstrated with financial evidence that this is not viable. As a guide, the tenure split should be 70% social rented, 25% First Homes, and 5% shared ownership.

The Local Housing Market Assessment (2020) outlines the recommended proportions for housing mix in development proposals submitted to Three Rivers District Council. These proposals should generally aim for a mix of 40% 1-bed units, 27% 2-bed units, 31% 3-bed units, and 2% 4-bed units.

However, the identified need for affordable housing, based on the current housing register and the family composition of customers in temporary accommodation provided by the Council, suggests the following updated preferred mix: 20% 1-bed units, 45% 2-bed units, 30% 3-bed units, and 5% 4+ bed units. The primary need is for 2-bed, 4-person units, as there is a significant demand for family-sized accommodation to ensure families in temporary housing are offered permanent, suitable properties in a timely manner.

I can confirm that Housing Services would generally support this application in principle, on the basis that 70% of the affordable housing to be provided is at social rent and the size of dwellings provided fulfils our current requirements.

9.30.2 Further comments 16.12.2025: [No objection]

Thank you for forwarding the updated affordable housing position and for the attached correspondence.

I note the removal of First Homes following the December 2024 NPPF revisions and the applicant's proposal to continue to provide 50% affordable housing, with the tenure mix aligned to the emerging Local Plan Regulation 19 policies. In principle, Housing Services are supportive of the revised approach, particularly the high proportion of rented provision and the inclusion of social rent within the overall mix.

The proposed split of 49% Social Rent, 21% Affordable Rent and 30% Affordable Home Ownership broadly reflects the direction of the emerging Local Plan and discussions previously held with Housing. Subject to the appropriate planning weight being applied to the emerging policy, we would have no objection to this tenure mix.

As previously advised, it remains important that the affordable housing delivered prioritises family-sized accommodation, particularly 2-bed and 3-bed units, to reflect current housing register demand and the need to move households out of temporary accommodation. This should be secured through the Section 106 agreement alongside tenure, rent levels and nomination rights.

On this basis, Housing Services would not wish to raise an objection to the application on affordable housing grounds, subject to the above matters being appropriately secured.

9.31 TRDC Tree and Landscape Officer: [No objection subject to suitable compensation/mitigation]

9.31.1 Initial comments 2.4.25 [No objection subject to suitable compensation/mitigation]

The site is in Metropolitan Green Belt and the woodland within its boundary is recorded as ancient on the Ancient Woodland Inventory. Within the fields are a number of notable and / or veteran field and hedgerow trees. There is a Right of Way (Public Footpath Sarratt 017) running east / west across the northern end of the site and another (Public Footpath Sarratt 063) running north / south along the western boundary. There are trees and woodland bordering the site that are protected by Tree Preservation Order (TPOs 182; 026 & 118). Most of this woodland is also recorded as ancient, and some of the woodland (Whippendell wood) is a designated SSSI (Site of Special Scientific Interest).

The National Planning Policy Framework states that:

'development resulting in the loss or deterioration of irreplaceable habitats (such as ancient woodland and ancient or veteran trees) should be refused, unless there are wholly exceptional reasons (70) and a suitable compensation strategy exists;

70 For example, infrastructure projects (including nationally significant infrastructure projects, orders under the Transport and Works Act and hybrid bills), where the public benefit would clearly outweigh the loss or deterioration of habitat.'

The outline plans indicate that there will be no direct impacts on trees and woodland on the site. With no trees needing to be felled or pruned, and no loss of irreplaceable habitats. In addition, no development is proposed to take place within the root protection areas of retained trees. Although some short sections of existing hedgerow would need to be removed.

However, the potential for indirect impacts on trees and woodlands, and the deterioration of irreplaceable habitats over the longer term, are significant. The proposal to site up to 600 new dwellings within 30 metres (at the closest points) to ancient woodland and notable / veteran trees would result in a significant increase in the residential population close to these irreplaceable habitats. This increase in population would inevitably lead to additional recreational pressures on the trees and woodland, such as the compaction of soils around important trees; the trampling of ground flora in woodland areas; erosion and widening of footpaths through woodland areas; and the disturbance of wildlife, through activities such as dog walking.

Other unintentional impacts of an increased population would be increased localised air and water pollution from vehicle movements, and the use of pesticides in gardens and allotment areas.

There will also be additional anti-social behaviour issues relating to an increased population. This may include vandalism; arson; off-road motorcycling and mountain biking; and fly-tipping, which would all contribute towards the deterioration of this irreplaceable habitat. Placing development close to notable and veteran trees and incorporating them into more formal green spaces will also increase the level of risk should a tree fail. This could be detrimental to these ecologically important trees if overzealous safety works to fell or heavily prune them is undertaken to address perceived safety concerns.

To prevent any long-term deterioration of these irreplaceable habitats would require a suitable compensation and mitigation strategy. The plans indicate that buffer zones between the housing areas, and the woodlands and trees, would be created, comprising of a Country Park, formal areas of green space, and allotment sites. These will provide some mitigation but over the long term, managing visitor access and pressure to the surrounding woodland and being able to deal with antisocial behaviour issues will be key to preventing the deterioration of the trees and woodlands. To successfully manage the open space, and visitor access and recreation, would require some form of ranger team or on-site maintenance staff to be able to respond to issues effectively and quickly. This ongoing management and maintenance would need to be adequately funded and resourced to ensure the irreplaceable habitats are protected over the long term.

9.31.2 Furter comments 4.11.25 [No objection subject to suitable compensation/mitigation]

Having had a look through the Woodland Recreational Management Plan, and amended landscape strategy, I don't think it really adds any new information to what we already have.

As mentioned in my previous comments, I think the key the aspect at this point is how is the long-term management of the country park and open space going to be organised and resourced (as hi-lighted in yellow in previous comments below). This will be key to the long-term protection of the veteran trees and ancient woodland. Effectively it will need some form of business plan/model, which sets out income and outgoings, staff costs, etc. so that it is clear that the management of the country park is sustainable over the long-term.

[Initial comments included at 9.31.1 above]

9.32 TRDC Leisure Development Officer: [No objection subject to conditions]

After full consideration of all the documents and information relating to the above planning application, Leisure Development Officers would recommend the following, in the submission of the planning application to Three Rivers DC.

These comments are given to help the development achieve the aims of Three Rivers District Council's Local and Strategic plans and National Policy Framework sections detailed below:

- Achieving Sustainable Development
- Promoting Healthy Communities
- Health and Wellbeing

- Any outdoor leisure equipment must conform to the following standards:
 - ☐ Playground Equipment & Surfacing – BS EN 1176 & 1177
 - ☐ MUGA's (Multi Use Games Areas) – BS EN 15312 – Free Access Multi Sports
 - ☐ Skate Parks – BS EN 14974 – Roller Sports Equipment
 - ☐ Outdoor Fitness Equipment – BS EN 16630
 - ☐ Parkour Equipment – BS EN 16899

- New play spaces should be located with regard to areas of deficiency (and designed following the same principles as if they were being implemented by the local authority)
- Particular attention should be given to DDA compliant access to any leisure areas including pathways, seating and equipment as per the Equality Act 2010 (or the Disability Discrimination Act 1995 in Northern Ireland).
- Provision of sustainable active travel to support an active lifestyle, such as being bike friendly.
- Where leisure provision is made by the developers, design advice must be sought from Three Rivers Leisure team which must include DDA compliant access, details of installation, quality details of all materials used, adherence to RoSPA recommendations such as gates and fences etc and RoSPA inspection of installed pieces of equipment.
- Please consider vehicle access for maintenance of any leisure areas.
- Operator signs for any leisure areas will need to be included for reporting of maintenance or reparation issues.
- A full Risk assessment of any leisure equipment should be considered.
- A RoSPA report or assessment should take place of any proposed play and/or leisure equipment.
- Provision for the on-going maintenance of any leisure facilities should be detailed, particularly if it the developer plans to formally hand over to the leisure facility to the Parish Council or Three Rivers District Council. This must include DDA compliancy certification as per the Equality Act 2010 (or the Disability Discrimination Act 1995 in Northern Ireland)., details of installation, quality details of all materials used with the relevant certification, detailed maintenance guides for each piece of equipment, RoSPA inspection of installed pieces of equipment, adherence to RoSPA recommendations such as gates and fences etc.

- Officers would recommend a community use agreement is put in place to enable local sports clubs and community organisations to access any facilities.
- Community use was not made clear in the planning application. If the applicant wishes to make the sports facilities available for community use outside of school hours, Officers recommend a community use agreement is put in place detailing hours of use, pricing and booking policy.
- As highlighted in the sports and leisure strategy, there is a lack of football pitches in the local area. Officers would like to see the proposed school site made available for community football use in the interim period until such time as the school is built.
- Officers would recommend that guidance on leisure facility planning (eg: Play England or Sport England) is sought from the relevant bodies and adhered to.

Therefore, A pre-commencement condition is therefore requested which requires

It is requested that the following condition is imposed which is based on:

- (a) No development shall commence until the following documents have been submitted to and approved in writing by the Local Planning Authority after consultation with Three Rivers District Council's Leisure Team
 - (i) A detailed assessment of community need for this equipment/building/MUGA.
 - (ii) A detailed specification of the proposed equipment/building/MUGA and other operations associated with grass and sports turf establishment, RoSPA assessment, ongoing maintenance and a programme of implementation.
- (b) The approved scheme shall be carried out in full and in accordance with the approved programme of implementation. The land shall thereafter be maintained in accordance with the scheme and made available for use in accordance with the scheme.

Reason: To ensure that the equipment/building/MUGA is prepared to an adequate standard and is fit for purpose and to accord with Development Plan Policy **.

Three Rivers District Council's Leisure team can provide examples of acceptable completed documents and contractor's specifications to the applicant to assist with meeting the requirements of the above condition.

If there are any queries about leisure facilities design in relation to the proposals, please feel free to contact the Head of Leisure and Natural Infrastructure.

9.33 TRDC Planning Policy Team: [No objection]

9.33.1 Initial comments 24.02.2025: [No objection]

The application site has not been allocated as a housing site by the Site Allocations Local Development Document (2014) and as such is not currently identified as part of the District's housing supply. The site should therefore be considered as a windfall site. Policy CP2 of the adopted Core Strategy (adopted 2011) states that applications for windfall sites will be considered on a case by case basis having regard to:

- i. the location of the proposed development, taking into account the Spatial Strategy
- ii. the sustainability of the development and its contribution to meeting local housing needs
- iii. infrastructure requirements and the impact on the delivery of allocated housing sites
- iv. monitoring information relating to housing supply and the Three Rivers housing target.

The Spatial Strategy states that new development will be directed towards previously developed land in the urban area of the Principal Town (Rickmansworth) which is identified as one of the most sustainable locations in the District. The site is not within a defined settlement (although adjoins the northern boundary of the Key Centre of Croxley Green) and is not previously developed land. The development would result in the net gain of up to 600 new dwellings. The Council cannot currently demonstrate a five-year supply of housing land as required by the NPPF and currently has a 1.7-year housing land supply. The delivery of up to 600 dwellings would make a significant and positive contribution to much needed housing provision within the District. Additionally, there has been an undersupply of affordable housing within the District throughout the plan period and as such there is a pressing need for the delivery of affordable housing. The submitted planning statement sets out that up to 50% of the dwellings would be affordable housing, which would make a significant and positive contribution to the affordable housing need within the District.

The application site is located in the Metropolitan Green Belt. Paragraph 153 of the NPPF states that inappropriate development is, by definition, harmful to the Green Belt and should not be approved except in very special circumstances. Paragraph 153 further sets out that very special circumstances will not exist unless the potential harm to the Green Belt by reason of inappropriateness, and any other harm resulting from the proposal, is clearly

outweighed by other considerations. Paragraph 154 of the NPPF states that development in the Green Belt is inappropriate unless certain exceptions apply. Paragraph 154 of the NPPF sets out the following exceptions to inappropriate development in the Green Belt:

- a) buildings for agriculture and forestry;*
- b) the provision of appropriate facilities (in connection with the existing use of land or a change of use), including buildings, for outdoor sport, outdoor recreation, cemeteries and burial grounds and allotments; as long as the facilities preserve the openness of the Green Belt and do not conflict with the purposes of including land within it;*
- c) the extension or alteration of a building provided that it does not result in disproportionate additions over and above the size of the original building;*
- d) the replacement of a building, provided the new building is in the same use and not materially larger than the one it replaces;*
- e) limited infilling in villages;*
- f) limited affordable housing for local community needs under policies set out in the development plan (including policies for rural exception sites); and*
- g) limited infilling or the partial or complete redevelopment of previously developed land (including a material change of use to residential or mixed use including residential), whether redundant or in continuing use (excluding temporary buildings), which would not cause substantial harm to the openness of the Green Belt.*
- h) Other forms of development provided they preserve its openness and do not conflict with the purposes of including land within it. These are:*
 - i. mineral extraction;*
 - ii. engineering operations;*
 - iii. local transport infrastructure which can demonstrate a requirement for a Green Belt location;*
 - iv. the re-use of buildings provided that the buildings are of permanent and substantial construction;*
 - v. material changes in the use of land (such as changes of use for outdoor sport or recreation, or for cemeteries and burial grounds); and*
 - vi. development, including buildings, brought forward under a Community Right to Build Order or Neighbourhood Development Order.*

Additionally, paragraph 155 of the NPPF sets out that the development of homes, commercial and other development in the Green Belt should also not be regarded as inappropriate where all the following apply:

- a.) The development would utilise grey belt land and would not fundamentally undermine the purposes (taken together) of the remaining Green Belt across the area of the plan;*
- b.) There is a demonstrable unmet need for the type of development proposed;*
- c.) The development would be in a sustainable location, with particular reference to paragraphs 110 and 115 of this Framework; and*
- d.) Where applicable the development proposed meets the 'Golden Rules' requirements set out in paragraphs 156-157*

Policy CP11 of the Core Strategy states that ‘there will be general presumption against inappropriate development that would not preserve the openness of the Green Belt, or which would conflict with the purpose of including land within it’.

Policy CP3 of the Core Strategy states that the Council will require housing proposals to take into account the range of housing needs, in terms of size and type of dwellings as identified by the Strategic Housing Market Assessment (SHMA). The most recent version of the Local Housing Needs Assessment (LNHA) was finalised in 2024 and is the most recent update to the SHMA. The recommended mix for Three Rivers in terms of market housing, affordable home ownership and social/affordable rented housing identified in the LNHA is shown below:

	1-bed	2-bed	3-bed	4+ bed
Market Housing	4%	21%	42%	32%
Affordable Home Ownership	19%	39%	30%	13%
Social / Affordable Rented Housing	20%	32%	35%	12%

It must be noted that Policy CP3 recognises that a proposed housing mix may need to be adjusted for specific schemes to take account of market information and specific site factors; where adjustment to the proportions is sought, applications should explain how relevant factors have contributed to the mix of housing proposed.

Policy CP4 of the Core Strategy requires 45% of all new housing to be provided as Affordable Housing, unless it can be clearly demonstrated with financial evidence that this is not viable. Policy CP4 sets out that the Council will “as a guide, seek 70% of the affordable housing provided to be social rented and 30% to be intermediate”.

On 24th May 2021, the Government published a Written Ministerial Statement (WMS) to set out the Government’s plans for the delivery of First Homes defining the product and changes to planning policy. Following publication of the WMS, Planning Practice Guidance (PPG) was updated to reflect the WMS and formed a material consideration in decision making. As a result of the introduction First Homes and changes to national policy, the Council released a First Home Policy Position Statement. This Policy Position Statement amended the tenure mix for affordable housing under Policy CP4 of the Core Strategy (2011) as:

- 25% First Homes
- 70% social rented, and
- 5% intermediate

However, changes were made to national policy following the publication of the newest version of the NPPF in December 2024. Within paragraph 6 of the NPPF, reference to the Written Ministerial Statement on Affordable Homes (24th May 2021), which contained policy on First Homes, has been removed and the prescriptive requirement that 10% of the total number of homes to be available for affordable home ownership as set out in former paragraph 66 has been deleted. As such, the Council will be reviewing its Policy Position Statement. It is advised that development complies with Policy CP4 as written, apportioning 70% of the affordable housing provision as social rented and 30% as intermediate.

A Local Wildlife Site is located within the site and the site adjoins another Local Wildlife Site to the north-west. Policy DM6 of the Development Management Policies Local Development Document sets out that:

“Development that would affect a Site of Special Scientific Interest, Local Nature Reserve, Local Wildlife Site or protected species under UK or European law, or identified as being in

need of conservation by the UK Biodiversity Action Plan or the Hertfordshire Biodiversity Action Plan , will not be permitted where there is an adverse impact on the ecological, geological or biodiversity interests of the site, unless it can be demonstrated that:

i) The need for the development would outweigh the need to safeguard the biodiversity of the site, and where alternative wildlife habitat provision can be made in order to maintain local biodiversity; and

ii) Adverse effects can be satisfactorily minimised through mitigation and compensation measures to maintain the level of biodiversity in the area.

9.33.2 Further comments 16.12.2025: [No objection]

Whilst the proposed Affordable Housing split does not comply with Policy CP4 of the Core Strategy, it aligns with the draft Affordable Housing policy within the emerging Local Plan. As such, the planning policy department have no objections to the revised Affordable Housing split for application 24/2073/OUT.

9.34 Watford Borough Council: No response received.

9.35 Watford Environmental Health (Commercial): [No objection subject to conditions]

Air Quality

I have reviewed the Air Quality Assessment prepared by BWB Consulting (Report ref. LGL-BWB-XX-ZZ-LA-RP-001-AQA).

The construction phase dust assessment was undertaken to evaluate the potential impact of construction activities on local air quality, the assessment indicates that with the implementation of the recommended mitigation measures, the residual impacts from the construction phase will be not significant.

The operational phase road traffic emissions assessment was undertaken to consider the impact of development generated road traffic at identified existing receptor locations. Road traffic emissions were modelled using dispersion modelling and concentrations of NO₂, PM₁₀ and PM_{2.5} were predicted at identified sensitive receptor locations. The development is not predicted to result in any new exceedances of the air quality objectives and the impacts of the development are considered to be negligible at all modelled receptor locations.

Pollutant concentrations were also predicted across the site. Concentrations of NO₂, PM₁₀ and PM_{2.5} were predicted to be below the relevant air quality objectives.

The impact of the proposed development on local air quality is considered to be not significant.

I would recommend that a condition requiring the submission of a dust management plan be applied to any permission granted. The Dust Management Plan should incorporate the mitigation measures presented in Section 5.14 of the Air Quality Assessment.

Land Contamination

I have reviewed the Phase 1 Geo-Environmental Assessment prepared by BWB Consulting (Report ref. LGL-BWB-EGT-XX-RP-LE-0001_Ph1).

The preliminary risk assessment has identified a number of plausible contaminant linkages that require further investigation.

An assessment of the potential risks associated with the site is considered necessary.

Based on this, the standard contaminated land condition is recommended on this and any subsequent applications for the site.

1. Prior to the commencement of development approved by this planning permission (or such other date or stage in development as may be agreed in writing with the Local Planning Authority), the following components of a scheme to deal with the risks associated with contamination of the site shall each be submitted to and approved, in writing, by the local planning authority:

i) A preliminary risk assessment which has identified:

- all previous uses
- potential contaminants associated with those uses
- a conceptual model of the site indicating sources, pathways and receptors
- potentially unacceptable risks arising from contamination at the site.

ii) A site investigation scheme, based on (i) to provide information for a detailed assessment of the risk to all receptors that may be affected, including those off site.

iii) The site investigation results and the detailed risk assessment (ii) and, based on these, an options appraisal and remediation strategy giving full details of the remediation measures required and how they are to be undertaken.

iv) A verification plan providing details of the data that will be collected in order to demonstrate that the works set out in (iii) are complete and identifying any requirements for longer term monitoring of pollutant linkages, maintenance and arrangements for contingency action. Any changes to these components require the express consent of the local planning authority. The scheme shall be implemented as approved.

Reason: To ensure that risks from land contamination to the future users of the land and neighbouring land are minimised, together with those to controlled waters, property and ecological systems, and to ensure that the development can be carried out safely without unacceptable risks to workers, neighbours and other offsite receptors.

2. Following completion of measures identified in the approved remediation scheme and prior to the first use or occupation of the development, a verification report that demonstrates the effectiveness of the remediation carried out must be produced together with any necessary monitoring and maintenance programme and copies of any waste transfer notes relating to exported and imported soils shall be submitted to the Local Planning Authority for approval. The approved monitoring and maintenance programme shall be implemented.

Reason: To ensure that risks from land contamination to the future users of the land and neighbouring land are minimised, together with those to controlled waters, property and ecological systems, and to ensure that the development can be carried out safely without unacceptable risks to workers, neighbours and other offsite receptors.

The above must be undertaken in accordance with the Environment Agency's 'Land contamination risk management (LCRM)' guidance, available online at <https://www.gov.uk/government/publications/land-contamination-risk-management-lcrm>.

3. Reporting of Unexpected Contamination: In the event that contamination is found at any time when carrying out the approved development that was not previously identified it must be reported in writing immediately to the Local Planning Authority. An investigation and risk

assessment must be undertaken in accordance with the requirements of condition 1, and where remediation is necessary a remediation scheme must be prepared in accordance with the requirements of condition 1, which is subject to the approval in writing of the Local Planning Authority. Following completion of measures identified in the approved remediation scheme a verification report must be prepared, which is subject to the approval in writing of the Local Planning Authority in accordance with condition 1.

Reason: To ensure that risks from land contamination to the future users of the land and neighbouring land are minimised, together with those to controlled waters, property and ecological systems, and to ensure that the development can be carried out safely without unacceptable risks to workers, neighbours and other offsite receptors.

9.36 Woodland Trust: [Objection]

9.36.1 Initial comment 18.2.25 [Objection – impact on Woodland Trust sites and ancient woodland]

The Woodland Trust is the UK's largest woodland conservation charity and a leading voice in bringing to the attention of government, landowners and the general public the state of the UK's woods and trees. We own over 1,000 sites across the UK, covering over 30,000 hectares and we have over 500,000 members and supporters.

We are an evidence-led organisation, using existing policy and our conservation and planning expertise to assess the impacts of development on ancient woodland and veteran trees. Planning responses submitted by the Trust are based on a review of the information provided as part of a planning application.

Woodland Trust Position

The Trust **objects** to this planning application on the basis of deterioration of Woodland Trust sites, and ancient woodlands designated on Natural England's Ancient Woodland Inventory (AWI), as detailed below:-

- Woodland Trust site Dell Wood (grid ref: TQ 07630 97103) - designated Ancient Semi Natural Woodland
- Woodland Trust site Harrocks Wood / Newland's Spring Wood (grid ref: TQ 07632 97418) - part designated Ancient Semi Natural Woodland
- Long Newland's Spring (grid ref: TQ 07448 96826) - designated Ancient Semi Natural Woodland
- Green Lane Wood (grid ref: TQ 08013 97009) - designated Ancient Semi Natural Woodland
- Whippendell Wood (grid ref: TQ 07939 97631) - designated Ancient Semi Natural Woodland, SSSI, and Wood Pasture and Parkland

Impact on Ancient Woodland

The application is for 600 dwellings, a school and associated infrastructure on land which includes, and is adjacent to, areas of ancient woodland and Woodland Trust sites. We are particularly concerned about the impact of the proposals on two Woodland Trust sites adjacent to the development - Dell Wood ancient woodland and Newland's Spring (part ancient woodland).

A key suggestion for mitigation of impacts on ancient woodland is the provision of a "Woodland Recreational Management Plan", the details of which are only briefly outlined in this application, but which appear to include both measures to manage recreational impacts within the woodlands, such as signposting and fencing, and measures to deter the public from accessing woodlands. We are not aware that the Woodland Trust Operational or Land & Property teams have been consulted with regards to any such measures or approached regarding any associated permissions.

The Ecological Impact Assessment concludes that the implementation of a Woodland Recreational Management Plan, together with an un-encroached buffer of 15 metres and a further encroached buffer of 15 metres, will be sufficient to mitigate impacts on Dell Wood and “*maintain the level of biodiversity within the woodland*”. However, there is no evidence provided in the application to support this conclusion.

As far as we are aware, the applicant has not approached the Woodland Trust to better understand or survey biodiversity within our woodland. It is not clear, on the basis of the information provided, whether it would be feasible to ensure that for example, sensitive species are not disturbed by noise and recreation; that sensitive ground flora will not be trampled; that pollution or disturbance from dogs will be avoided; or that cat predation will be controlled.

Dell Wood is already experiencing significant deterioration. The name “Dell Wood” is a reference to the large hollow within the woodland, which currently suffers from anti-social behaviour, fires and barbecues. This has resulted in a large area of compacted bare ground within the woodland and high levels of discarded items and broken glass. The hollow is surrounded by vegetation, which increases the risk of fire spreading through the woodland during periods of drought.

The Woodland Trust is not in a position to agree to the principle of a development of this nature and scale at this location in the absence of a robust evidence-based assessment of the impact on Dell Wood and proposals for mitigation.

We have similar concerns with regards to Newland’s Spring wood, although to a lesser extent as this woodland would be adjacent to the new Country Park and further from built up areas.

Natural England and Forestry Commission have identified impacts of development on ancient woodland and veteran trees within their standing advice. This guidance should be considered the Government’s position with regards to development impacting ancient woodland or veteran trees.

We note that Natural England has specified a “minimum 30 metre buffer” and has drawn attention to the need for the local planning authority to consider any impacts on ancient woodland and ancient and veteran trees in line with paragraph 193(c) of the NPPF and the standing advice.

The applicant is proposing 15 metres of undeveloped buffer, with a further 15 metre zone incorporating some development, such as pathways and allotments. However, there is no supporting assessment to demonstrate that these proposals will be adequate to prevent impacts on the woodland from the increase in recreational pressure associated with a housing development of this scale.

The appropriate width, design and management of a buffer zone will be influenced by numerous factors, including, but not limited to: the proposed housing mix and density; the nature and extent of existing development close to ancient woodland; existing recreational use of the woodland; the position of the woodland within the landscape in relation to the development; and the design of the development, including green space and available options for activities such as recreation and dog walking.

It is stated in the Ecological Impact Assessment that the pressures on Dell Wood could be of a similar magnitude to the pressures on Green Lane Wood, and yet the circumstances are completely different. There are public footpaths leading directly to Dell Wood from the development site, whereas Green Lane Wood would be enclosed with barrier fencing. It is not clear why Green Lane Wood would be provided with an un-encroached 30 metre buffer, whereas Dell Wood would be provided with a 15 metre un-encroached buffer. Even with a

30 metre buffer, the applicant concedes that it would not be possible to fully mitigate all potential negative urban edge impacts to Green Lane Wood.

In addition to the woodlands discussed above, we are concerned that impacts have not been assessed with regards to the finger of ancient woodland (Long Newland's Spring) connecting Dell Wood with Little Green Lane. This woodland will be particularly vulnerable to intensified use due to its extremely narrow width, and the location of the public footpath within it. The application should include an assessment of the impact of the development on Long Newland's Spring.

With regards to lighting, it is unclear how lighting will be controlled into the future as residents make changes to their properties. We are aware of research that suggests light pollution above 0.1 lux around ancient woodland and ancient and veteran trees will elicit responses in animals (Azam et al., 2018). Mitigation of light pollution through buffers and screened zones that result in light pollution levels of 0.1 lux or below is suitable mitigation.

To conclude, we have not been able to find any modelling to assess the level of intensification of access and use of the woodlands, and therefore it is not possible to fully understand the pressures on the various areas of ancient woodland, including Woodland Trust sites, from the increase in people, dogs and cats associated with a development of 600 houses. It does not appear that the scale of recreational pressure resulting from the housing mix has been properly considered through evidence-based analysis.

Protection for ancient woodland is outlined within National Planning Policy Framework (NPPF) at paragraph 193(c). This policy provides a test for developments and impact on ancient woodland. However, the test for impact is not a test of significance or magnitude, it is a test of whether there would be any negative impact.

In this case, not only has the feasibility of mitigating impact not been demonstrated, but the applicant has acknowledged that it will not be possible fully to mitigate impact with the current proposals. Feasibility of adequate mitigation needs to be demonstrated by the applicant before this outline application can be approved.

Impacts on Veteran Trees

We are concerned to ensure that all veteran trees on site have been correctly identified and appropriately protected. In this respect, we note that the RAVEN methodology has been used to assess for the presence of veteran trees.

The Woodland Trust does not use, or agree with, the RAVEN methodology as we consider that the application of a standard 'tick box' methodology and use of disqualifying factors such as girth is not in line with government guidance. Planning Practice Guidance for the 'Natural environment' (Natural environment - GOV.UK (www.gov.uk), which is intended to clarify and interpret the NPPF, states: "*Trees become ancient or veteran because of their age, size or condition. Not all of these three characteristics are needed to make a tree ancient or veteran as the characteristics will vary from species to species.*" The Arboricultural Association provides further information here Arboricultural Association - VETcert (trees.org.uk).

When assessing veteran status, size alone should not be a disqualifier and we would expect to see full consideration of the tree's condition and whether significant decay features have been identified, in line with the most recent government definition provided within The Biodiversity Gain Requirements (Irreplaceable Habitat) Regulations 2024. This states:

"Ancient and veteran trees can be found as individual trees or collections of trees in any setting.

Ancient trees have passed beyond maturity into an ancient life stage or are old in comparison with other trees of the same species which exhibit one or more of the following—

(i) demonstrably great age relative to others of the same species

(ii) changes to their crown and trunk development indicative of the ancient life stage

Veteran trees are mature trees that share physical and other characteristics in common with ancient trees, due to their life or environment, but are neither developmentally nor chronologically ancient. All ancient trees are veteran trees, but not all veteran trees are ancient. Veteran and ancient trees which have died are still recognised as such because they retain significant biodiversity value for many decades.

Veteran trees exhibit one or more of the following—

- (i) significant decay features such as deadwood, hollowing or signs of advanced decay in the trunk or major limbs*
- (ii) a large girth, depending on and relative to species, site and management history*
- (iii) a high value for nature, especially in hosting rare or specialist fungi, lichens and deadwood invertebrates”*

We would therefore encourage the involvement of the Council's tree officer to help determine the veteran status of trees on site. For example, we are concerned that oak tree T15 may need further assessment, and that its relatively small girth may have resulted in potential veteran status being ruled out. Any veteran trees on site should be provided with a veteran tree buffer zone in line with the standing advice.

Supporting Information - Ancient Woodland

Ancient woodland is an irreplaceable resource of great importance for its wildlife, soils, recreational and cultural value, historical and archaeological significance, and the contribution it makes to our diverse landscapes. It is a scarce and threatened resource, covering only 2.5% of England's land area, and has a high level of protection in planning policy.

Natural England and the Forestry Commission, the Government's respective bodies for the natural environment and woodlands, define ancient woodland as follows within their standing advice:-

“Ancient woodland takes hundreds of years to establish and is defined as an irreplaceable habitat. It is a valuable natural asset important for: wildlife (which include rare and threatened species); soils; carbon capture and storage; contributing to the seed bank and genetic diversity; recreation, health and wellbeing; cultural, historical and landscape value. It has been wooded continuously since at least 1600AD. It includes:-

- Ancient semi-natural woodland [ASNW] - mainly made up of trees and shrubs native to the site, usually arising from natural regeneration.*
- Plantations on ancient woodland sites [PAWS] - replanted with conifer or broadleaved trees that retain ancient woodland features, such as undisturbed soil, ground flora and fungi”*

In May 2022, the Government published an updated policy statement on ancient woodland, entitled 'Keepers of Time: ancient and native woodland and trees policy in England'. The Government's 'Keepers of Time' policy accentuates the importance of ancient woodland, stating: *“Ancient woodlands, ancient wood pastures and parkland and ancient and veteran trees are irreplaceable habitats which must be protected. Their long-standing presence, species and form serve as a rich cultural record of past management practices.”*

Supporting Information - Veteran Trees

Ancient and veteran trees are irreplaceable habitats and afforded a high level of protection in planning policy. They possess unique features which provide a rich and diverse range of habitats, playing host to countless other species. In particular, many rare invertebrate, fungi and lichen species are dependent on the decaying wood provided by such trees. They are irreplaceable keystone structures disproportionately supporting ecosystem function and acting as critical refugia for biodiversity. Where they occur outside of woods they are also particularly important for landscape connectivity. They are an essential part of our landscape and cultural heritage.

Natural England and Forestry Commission's standing advice on ancient and veteran trees states that they *“can be individual trees or groups of trees within wood pastures, historic parkland, hedgerows, orchards, parks or other areas. They are often found outside ancient woodlands. They are also irreplaceable habitats.*

“A veteran tree may not be very old, but it has significant decay features, such as branch death and hollowing. These features contribute to its exceptional biodiversity, cultural and heritage value.

“An ancient tree is exceptionally valuable. Attributes can include its: great age; size; condition; biodiversity value as a result of significant wood decay and the habitat created from the ageing process; and cultural and heritage value.”

Planning Policy

The National Planning Policy Framework, paragraph 193, states: “When determining planning applications, local planning authorities should apply the following principles:-

c) development resulting in the loss or deterioration of irreplaceable habitats (such as ancient woodland and ancient or veteran trees) should be refused, unless there are wholly exceptional reasons and a suitable compensation strategy exists;”

Footnote 70 defines exceptional reasons as follows: “For example, infrastructure projects (including nationally significant infrastructure projects, orders under the Transport and Works Act and hybrid bills), where the public benefit would clearly outweigh the loss or deterioration of habitat.”

There is **no wholly exceptional reason** for the development in this location and as such this application in its current form does not comply with national planning policy.

Conclusion

Ancient woodland is an irreplaceable habitat. As such, it should be protected from any form of development that will result in its loss or deterioration.

The Trust **objects** to this planning application on the basis that the feasibility of mitigating deterioration of ancient woodland has not been demonstrated. The applicant should submit additional information to demonstrate that effective mitigation could be provided. Until such time as the application is supported by an evidence-based assessment, it is not possible to determine whether a development of this nature and scale could be delivered in accordance with the National Planning Policy Framework.

Please don't hesitate to contact us at planningcasework@woodlandtrust.org.uk if it would be helpful to discuss any of the points raised.

9.36.2 Further comment 12.11.25 following review of Woodland Management Plan:

Thank you for re-consulting the Woodland Trust on the revised proposals. We have reviewed the additional information and confirm that we maintain our objection to this application.

Our concerns relate to the impact of the development on ancient woodland and veteran trees, in addition to the impact on sites owned and managed by the Woodland Trust. We have summarised our concerns below, followed by more specific detail to illustrate the key points. Please also refer to our original objection letter dated 18th February 2025.

Summary

It is important at Outline stage to demonstrate that it will be **feasible** to mitigate impacts on ancient woodland and veteran trees. This requires a baseline assessment of the nature and scale of impact. However, it remains the case that the applicant has not assessed the impacts of this development on ancient woodland.

Various mitigation measures are proposed in the 'Woodland Recreational Management Plan' and the applicant suggests that the scope and detail of these mitigation options can be agreed at Reserved Matters stage further to ongoing dialogue with the Woodland Trust or other landowners. It is also suggested that elements of the proposed mitigation could be secured by obligation, including agreement with the Woodland Trust.

At this stage we can confirm that we have not received any communication from the applicant or request to discuss the proposals. But in the absence of an assessment of impact it would nevertheless not be possible to consider whether the proposals for mitigation (including buffer width and treatment and the types of measures suggested in the Woodland Recreational Management Plan) would be sufficient to prevent deterioration of the ancient woodlands within and adjacent to the site.

We therefore do not consider there is sufficient information for the planning authority to determine the application in line with the National Planning Policy Framework. Additionally, it is not possible for the Woodland Trust to assess the adequacy of the mitigation measures proposed specifically for our own sites.

Please find further detail below.

Lack of assessment of impacts on ancient woodland

In response to the concerns detailed in our original letter the applicant states that: -

"An impact assessment and outline mitigation solutions have been provided in the form of this Management Plan, based on our site scoping visit, to provide a robust framework for further dialogue with the Trust and other relevant stakeholders. It is not therefore considered that detailed visitor modelling would be required, particularly at this outline stage of planning, as the pressures on the surrounding Ancient Woodlands can be predicted, through desk-based, site-based and stakeholder input who would have local knowledge of the site conditions."

We consider that it is precisely at this stage of the planning process that visitor modelling is required. If this is carried out at Reserved Matters stage when the buffer proposals have already in principle been agreed then it may not be possible for the supporting mitigatory measures to ensure there is no deterioration of ancient woodland. Whereas the Woodland Recreational Management Plan outlines the generic types of impacts that might be expected to arise and comments on how the existing condition of the ancient woodlands is currently being impacted by public access and recreation, it does not analyse the extent or nature of specific impacts likely to arise from this development.

We note the Woodland Recreational Management Plan refers to "RS 2025 EcIA" as providing a "detailed account of predicted impacts to surrounding Ancient Woodlands, including those arising from the operational phase of the Scheme, such as recreational and urban edges pressures resulting from a local increase in population size". We have not been able to locate this document. However, we note that the Ecological Impact Assessment submitted in 2024 did not include an assessment of the increase in population and associated impacts.

Although the Woodland Trust may be able to provide estimates of the current usage of woodlands managed by us, and information about the impacts our woodlands are currently experiencing, it is not for the Woodland Trust to estimate the likely increase in people, dogs and cats, or their behaviours, arising from this particular development. It is for the applicant to provide such an assessment.

In the absence of such an assessment it is not possible to determine whether the proposed mitigation will be adequate.

Lack of justification for proposed buffer width

A development of up to 600 dwellings, schools, healthcare, retail and parking will significantly change the nature of activity adjacent to and within the woodlands. There is no discussion in the application to demonstrate that a 30 metre buffer (rather than, for example, 40 metres or 50 metres or some other width) is appropriate for a such a key mitigatory design feature.

We raised concerns in our original objection that the applicant has not demonstrated the buffer widths would be sufficient to mitigate impacts. The applicant has responded that buffer zones are not intended as the sole deterrent.

It is of course good practice to provide supporting mitigatory measures, however, a key factor in mitigating impacts arising from development adjacent to ancient woodland is designing an appropriate buffer zone. Buffer zones can be secured and planted at the beginning of a development, before construction or occupation, and with good design and sufficient width can provide both ecological enhancement to the ancient woodland and additional open space to absorb increased footfall. The standing advice, which describes a number of mitigatory design interventions, provides particular advice on the use of buffer zones.

We also note a lack of clarity across the documentation with regards to buffer width, infrastructure encroachment, and the extent to which access would be encouraged or deterred. To illustrate, the Preliminary Arboricultural Impact Assessment states: "ASNW buffers will be kept semi-natural in terms of landscape design, with no play or recreational areas located within the 30m." However, plans appear to show LEAPs and allotments adjacent to the 15 metre buffer, and in some cases fencing adjacent to the woodland. The Design and Access Statement states: "A mown grass edge should be retained around the ancient woodland located within the Site to enable informal access to the woodland edge and interactions with nature."

The proposals for buffer widths, degree of encroachment, and the extent to which buffer zones contribute to available public green space or ecological enhancement, need to be clearly and consistently set out. The plans should also show distances from the boundary of the ancient woodland to the closest infrastructure.

Impacts on Veteran Trees

We note the Woodland Recreational Management Plan states: "This Management Plan does not consider in detail consultee concerns to veteran and mature trees within the Site. It is understood that an Arboricultural Technical Note in this respect has been submitted to TRDC by Tyler Grange on 11th March 2025."


We are unable to find this Technical Note and it appears that the amended Preliminary Arboricultural Impact Assessment does not address our concerns on veteran trees.

Conclusion

The Trust maintains an objection to this application due to deterioration of ancient woodland and veteran trees. Until such time as the application is supported by an evidence-based assessment, it is not possible to determine whether this development could be delivered in accordance with the National Planning Policy Framework. As such in its current form we consider that the application should be refused.

This page is intentionally left blank

Site Location



Aerial Image



LEGEND

Site boundary

LAND USE PARAMETERS

- Proposed open space**
Proposed open space for recreation, passive recreation, and other uses.
- Proposed medium-density residential**
Proposed medium-density residential development.
- Proposed high-density residential**
Proposed high-density residential development.
- Proposed medium-density residential**
Proposed medium-density residential development.

ACCESS PARAMETERS

- Proposed access for all modes**
Proposed access for all modes of transport.
- Proposed access for bicycles**
Proposed access for bicycles.
- Proposed access for pedestrians**
Proposed access for pedestrians.
- Building as a light of any access vehicle**
Building as a light of any access vehicle.

Illustrative Masterplan




ILLUSTRATIVE MASTERPLAN | Not to scale


LEGEND

	SITE LOCATION		COMMUNITY ORCHARD		PROPOSED HEDGEROW
	PUBLIC OPEN SPACE AND AMENITY SPACE		AREA FOR PLAY		SHALE
	HARD LANDSCAPE FEATURE SQUARES/ FOCAL SPACES WITH PEDESTRIAN/CYCLE PRIORITY		SUSTAINABLE DRAINAGE		MOORLANDS
	EXISTING TREES		TRAIL ROUTE (20M)		PROPOSED SHARED PEDESTRIAN / CYCLE WAY ALONG CANTERBURY ROAD
	NEW TREE PLANTING		PROPOSED NATIVE THICKET PLANTING		
	WILDFLOWER / LONG GRASS		PROPOSED ORNAMENTAL SHRUBS		


Indicative Building Heights



Proposed Site Access – Links Way



Proposed Site Access – Durrants Drive



PLANNING COMMITTEE - 22 JANUARY 2026

25/0195/FUL: Demolition of existing dwelling and construction of detached building containing 5 residential flats, with associated landscaping, provision of new vehicular access, car parking, cycle and refuse storage at 80 THE DRIVE, RICKMAMSWORTH, HERTS, WD3 4DU

Parish: Chorleywood

Ward: Chorleywood North and Sarratt

Expiry of Statutory Period: EOT: 16.12.2025

Case Officer: Claire Wilson

Development Type: Minor Dwellings

Recommendation: That Planning Permission is Refused.

Reason for consideration by the Committee: The application has been called in by the Head of Regulatory Services given the level of public interest.

The application has also been called in by three members of the Planning Committee if officers are minded to approve for the following reasons:

- 1) There are concerns about introducing flatted development along this road where none is believed to exist and the impact this would have on the character of the road.
- 2) Herts Highways have objected so concerns are raised on highways issues also.
- 3) There is a considerable amount of local dissent on the scheme.
- 4) Finally, there is a fear that the privacy of those using the neighbouring school grounds could be adversely affected by overlooking.

Chorleywood Parish Council have also called in the application in the event officers are minded to approve due to concerns including in relation to parking and character as set out in their comments in paragraph 4.1.1 of the analysis below.

To view all documents forming part of the application, please go to the following website:

[25/0195/FUL | Demolition of existing dwelling and construction detached building containing 5 residential flats, with associated landscaping, provision of new vehicular access, car parking, cycle and refuse storage | 80 The Drive Rickmansworth Hertfordshire WD3 4DU](#)

1 Relevant Planning History

- 1.1 8/280/74: Erection of dwellinghouse (In Grounds of no. 82). Application permitted.
- 1.2 8/28/75: Erection of dwellinghouse.
- 1.3 8/516/75: Dwellinghouse and access to the highway. Application permitted.

2 Description of Application Site

- 2.1 The application site consists of a two- storey detached residential dwelling located on the southern side of The Drive, Rickmansworth. The streetscene is mainly characterised by detached dwellings of varied architectural design, set on large plots with generous spacing between dwellings. Located to the east of the dwelling is Charlotte House Prep School, with

the nearest adjacent building on this site being two storey in height. To the west of the site and opposite, are detached residential dwellings.

- 2.2 The existing dwelling is set at a significantly lower land level to the adjacent highway. It has a brick external finish, pitched roof form with gable ends to the flank elevations. To the front of the dwelling is a single storey projection containing the entrance, and adjacent to the boundary with the school is an attached garage with mono pitched roof form. The site is accessed via a single vehicular crossover, which serves a driveway which slopes steeply down from the main road.
- 2.3 To the rear of the site, the dwelling has an existing single storey side projection located adjacent to the boundary with Charlotte House and there is also a single storey outbuilding sited adjacent to the western boundary. This sits at a lower land level to the dwelling. Immediately to the rear of the dwelling itself is a paved patio area set at the same level as the dwelling, with the remaining garden laid to lawn and sloping down towards the rear boundary. At the time of the site visit, it was observed that there is an existing MUGA/Tennis Court within the grounds of Charlotte House, which is enclosed by mesh fencing and immediately adjoins the boundary with the application site.
- 2.4 The neighbouring dwelling to the west known as no.78 extends significantly beyond the rear of the host dwelling and has a higher ridge line relative to the application dwelling. This neighbour dwelling appears to be served by a large projecting, glazed balcony area which is visible from the application site.
- 2.5 The site is affected by an existing Tree Preservation Order (TPO Reference: TPO Title: TR (The Drive, Chorleywood) 2010).

3 Description of Proposed Development

- 3.1 The applicant is seeking full planning permission for the demolition of the existing detached dwelling and construction of a detached building containing five residential flats with associated landscaping, new vehicular access and refuse storage. The proposed development would provide 3 x 2 bedroom units, and 2 x 3 bedroom units.
- 3.2 The proposed building would be set back approximately 12.3m from the front boundary of the site. The building would have a width of approximately 14.4m and a maximum depth (to the rear most projection of the building) of 17.4m. The plans indicate that the western flank elevation would be set a maximum of 2m from the boundary with no.78 The Drive (and a minimum of 1.6m due to the nature of the boundary). The plans also indicate a distance retained to the eastern boundary with Charlotte House School of 1.55m.
- 3.3 In terms of design, the building would appear as having a two storey appearance when viewed from The Drive. The plans indicate that the building would have a maximum height of 9.4m (as taken from the lowest land level marked on the front elevation). The building would have two front gabled projections to either side of the front elevation. The entrance door to the flats will be located centrally with this recessed area being timber clad, whilst the gables would have a white rendered appearance. Due to the nature of the land levels, the building would have a three storey appearance to the rear elevation with the plans indicating a maximum height of 12.4m. The plans indicate a crown roof form with the proposed crown roof having a depth of 5.3m and a width of 14.8m. The proposed rear projection would have a hipped roof form which would be set down from the main ridge. The plans suggest that the rear elevation would be white rendered with areas of cladding proposed to the fenestration detail.
- 3.4 The applicant is proposing to retain the existing vehicular access point, whilst also proposing a new vehicular access adjacent to Charlotte House. The plans indicate that the land levels would be built up in order to provide a car parking area level with the highway with provision for five off street car parking spaces. The plans show that the parking area

would be set at a higher land level to the ground floor level of the proposed building. In order to facilitate the car parking area, a retaining wall is proposed which would be located approximately 2m from the front elevation of the building. Balustrading is proposed to be constructed to the rear of the car parking area closest to the proposed building. Stepped access is proposed down from the car parking area to access the main entrance to the flats which is set at a lower land level relative to the highway. Stepped access is also proposed to either side of the building in order to access the rear amenity area.

3.5 To the rear, the plans indicate a private amenity space serving the lower ground floor unit (flat 1), with a terrace area proposed to serve flat 3 at ground floor level. A privacy screen is proposed to the side of this terrace to provide screening from Charlotte House School. In addition, the plans indicate the provision of 2m high fencing to the boundary with this neighbour. The remaining garden area would be utilised as a communal amenity space.

3.6 Amended plans have been received during the course of the application as follows:

- Cycle ramp added in order for bikes to be transported from street level to the proposed ground floor level of the building.
- Gate added adjacent to front entrance door.
- Cycle storage relocated to rear garden.
- Privacy screen added to rear terrace.
- Reflective glass added to ground floor front windows.
- Car parking spaces set approximately 0.5m further back than previously illustrated.
- Landscaping increased to the rear.

3.7 Officers have not re-consulted on the amended drawings, as no significant material changes have been proposed to the scheme which would require additional consultation.

4 Consultation

4.1 Statutory Consultation

4.1.1 Chorleywood Parish Council: [Objection]

The Committee had Objections to this application on the following grounds and wish to CALL IN, unless the Officers are minded to refuse.

The level of parking proposed is only half of that required under Appendix 5 of the Development Management Policies. The site is approximately 1 mile from the local station and shops, so there should be no reduction below that given the Development Management Policies.

Despite the assertions of the developers On Street Traffic Survey, the surrounding streets already suffer significant parking pressure due to the school and nearby roads, such as High Close, can easily be obstructed by parked cars

Under Policy 5 of the Chorleywood Neighbourhood Development Plan (NDP), flatted development should only be undertaken near to stations and / or local facilities & amenities. As this site is approximately 1 mile from the nearest station and the main facilities & amenities, this proposed development is not in accordance with the NDP.

There are concerns over the overlooking of the school playgrounds from the living rooms of the upper flats.

The local area of the site consists of large dwellings on large plots. Development of flats here would result in an increase in density not suited to the site.

There are concerns that a habitable home is being demolished to achieve this development with an unnecessary release of Carbon (approximately 100 tonnes more than required to undertake extension) and the creation of considerable waste.

Should the plans or supporting information be amended by the Applicant, please advise the Parish Council so the comments can be updated to reflect the amended.

4.1.2 Herts Highways: [Initial objection overcome]

4.1.2.1 [Initial objection]

Proposal: Demolition of existing dwelling and construction detached building containing 5 residential flats, with associated landscaping, provision of new vehicular access, car parking, cycle and refuse storage

Recommendation: Notice is given under article 22 of the Town and Country Planning (Development Management Procedure) (England) Order 2015 that Hertfordshire County Council as Highway Authority recommends that permission be refused for the following reason:

The proposed access arrangements are not in accordance with Hertfordshire County Council policies and specifications and has the potential to interfere with the free and safe flow of highway users on the adjacent highway. The proposals are therefore contrary to policy guidelines as outlined in the National Planning Policy Framework (NPPF) and Hertfordshire Local Transport Plan (LTP4).

Comments/Analysis

Description of Proposal: Demolition of existing dwelling and construction detached building containing 5 residential flats, with associated landscaping, provision of new vehicular access, car parking, cycle and refuse storage

Site and Surroundings: The Drive is an unclassified local access route subject to a 30mph speed limit which is highway maintainable at public expense. As per the Place and Movement Network within the PMPDG, The Drive is classified as a P2/M1. The site is in residential area to the north of the centre of Rickmansworth with a school being adjacent to the site itself.

Highway Impact

The proposed access arrangements are not in accordance with HCC specifications and policies as two accesses are proposed at the site. Any additional access at a site is considered to be an additional conflict point between vehicles crossing the footway and pedestrians. The additional access also means that the site is giving priority to vehicles crossing the footway over pedestrians, infringing upon LTP4 policies 1 and 5 which aim to maintain a highway user hierarchy where pedestrian movements are prioritised. Secondary accesses are also not permitted within the Residential Dropped Kerb Policy, although this is not a householder application the policy remains relevant due to the residential nature of the area and the proposal. It would be suggested that a central shared dropped kerb access, measuring a maximum of 7.2m wide, should be explored with swept path drawings showing how vehicles can access the proposed parking spaces. It is also noted that there is not 6m

behind each of the parking spaces, a measurement defined in Manual for Streets which is required to allow for vehicles to safely manoeuvre in and out of a space. The parking spaces should therefore be widened, to make movements easier, and swept path drawings provided to ensure that vehicles will not be doing any manoeuvring over the highway footway when using the parking spaces.

Conclusion

HCC as the Highway Authority have reviewed the supporting documents and drawings and wishes to raise an objection to the application. This is due to highway concerns as the proposals are contrary to the design standards contained in Manual for Streets and infringes upon LTP4 policies 1 and 5.

4.1.2.2 Officer comment: Following the above objection, further information was submitted by the applicant.

4.1.2.3 [Second Comment: No objection subject to conditions]

Recommendation: Notice is given under article 22 of the Town and Country Planning (Development Management Procedure) (England) Order 2015 that Hertfordshire County Council as Highway Authority does not wish to restrict the grant of permission subject to the following conditions:

1. Additional details (might be more appropriate to submit and approve prior to decision to remove need for condition).

No development shall commence until full details have been submitted to and approved in writing by the Local Planning Authority to illustrate the following:

- a. Swept path analysis / tracking to illustrate that cars would be able to use the proposed car parking spaces, turn around on site and egress the site in forward gear. Any turning areas should not utilise any of the adjacent highway footway.
- b. Amended site plan to illustrate the existing vehicle crossover access and the new vehicle crossover with a width of 5.4m (made up of four flat kerbs and two ramped kerbs).

Reason: To ensure suitable, safe and satisfactory planning and development of the site in accordance with Policy 5 of Hertfordshire's Local Transport Plan (adopted 2018).

2. A Highway Improvements – Offsite (Design Approval)

Notwithstanding the details indicated on the submitted drawings no on-site works above slab level shall commence until a detailed scheme for the offsite highway improvement works have been submitted to and approved in writing by the Local Planning Authority. The works shall include:

- An additional new vehicle crossover access made up of four flat kerbs and two ramps kerbs and any associated works.

B Highway Improvements – Offsite (Implementation / Construction)

Prior to the first use of the development hereby permitted the offsite highway improvement works referred to in Part A of this condition shall be completed in accordance with the approved details.

Reason: To ensure construction of a satisfactory development and that the highway improvement works are designed to an appropriate standard in the interest of highway safety and amenity and in accordance with Policy 5, 13 and 21 of Hertfordshire's Local Transport Plan (adopted 2018).

Provision of Access and Parking Areas

Prior to the first occupation of the development hereby permitted the necessary access and on-site car parking and turning area shall be laid out, demarcated, surfaced and drained in accordance with the approved plan and retained thereafter available for that specific use.

Reason: To ensure construction of a satisfactory development and in the interests of highway safety in accordance with Policy 5 of Hertfordshire's Local Transport Plan (adopted 2018).

4. Construction Management

No development shall commence until a Construction Management Plan/Statement has been submitted to and approved in writing by the Local Planning Authority. Thereafter the construction of the development shall only be carried out in accordance with the approved Plan. The Construction Management Plan shall include details of:

- a. Construction vehicle numbers, type, routing;
- b. Any traffic management requirements
- c. Construction and storage compounds (including areas designated for car parking, loading / unloading and turning areas);
- d. Siting and details of wheel washing facilities;
- e. Timing of construction activities to avoid peak periods and school drop off and pick up times;

Reason: In order to protect highway safety and the amenity of other users of the public highway and rights of way in accordance with Policies 5, 12, 17 and 22 of Hertfordshire's Local Transport Plan (adopted 2018).

Highway Informatives

Construction standards for works within the highway (s278 works): The applicant is advised that in order to comply with this permission it will be necessary for the developer of the site to enter into an agreement with Hertfordshire County Council as Highway Authority under Section 278 of the Highways Act 1980 to ensure the satisfactory completion of the access and associated road improvements. The construction of such works must be undertaken to the satisfaction and specification of the Highway Authority, and by a contractor who is authorised to work in the public highway. Before works commence the applicant will need to apply to the Highway Authority to obtain their permission and requirements. Further information is available via the website

<https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/business-and-developer-information/development-management/highways-development-management.aspx>

Comments: The proposal comprises of the demolition of the existing dwelling and development of 5 residential dwellings and associated works at 80 The Drive, Rickmansworth. The Drive is designated as an unclassified local access road, subject to a speed limit of 30mph and is highway maintainable at public expense. Dawes Lane is classed as P2/M1 (residential street) on HCC's Place & Movement Network.

A Transport Statement (TS) has been submitted as part of the application.

Access: There is an existing vehicle crossover access into the site. The proposals include an additional vehicle access point.

Following consideration of the letter submitted in response to the original highway comments and the fact that the proposals are for more than one dwelling, it has been considered that there would not be sufficient grounds to recommend objection to the proposals on the grounds of an additional vehicle access. Nevertheless HCC as Highway

Authority would recommend swept path analysis / tracking to illustrate that cars would be able to use the proposed car parking spaces, turn around on site and egress the site in forward gear. Any turning areas should not utilise any of the adjacent highway footway and would be important when taking into account the adjacent school.

It would also be recommended (as there would be two accesses) that each is no wider than 5.4m (made up of four flat kerbs and two ramped kerbs) and therefore if these should be shown or at least labelled / indicated on a scaled plan. The existing VXO appears to be this size already.

Visibility splays of 2.4m by 40m to either side of both access have been illustrated on drawing number 6115/001 B. The normally required visibility splays for 30mph is 43m but this is also considered to be available and therefore the access proposals are in accordance with HCC's Place & Movement Planning and Design Guidance (PMPDG) and Manual for Streets in this respect.

The proposals include the provision of storage for on-site refuse / recycling bins. The collection method for refuse / recycling would also need to be confirmed as acceptable by Three Rivers District Council (TRDC) as waste collection authority.

The proposals would enable emergency vehicle access to within 45 metres from all parts of the proposed dwellings. This adheres to guidelines as recommended in MfS, Roads in Hertfordshire; A Design Guide and Building Regulations 2010: Fire Safety Approved Document B Vol 1 –Dwellinghouses (and subsequent updates).

The proposed development would also need to make adequate provision for drainage on site to ensure that surface water is disposed of on site and does not discharge onto the highway.

Section 278 Highway Works

The applicant would ultimately need to enter into a Section 278 Agreement with HCC as Highway Authority in relation to the approval of the design and implementation of the works that would be needed on highway land including:

- New vehicle crossover access made up of four flat kerbs and two ramps kerbs and any associated works.

Prior to applying to enter into a Section 278 Agreement with the Highway Authority, the applicant would need to obtain an extent of highway plan to clarify the works which would be within the existing highway. Please see the above conditions and informatives

Trip Generation

A trip generation assessment for the proposed use has been included as part of the TS, the details of which have been based on trip rate information from the TRICS database. This approach is considered to be acceptable by HCC as Highway Authority. The level of trips and impact on the surrounding highway network for a development of this size would not be considered to be significant or severe

Parking

The proposal includes the provision of 5 on car site parking spaces, each with an electric vehicle charging facility. The proposals in this respect are in accordance with LTP4, Policy 5h, which states that developments should “ensure that any new parking provision in new developments provides facilities for electric charging of vehicles”.

The proposals include the provisions of on-site cycle stores (with provision for 12 cycles to park), which would be supported by HCC as Highway Authority to promote cycling as a sustainable travel option to and from the site.

TRDC as the planning authority would ultimately need to be satisfied with the overall level and type of parking to ensure accordance with their adopted standards.

Conclusion

HCC as Highway Authority considers that the proposal would not have an impact on the safety or severe impact on operation of the surrounding highway. The applicant would need to enter into a Section 278 Agreement with HCC to cover the technical approval of the design, construction and implementation of the necessary highway and access works. Therefore HCC has no objections on highway grounds to the application, subject to the inclusion of the above recommendation for additional information, planning conditions and highway informatives.

4.1.2.4 Officer comment: In response the applicant has provided further information stating that it was not possible for vehicles to manoeuvre within the site and therefore the condition as requested by Herts Highways could not be fulfilled. As such, this was raised with Herts Highways for consideration.

4.1.2.5 [Third comment: No objection]

Recommendation: Notice is given under article 22 of the Town and Country Planning (Development Management Procedure) (England) Order 2015 that Hertfordshire County Council as Highway Authority does not wish to restrict the grant of permission subject to the following conditions:

1. Provision of Access and Parking Areas

Prior to the first use of the development hereby permitted, the new vehicle crossover access shall be provided at a width of no greater than 5.4m (made up of four flat kerbs and two ramped kerbs) and the on-site car parking shall be laid out, demarcated, surfaced and drained in accordance with the approved plan and retained thereafter available for that specific use.

Reason: To ensure construction of a satisfactory development and in the interests of highway safety in accordance with Policy 5 of Hertfordshire's Local Transport Plan (adopted 2018).

2. Provision of Pedestrian Visibility Splays

Prior to the first use of the development hereby permitted 0.65 x 0.65 metre pedestrian visibility splays shall thereafter be retained at all times to each side of the new and existing access points. They shall be measured from the point where the edges of the access way cross the highway boundary, 0.65 metres into the site and 0.65 metres along the highway boundary therefore forming a triangular visibility splay. Within which, there shall be no obstruction to visibility between 0.6 metres and 2.0 metres above the carriageway.

Reason: To ensure construction of a satisfactory development and in the interests of highway pedestrian safety in accordance with Policies 5 and 7 of Hertfordshire's Local Transport Plan (adopted 2018).

3. Construction Management

No development shall commence until a Construction Management Plan/Statement has been submitted to and approved in writing by the Local Planning Authority. Thereafter the construction of the development shall only be carried out in accordance with the approved Plan. The Construction Management Plan shall include details of:

- a. Construction vehicle numbers, type, routing;
- b. Any traffic management requirements
- c. Construction and storage compounds (including areas designated for car parking, loading / unloading and turning areas);
- d. Siting and details of wheel washing facilities;

e. Timing of construction activities to avoid peak periods and school drop off and pick up times;

Reason: In order to protect highway safety and the amenity of other users of the public highway and rights of way in accordance with Policies 5, 12, 17 and 22 of Hertfordshire's Local Transport Plan (adopted 2018).

Highway Informatives

HCC as Highway Authority recommends inclusion of the following Advisory Note (AN) / highway informative to ensure that any works within the highway are carried out in accordance with the provisions of the Highway Act 1980:

AN) New or amended vehicle crossover access (section 184): Where works are required within the public highway to facilitate a new or amended vehicular access, the Highway Authority require the construction of such works to be undertaken to their satisfaction and specification, and by a contractor who is authorised to work in the public highway. If any of the works associated with the construction of the access affects or requires the removal and/or the relocation of any equipment, apparatus or structures (e.g. street name plates, bus stop signs or shelters, statutory authority equipment etc.) the applicant will be required to bear the cost of such removal or alteration.

Before works commence the applicant will need to apply to the Highway Authority to obtain their permission, requirements and for the work to be carried out on the applicant's behalf. Further information is available via the County Council website at:

<https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/changes-to-your-road/dropped-kerbs/dropped-kerbs.aspx>

Comment: The proposal comprises of the demolition of the existing dwelling and development of 5 residential dwellings and associated works at 80 The Drive, Rickmansworth. The Drive is designated as a unclassified local access road, subject to a speed limit of 30mph and is highway maintainable a public expense. Dawes Lane is classed as P2/M1 (residential street) on HCC's Place & Movement Network.

A Transport Statement (TS) was submitted as part of the application. Updated plans have been submitted by the applicant in Dec 2025.

Access: There is an existing vehicle crossover access into the site. The proposals include an additional vehicle access point.

Following consideration of the letter submitted in response to the original highway comments and the fact that the proposals are for more than one dwelling, it has been considered that there would not be sufficient grounds to recommend objection to the proposals on the grounds of an additional vehicle access.

It would also be recommended (as there would be two accesses) that the new VXO is no wider than 5.4m (made up of four flat kerbs and two ramped kerbs). The existing VXO appears to be this size already. Therefore the above condition has been recommended in this respect.

HCC as Highway Authority had also previously requested that the applicant provides details that vehicles would be able to turn around on site and egress in forward gear to the highway. The applicant subsequently stated that this would not be achievable and that it would be reasonable for vehicles to reverse in or out. On balance and consideration of the speed limit and nature of the highway, HCC as Highway Authority has considered that there would not be sufficient grounds to recommend refusal in this respect. Nevertheless, the above condition in respect to visibility has been recommended to ensure that vehicular to pedestrian visibility is maximised and provided at a sufficient level on both sides of the new

access. Essentially any boundary features within the pedestrian visibility splay areas would need to be provided and retained at a height of no greater than 0.6m.

Vehicular to vehicular visibility splays of 2.4m by 40m to either side of both access have been previously shown on illustrated on drawing number 6115/001 B. The normally required visibility splays for 30mph is 43m but this is also considered to be available and therefore the access proposals are in accordance with HCC's Place & Movement Planning and Design Guidance (PMPDG) and Manual for Streets in this respect.

The proposals include the provision of storage for on-site refuse / recycling bins. The collection method for refuse / recycling would also need to be confirmed as acceptable by Three Rivers District Council (TRDC) as waste collection authority.

The proposals would enable emergency vehicle access to within 45 metres from all parts of the proposed dwellings. This adheres to guidelines as recommended in MfS and Building Regulations 2010: Fire Safety Approved Document B Vol 1 – Dwellinghouses (and subsequent updates).

The proposed development would also need to make adequate provision for drainage on site to ensure that surface water is disposed of on site and does not discharge onto the highway.

Trip Generation

A trip generation assessment for the proposed use has been included as part of the TS, the details of which have been based on trip rate information from the TRICS database. This approach is considered to be acceptable by HCC as Highway Authority. The level of trips and impact on the surrounding highway network for a development of this size would not be considered to be significant or severe.

Parking

The proposal includes the provision of 5 on car site parking spaces, each with an electric vehicle charging facility. The proposals in this respect are in accordance with LTP4, Policy 5h, which states that developments should “ensure that any new parking provision in new developments provides facilities for electric charging of vehicles”.

The proposals include the provision of an on-site cycle store. The location of the store has been amended to be located in the rear of the site with a cycle track added to both sets of steps to facilitate the movement of bicycles, which is an improvement on the previous plan that did not consider this. The cycle store should be covered and secure.

TRDC as the planning authority would ultimately need to be satisfied with the overall level and type of parking to ensure accordance with their adopted standards.

Conclusion: HCC as Highway Authority considers that the proposal would not have an impact on the safety or severe impact on operation of the surrounding highway. The applicant would need to enter into a VXO agreement with HCC to cover the technical approval of the design, construction and implementation of the necessary highway and access works. Therefore HCC has no objections on highway grounds to the application, subject to the inclusion of the above planning conditions and highway informatives.

4.1.3 Officer comment: Further clarification was sought from Herts Highways with regard to the safety of the new access and its relationship with the school and the following comments have been received:

4.1.4 Herts Highways: [No objection]

HCC as Highway Authority did originally resist the additional vehicular access point to keep the number of entrance points onto the highway network to a minimum and encourage vehicles to have the ability to turn around on site. However due to site constraints, the applicant has not been able to demonstrate this. Nevertheless following consideration of the remaining proposals with a low number of vehicle movements and sufficient levels of visibility it has been deemed that there would not be a highway safety reason to recommend refusal.

4.1.5 Herts Ecology: [Initial objection overcome]

4.1.5.1 [Initial objection]

ECOLOGICAL IMPLICATIONS

Thank you for consulting this office on the above application.

Overall Recommendation:

The planning officer should either:

1. Refuse the application or advise it is withdrawn or,
2. Request further information from the applicant and re-consult the Ecology Service (LEADS) when it is furnished.

Summary of Advice:

- Insufficient information on bats to advise determination of the application – Two bat emergence surveys should be undertaken in the bat activity period, and a report submitted prior to determination.
- Protected species Informative.
- Species Enhancement Plan Condition.
- BNG sufficient for determination.
- Offsite BNG required – HMMP needed.

Supporting documents:

- Preliminary Ecological Appraisal and Roost Assessment (Arbtech, September 2024).
- Bat Survey Report (NRG Consulting, December 2024).
- Biodiversity Net Gain Assessment Report (Arbtech, January 2025).
- Biodiversity Metric.

Comments:

The application site is within a residential area and is of limited ecological interest. However, there are various trees present, which form part of established gardens connecting the site to other habitats in the vicinity. A Preliminary Ecological Appraisal (PEA: Arbtech, September 2024) and Bat Survey Report (NRG Consulting, December 2024) have been submitted as part of the application.

B1 was assessed to have moderate potential for roosting bats, and B2, negligible. The classification of B1's moderate potential was owed to the gaps and raised tiles on the roof, and gaps in the soffits. Multiple trees will be felled to facilitate the development, however, none of these were identified to possess roosting features for bats, therefore no further surveys for trees are required. In line with the Bat Conservation Trust Guidelines (2023), moderate potential prompts the need for two bat emergence surveys to be undertaken.

A Bat Survey Report has been submitted by NRG Consulting. This contains the results of only one emergence survey visit, and this was undertaken in December 2024, which is outside of the bat activity period and within the peak hibernation period. Whilst bats sometimes emerge from hibernation on warm nights, typically, in December, they are unlikely to do this. An emergence survey during this time is insufficient and is unlikely to give

a true representation of whether this building is/has been utilised as a bat roost. Furthermore, only one emergence survey was conducted, which is not in line with the “moderate” potential given by Arbtech.

Currently, I consider there to be insufficient information on bats to advise determination of the application. Bats are fully protected under national and international law, and sufficient information should be submitted prior to determination to ensure the LPA can consider the impact of the proposal on bats and discharge their legal obligations under the Conservation of Habitats and Species Regulations 2019 (as amended).

Consequently, I advise that two emergence surveys should be undertaken in the bat activity period (May-August, and September if the weather remains warm). The results of these surveys should be incorporated into a bat report, which should be submitted to the LPA for approval prior to determination.

Other protected species: The PEA did not find evidence of any protected species onsite. In the unlikely event that they are found, I advise the following informative should be added to any permission granted:

To avoid the killing or injuring of wildlife during development, best practice should keep any areas of grass as short as possible and any longer, ruderal vegetation should be cleared by hand. To avoid creating refugia that may be utilised by wildlife, materials should be carefully stored on-site on raised pallets and away from the boundary habitats. Any trenches on site should be covered at night or have ramps to ensure that any animals that enter can safely escape, and this is particularly important if excavations fill with water. Any open pipework with an outside diameter greater than 120mm must be covered at the end of each working day to prevent animals entering / becoming trapped.

In order to protect breeding birds, their nests, eggs and young, demolition or vegetation clearance should only be carried out during the period October to February inclusive. If this is not possible then a pre-development (i.e. no greater than 48 hours before clearance begins) search of the area should be made by a suitably experienced ecologist. If active nests are found, then works must be delayed until the birds have left the nest or professional ecological advice taken on how best to proceed.”

Ecological Enhancements: Given the suitable habitat in the vicinity, I advise that in line with the NPPF, species enhancements should be included in the development plan. Consequently, I advise that a Species Enhancement Plan should be submitted to the LPA as a Condition of approval.

“Prior to commencement of the development (including vegetation clearance, demolition and ground works), a Species Enhancement Plan shall be prepared. It will include a graphical plan, setting out the number, type and position of enhancement features to be incorporated into the design scheme. The number of features should be proportional to the size of the development, and should be integrated in nature. This plan shall be submitted to the Local Planning Authority for written approval and the development shall be carried out in accordance with the approved plan unless otherwise agreed in writing with the Local Planning Authority”.

Biodiversity net gain: This application is subject to mandatory biodiversity net gain. A Biodiversity Metric and Biodiversity Net Gain Assessment report have been submitted (Arbtech).

The baseline habitat units stand at 2.30BU, with the onsite net change being -0.35 which equates to a net loss of 15.33%. This net loss is predominantly owed to the loss of trees that have not been fully compensated for. Habitat creation includes other neutral grassland, and urban tree.

The hedgerow baseline units stand at 0.04BU, with the onsite net change being 0.01 equating to a biodiversity net gain of 32.20%. This net gain is owed to the creation of a non-native and ornamental hedgerow.

Given that the habitat creation will be within the curtilage of privately owned gardens with no public access, onsite gains cannot be legally secured. This means that the habitat creation of other neutral grassland, and urban tree cannot technically count towards the biodiversity net gain if this is created on site. Furthermore, creating and maintaining other neutral grassland in a small communal garden is not considered a good option since this grassland will be subject to significant recreational pressure from the people residing in the five flats.

It has been noted in the BNG report that offsite BNG is likely required. Therefore, I advise that the habitat creation should be changed to only “vegetated garden” and “developed land”, and the full 10% net gain should be met using an offsite location.

Whilst the biodiversity gain condition is a post determination matter, given the present information shows a net loss in biodiversity, presently we cannot advise the LPA that they can have confidence at this stage that the general Biodiversity Condition can be discharged.

Nevertheless, in line with government guidance it would generally be inappropriate for concerns about the ability to discharge the condition to be used as a reason to refuse an application. However, the applicant should be made aware the general biodiversity condition is a pre commencement condition and that these matters will need to be addressed either now or at the post determination stage.

At the biodiversity gain plan stage an updated metric will need to be submitted showing how a net gain can be delivered using an off-site location, with the provision of the Biodiversity Gain Site Register reference number for that site. As a last resort if an off-site location cannot be found Biodiversity Credits would need to be purchased. In this latter case the applicant must demonstrate to the satisfaction of the LPA that all other options have been fully explored and that the BNG hierarchy has been followed

The minimum requirement of a completed baseline has been demonstrated. The biodiversity gain condition will apply to this application, whereby a biodiversity gain plan will be submitted as part of this condition. We advise that the government template for the biodiversity gain plan should be used, and a metric which corresponds with the gain plan should be submitted alongside this.

Given it is stated that an off-site solution is needed to achieve BNG, the LPA is required to secure this off-site net gain via legal agreement whether through an S106 agreement or conservation covenant. Any off-site land used for the purpose of achieving biodiversity units must be registered on the biodiversity gain sites register.

We advise that a Habitat Monitoring and Management Plan (HMMP) should be secured as part of the legal agreement. This shall demonstrate how the habitat enhancement and creation, and subsequent target habitat conditions will be created, enhanced, and monitored over 30 years following the completion of the capital works required to create them. It is recommended that the HMMP should be in line with the HMMP template produced by DEFRA. Considerations should also be given within any legal agreement to secure resources to allow adequate monitoring over the 30-year period

4.1.5.2 Officer comment: Following the above comments, the applicant submitted further information and Herts Ecology were re-consulted.

4.1.5.3 [Second Comment: Objection]

ECOLOGICAL IMPLICATIONS

Thank you for consulting this office on the above application.

Overall Recommendation: The planning officer should either:

1. Refuse the applicant or advise it is withdrawn

or,

2. Request further information from the applicant and re-consult the Ecology Service (LEADS) when it is furnished.

Summary of Advice:

- There is still insufficient information on bats to advise determination.
- Only one survey has been carried out in May 2025, and a building with moderate potential requires a minimum of two dusk emergence surveys to be conducted
- The results of the December survey are wholly unreliable since bats are in hibernation and are unlikely to emergence during this time.
- The bat activity is between May and September. Therefore, a second dusk emergence survey completed within the appropriate time of year should be carried out.
- The results of this survey should be submitted prior to determination.

Supporting documents:

- Bat Survey Report – Emergence Survey (NRG Consulting, May 2025).

Comments: Subsequent to our previous comments dated 11/06/2025, a bat report has now been submitted containing the results of one further bat emergence survey conducted in May 2025.

The below will supersede our previous advice on bats, however, all other advice in our letter dated 11/06/2025 still stands.

We previously advised that given the date of the last emergence survey that was carried out (December 2024), there was still insufficient information to advise determination. The potential given in the PRA was “moderate” potential, which in line with the Bat Conservation Trust guidelines, two dusk emergence surveys are required within the bat activity period (May-August, and September if the weather remains warm). Since the first survey was conducted in December, this survey should be overlooked since bats are in hibernation and are unlikely to emerge during this time. Therefore, for the LPA to be confident that bats are likely absent from the building, it is fundamental for the two dusk emergence surveys to be carried out at the appropriate time of year.

The bat report only contains details relating to one dusk emergence survey carried out in May 2025, and there is no evidence of a second survey. As mentioned, the results of the December survey are redundant as they are contradictory to the Bat Conservation Trust guidelines.

Therefore, the proposals should not be approved until another bat emergence survey is carried out before the end of September 2025 (assuming the weather in September is appropriate). The results of this survey should be submitted to the LPA for approval prior to determination.

4.1.5.4 Officer comment: Following the above comments, further information was submitted by the applicant and Herts Ecology were re-consulted.

4.1.5.5 [Third comment: No objection]

ECOLOGICAL IMPLICATIONS

Thank you for consulting this office on the above application.

Overall Recommendation:

☒ Application can be determined with no ecological objections (with any informatives/conditions listed below).

Summary of Advice:

- Bat informative.

Supporting documents:

- Bat Survey Report (NRG Consulting, August 2025).

Comments: Advice in our letter dated 11/06/2025 still stands, however the below will supersede our previous objection relating to bats.

Subsequent to our letter dated 06/08/2025, a bat emergence survey was conducted in August 2025. In line with the Bat Conservation Trust Guidelines (2023) for buildings with moderate potential, two dusk emergence surveys at the appropriate time of year have now been carried out. No bats were seen emerging from the building on either survey.

In the unlikely event that bats are found during the works, I advise the following informative should be added to any permission granted:

"If bats or evidence of them are discovered during the course of works, work must stop immediately, and advice sought on how to proceed lawfully from an appropriately qualified and experienced Ecologist or Natural England to avoid an offence being committed."

4.1.6 TRDC Tree and Landscape Officer: [Objection]

4.1.6.1 [First comment: No objection]

No objection in principle to this, however further information on the landscaping of the front garden following development will be needed, particularly the landscaping around the protected trees.

4.1.6.2 Officer comment: In light of the Landscape Officer comments in relation to landscaping around the protected trees, and in view of the level changes affecting the front of the site, additional concerns were raised with the agent. Officers were unclear as to whether the engineering operations required would put existing trees along the boundary with Charlotte House at risk and further clarification was sought in relation to retaining walls. Officers were also concerned regarding the extent of hardstanding around the protected trees.

In response, the applicant provided amended plans and an updated arboricultural method statement. The applicant advised that the level of soft bedding around trees T2 and T3 would be sufficient to allow them to develop. The Landscape Officer was re-consulted in relation to the updated information and the following comments were received:

4.1.6.3 [Second comment: Objection]

Further to my previous comments, I do not think the additional plans overcome the concerns regarding the long-term prospect for the trees, allowing sufficient space for their future growth and the impact on them from the extent of hard standing which appears to substantially exceed the 20% advised in BS5837. Even though the swept path analysis indicates that the cars can enter and exit the site, the constrained nature of the front garden for substantial numbers of cars, will lead to a degradation of the tree cover on the front boundary over the long term. Refusal is recommended as the existing trees are unlikely to be able to grow to maturity without causing undue problems of visibility, shading or damage

and are likely to result in future requests for significant topping, lopping or felling, resulting in the loss or deterioration of protected trees.

The proposal is contrary to Policy DM6 of the Three Rivers Local Plan 2014

Recommend: Refusal

The submitted plans indicate that the trees to the front garden, protected by TPO, will be retained. However, the proposed landscaping plans indicate that their Root Protection Areas (RPA) will be significantly encroached upon. Even with use of 'no dig' surfacing the extent of hard surfacing and level build up will result in coverage well in excess of the 20% maximum, as stated in the British Standard, BS5837. The current car parking plan appears constrained, and the manoeuvring of vehicles would appear difficult and likely to lead with collisions with retained trees. Highways have advised the production of swept path analysis to demonstrate that vehicle movements can be safely carried out. However, this has not been produced, and if the hard surfacing were to be reduced for the benefit the RPAs of trees and allow for future growth, this would further restrict space for vehicle movements.

As a result, it is not feasible to retain a sufficient amount soft landscaping within the RPA of the trees, without significantly reducing the hard standing to a point where vehicle movements are impossible and the number of parking spaces need to be reduced. Refusal is recommended due to the lack of space to accommodate sufficient parking and vehicle movement space, without resulting in damage to protected trees and constraining the space for their long-term retention.

The proposal is contrary to Policy DM6 of the Three Rivers Local Plan 2014.

4.1.6.4 Officer comment: Officers clarified the above with the Landscape Officer as the comments note that a swept path analysis has not been produced, however, this has been produced. The Landscape Officer provided further clarification as follows:

4.1.6.5 [Third comment: Objection]

Further to previous comments, the additional plans do not overcome the concerns regarding the long-term prospect for the trees, allowing sufficient space for their future growth and the impact on them from the extent of hard standing which appears to substantially exceed the 20% advised in BS5837.

Even though the swept path analysis indicates that cars can enter and exit the site, the constrained nature of the front garden for substantial numbers of cars, will lead to a degradation of the tree cover on the front boundary over the long term. The provision of only five parking spaces for five, two bedroomed, flats would appear inadequate, particularly as there are parking restrictions on The Drive, and is likely to lead to double parking on the driveway, increasing the risk of damage to protected trees.

Refusal is recommended due to the lack of space to accommodate sufficient parking and vehicle movement space, without resulting in damage to protected trees and constraining the space for their long-term retention.

The proposal is contrary to Policy DM6 of the Three Rivers Local Plan 2014.

4.2 Public/Neighbour Consultation

4.2.1 Number consulted: 6

4.2.2 No of responses received: 158 (some residents have made more than one comment)

4.2.3 Site Notice: Expiry: 31 March 2025

4.2.4 Summary of Responses

Character

In conflict with NPPF policies.

The development is out of character as the street is characterised by single dwellinghouses. Will set a precedent for the area which would alter the character of the residential area.

The development of five flats would be disproportionate to the size and character of the existing site and surrounding area.

A three -storey block plus roof height is not suitable for this area.

Bulk and mass of the proposed building is out of character. The flats are not in keeping with the architectural style and character of the surrounding area.

The proposal is excessive density or overuse of the site leading to cramped conditions. The site is smaller than others in the vicinity.

Will result in the removal of trees which will impact on the natural beauty of the area.

Trees have been cut down.

Loss of valuable green space which contributes to the character of the street and provides environmental benefits.

Proposal will degrade the sylvan character of the Drive which has TPOS.

Building is not in keeping with the existing architectural style.

Insufficient amenity space.

Will lead to cramped living conditions.

Privacy and Amenity

Would increase overlooking of the adjacent school which causes safeguarding concerns.

Noise from residents will impact on the educational environment

Air quality would be affected which would impact on pupils at the school, proximity of outdoor play area and learning areas to the development.

Bulk and mass will cause overshadowing

Overlooking to Valley Road.

Services

The development will put additional strain on local services such as school, healthcare. Drainage, local amenities such as Chorleywood Common and public transport which are already at or near capacity.

No nearby walking facilities for children such as playgrounds, schools, etc so the only way to get there is by car causing traffic issues

Insufficient sewage capacity

Access and Car parking

Already traffic issues in the area as when traffic from Chorleywood backs up and diverts onto The Drive and surrounding roads.

Majority of residents park cars on the driveway which keeps the road safe and free from accidents.

The lack of car parking on the blind corner creates a hazard and risk of collisions. The development will increase the likelihood of collisions

There are currently restrictions on parking times during the day, and this will create issues with parking.

Additional dropped kerb next to school is unsafe.

Development would require cars to reverse out onto their drive which would be unsafe for passing cars and pedestrians

Development will compromise the safety of children attending the school.

Parking spaces are not of sufficient size as per comments from Highways Officer who notes that there is not 6m behind each bay.

Concerns with visibility due to location of site on a sharp bend.

Current plans are crossing the zig zag keep clear signs currently present for children safety.

High Close is a narrow single tract road on which parking is not possible on either side.

There are not 18 spaces available on High Close as set out in the Parking Survey. Parking on High Close would cause issues for emergency vehicles and other safety issues. The parking survey conducted is not a fair reflection. It was done in the early hours of the morning and not at school drop off time. In addition, it does not take into account the impact of the weather.

Note that parking survey states there is ample parking on The Climb but this is not the case. We would ask the Council to apply single yellow line parking restrictions to adjacent roads. Buses at RMS are not adequate reason to reduce parking as the access to Chorleywood Road is via a steep access which is not viable for many residents.

Parking of contractors during construction would have a severe impact on peak traffic.
No construction management plan

Wildlife

The bat survey needs to be repeated at the correct time of the year.

Swift bricks are required

Habitats are being destroyed.

Other Issues

Amended plans do not address previous objections.

Not re-consulted on amended plans.

Paving will increase surface water run off.

Issues raised in relation to the company Ealing Developers Ltd, a company under the control of the applicant.

There would be a need for more bins which would lead to blocked pathways on collection days.

There are covenants which prohibit the construction of flats on the land.

Unnecessary demolition of an existing habitable home further contributes to environmental waste and disruption.

Economic analysis presented is incomplete and has missing data.

Objection to content of viability report, and that this may impact on positive contributions to local affordability

Luxury flats will not be affordable for first time buyers.

A check should be made from the planning archives on the initial application from around October 1975 or March 1978. This may provide good reason for a small property.

Development is legally, environmentally, and socially indefensible and leaves the committee open to legal challenge.

- 4.2.5 Officer comment: Covenants are not a material planning consideration and are a civil/legal matter.

There is no such thing as a precedent in planning terms, and each site is assessed on its own individual merits.

With regard to the impact on healthcare, and schools, the application does not constitute a major planning application, and as such the LPA is unable to seek infrastructure related contributions. However, it is noted that the development would be CIL Liable.

With regard to the issues raised in relation to the development company, this is not a material planning consideration.

5 Reason for Delay

- 5.1 Ongoing discussions to try to resolve areas of concern.

6 Relevant Planning Policy, Guidance and Legislation

- 6.1 National Planning Policy Framework and National Planning Practice Guidance

In December 2024 the National Planning Policy Framework was revised. This is read alongside the National Planning Practice Guidance (NPPG). The determination of planning applications is made mindful of Central Government advice and the Local Plan for the area. It is recognised that Local Planning Authorities must determine applications in accordance with the statutory Development Plan, unless material considerations indicate otherwise, and that the planning system does not exist to protect the private interests of one person against another. The 2024 NPPF is clear that “existing policies should not be considered out-of-date simply because they were adopted or made prior to the publication of this Framework. Due weight should be given to them, according to their degree of consistency with this Framework”.

The NPPF states that ‘good design is a key aspect of sustainable development, creates better places in which to live and work and helps make development acceptable to communities’. The NPPF retains a presumption in favour of sustainable development. This applies unless any adverse impacts of a development would ‘significantly and demonstrably’ outweigh the benefits.

6.2 The Three Rivers Local Plan

The application has been considered against the policies of the Local Plan, including the Core Strategy (adopted October 2011), the Development Management Policies Local Development Document (adopted July 2013) and the Site Allocations Local Development Document (adopted November 2014) as well as government guidance. The policies of Three Rivers District Council reflect the content of the NPPF.

The Core Strategy was adopted on 17 October 2011 having been through a full public participation process and Examination in Public. Relevant policies include Policies PSP1, CP1, CP3, CP4, CP9, and CP12.

The Development Management Policies Local Development Document (DMLDD) was adopted on 26 July 2013 after the Inspector concluded that it was sound following Examination in Public which took place in March 2013. Relevant policies include DM1, DM4, DM6, DM7, DM9, DM12, DM13 and Appendix 5.

The Chorleywood Neighbourhood Plan (2020). Policies 2, 3 and 5 are relevant.

6.3 Other

The Community Infrastructure Levy (CIL) Charging Schedule (adopted February 2015).

The Localism Act received Royal Assent on 15 November 2011. The growth and Infrastructure Act achieved Royal Assent on 25 April 2013.

The Wildlife and Countryside Act 1981 (as amended), the Conservation of Habitats and Species Regulations 2010, the Natural Environment and Rural Communities Act 2006 and the Habitat Regulations 1994 may also be relevant.

The Environment Act

7 **Planning Analysis**

7.1 Principle of Demolition

- 7.1.1 The existing detached residential dwelling is not statutorily listed, nor is the site located within a Conservation Area. As such, there is no objection raised to the principle of demolition of the existing dwelling.

- 7.1.2 It is noted that Chorleywood Parish Council have raised concerns regarding the demolition of a habitable dwelling. Whilst these concerns are acknowledged, this would not be a reason to refuse planning permission.
- 7.2 Principle of Development
- 7.2.1 The proposed development would result in a net gain of four residential dwellings. The site is not identified as a housing site in the Site Allocations Document and therefore would be considered as a windfall site. However, as advised in this document where a site is not identified for development, it may still come forward through the planning application process where it will be tested in accordance with the relevant national and local policies.
- 7.2.2 Chapter 11 of the NPPF promotes the efficient use of land and sets out *that 'planning policies and decisions should promote an effective use of land in meeting the needs for homes and other uses, whilst safeguarding the environment and ensuring safe and healthy living conditions'*. In addition, paragraph 125 of the NPPF emphasises that planning policies and decisions should:
- c) give substantial weight to the value of using suitable brownfield land within settlements for homes and other identified needs, proposals for which should be approved unless substantial harm would be caused, and support appropriate opportunities to remediate spoiled, degraded, derelict, contaminated or unstable land.*
- 7.2.3 Policy CP2 of the Core Strategy advises that in assessing applications for development not identified as part of the District's housing land supply including windfall sites, applications will be considered on a case by case basis, having regard to:
- i. The location of the proposed development, taking into account the Spatial Strategy
 - ii. The sustainability of the development and its contribution to meeting local housing needs
 - iii. Infrastructure requirements and the impact on the delivery of allocated housing sites and
 - iv. Monitoring information relating to housing supply and the Three Rivers Housing targets.
- 7.2.4 The application site is located in Rickmansworth which is identified as the Principal Town in the Three Rivers Settlement hierarchy. Policy PSP1 states that development in Rickmansworth will 'focus future development predominantly on sites within the urban area, on previously developed land'. In addition, it sets out that development in the Principal Town will 'provide approximately 15% of the District's housing requirements over the plan period'. Policy 3 of the Chorleywood Neighbourhood Plan is also relevant and notes that development on brownfield land will be encouraged. In addition, it states *that 'development proposals resulting in a net increase in housing density on an accessible site will be encouraged only if they include necessary infrastructure to support the development including utilities, parking and amenity space to create a sustainable development'*.
- 7.2.5 Annexe 2 of the NPPF defines previously developed land and excludes land in built up areas such as residential gardens. It is acknowledged that the proposed development would project further into the site than the existing built form and therefore would result in some encroachment onto existing garden land. However, notwithstanding this, part of the site would be considered to be previously developed land and is within the defined Principal Town, within an urban area. As such, there is no in principle objection to residential development of the application site in the context of Policy CP2, subject to consideration against all other material considerations as set out within this report.
- 7.2.6 An objection received notes that there are covenants on the land which restrict the development of flats. However, the presence of covenants is a legal matter, and is not a material planning consideration.

7.3 Housing Mix

- 7.3.1 Policy CP3 of the Core Strategy sets out that the Council will require housing proposals to take into account the range of housing needs as identified by the Strategic Housing Market Assessment (SHMA) and subsequent updates. The need set out in the Core Strategy is 30% one-bedroom units, 35% two-bedroom units, 34% three-bedroom units and 1% four bedroom and larger units. and type of dwellings as identified by the Strategic Housing Market Assessment (SHMA). However, most recent version of the Local Housing Needs Assessment (LNHA) was finalised in 2024 and is the most recent update to the SHMA. The recommended mix for Three Rivers in terms of market housing, affordable home ownership and social/affordable rented housing identified in the LNHA is shown below:

	1 Bedroom	2 Bedroom	3 Bedroom	4+ Bedroom
Market Housing	4%	21%	42%	32%
Affordable Home Ownership	19%	39%	30%	13%
Social/Affordable Rented Housing	20%	32%	35%	12%

- 7.3.2 In this case, the applicant is proposing the provision of 2 x 3 bedroom flats, and 3 x 2 bedroom flats which would not accord with the above guidance. However, given the scale of the development, it is not considered that this would prejudice the ability of the Council to deliver housing targets and therefore it is not considered reasonable to raise an objection. The proposed development is therefore considered acceptable and in accordance with Policy CP3 of the Core Strategy (adopted October 2011).

7.4 Affordable Housing.

- 7.4.1 Appendix A of this report sets out the position of the Council and evidence relating to the application of the affordable housing threshold in Policy CP4 of the Core Strategy.
- 7.4.2 The proposed development would result in a net gain of 4 residential dwellings and as such, the development would be liable for a commuted sum payment in respect of affordable housing. The site is within Highest Value Three Rivers market area where the payment would be £1250 per square metre of habitable floor space. It has been calculated that based upon a habitable floor space of approximately 194 metres (average) that a policy compliant contribution of £242,500 would be required (this would also be subject to indexation).
- 7.4.3 A Viability Assessment was submitted with the application and sets out that an affordable housing contribution would not be viable. This has been subject to assessment by an independent assessor on the LPA's behalf who concludes that the 'appraisal carried out which includes the benchmark land value of £1,000,000 and the required affordable housing payment of £242,500 shows a deficit negative of £529,866. As such, the proposed development would not be viable to support an affordable housing contribution. Consequently, no objections are made in this regard and the development accords with Policy CP4 of the Core Strategy (2011).

7.5 Streetscene & Character

- 7.5.1 Policy CP1 of the Core Strategy (adopted October 2011) seeks to promote buildings of a high enduring design quality that respect local distinctiveness and Policy CP12 of the Core Strategy (adopted October 2011) relates to design and states that in seeking a high standard of design the Council will expect development proposals to 'have regard to the local context and conserve or enhance the character, amenities and quality of an area'. Development should make efficient use of land but should also respect the 'distinctiveness of the surrounding area in terms of density, character, layout and spacing, amenity, scale, height, massing and use of materials'; 'have regard to the local context and conserve or enhance the character, amenities and quality of an area' and 'incorporate visually attractive

frontages to adjoining streets and public spaces'. Paragraph 135 of the NPPF relates to design and sets out that planning decisions should *'sympathetic to local character and history, including the surrounding built environment and landscape setting, while not preventing or discouraging appropriate innovation or change (such as increased densities)*.

7.5.2 In terms of new residential development, Policy DM1 of the Development Management Policies LDD advises that the Council will protect the character and residential amenity of existing areas of housing from forms of 'backland', 'infill' or other forms of new residential development which are inappropriate for the area. Development will only be supported where it can be demonstrated that the proposal will not result in:

- i. Tandem development;
- ii. Servicing by an awkward access drive which cannot easily be used by service vehicles;
- iii. The generation of excessive levels of traffic
- iv. Loss of residential amenity
- v. Layouts unable to maintain the particular character of the area in the vicinity of the application site in terms of plot size, plot depth, building footprint, plot frontage width, building frontage line, height, gaps between buildings and streetscape features (eg hedges, walls, grass verges etc).

7.5.3 The Chorleywood Neighbourhood Plan is also relevant. Policy 2 of this document sets out that 'all development should seek to make a positive contribution to the streetscene by way of frontage, building line, scale and design'. In addition, it sets out that 'development proposals should seek to maintain local distinctiveness through the built environment, in terms of buildings and public spaces, and enhance the relationships and linkages between the built and natural environment'. Policy 5 of the Chorleywood Neighbourhood Plan is also relevant and advises that *'flatted development will be accepted if built in close proximity to public transport and other locations that are sustainable and near arterial roads (where it can be demonstrated the living conditions of the occupiers will be satisfactory). Flatted development will usually be limited to three storeys in height unless it can be clearly demonstrated that the proposal would be visually satisfactory in its context taking account of the topography and character of the surrounding area'*.

7.5.4 The Drive and the surrounding roads are generally characterised by single detached dwellings located on large plots with generous spacing between dwellings. Consequently, it is acknowledged that the proposal to provide flats in this location would not necessarily be characteristic of the locality and would result in an increased density on this site. However, the front elevation has been designed to have the appearance of a single residential dwelling, with one entrance door located centrally providing access for residents. Whilst the building is acknowledged to be large, given the scale of surrounding residential dwellings and their varied design it is not considered that a flatted development in this location can be objected to in principle, particularly given the design approach taken. Furthermore, it is noted that the site is located on a section of the road which is not wholly residential in character as it is located directly adjacent to Charlotte House Prep School, which has a materially different character to the existing residential dwellings in the locality. As such, given that the building has been designed to appear as a single residential dwelling, it is not considered that it would incongruous.

7.5.5 In terms of siting, the proposed building would front The Drive and as such would not constitute a tandem form of development. The proposed block plan indicates that the proposed building would sit forward of the existing residential dwellings to the west, and the adjacent building at Charlotte House. However, the building line on The Drive is irregular and as such, it is not considered that the building would appear unduly prominent in this regard, particularly given it would be located at a lower land level relative to the adjoining highway. Appendix 2 of the Development Management Policies LDD provides further guidance on siting, and notes that the first floor flank walls should be positioned a minimum of 1.2m from the flank boundary, however, this distance should be increased in lower

density areas. In this case, the plans indicate that the building would be positioned approximately 1.5m from the boundary with Charlotte House, and approximately 2m from the boundary with no.78. As such, it is considered that appropriate spacing would be retained, in keeping with the character and appearance of the streetscene.

- 7.5.6 Whilst objections have been received by residents in relation to the height of the building, a streetscene drawing has been submitted which demonstrates the ridge height of the proposed building would be lower than both neighbouring buildings and therefore this would prevent the building from being unduly prominent in terms of height. As set out above, the building has been designed to appear as a single residential dwelling from the frontage with the entrance door located centrally. The front elevation of the building would be two-storey in appearance, however, due to the nature of the levels, the plans indicate that only the first-floor element and roof would be readily visible from the front elevation. In terms of the design, the dwelling would have a gabled roof form with two gabled projections located to either side of the dwelling. The submitted information indicates that the building would have a white rendered finish with elements of timber cladding located adjacent to the proposed windows with cladding also installed centrally. Given the varied nature of the streetscene, no objection is raised to the design and proposed external finishes. However, were the development to be viewed as acceptable, a condition could be added requiring full details of external finishes (including digital samples) to be submitted via a condition.
- 7.5.7 Some concerns have been raised by residents, in relation to the scale of the building and that it would be uncharacteristic of the surrounding area. It is noted that due to the land levels, the building would have a three storey appearance to the rear by reason of the provision of a lower ground floor level. This would not be discernible from the front elevation, and as such would not be considered harmful to the visual amenities of the streetscene. It is also noted that the building would be relatively deep by reason of the hipped roofed projection to the rear. However, this would be read against the neighbouring dwellings no.78 and 76 which have deep flank elevations and consequently this would not be uncharacteristic. It is also considered that the hipped roof proposed here acts to minimise the overall bulk and massing. As such, it is considered that the scale of the building would be comparable to others within the vicinity and therefore would not be incongruous in this regard.
- 7.5.8 To the rear, the garden would be used as a communal amenity space and would not be subdivided into individual spaces. Consequently, this would be in keeping with the wider character of the locality where long, rearward gardens are prevalent.
- 7.5.9 Alterations are also proposed to the frontage including the provision of a new vehicular access to create a carriage driveway. This would result in the removal of some vegetation and in addition, the levels would be built up in order to provide a level car parking area for future occupiers. As such, it is acknowledged that there would be an increase in hardstanding on the site. However, there are many residential dwellings within the vicinity with extensive areas of hardstanding. In this case, the proposal would be read next to Charlotte House which has a large area of hardstanding extending across its site which therefore further prevents the development appearing incongruous. Whilst the land would be built up to provide car parking, given that the land levels vary in the vicinity, it is unlikely that this would be unduly prominent in the streetscene. Full details of the surfacing could be required by condition if the development was considered to be acceptable.
- 7.5.10 In summary, it is considered that whilst flats are not characteristic within the locality, the design of the building would ensure that it appears more akin to a single residential dwelling, particularly given that it would be located at a lower land level to the highway. In addition, no objection is raised to the proposed design of the building given the varied nature of buildings in the locality. Consequently, subject to conditions, the development is considered to be acceptable and in accordance with Policies CP1 and CP12 of the Core Strategy, Policy DM1 and Appendix 2 of the Development Management Policies LDD and Policy 2 of the Chorleywood Neighbourhood Plan.

7.6 Impact on amenity of neighbours

- 7.6.1 Policy CP12 of the Core Strategy advises that development proposals should 'protect residential amenities by taking into account the need for adequate levels and disposition of privacy, prospect, amenity and garden space'. Appendix 2 of the Development Management Policies LDD states that 'oversized, unattractive, and poorly sited development can result in loss of light and outlook for neighbours and detract from the character and appearance of the streetscene'
- 7.6.2 The plans indicate that the proposed building would sit forward of the neighbouring residential dwelling (No.78). However, this neighbour is set in from the boundary and thus given the separation, it is not considered that this would result in an overbearing form of development in relation to this neighbour. Likewise, although the building sits forward of the adjacent school buildings, the submitted streetscene indicates that the building would have a lower ridge line and again the separation between the buildings would ensure that it would not be unduly prominent or overbearing in this regard. It is not considered that the building would be overbearing or prominent in relation to neighbours opposite due to the separation by the highway and that the building itself would sit at a lower level in relation to the highway.
- 7.6.3 With regard to two storey development, Appendix 2 of the Development Management Policies LDD notes the following:
- Rear extensions should not intrude into a 45 degree splay line drawn across the rear garden from a point on the joint boundary, level with the rear wall of the adjacent property. This principle is dependent on the spacing and relative positions of the dwellings and consideration will also be given to the juxtaposition of properties, land levels and the position of windows and extensions on neighbouring properties. See Figure 1 for illustrative examples.*
- 7.6.4 With regard to Charlotte House, the plans indicate that the gabled element of the roof form would intrude the 45 degree by approximately 0.6m and the two storey projection would intrude the 45 degree line by approximately 1.5m. Given the use of the adjacent site and the modest nature of the intrusion at the point nearest to the boundary, it is not considered that significant adverse harm would occur to justify refusal for this reason. The plans do not indicate an intrusion from the adjacent residential dwelling.
- 7.6.5 It is noted that some of the objections raise concerns regarding the redevelopment of the site for flatted development, in particular, that the proposal would result in overlooking to Charlotte House, an existing school. These concerns are acknowledged, however, Charlotte House is located in an established residential area and is already located immediately next to a residential dwelling. Furthermore, it is not unusual for residential developments to be located immediately adjacent to school sites. Whilst it is acknowledged that the use of the site would be intensified, it is not considered that this would result in increased harm to justify refusal on this basis. In addition, there are no windows proposed in the flank elevations facing towards Charlotte House. It is acknowledged that the rear facing windows would have some outlook towards Charlotte House, however, this would not be significantly different from the existing situation and furthermore, it is again emphasised that it is not unusual for schools to be located next to residential developments. Consequently, it is not considered that a reason for refusal can be substantiated on this basis.
- 7.6.6 The plans indicate the provision of a terrace serving Flat 3, which would be set at first floor level (due to the nature of the land levels on site). Some concern was raised during the course of the application in relation to overlooking to Charlotte House School. In response, the applicant has provided a privacy screen with a maximum height of 2.1m which would minimise overlooking impact to Charlotte House. In addition, the amended plans illustrate the provision of 2m high fencing along this boundary.

- 7.6.7 A number of windows are proposed facing towards the adjacent residential dwelling. However, given the nature of the rooms they serve, including kitchens, bathrooms and an office, it is considered that if the development were acceptable, they could be conditioned to be obscure glazed and top vent opening only. Residents to the rear of the site on Valley Road have raised concern in relation to overlooking. Appendix 2 of the Development Management Policies LDD sets out that a back- to -back distance of 28m is required between residential dwellings although states *that 'distances should be greater between buildings in excess of two storeys (especially dwellings/flats) with elevations which directly face one another or in situations where there are level differences involved'*. The .T residential neighbours located on Valley Road are located in excess of 90m from the rear boundary of the application site which is ample to prevent any harm to these neighbouring dwellings.
- 7.6.8 In summary, the proposed development is considered acceptable and in accordance with Policies CP1 and CP12 of the Core Strategy and Policy DM1 and Appendix 2 of the Development Management Policies LDD.
- 7.7 Quality of accommodation for future occupiers.
- 7.7.1 Appendix 2 of the Development Management Policies sets out amenity space standards for residential developments and states the following:
- Flats: One bed- 21 square metres
Additional bedrooms: 10 square metres (space can be allocated specifically to each flat or communally).
- 7.7.2 The proposed development would therefore generate a requirement for 175 square metres of amenity space. In this case, the proposed amenity space would mainly take the form of a communal garden with an area of over 400 square metres which would therefore be sufficient for a development of this size. It is also noted that the lower ground floor flat (flat 1) and one of the ground floor flats (flat 3) would also benefit from individual amenity spaces. Consequently, it is considered that there is sufficient amenity spaces available for use by future occupiers of the site.
- 7.7.3 With regard to the accommodation itself, no objection is raised. However, it is noted that ground floor bedroom windows in the front elevation serving flats 2 and 3 as these windows would be located in close proximity (approximately 2m) to the retaining wall for the proposed parking area, with the parking area being located at a higher level in relation to these windows. Although the relationship is acknowledged, it is noted that these windows do not serve the main primary living accommodation and that future buyers would be aware of the situation. Furthermore, the plans indicate that the open plan kitchen/living rooms would be located to the rear and would have outlook over the rear amenity space.
- 7.7.4 In addition, some concerns were raised in relation to the privacy of the ground floor windows, as residents would pass by the ground floor bedroom windows in order to access the communal amenity space and bike stores to the rear. In response, the applicant has provided an amended plan which includes a gate adjacent to the front door which would prevent occupiers passing the bedroom windows of flat 3. However, residents could still pass by the front windows of flat 2 in order to access the rear of the site. In order to protect the privacy of future residents, the amended plans include the provision of reflective glass to the front window serving the ground floor bedroom of unit 2. The use of reflective glass means that the privacy of the future occupier would be maintained, whilst providing a view out for the future occupier. It is considered that this would be an appropriate solution and a condition could be added requiring full details to be submitted and approved in writing by the Local Planning Authority in the event that the application was viewed as acceptable.
- 7.7.5 With regard to accessibility, the amended plans have also included cycle ramps to ensure that bikes can be easily moved from the storage areas up to the level of the highway. This

is considered to be an acceptable solution and furthermore, future occupiers would be aware of the nature of the land levels on this site.

- 7.7.6 In summary, although the nature of the outlook to the ground floor bedroom windows at the front of the building is acknowledged, it is considered that future occupiers would be aware of the situation. Furthermore, the primary living areas are all considered to benefit from ample outlook and light and thus no objections are raised in this regard. The development is therefore concluded to be acceptable and in accordance with Policy CP12 of the Core Strategy and Policy DM1 and Appendix 2 of the Development Management Policies LDD.

7.8 Trees and Landscaping.

- 7.8.1 Policy DM6 of the Development Management Policies LDD relates to 'Trees, Woodlands and Landscaping'. This sets out that the following:

- i) Proposals for new development should be submitted with landscaping proposals which seek to retain trees and other important landscape and nature conservation features. Landscaping proposals should also include new trees and other planting to enhance the landscape of the site and its surroundings as appropriate.*
- ii) Development proposals on sites which contain existing trees and hedgerows will be expected to retain as many trees and hedgerows as possible, particularly those of local amenity or nature conservation value or hedgerows considered to meet the criteria of the Hedgerow Regulations 1997.*
- iii) Development proposals should demonstrate that existing trees, hedgerows and woodlands will be safeguarded and managed during and after development in accordance with the relevant British Standards*
- iv) Development should be designed in such a way as to allow trees and hedgerows to grow to maturity without causing undue problems of visibility, shading or damage*

- 7.8.2 The application site is heavily vegetated at present, and it is noted that this is characteristic of The Drive which has a largely sylvan character. The application site is subject to a Tree Preservation Order, TPO741 (The Drive, Chorleywood) 2010, which affords protection to the existing trees on site. At present, the site is served by an existing single vehicular access which provides access to a driveway which slopes steeply down to the existing attached garage. There are areas of greenery to the front of the site and set forward of the existing dwelling.

- 7.8.3 Whilst it is acknowledged that the Landscape Officer originally raised no objection to the proposed development, this was subject to further information relating to landscaping, in particular in relation to soft landscaping around protected trees. Given this requirement, concerns were expressed by officers regarding the potential impact to existing protected trees. It was noted that the works to the frontage would result in significant alterations to the land levels, and the need for retaining walls and additional hard surfacing closer to the trees. It was therefore unclear as to how this would impact on protected trees. In addition, officers noted that the existing protected trees would have more vehicles passing around them and closer to them than existing. As such, it was unclear as to whether any further measures would be required to ensure their protection from operational vehicles, for example from residents reversing into the trees as they try to manoeuvre out of the site. Officers expressed concerns that the relationship between the parking area and trees, could lead to pressure from residents for tree works due to inability to manoeuvre easily on the site. Those pressures, and the potential loss of the trees or their amenity value, would be contrary to Policy DM6 of the Development Management Policies LDD. Officers therefore suggested that further information would be required, including swept path drawings which could demonstrate that the parking arrangements work and that residents would be able to manoeuvre around trees.

- 7.8.4 In response to the concerns raised, an updated Arboricultural Method Statement was provided. In addition, the amended plans indicate that the parking bays would be relocated

and set further from the trees and closer to the building. The Landscape Officer was re-consulted in relation to the updated information, however, considers that the submitted information fails to overcome the concerns raised. The Landscape Officer has noted that the proposals fail to secure the long-term protection of the trees and would not allow sufficient space for their future growth. In addition, there would be an impact on them from the extent of hardstanding which appears to substantially exceed the 20% advised in BS5837. The Landscape Officer notes that even with the use of 'no dig' surfacing, the extent of hardstanding and level build up will result in coverage significantly in excess of the 20% standard as set out in the British Standard, BS5837. Consequently, the proposed development would be contrary to Policy DM6 of the Development Management Policies LDD.

7.8.5 Furthermore, whilst it is acknowledged that the swept path analysis indicates that vehicles could enter and exit the site, the constrained nature of the front garden for cars, is likely to lead to a degradation of the tree cover on the front boundary in the long term. The Landscape Officer considers that the existing trees would be unlikely to be able to grow to maturity without impacting visibility. Similarly there are concerns that they would result in shading or damage which would likely to lead to further requests for significant topping, lopping or felling.

7.8.6 In summary, the proposed development by reason of the alterations to the frontage would result in significant encroachment into the root protection areas of existing protected trees. Consequently, the proposed development would fail to allow sufficient space for future growth. Furthermore, the relationship between the car parking bays and existing trees will likely lead a degradation of tree cover on the front boundary over the long term. The existing trees are unlikely to be able to grow to maturity without impacting visibility or resulting in shading or damage and are likely to result in future requests for significant topping, lopping or felling, resulting in the loss or deterioration of protected trees. The loss of protected trees would impact on the sylvan character of the streetscene and thus would be detrimental to the visual amenities of the locality, contrary to Policy CP12 of the Core Strategy and Policy DM6 of the Development Management Policies LDD.

7.9 Wildlife and Biodiversity

7.9.1 Section 40 of the Natural Environment and Rural Communities Act 2006 requires Local Planning Authorities to have regard to the purpose of conserving biodiversity. This is further emphasised by regulation 3(4) of the Habitat Regulations 1994 which state that Councils must have regard to the strict protection for certain species required by the EC Habitats Directive.

7.9.2 The protection of biodiversity and protected species is a material planning consideration in the assessment of applications in accordance with Policy CP9 of the Core Strategy (adopted October 2011) and Policy DM6 of the DMLDD. National Planning Policy requires Local Authorities to ensure that a protected species survey is undertaken for applications that may be affected prior to determination of a planning application.

7.9.3 Initial objections were raised by Herts Ecology in relation to bats. It was noted that the Bat Survey Report as originally submitted was undertaken in December 2024, which is outside of the bat activity period and was within the peak hibernation period. As such, an emergence survey during this time was considered insufficient and unlikely to give a true representation of whether this building is or has been utilised as a bat roost. As such, the information as initially submitted was considered insufficient.

7.9.4 Following this, further information was submitted by the applicant. However, this was still deemed insufficient by Herts Ecology as only one dusk emergence survey had been undertaken rather than two. Consequently, it was deemed that further information was still required in relation to the impact of the proposals on bats.

- 7.9.5 In response, the applicant then provided a second dusk emergence survey which noted that no bats were seen as emerging from the building on either survey. Herts Ecology have therefore withdrawn their objections and have advised that in the event of an approval, an informative should be required reminding the applicant of what to do if bats are found during the course of the development.
- 7.9.6 With regard to other protected species, the Ecology Officer noted that the Ecological Appraisal did not find any other protected species on site. As such, the comments received note that an informative in relation to wildlife should be added in the event of an approval. It is also noted that the Ecology Officer has advised that given suitable habitat within the vicinity, that enhancements should be included in the development plan. Consequently, in the event that the application was deemed acceptable, then a condition requiring the submission of a Species Enhancement Plan should be added as a condition.
- 7.9.7 Therefore, in summary, following the additional information received, it is not considered that the development would have an impact on any protected species and consequently, the development is considered to be acceptable in this regard and in accordance with Policy DM6 of the Development Management Policies LDD.
- 7.10 Mandatory Biodiversity Net gain.
- 7.10.1 Paragraph 13 of Schedule 7A of the Town and Country Planning Act 1990 sets out that every planning permission granted for the development of land in England shall be deemed to have been granted subject to the 'biodiversity gain condition' requiring development to achieve a net gain of 10% of biodiversity value. This is subject to exemptions as set out in The Biodiversity Gain Requirements (Exemptions) Regulations 2024.
- 7.10.2 In this case, a BNG Assessment accompanied the application and demonstrates the site's pre and post development unit values and demonstrates that the site would result in a 15.33% net loss in habitat and a 32.2% net gain in hedgerow units. As such, the scheme would not meet the 10% mandatory biodiversity net gain. No proposals have been submitted as part of the application for the provision for the 10% gain to be made on site. It is noted that the Biodiversity Gain Hierarchy and its effect for the purpose of the statutory framework for biodiversity net gain is set out in Articles 37A and 37D of the Town and Country Planning (Development Management Procedure) (England) Order 2015. This hierarchy (which does not apply to irreplaceable habitats) sets out a list of priority actions:
- *first, in relation to onsite habitats which have a medium, high and very high distinctiveness (a score of four or more according to the statutory biodiversity metric), the avoidance of adverse effects from the development and, if they cannot be avoided, the mitigation of those effects; and*
 - *then, in relation to all onsite habitats which are adversely affected by the development, the adverse effect should be compensated by prioritising in order, where possible, the enhancement of existing onsite habitats, creation of new onsite habitats, allocation of registered offsite gains and finally the purchase of biodiversity credits.*
- 7.10.3 As set out above, the Biodiversity Gain Hierarchy requires adverse effects to be compensated by prioritising enhancing existing habitats, then creating new habitats, and after that the allocation of off-site gains and biodiversity credits. In this instance, the development would result in the provision of private garden space for use by future occupiers and therefore the enhancement and creation of onsite habitats would not be appropriate as the LPA would not be able to monitor these in the future. As such, given the nature of the proposals it is considered that the purchase of off-site biodiversity credits is an appropriate means of securing a 10% net gain. Were the development to be considered acceptable, the LPA would then be required to consider the full detail when an application to discharge the Biodiversity Gain Plan condition was submitted. It is noted that Ecology Officer has commented that off-site solutions should be secured via a S106 agreement. However, in response, given the agreement would not be between the LPA and the

developer, a S106 agreement would not be required. The developer would be required to provide evidence of the purchase of off-site credits at the time of an application to discharge the mandatory condition

- 7.10.4 In summary, the development is considered acceptable in that the 10% biodiversity net gain would be secured off site and this would be evidenced as part of the discharge of the mandatory BNG condition. Consequently, no objections are raised in this regard.

7.11 Highways, Access and Parking

- 7.11.1 Access Arrangements: Paragraph 115 of the NPPF advises that ‘in assessing sites that may be allocated for development in plans or specific applications for development, it should be ensured that:

- a) sustainable transport modes are prioritised taking account of the vision for the site, the type of development and its location;
- b) safe and suitable access to the site can be achieved for all users.

- 7.11.2 Paragraph 116 of the NPPF advises that ‘development should only be prevented or refused on highway grounds if there would be an unacceptable impact on highway safety, or the residual cumulative impacts on the road network, following mitigation, would be severe, taking into account all reasonable future scenarios’.

- 7.11.3 Policy CP10 of the Core Strategy requires development to demonstrate that it will provide a safe and adequate means of access.

- 7.11.4 With regard to access, the existing dwelling is served by a single vehicular crossover, whereas the proposed development would include the creation of a second vehicular access. The Highways Officer raised an initial objection, noting that this would not be in accordance with Herts County Council policies. The consultee comments note that any additional access point is considered to be an additional conflict point between vehicles crossing the footway and pedestrians and means that the site gives priority to vehicles rather than pedestrians. Concerns were also raised by the Highways Officer in relation to the proposed parking arrangements. They advised that a swept path analysis drawing should demonstrate that vehicles would not be manoeuvring over the highway footway.

- 7.11.5 In response to the objection raised, the applicant submitted further information which was considered by Herts Highways. The Highways Officer subsequently withdrew their objection, noting that given the fact that the proposals are for more than one dwelling, there would not be sufficient grounds to raise an objection on the grounds of an additional access point. Nevertheless, the Highways Officer considered that a number of conditions were necessary including the submission of swept path analysis tracking to illustrate that cars would be able to use the car parking spaces, turn on site and egress in a forward gear. Any turning areas should not utilise the highway footway which is important given the location of the site as adjacent to an existing school. In response to the consultee comments, officers did not consider that it was appropriate for the above to be secured via a condition, and that this should be demonstrated prior to the grant of any permission for the site.

- 7.11.6 The applicant provided a further response in relation to the conditions required by Herts Highways and stated that it would not be possible for vehicles to turn on site and exit in a forward gear. However, the applicant set out that they did not consider that this was necessary given that The Drive is subject to a 30mph speed limit. In addition, the applicant notes that the County Council’s own policy states *‘that this is acceptable and is unacceptable where roadways are located on roads with speed limits for 40mph or above. In this instance, The Drive is 30mph and therefore there is no requirement for vehicles to manoeuvre within the site’*. Herts Highways were subsequently re-consulted in relation to the above comments.

- 7.11.7 In response, Herts Highways have advised that they raise no objection to the parking arrangement. The Highways Officer notes that the new vehicle crossover point closest to the school is designed to provide access to only three car parking spaces and that the number of movements associated with this number of parking spaces linked to a residential use would be low and not significant. Given this, and the availability of sufficient visibility for a 30mph speed limit and the requirement to provide sufficient vehicular to pedestrian visibility via a condition, the Highways Officer has confirmed that there would not be grounds from a highway safety perspective to recommend refusal of the application. It is emphasised that visibility splays would be required and a condition has been suggested should the LPA be minded to approve the application. As such, given the comments made by Herts Highways, it is considered that the proposed access arrangements and parking layout would be acceptable and would not have an impact on the safety or operation of the highway network in accordance with the provisions of the NPPF and Policy CP10 of the Core Strategy.
- 7.11.8 Car Parking: Policy DM13 and Appendix 5 of the Development Management Policies LDD sets out off street car parking requirements for developments and advises the following:
- 2 bedroom dwelling: 1.75 spaces (1 assigned)
- 3 bedroom dwelling: 2.25 spaces (2 assigned)
- 7.11.9 In this case, the following off street car parking provision would be required to be policy compliant:
- Lower ground floor: 1 x 2 bedroom flat = 1.75 spaces (1 assigned)
- Proposed ground floor: 1 x 2 bedroom flat= 1.75 spaces (1 assigned space)
1 x 3 bedroom flat= 2.25 spaces (2 assigned spaces)
- Proposed first floor: 1 x 2 bedroom= 1.75 spaces (1 assigned)
2 x 3 bedroom= 2.25spaces (2 assigned)
- Total: 9.75 spaces (7 assigned spaces)
- 7.11.10 The proposed development would provide 5 off street car parking spaces, thus providing 1 allocated car parking space per unit. As such, there would be a total shortfall of 4.75 spaces against the maximum standard and a shortfall of 2 assigned spaces. The development would therefore fail to be in accordance with Policy DM13 and Appendix 5 of the Development Management Policies LDD. However, on balance, no objections are raised for the following reasons. The proposed development would provide one allocated space per unit, and there would only be a shortfall of 2 assigned car parking spaces. The site is within a twenty minute walk of Rickmansworth Town Centre and its transport links and amenities. Officers note that the walking route is via a pavement containing street lighting and thus a safe route to services would be achievable. It is noted that an alternative route is also available via a footpath to Chorleywood Road, however, it is acknowledged that this would not be suitable for all pedestrians. It is also noted that the proposed development would provide cycle storage to the rear of the site, with the amended plans indicating ramped access for bikes to ensure that they can easily be manoeuvred on site by future occupiers.
- 7.11.11 It is noted that some of the objections received raise concerns in relation to parking and state that the shortfall in car parking would exacerbate car parking issues within the area and compromise the safety of children attending the school.. It is also noted that a car parking survey has accompanied the application and residents have raised objections to its contents, including that it was undertaken in the early hours of the morning. These concerns are noted, however, the applicant has advised that the parking survey was undertaken

during these hours as this was during a time when the highest number of residents would be at home. The parking survey undertaken has found that the on street parking stress within the area is low, and is at less than 10%. This is partly due to the fact that many residents within the vicinity benefit from existing driveways. However, officers do recognise, that there may be increased stress on both parking and traffic in the area at drop off and pick up times, which is the case for many schools within the locality.

- 7.11.12 In addition, officers note that due to the location of the site adjacent to the school, that there are parking restrictions operating at certain times of the day within the locality which means that future occupiers and visitors to the site would need to park on street further from the site if required. Residents have raised concerns that vehicles would be displaced to High Close which is a narrow road or to The Climb. Whilst these concerns are acknowledged, it is noted that other parts of The Drive are not covered by restrictions and therefore vehicles may park further into The Drive and future occupiers would not be reliant only on The Climb or High Close. In addition, the shortfall is not considered so significant that a large number of vehicles would be displaced to result in harm. Furthermore, it is emphasised that Herts Highways have raised no objection to the development from a highway safety perspective.
- 7.11.13 In summary, taking into consideration the comments received from Herts Highways, it is not considered that the proposed development would result in significant harm to the safety of the highway network or the free flow of traffic to justify refusal. With regard to car parking provision, the shortfall is acknowledged. However, for the reasons outlined above, it is considered that this would result in significant harm to justify refusal of the application. Whilst officers acknowledge that there is traffic and parking stress in the area associated with school pick up and drop off times, the shortfall in car parking would not result in increased demonstrable harm to justify refusal. The proposed development is considered to be acceptable and in accordance with Policy CP10 of the Core Strategy and Policy DM13 and Appendix 5 of the Development Management Policies LDD. .

7.12 Energy Efficiency

- 7.12.1 Policy CP1 of the Core Strategy requires the submission of an Energy and Sustainability Statement demonstrating the extent to which sustainability principles have been incorporated into the location, design, construction and future use of proposals and expected carbon emissions.
- 7.12.2 Policy DM4 of the Development Management Policies LDD requires applicants to demonstrate that development will produce 5% less carbon dioxide emissions than Building Regulations Part L (2013) requirements having regard to feasibility and viability, This may be achieved through a combination of energy efficiency measures, incorporation of on site low carbon and renewable technologies, connection to a local, decentralised, renewable or low carbon energy supply.
- 7.12.3 An Energy Report has accompanied the application and sets out that the proposed development would achieve a 59.61% less carbon emissions relative to Building Regulations Part L (2022) and therefore would exceed the requirements set out in Policy DM4 of the Development Management Policies LDD. The report sets out that this would be achieved through the design of the external elements of the building and through the use of an air source heat pump. It is noted that full details of the air source heat pump have not been provided with the application, and therefore, if the development was considered to be acceptable, full details of its siting and any necessary mitigation measures in relation to noise would be required via a condition.

7.13 Refuse and Recycling

- 7.13.1 Policy DM10 (Waste Management) of the DMLDD advises that the Council will ensure that there is adequate provision for the storage and recycling of waste and that these facilities are fully integrated into design proposals. New developments will only be supported where:

- i) The siting or design of waste/recycling areas would not result in any adverse impact to residential or work place amenity
- ii) Waste/recycling areas can be easily accessed (and moved) by occupiers and by local authority/private waste providers
- iii) There would be no obstruction of pedestrian, cyclists or driver site lines.

7.13.2 The plans indicate the provision of bin storage located adjacent to the boundary with no.84. It is assumed that kerb side collection would be required as is the existing situation and no objection is raised. Were the development to be considered acceptable, a full waste and recycling strategy could be secured via a condition. This would be required to ensure that the bins did not obstruct access or the adjoining highway on collection days.

7.14 Planning Balance

7.14.1 The LPA cannot currently demonstrate a 5-year housing land supply, and therefore paragraph 11 of the NPPF (2024) is engaged. Paragraph 11 and footnote 8 clarifies "this includes, for applications involving the provision of housing, situations where: the local planning authority cannot demonstrate a five year supply of deliverable housing sites". The most important policies for determining a housing application are considered to be Policies CP2 (Housing Supply) and Policy CP3 (Housing Mix and Density). In the context of decision-taking Paragraph 11 continues,

"Plans and decisions should apply a presumption in favour of sustainable development b) strategic policies should, as a minimum, provide for objectively assessed needs for housing and other uses, as well as any needs that cannot be met within neighbouring areas, unless...

i. the application of policies in this Framework that protect areas or assets of particular importance provides a strong reason for restricting the overall scale, type or distribution of development in the plan area; or

ii. any adverse impacts of doing so would significantly and demonstrably outweigh the benefits, when assessed against the policies in this Framework taken as a whole."

7.14.2 Therefore, the tilted balance exercise requires planning permission to be granted unless any adverse impact of doing so would significantly and demonstrate outweigh the benefits.

7.14.3 The NPPF identifies that there are 3 dimensions to sustainable development: social, economic and environmental. The development would make a moderate contribution towards making up the shortfall in housing in the district, by adding four dwellings to the overall housing supply. There would also be some limited economic benefits from the construction activities and the future occupiers' ability to assist in supporting local settlements by using nearby amenities, albeit this would be limited.

7.14.4 However, the above analysis has identified that the proposed development by reason of the alterations to the frontage would result in significant harm to trees which are protected by an existing tree preservation order. The extent of encroachment into the RPA by more than 20%, means that the trees would be unable to develop to maturity. Furthermore, whilst technically, vehicles would be able to enter and exit the site, the constrained nature of the frontage and its use will likely lead to a degradation of tree cover along the frontage and result in future pressure for significant topping, lopping and felling. This would significantly impact on the sylvan character of The Drive and the visual amenities of the wider locality. The harm is considered to be significant. It is therefore considered that the adverse impacts of granting would significantly and demonstrably outweigh the benefits.

8 That PLANNING PERMISSION IS REFUSED for the following reason:

The proposed development by reason of the alterations to the frontage including the increase in hardstanding will result in significant encroachment into the existing root

protection of areas of protected trees, allowing insufficient space for their future growth. Furthermore, the constrained nature of the proposed parking area will likely lead to degradation of tree cover along the front boundary. The proposed development would fail to allow the existing protected trees to grow to maturity without impacting visibility or resulting in shading and damage, leading to future requests for topping, lopping and felling. The deterioration or loss of protected trees will be detrimental to the sylvan character of the locality and the visual amenities of the area, contrary to Policy CP12 of the Core Strategy (2011), Policy DM6 of the Development Management Policies LDD (2013) and the NPPF.

8.1 Informatives:

- I1 The Local Planning Authority has been positive and proactive in considering this planning application in line with the requirements of the National Planning Policy Framework and in accordance with the Town and Country Planning (Development Management Procedure) (England) Order 2015. Whilst the applicant and/or their agent and the Local Planning Authority engaged in pre-application discussions, and the applicant and/or their agent and the Local Planning Authority discussed the scheme during the course of the application, the proposed development as amended fails to comply with the requirements of the Development Plan and does not maintain/improve the economic, social and environmental conditions of the District.

This page is intentionally left blank







This page is intentionally left blank

PLANNING COMMITTEE – Thursday 22 January 2026

25/1671/FUL – Variation of Condition 2 (Plans) and 25 (Obscure Windows) pursuant to planning permission 22/1148/FUL to allow alterations to fenestration detailing, omission of terrace balconies, addition of AOV rooflights and submission of hard and soft landscaping details including landscape management at BEESONS YARD, BURY LANE, RICKMANSWORTH, HERTS.

Parish: Batchworth Community Council
Expiry of Statutory Period: 29 December 2025
Agreed Extension of Time: 30 January 2026

Ward: Rickmansworth Town
Case Officer: Matthew Roberts

Development Type: Major development

Recommendation: That planning permission is **granted**, subject to the completion of a Deed of Variation to a Section 106 Agreement pursuant to planning permission 22/1148/FUL dated 18 December 2023; securing an occupancy age restriction, affordable housing contribution, controls on parking permits, amendment to traffic regulation order and Waste Management Scheme, and planning conditions as set out below at Section 7.

Reason for consideration by the Committee: This application has been called in by Batchworth Community Council for the reasons expressed in paragraphs 4.1.2 and 4.1.3.

To view all documents forming part of this application please go to the following website:

[25/1671/FUL | Variation of Condition 2 \(Plans\) and 25 \(Obscure Windows\) pursuant to planning permission 22/1148/FUL to allow alterations to fenestration detailing, omission of terrace balconies, addition of AOV rooflights and submission of hard and soft landscaping details including landscape management. | Beesons Yard Bury Lane](#)

1 Relevant planning and enforcement history of the application site

- 1.1 16/2620/FUL: Demolition of existing single storey temporary storage building and construction of four storey commercial building connecting to the existing two storey commercial building. Withdrawn.
- 1.2 21/1971/FUL: Demolition of existing buildings and structures and erection of a 48-unit Extra Care facility (Use Class C2) with car parking and associated landscaping. Refused, for the following reasons:

R1: The proposed building by virtue of its excessive height, elevated bulk and massing which is exacerbated by the use of large crown roofs would result in an unduly prominent form of development which would have a significant harmful impact on the character and appearance of the area and adjacent street scenes. The development is therefore contrary to Policies CP1, CP3 and CP12 of the Core Strategy (adopted October 2011), Policy DM1 and Appendix 2 of the Development Management Policies LDD (adopted July 2013) and the NPPF (2021).

R2: The proposed building by virtue of its height and the lack of separation distances to Chesswood Court would significantly alter current privacy levels enjoyed by the occupants of Chesswood Court and would also unacceptably impact the level of light reception to a number of flats within the adjacent flatted development. The reduced privacy levels would adversely affect the occupants of Chesswood Court while the loss of light would further impact the residents' enjoyment of the flats to such an extent that their living conditions would be unacceptably eroded to the detriment of their residential amenity. The

development is therefore contrary to Policies CP1 and CP12 of the Core Strategy (adopted October 2011), Policy DM1 and Appendix 2 of the Development Management Policies LDD (adopted July 2013) and the NPPF (2021).

R3: In the absence of a Section 106 agreement to remove the ability for future occupiers to obtain parking permits the development would give rise to exacerbation of parking pressure within the Rickmansworth Town Centre locality and therefore fails to ensure that the development is acceptable in accordance with the requirements of Policy DM13 and Appendix 5 of the Development Management Policies LDD (adopted July 2013) and the NPPF (2021).

- 1.2.1.1 A planning appeal made against the refusal was subsequently allowed on 4 November 2022 (APP/P1940/W/22/3300549). Not implemented.
- 1.2.2 22/1148/FUL: Demolition of existing buildings and structures and construction of a 43-unit retirement living scheme (Use Class C3) with car parking and associated landscaping. Permitted and being built out.
- 1.2.3 24/0890/NMA: Non-material amendment to planning permission 22/1148/FUL: To allow amendments to wording of Condition 19 (Parking Management Plan) and submission of Parking Management Plan. Permitted.
- 1.2.4 24/1123/NMA: Non-material amendment to planning permission 22/1148/FUL to allow for alterations to external materials, alterations to balcony structure and increase to ground floor footprint to south western corner. Permitted.
- 1.2.5 24/0143/COMP: Breach of Condition 3 (Construction Management Plan) of planning permission 22/1148/FUL, works not in accordance with planning permission. Pending.

2 Description of Application Site and Surroundings

- 2.1 The application site contains a recently constructed part four, part three storey building containing 43 flats for retirement living along with associated parking area, amenity area, soft landscaping and attenuation pond. The application site is accessed by a long internal road from the western side of Bury Lane in Rickmansworth. The building is not yet occupied.
- 2.2 The access road abuts Gables Cottage (a Locally Important Building, Non-Designated Heritage Asset), Chesswood Court and Bury Mews. Chesswood Court comprises two flatted developments, a two storey building fronting Bury Lane and a three storey building with its associated parking and communal gardens, the latter of which abuts the eastern boundary of the application site. Bury Mews is a collection of two storey dwellings, two of which front Bury Lane with three immediately behind.
- 2.3 To the immediate south of the site there is a large garage court which is accessed via Goral Mead. Further garage courts adjoin the north western boundary of the site, also accessed via Goral Mead. Within Goral Mead there are a number of three/four storey buildings with parking bays abutting the application site. To the north is the Town Ditch which separates the site from the gardens of two storey dwellings which front Ebury Road.
- 2.4 In terms of policy designations, the application site falls within the Principal Town, Source Protection Zone 1, Flood Zones 2 and 3 and parts of the access drive fall within the Rickmansworth Town Centre Conservation Area, the boundary of which abuts the Town Ditch to the immediate north of the application site.

3 Description of Proposed Development

- 3.1 This application has been submitted via section 73 of The Town and Country Planning Act 1990 (as amended) which enables the determination of applications to develop land without

compliance with conditions previously attached. The development has been largely fully constructed. This report will only focus on the changes proposed as the building and its use has been the subject to a previous grant of planning permission (22/1148/FUL) so the principle of the development cannot be re-visited as part of this application.

3.2 The applicant is applying to vary Condition 2 (Plan Numbers) and Condition 25 (Obscure Windows) pursuant to planning permission 22/1148/FUL to allow for the following changes from the permitted development, hereafter referred to as “the original planning permission”:

- **Larger windows within the northern and western elevations:** The applicant has stated that these windows were enlarged in height and design to achieve a clear actual ventilation area to accord with Approved Document B Fire Safety of the Building Regulations. The windows are Automatic Opening Vents (AOVs) and thus when required to do so can mechanically tilt open. The windows to the northern elevation have been fitted with obscure film, rather than purpose made obscure glazing. However, during the course of the application the applicant has confirmed that they intend to install purpose made obscure glazing (level of obscurity at level 5) to the windows within the northern elevation, prior to first occupation of the building (subject to change as awaiting confirmation from the applicant). There was no requirement to install obscure glazing to the windows within the western elevation.
- **Stairwell windows to northern elevation:** These windows have been inserted smaller in height than approved, have been fitted with purpose made obscure glazing but are contrary to Condition 25 of the original planning permission as they are bottom opening. The windows have all subsequently been fitted with a restrictor which prevents the windows opening outwards by more than 50mm. The applicant therefore is seeking an amendment to Condition 25 to read as:

“Prior to the first occupation of the development hereby permitted, the windows on the northern elevation (closest to the northern boundary of the application site) above ground floor level; shall be fitted with purpose made obscured glazing or coated with a permanent obscured ‘film’. The windows shall be top level opening at 1.7m above the floor level, or fitted with a 50mm restrictor to restrict opening to an extent that prevents views out of the windows to neighbouring property. The windows shall be permanently retained in an obscured and restricted manner thereafter.”
- **Plans updated to ensure consistency between floor plans and elevations:** The elevation drawing (PL 506 Rev H) showing the recessed fourth floor has been updated to reflect the approved floor plans, i.e. three Juliet balconies and four windows.
- **Safety railing added to eastern elevation:** A metal balustrade has been added to the parapet wall on the eastern elevation at the fourth floor to allow for maintenance. All Juliet balconies required to the flats to this part of the building have been affixed as per the original planning permission (*note: the flat roof was conditioned only to be accessed for maintenance purposes*).
- **Addition of roof hatches:** Two roof AOV rooflights have been installed which according to the applicant required were following consultation with Herts Fire and Rescue Service.
- **Omission of external stack balconies to western elevation and corner elevations:** The two stacked balconies to the western elevation have not been installed nor have the corner balconies between the western and corner with the set back northern elevation. The reasoning for their omission is because they would create an evacuation risk and to improve daylight / sunlight levels for flats on the north facing elevation. Black metal Juliet balconies have been installed instead.

- **Submission of hard and soft landscaping details including landscape management:** During the course of the application the soft landscaping scheme was amended to retain existing trees to the northern boundary, adjacent to the attenuation pond as well an area for a potting shed and planters. The use of permeable block pavements to the access road has also been altered to permeable tarmac which does not alter the drainage strategy for the development.

- 3.3 The changes including comparisons with the original planning permission have also been set out in **Appendix A, along with site photographs.**
- 3.4 A number of reiterations of drawings have been submitted during the course of the application as the original plans failed to adequately relate to the works as built and applied for. Further works have also occurred during the application process which have led to further changes, all of which have been referred to above. Two Covering Letters were provided by the applicant, dated 4 November 2025 and 9 December 2025 which highlight the changes. The changes to the drawings led to three consultations exercises.
- 3.5 The development will still be served by 30 parking spaces as per the original planning permission, with the layout having been slightly altered.
- 3.6 Recent reports from local residents have also referred to the installation of a greater number of bollard lighting within the car park area, contrary to the details approved by the Council as part of the original planning permission, secured by Condition 27. This condition does provide some degree of flexibility on external lighting, but it must be agreed by the Local Planning Authority (LPA) which is not the case yet and is currently being discussed outside of this application.

4 Consultation

4.1 Statutory Consultation

4.1.1 Batchworth Community Council: 1st comments provided on 14 October.

BCC discussed and noted this application

4.1.2 Batchworth Community Council: 2nd comments provided on 14 October [Object, Call-in]

Given the increased scale of the side windows compared with the approved plans, and the proximity of the smaller neighbouring dwellings, the change materially increases light spill and visual intrusion. To protect residential amenity, it is reasonable and proportionate to require proper obscure glazing and appropriate light-control measures — such as tinting and timed or automatic lighting — to ensure the development does not result in unacceptable harm.

In addition to this BCC further request:

- All the currently 'film covered' windows be changed to obscure glazing compliant with current regulations.
- All communal areas such as corridors are to be illuminated by motion sensors.
- An additional planting scheme of hedging and / or tree saplings for screening on the North side of the plot be submitted and approved.

BCC would like to call this into committee unless officers are minded to refuse.

4.1.3 Batchworth Community Council: 3rd comments provided on 17 December [Object, Call-in]

BCC would like to continue to call this application into committee, as we feel our previous comments have not been fully addressed. In particular, it is not clear that the glass within the stair and corridor windows have been replaced with obscured glass rather than obscured film.

4.1.4 Herts Fire & Rescue: Advisory comments.

Re the corridor AOV windows, they are required due to the extended travel distances in the corridors, it's not a demand by HFRS as such. They are required to comply with the guidance as given by Approved Document B. The size is dictated by the required available free space. As they appear to be louvred windows then the free space is calculated by the area of opening with the louvres in the open position. This would normally mean the free space is less than the area of the window.

The roof AOV does have to be above the flat roof and the height will be determined by what else is around it, this is to ensure the smoke is blown clear of the vent and does not re-enter the stairs as the smoke cools.

The height of the roof vent and the size of the windows is calculated as part of the fire strategy for the building and in designing the AOV system. It is not calculated by HFRS.

4.2 Public/Neighbour Consultation

4.2.1 As a result of amendments to the scheme, three re-consultations took place; 3 October; 6 November and 10 December.

4.2.2 Number consulted: 186

4.2.3 No of responses received:

- 8 (1st consultation - objections)
- 1 (2nd consultation - objections)
- 4 (3rd consultation - objections)

4.2.4 Site Notices: Expired 27.11.2025

4.2.5 Press Notice: Expired: 05.12.2025 (Watford Observer)

4.2.6 Summary of Responses from consultations:

- No longer a run of equal shaped windows on the north elevation
- Original window shape looks better than the change
- Window design out of keeping with the style originally approved as twice the size
- Has an adverse effect on the conservation area and Ebury Road streetscene
- Large windows increase light pollution and have an overwhelming, oppressive impact on the private amenity of the residential properties in Ebury Road
- Windows not installed with purpose made obscure glazing
- Proposed amended condition relating to stairwell window is ambiguous
- Window frames should be more in keeping and glass made less reflective / mirror like
- No evidence to support that the AOV windows need to be full height
- Developer has previously breached planning conditions
- Council should insist on compliance to agreed conditions, i.e. require proper obscure glazing, not inadequate film and corridors and stairwells to be illuminated by motion sensor activated lighting.

- 4.2.7 Comments were also received from The Rickmansworth & District Residents Association (RDRA) objecting to the application for similar reasons referred to above.

5 Relevant Planning Policy, Guidance and Legislation

Legislation

- 5.1 Planning applications are required to be determined in accordance with the statutory development plan unless material considerations indicate otherwise (S38(6) Planning and Compulsory Purchase Act 2004 and S70 of Town and Country Planning Act 1990).
- 6.2 S72 of Planning (Listed Buildings and Conservation Areas) Act 1990 requires LPAs to have special regard to the desirability of preserving or enhancing the character or appearance of conservation areas.
- 5.2 The Localism Act received Royal Assent on 15 November 2011. The Growth and Infrastructure Act achieved Royal Assent on 25 April 2013.
- 5.3 The Conservation of Habitats and Species Regulations 2010, the Natural Environment and Rural Communities Act 2006 and the Habitat Regulations 1994 may also be relevant.
- 5.4 Environment Act 2021.

Policy / Guidance

5.5 NPPF:

- 5.5.1 In December 2024 the revised NPPF was published, to be read alongside the online National Planning Practice Guidance. The 2024 NPPF is clear that “existing policies should not be considered out-of-date simply because they were adopted or made prior to the publication of this Framework. Due weight should be given to them, according to their degree of consistency with this Framework”.

5.6 Development Plan:

5.6.1 The Three Rivers Local Plan:

- 5.6.1.1 The Development Management Policies LDD was adopted on 26 July 2013 having been through a full public participation process and Examination in Public. Relevant policies include: DM1, DM3, DM4, DM6, DM8, DM9, DM10, DM13 and Appendices 2 and 5.
- 5.6.2 The Core Strategy was adopted on 17 October 2011 having been through a full public participation process and Examination in Public. Relevant policies include: PSP1, CP1, CP2, CP3, CP4, CP6, CP8, CP9, CP10, CP12 and CP13.
- 5.6.3 The Batchworth Neighbourhood Plan (Referendum Version) January 2025. Relevant policies include: BW GB1 (Biodiversity), BW CC1 (Sustainable design and construction), BW CC3 (Sustainable Drainage), BW C01 (Housing type), BW CO2 (Rickmansworth town centre uses), BW CO4 (Rickmansworth town centre design principles), BW CO7 (Employment), BW DE1 (High quality design) and BW AM1 (Active and healthy travel).

Other:

- 5.7 The Community Infrastructure Levy (CIL) Charging Schedule (adopted February 2015)
- 5.8 Planning Practice Guidance (NPPG)
- 5.9 Rickmansworth Conservation Area Appraisal and Character Assessment (adopted 1993)

- 5.10 Affordable Housing Supplementary Planning Document (adopted June 2011)
- 5.11 Evidence Relating to the Application of the Affordable Housing Threshold in Core Strategy Policy CP4: Affordable Housing (February 2022)
- 5.12 South West Hertfordshire Local Housing Need Assessment (September 2024)
- 5.13 Housing Delivery Test Action Plan (June 2024).
- 5.14 Housing Land Supply Update (December 2024).
- 5.15 Technical Housing Standards – nationally described space standards (March 2015).

6 Planning Analysis

6.1 Overview

6.1.1 The original planning permission was granted by the LPA via reference 22/1148/FUL on 20 December 2023 and was subject to a section 106 agreement which secured the following heads of terms:

- an occupancy restriction (as the development is for retirement living)
- restriction on ability for future residents to apply for parking permits
- contribution towards traffic regulation order amendment (£2,000)
- waste management scheme for private collection
- an affordable housing contribution (£549,603 - index linked from the date of the deed).

6.1.2 Following the grant of the original planning permission two Non-Material Amendment applications have been permitted for amendments to the wording of the condition relating to the Parking Management Plan (24/0890/NMA) and alterations to external materials, alterations to balcony structure and increase to ground floor footprint to south western corner (24/1123/NMA).

6.1.3 An alternative scheme was granted at appeal for the demolition of the existing buildings and structures and the erection of a 48-unit Extra Care facility (Use Class C2) with car parking and associated landscaping. This scheme was never implemented.

6.1.4 During construction works relating to the original planning permission there have been breaches of planning control. These relate to the hours of work as secured by the Construction Management Plan and works not conforming to the original planning permission. This application has been submitted as a direct result of discussions with officers pertaining to the on-going enforcement investigation 24/0143/COMP.

6.1.5 In consideration of this section 73 application, the LPA can decide to:

- a) grant planning permission subject to conditions differing from those subject to which the original planning permission was granted, or,
- b) decide that planning permission should be granted subject to the same conditions as those subject to which the original planning permission was granted, then this application should be refused.

6.1.6 Paragraph 140 of the NPPF states that local planning authorities should also seek to ensure that the quality of approved development is not materially diminished between permission and completion, as a result of changes being made to the permitted scheme.

6.1.7 The relevant material considerations are set out below.

6.2 Principle of development:

6.3 The principle of development has been agreed and the development constructed but not yet occupied. It is therefore considered that the need for this type of housing development and the loss of the pre-existing commercial units does not need to be revisited as part of this application.

6.4 Impact on neighbouring amenity

6.4.1 Policy DM1 and Appendix 2 (Design Criteria) of the Development Management Policies LDD states that new development should take into consideration impacts on neighbouring properties, both within and surrounding the development. Oversized, unattractive and poorly sited development can result in loss of light and outlook for neighbours and detract from the character and appearance of the streetscene.

6.4.2 Policy DM9 of the Development Management Policies LDD states the Council will refuse planning permission for development which would or could give rise to polluting emissions to land, air and/or water by reason of disturbance, noise, light, smell, fumes, vibration, liquids, solids or other (including smoke, soot, ash, dust and grit) unless appropriate mitigation measures can be put in place and be permanently maintained.

6.4.3 Objections have been raised regarding the detrimental impact the changes will cause to neighbouring amenity, especially those on Ebury Way who back onto the site. A site visit was undertaken to neighbouring properties on Ebury Road in August 2025, prior to the submission of the planning application.

6.4.4 When considering the changes and their associated impacts, each relevant change has been considered in turn.

Larger windows within the northern and western elevations:

6.4.5 It is recognised that the windows serving the communal corridors within the northern and western elevations were consistent with the adjacent stairwell windows, in terms of size, colour and the requirement for the windows in the northern elevation to be inserted with purpose made obscure glazing.

6.4.6 The new AOV windows given their increased height, siting, and tilted opening design means they now appear more visually apparent than what would likely have been the case if the original permitted windows were installed. It is further acknowledged that their visibility from properties on Ebury Way will change depending on the time of year given the patchy vegetated coverage along the boundary with the application site / Town Ditch. However, whilst larger and visually more apparent, the windows are not considered to be un-neighbourly or have a detrimental impact on residents' outlook. However, it is recognised that the impact arising from the windows presence within the northern elevation is mitigated significantly by the window's obscurity, as this ensures that privacy levels are maintained and the intensity of the internal lighting is suitably mitigated to prevent any harmful impacts. Whilst residents from Ebury Lane have highlighted concerns with the level of internal lighting omitting from these windows, this was prior to the application of an obscure film. Additionally, the applicant has confirmed that corridor lights will be operated as motion sensors when the building is operational.

6.4.7 In terms of the obscured nature of the windows, it is noted that they have not been installed with purpose obscure windows as required, but instead applied with an obscure film which is not a permanent solution. Policy DM9 sets out that appropriate mitigation measures can be put in place but must be permanently maintained. It is recognised that a suitably worded planning condition can ensure that the film is always maintained and from an internal site visit the film applied is difficult to remove and serves a communal area. However, given the siting and increased size of the windows, the concerns of residents are understood, and a more permanent solution would provide greater safeguards. The applicant has confirmed

that they will be replacing the windows to ensure they are inserted with purpose made obscure glazing. To ensure that the residents privacy levels are permanently maintained, a suitably worded condition has been applied to require the windows to be altered.

- 6.4.8 In terms opening abilities of the AOV windows, as approved they should have been top-opening only. However, the windows are now able to tilt open for its full height, however, importantly this will only occur in the case of an emergency and is mechanically operated. On the basis that the windows are likely to remain shut, a suitably worded condition can be applied to safeguard privacy levels.
- 6.4.9 The change to AOV windows on the western elevation has had no detrimental effect on the residents of Goral Mead as they overlook the adjacent road and parking areas.

Stairwell windows to northern elevation:

- 6.4.10 The stairwell windows have been inserted with purpose made obscure glazing and whilst bottom opening, a restrictor has been applied which significantly restricts the ability to open the windows by more than 50mm. Additionally, the windows serve stairwells and do not form part of the flats. Therefore, subject to a suitably worded condition, these windows are acceptable and do not harm residential amenity.

Safety railing added to eastern elevation:

- 6.4.11 The addition of the metal balustrades to the eastern elevation serving a flat roof area do not affect neighbouring amenity. A condition previously applied to the original planning permission in respect of the use of the flat roof would continue to be applied to prevent use by residents.

Addition of roof hatches:

- 6.4.12 The roof hatch adjacent to the northern elevation is visible, but generally only glimpsed when at ground level, unless at a significant distance away. The rooflights are relatively minimal in scale and do not adversely affect residential properties on Coral Mead or Ebury Road.

Omission of external stack balconies to western elevation and corner elevations:

- 6.4.13 The omission of the balconies does not affect neighbouring amenity given their siting relative to residential properties.

Summary:

- 6.4.14 To summarise, the changes are considered acceptable with the exception of the use of film to the AOV windows at first, second, third and fourth levels within the northern elevation which has subsequently been agreed to change to purpose made obscure glazing. The development subject to conditions is therefore considered to comply with Policies CP1 and CP12 of the Core Strategy and Policies DM1, DM9 and Appendix 2 of the Development Management Policies LDD.

6.5 Design, impact on the character of the area and towards heritage assets (Rickmansworth Conservation Area and Locally Important Buildings)

- 6.5.1 Policy CP1 of the Core Strategy seeks to promote buildings of a high enduring design quality that respect local distinctiveness. Policy CP12 states that in seeking a high standard of design, the Council will expect development proposals to 'have regard to the local context and conserve or enhance the character, amenities and quality of an area' and 'conserve and enhance natural and heritage assets'.

- 6.5.2 Policy DM1 and Appendix 2 of the Development Management Policies document seek to ensure that development does not lead to a gradual deterioration in the quality of the built environment. Appendix 2 of the Development Management Policies LDD sets out that development should not have a significant impact on the visual amenities of the area. Development should not be excessively prominent and should respect the existing character of the dwelling, particularly with regard to roof form, positioning and style of windows and doors, and materials.
- 6.5.3 Policy DM3 of the Development Management Policies document states that within conservation areas development will only be permitted if the proposal is of a design and scale that preserves or enhances the character or appearance of the area and does not harm important views into, out of or within the Conservation Area. The policy is silent with regards to the impact on the setting of Locally Important Buildings (referred to as non-heritage designated assets within the NPPF).
- 6.5.4 Policy BW DE1 of the Batchworth Neighbourhood Plan states that development shall respond to local character and wherever possible, contribute towards improvements to character.
- 6.5.5 In close proximity to the application site and fronting Bury Lane are Beresford Almhouses and The Gables, both Locally Important Buildings (non-designated heritage assets).
- 6.5.6 The building is not located within the Rickmansworth Conservation Area but it is visible from views within, especially from Bury Lane and gaps between dwellings in Ebury Way. Whilst visible from Ebury Way, given the wider backdrop of the building and distances involved, the change to the fenestration detailing, addition of rooflights and balustrades do not adversely affect the setting of the Rickmansworth Conservation Area.
- 6.5.7 It is recognised that the larger windows are now no longer consistent with other permitted windows within the northern elevation, however, when considered against the whole building it is not considered that they are out of character or incongruous.
- 6.5.8 The introduction of the metal balustrades to the front elevation, facing Chesswood Court are largely screened by the parapet wall. Nevertheless, their design is consistent with the privacy screens and stacked balconies which are evident elsewhere on the front elevation ensuring that their introduction is in-keeping.
- 6.5.9 The omission of the balconies towards the rear of the building has meant that the length of the building is now not broken up as well as it would have been with the introduction of the stacked balconies which were to provide some visual contrast and interest. However, this part of the building is not readily visible from the adjacent conservation area and is primarily viewed from Goral Mead. When viewed from Goral Mead, there is one stacked balcony and Juliet balconies have been installed which does provide some degree of visual variation. That said, the omission of the balconies and replacement with Juliet balconies has still ensured that the quality of the design of the development has not been materially diminished and does not have a harmful impact on the character of the area.
- 6.5.10 To summarise, it is not considered that the changes adversely affect the setting of the Rickmansworth Conservation Area and non-designated heritage assets, nor do they unacceptably erode the character of the development as initially approved nor harm the character of the area. As a result, the changes to the original planning permission accord with Policies CP1 and CP12 of the Core Strategy and Policies DM1, DM3 and Appendix 2 of the Development Management Policies LDD, Policy BW DE1 of the Batchworth Neighbourhood Plan and the NPPF.
- 6.6 Affordable Housing

- 6.6.1 Core Strategy Policy CP4 states that in order to increase the provision of affordable homes in the district and meet local housing need, the council will seek an overall provision of around 45% of all new housing as affordable housing, incorporating a mix of tenures. All new development resulting in a net gain of one or more dwellings will be expected to contribute to the provision of affordable housing.
- 6.6.2 The original planning permission was supported by a Viability Assessment which was independently reviewed. Upon initial review the Council's Independent Viability Assessor concluded that the applicant should provide the full provision of 19 1 bed and 2 bed flats with a tenure split of 70/30. However, the applicant disagreed with the assessor's Benchmark Land Value (BLV) amount of £750,000. Due to the disagreements, an Independent Commercial Expert was instructed to review the BLV. The findings of the Commercial Expert agreed with the applicant and thus it meant that it would not be viable for the scheme to provide a policy compliant amount of affordable housing. However, the Independent Viability Assessor through his amended review concluded that the scheme could provide for 5, 1 bed flats and 5, 2 bed flats for shared ownership.
- 6.6.3 Nevertheless, due to the nature of the development whereby service charges will be applied to future residents as well incorporating the cost of the private waste collection, on-site affordable units were not considered appropriate in this instance. With this in mind and further to additional guidance received from the Council's Independent Viability Assessor, it was considered that an off-site financial contribution of £549,603 (index linked from the date of the deed), as concluded by the Independent Viability Assessor in their final review, would be the most appropriate means of securing affordable housing (a policy compliant off-site contribution would equate to £3,316,612.5).
- 6.6.4 It was agreed that the contribution should be paid in two instalments, 50% at commencement and 50% prior to occupation, in lieu of any late stage review mechanism.
- 6.6.5 At time of this report, 50% of the contribution has been paid to due with final 50% due prior to occupation. To secure the outstanding affordable housing payment, a deed of variation is required to the section 106 agreement relating to planning permission 22/1148/FUL.
- 6.7 Living conditions of future occupants
- 6.7.1 Policy CP12 of the Core Strategy states that development must protect residential amenities by taking into account the need for adequate levels and disposition of privacy, prospect, amenity and garden space.
- 6.7.2 Appendix 2 of the Development Management Policies LDD states that amenity space must be provided within the curtilage of all new residential developments. Depending on the character of the development, the space provided may be in the form of private gardens or in part, contribute to formal spaces/settings for groups of buildings or existing mature trees.
- 6.7.3 When applying the development to the indicative standards for flats there would be a requirement for 1,083sqm. From the plans previously approved the total amount of amenity space equated to approximately 700sqm which took into account the communal gardens, private amenity spaces and external balconies (excluded attenuation pond). The resultant external amenity area as built is largely as approved.
- 6.7.4 One of the changes which impacts the quality of accommodation provided is the loss of the stacked balconies which means 21 out of 43 flats would no longer have their own private amenity area, as the balconies have been replaced with Juliet balconies. As permitted, only eight had no private amenity area.
- 6.7.5 Notwithstanding the further loss of private balconies, the corner flats will now benefit from greater light reception which enhances the quality of accommodation on offer. Additionally, whilst recognising the level of amenity space for the original planning permission fell short

of the indicative level required by Appendix 2, it was acknowledged that the application site is within a town centre location where there is a general acceptance that developments have smaller amenity spaces given the site constraints and higher densities. In addition, the site is within a short walking distance (8-10 mins) of the Rickmansworth Aquadrome and close to other local public open spaces within Rickmansworth such as The Bury Gardens, Rose Garden and Rickmansworth Park.

- 6.7.6 Additionally, there are a number of distinct areas whereby residents will be able to use, including a landscaped garden with benches/covered seating, and areas of lawn areas. Whilst not sizable in their own right they will still provide spaces for residents to use and full walking connectivity around the entire building will be possible. Consequently, the loss of private balconies is not considered to be detrimental to the living conditions of future residents.

6.8 Impact on trees / landscaping

- 6.8.1 Policy DM6 of the Development Management Policies LDD states that development proposals should seek to retain trees and other important landscape and nature conservation features whilst including new trees and other planting to enhance the landscape of the site and its surroundings as appropriate.
- 6.8.2 Due to the built-up nature of the application site the majority of trees and landscape features were prior to the redevelopment found along the site's perimeter to the north.
- 6.8.3 In order to facilitate the new building the hedging within the site was removed as approved; with new trees and soft landscaping areas to be introduced to compensate any loss. Two trees along the northern boundary were also shown to be retained and these have remained in situ throughout construction works.
- 6.8.4 Condition 21 of the original planning permission required the submission of a hard and soft landscaping scheme, based on the details provided on drawings PL 500 Rev A & MCS23387 10A (Landscape Masterplan) of the original planning permission which was indicative, to some degree.
- 6.8.5 This application has been supported by a comprehensive landscape proposal which includes the required details secured by Condition 21 of the original planning permission. This has been amended during the application process to retain two existing trees along the northern boundary, which provide valued screening for residents on Ebury Road.
- 6.8.6 Whilst trees have been omitted from the boundary with Chesswood Court, it is not considered that this erodes the quality of the landscaping proposal, especially when considering that this boundary is already well vegetated from the Chesswood Court side.
- 6.8.7 The development proposal would therefore be acceptable in accordance with Policy DM6 of the Development Management Policies LDD.

6.9 Impact on highway safety and parking

- 6.9.1 Policy CP10 of the Core Strategy states that all development proposals should be designed and located to minimise the impacts of travel by motor vehicle on the District. In particular, major development will be expected to be located in areas of highly accessible by the most sustainable modes of transport, and to people of all abilities in a socially inclusive and safe manner. The NPPF at paragraph 111 states that developments should only be prevented or refused on highway grounds if there would be an unacceptable impact on highway safety, or the residual cumulative impacts on the road network would be severe.
- 6.9.2 The application site is served by a single vehicular access from Bury Lane.

- 6.9.3 Internally within the site and along the access road the defined pedestrian route has been removed. There is no objection to this change.
- 6.9.4 With regards to parking, Policy DM13 and Appendix 5 of the Development Management Policies LDD states that for C3 residential (elderly person's accommodation / retirement dwellings) there should be 1.5 spaces per unit for 1 and 2 beds flats which includes a 0.25 allowance for a visitor space. When applied to the development as approved there was a requirement to provide 65 spaces (rounded up from 64.5). The development provided for 30 on-site parking spaces, resulting in a shortfall of 35 spaces.
- 6.9.5 As justification for the shortfall, it was accepted that visitors will attend the site; however, the surrounding roads are all permit parking (or 1 hour no return within 1 hour (Mon-Sat 8.30 to 6.30pm)) meaning the majority of visitors will either park on site, use the parking bays on local roads for an hour or use the local public car parks, of which there are plenty within a short walking distance. The existence of permit parking and 1 hour return was also considered to deter future residents from parking here as they would need to park outside the parking zone which is a significant walk from the site. Notwithstanding the above, to ensure that residents and staff are unable to park on the surrounding road networks, a legal obligation was secured preventing those associated with the development from applying for a permit. The deed of variation to the legal agreement would need to secure the parking permit controls to prevent the permanent use of the permit parking spaces along Bury Lane and other nearby roads as well as ensuring that parking in the area is not displaced or put under further pressure as a result of this development. Secondly, the development will be age restricted where car ownership is statistically lower. Additionally, all residents will be aware of the parking requirements on site; however, importantly the site is well connected to local amenities and transport connections. Lastly, the development would be served by an electric car club on site which will enable a vehicle to be shared and offer greater choice for future occupiers. The details of the car club have been secured by condition and will be re-imposed as a compliance condition.
- 6.9.6 In respect of cycling parking, Appendix 2 sets out that for retirement dwellings there should be 1 short-term space per 3 flats and 1 long-term space per 5 flats. When applied to the development 22.6 cycle spaces (14 externally and 8.6 internally) should be provided. Externally, there would be a cycle rack for 4 cycles, while none are currently provided internally. However, the buggy store could be used flexibly to cater for demand amongst residents. Whilst the external storage is lower than required, it is recognised that the development can be flexible to increase storage if demand requires. Therefore, no objection is held in this regard.
- 6.10 Waste Management
- 6.10.1 Policy DM10 (Waste Management) of the Development Management Policies LDD (adopted July 2013) advises that the Council will ensure that there is adequate provision for the storage and recycling of waste and that these facilities are fully integrated into design proposals. New developments will only be supported where:
- i) The siting or design of waste/recycling areas would not result in any adverse impact to residential or work place amenity
 - ii) Waste/recycling areas can be easily accessed (and moved) by occupiers and by local authority/private waste providers
 - iii) There would be no obstruction of pedestrian, cyclists or driver site lines
- 6.10.2 The proposal development falls within a residential use whereby there is an obligation for the residents to have their waste collected by the Council. However, due to access constraints given the location of the parking bays on Bury Lane, the vehicles used by the Environmental Protection department would be unable to enter the site to collect waste.

- 6.10.3 When looking at alternatives as part of the original planning permission, there was insufficient room within the internal access road to provide a bin collection point which could have been collected by the Council. This part of the site is also within the Rickmansworth Conservation Area where such a collection point may be visually unacceptable. As a result, it is considered that the only option was for the waste and recycling to be collected by a private contractor. The details of which were secured by a Waste Management Scheme which formed part of the S106 agreement. Such details would need to be re-secured prior to the grant of this application.
- 6.10.4 In light of the above, subject to the agreement of a deed of variation to the S106 agreement the use of a private contractor would, in this instance due to the site circumstances, be acceptable and would ensure acceptable waste management in accordance with Policy DM10 of the Development Management Policies LDD.
- 6.11 Flooding and Drainage
- 6.11.1 The NPPF at paragraph 170 states that inappropriate development in areas at risk of flooding should be avoided by directing development away from areas at highest risk. Where development is necessary in such areas, the development should be made safe for its lifetime without increasing flood risk elsewhere.
- 6.11.2 Policy CP1 of the Core Strategy recognises that taking into account the need to avoid development in areas at risk of flooding will contribute towards the sustainability of the District. Policy CP12 of the Core Strategy also acknowledges that the Council will expect development proposals to build resilience into a site's design taking into account climate change, for example flood resistant design. Policy DM8 (Flood Risk and Water Resources) of the Development Management Policies LDD advises that development will only be permitted where it would not be subject to unacceptable risk of flooding and would not unacceptably exacerbate the risks of flooding elsewhere and that the Council will support development where the quantity and quality of surface and groundwater are protected and where there is adequate and sustainable means of water supply. Policy DM8 also requires development to include Sustainable Drainage Systems (SuDs).
- 6.11.3 Policy DW CC3 of The Batchworth Neighbourhood Plan 2023-2038 (Referendum Version) states that the design of SuDS should reflect best practice and follow the SuDS hierarchy as set out in the LLFA Summary Guidance for Developers.
- 6.11.4 There are no changes to the approved drainage strategy which is in the process of being implemented on site. Conditions have been applied which requires the drainage strategy to be constructed as originally approved and that details of the completed drainage works are submitted to the Council.
- 6.12 Wildlife & Biodiversity
- 6.12.1 Section 40 of the Natural Environment and Rural Communities Act 2006 requires Local Planning Authorities to have regard to the purpose of conserving biodiversity. This is further emphasised by regulation 3(4) of the Habitat Regulations 1994 which state that Councils must have regard to the strict protection for certain species required by the EC Habitats Directive. The Habitats Directive places a legal duty on all public bodies to have regard to the habitats directive when carrying out their functions.
- 6.12.2 The protection of biodiversity and protected species is a material planning consideration in the assessment of this application in accordance with Policy CP9 of the Core Strategy and Policy DM6 of the Development Management Policies document. Policy DM6 sets out that development must conserve, enhance and, where appropriate, restore biodiversity. It refers to measures that relate to protection, compensation and management of habitats and species, amidst others.

- 6.12.3 Paragraph 193 of the NPPF states that when determining planning applications, local planning authorities should a) if significant harm to biodiversity resulting from a development cannot be avoided, adequately mitigated, or as a last resort, compensated for, then planning permission should be refused, b) development on land or outside of a Site of Special Scientific Interest, and which is likely to have an adverse effect should not normally be permitted, c) development resulting in the loss or deterioration of irreplaceable habitats should be refused, unless there are wholly exceptional reasons and d) development whose primary objective is to conserve or enhance biodiversity should be supported, while opportunities to improve biodiversity in and around developments should be integrated as part of their design.
- 6.12.4 The changes proposed have no detrimental impact on biodiversity.
- 6.13 Biodiversity Net Gain (BNG)
- 6.13.1 Paragraph 13 of Schedule 7A of the Town and Country Planning Act 1990 sets out that every planning permission granted for the development of land in England shall be deemed to have been granted subject to the 'biodiversity gain condition' requiring development to achieve a net gain of 10% biodiversity value. This is subject to exemptions as set out in the Biodiversity Gain Requirements (Exemptions) Regulations 2024.
- 6.13.2 Policy BW GB1 of The Batchworth Neighbourhood Plan 2023-2038 (Submission Version) states that development proposals must manage impacts on biodiversity and secure a minimum net biodiversity gain of 10%.
- 6.13.3 This application is exempt from BNG as it is a variation to a planning permission which was granted prior to the mandatory BNG taking effect.
- 6.14 Sustainability
- 6.14.1 Policy DM4 of the Development Management Policies LDD sets out that development must produce at least 5% less carbon dioxide emissions than Building Regulations Part L (2013) requirements having regard to feasibility and viability. This may be achieved through a combination of energy efficiency measures, incorporation of on-site low carbon and renewable technologies, connection to a local, decentralised, renewable or low carbon energy supply.
- 6.14.2 Policy BW CC1 of The Batchworth Neighbourhood Plan states that the design and standard of any new development should aim to meet a high level of sustainable design and construction and be optimised for water and energy efficiency.
- 6.14.3 The development has been incorporated by energy efficient building fabric, double glazed windows, low energy lighting, high efficient heating systems and solar panels (located on the roof) which combined exceeded the policy standard.
- 6.14.4 The changes proposed under this application do not effect compliance with the previous requirements.
- 6.15 Planning Balance
- 6.15.1 The NPPF at paragraph 11 states the plans and decisions should apply a presumption in favour of sustainable development. For decision making in this means (c) approving development proposals that accord with an up-to date development plan without delay; or (d) where there are no relevant development plan policies, or the policies which are most important for determining the application are out-of-date, granted planning permission unless:

- (i) the application of policies in this Framework that protect areas or assets of particular importance provides a strong reason for refusing the development proposed; or
- (ii) any adverse impacts of doing so would significantly and demonstrably outweigh the benefits, when assessed against the policies in this Framework taken as a whole, having particular regard to key policies for directing development to sustainable locations, making effective use of land, securing well-designed places and providing affordable homes, individually or in combination.

6.15.2 The above assessment has found that the development is acceptable in accordance with the development plan. However, if an alternative view was taken, paragraph 11 of the NPPF and the presumption in favour of sustainable development must be considered.

6.16 Summary, Conditions and S106

6.16.1 The changes proposed and as amended during the course of the application are acceptable and planning permission should be granted subject to conditions differing from those subject to which the original planning permission was granted.

6.16.2 As the building has been built many previously imposed planning conditions now fall away. However, it is important that the conditions listed at section 7 are imposed to ensure an acceptable form of development which safeguards neighbouring amenity and preserves the character of the area. The majority are compliance conditions as details have previously been approved by Approval of Details Applications (commonly referred to as discharge of condition applications). Additionally, the suggested amendment to Condition 25 by the applicant has been amended and is now listed as Condition 20 at section 7.

6.16.3 A deed of variation is required to the Section 106 Agreement which was secured via planning permission 22/1148/FUL. The heads of terms remain the same as those previously secured. The affordable housing contribution (£274,801.50) due prior to commencement and the contribution towards the amendment to the traffic regulation order (£2,000) have already been paid. The S106 will however need to secure the remaining 50% of the affordable housing contribution (£274,801.50), controls on parking permits, occupancy age restrictions, and the submission of a Waste Management Scheme for agreement.

7 **Recommendation**

7.1 That **PLANNING PERMISSION IS GRANTED**, subject to the completion of a Deed of Variation to a Section 106 Agreement pursuant to planning permission 22/1148/FUL dated 18 December 2023; and the following conditions:

C1 In accordance with plans:

The development hereby permitted shall be carried out in accordance with the following approved plans:

*LP 01 (site location plan); LP02 (Site Context - Conservation Area Plan); LP 03 (Site Context Plan - Building Heights); LP 04 (Combined Title Information Plan); TS15129X1 (Existing Floor Plans 1); TS15129X2 (Existing Floor Plans 2); TS15129X3 (Existing Floor Plans 3); TS15129X4 (Existing Elevations); **PL 500 Rev B (Proposed Site Plan); PL 503 Rev F (Proposed Ground & First Floor Plans); PL504 Rev F (Second & Third Floor Plans); PL505 Rev C (Proposed Roof Plan); PL506 Rev H (Proposed South & Eastern Elevations); PL 507 Rev H (Proposed Northern & Western Elevations); PL 509 (Sub-station Elevations); SV 01 (Topographic Survey); MCS23387 11M (Landscape Masterplan); MCS23387-15D (Landscape Boundary Details); 1691-KC-XX-YTREE-TPP01 Rev 0 (Tree Protection Plan).***

Reason: For the avoidance of doubt, in the proper interests of planning and in accordance with Policies PSP1, CP1, CP2, CP3, CP4, CP8, CP9, CP10 and CP12 of the Core Strategy (adopted October 2011), Policies DM1, DM3, DM4, DM6, DM10, DM13 and Appendices 2 and 5 of the Development Management Policies LDD (adopted July 2013), Policy SA2 of the Site Allocations Local Development Document (adopted November 2014), and Policies BW GB1, BW CC1, BW CC2, BW CC3, BW C07, BW CO8, BW DE1 & BW AM1 of the Batchworth Neighbourhood Plan 2023-2038 and the NPPF (2024).

C2 Construction Management Plan:

The construction of the development shall only be carried out in accordance with the Construction Management Plan agreed via Approval of Details Application 24/0148/DIS, granted by the Local Planning Authority on 28 March 2024.

Reason: In order to protect highway safety and to mitigate the impact of construction activity on adjacent residential properties, in accordance with Policies CP1 and CP10 of the Core Strategy (adopted October 2011) and Policies DM9 and DM10 of the Development Management Policies LDD (adopted July 2013).

C3 Archaeology Written Scheme of Investigation including post investigation assessment:

The development shall be carried out in accordance with the Written Scheme of Investigation for an Archaeological Evaluation (December 2023), agreed via Approval of Details Application 24/0148/DIS granted by the Local Planning Authority on 28 March 2024 and the Archaeological Evaluation (November 2024), agreed via Approval of Details Application 25/0106/DIS granted by the Local Planning Authority on 3 April 2025.

Reason: To evaluation/mitigation necessary to protect any archaeological remains present within the development site in accordance with Policy CP1 of the Core Strategy (adopted October 2011), Policy DM3 of the Development Management Policies LDD (adopted July 2013) and the NPPF (2024).

C4 Remediation Strategy:

The development shall be carried out in accordance with the Remediation Strategy and Verification Plan (June 2024) prepared by Crossfield Consulting, agreed via Approval of Details Application 24/1131/DIS granted by the Local Planning Authority on 12 August 2024.

Reason: To ensure that the development does not contribute to and is not put at unacceptable risk from or adversely affected by unacceptable levels of water pollution in accordance with Policy DM9 of the Development Management Policies LDD (adopted July 2013).

C5 Surface Water Drainage Scheme:

The development shall be carried in accordance with the Detailed Surface Water Drainage Scheme (Issue 1 dated 19 January 2024) prepared by Infrastructure Design Limited and letter dated 8 May 2024 from Infrastructure Design Limited, agreed via Approval of Details Application 24/0660/DIS granted by the Local Planning Authority on 5 June 2024.

Reason: To ensure that the development would not be subject to unacceptable risk of flooding in accordance with Policy CP1 of the Core Strategy (adopted October 2011), Policy DM8 of the Development Management Policies LDD (adopted July 2013) and Policy BW CC3 of the Batchworth Neighbourhood Plan 2023-2038.

C6 Construction Ecological Management Plan:

The development shall be carried in accordance with the Construction Management & Construction Ecological Management Plan (March '24 WT V3), agreed via Approval of Details Application 24/0148/DIS granted by the Local Planning Authority on 28 March 2024.

Reason: To prevent flooding by ensuring the satisfactory storage of and disposal of surface water from the site in accordance with Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM8 of the Development Management Policies LDD (adopted July 2013).

C7 Contamination:

If, during development, contamination not previously identified is found to be present at the site then no further development (unless otherwise agreed in writing with the local planning authority) shall be carried out until a Remediation Strategy detailing how this contamination will be dealt with has been submitted to, and approved in writing by, the Local Planning Authority. The Remediation Strategy shall be implemented as approved.

Reason: To ensure that the development does not contribute to and is not put at unacceptable risk from or adversely affected by unacceptable levels of water pollution from previously unidentified contamination sources at the development site. This is in line with paragraph 174 of the NPPF (2021) and in accordance with Policy DM9 of the Development Management Policies LDD (adopted July 2013).

C8 Materials:

The development shall be carried in accordance with the External Finishes Schedule Rev A (Document reference: NL-2783-04-AC-1987), agreed via Approval of Details Application 24/1313/DIS granted by the Local Planning Authority on 11 November 2024.

Reason: To ensure that the external appearance of the building and site in general is acceptable and preserves the character and appearance of the Rickmansworth Conservation Area in accordance with Policies CP1 and CP12 of the Core Strategy (adopted October 2011), Policies DM1, DM3 and Appendix 2 of the Development Management Policies LDD (adopted July 2013), Policy BW DE1 of the Batchworth Neighbourhood Plan 2023-2038 and the Rickmansworth Conservation Area Appraisal and Character Assessment (adopted 1993).

C9 Biodiversity Enhancements:

The development shall be carried in accordance with drawing number NL-2783-05-AC-001 Rev C01, agreed via Approval of Details Application 24/1313/DIS granted by the Local Planning Authority on 11 November 2024.

The approved measures shall thereafter be implemented in accordance with the approved details prior to the first occupation of the development hereby approved.

Reason: To ensure biodiversity net gain and to meet the requirements of Policies CP1, CP9 and CP12 of the Core Strategy (adopted October 2011), Policy DM6 of the Development Management Policies LDD (adopted July 2013) and Policy BW GB1 of the Batchworth Neighbourhood Plan 2023-2038.

C10 Energy Measures:

The development shall be carried in accordance the Energy Statement (August 2024) prepared by Focus, agreed via Approval of Details Application 24/1313/DIS granted by the Local Planning Authority on 11 November 2024.

Reason: In order to ensure that the development will meet the requirements of Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM4 of the Development Management Policies LDD (adopted July 2013) and to make as full a contribution to sustainable development principles as possible.

C11 Travel Plan Statement:

The approved Travel Plan Statement (February 2025), agreed via Approval of Details Application 25/0106/DIS granted by the Local Planning Authority on 3 April 2025, shall be implemented in accordance with the timetable and target contained therein and shall continue to be implemented as long as any part of the development is occupied.

Reason: To ensure that sustainable travel options associated with the development are promoted and maximised to be in accordance with Policies CP1 and CP10 of the Core Strategy (adopted July 2013) and Policy BW AM1 of the Batchworth Neighbourhood Plan 2023-2038.

C12 Archaeology Post Investigation Assessment:

The development shall be carried in accordance with the Archaeological Evaluation (November 2024).

The development shall not be occupied until the site investigation and post investigation assessment has been completed in accordance with the programme set out in the Written Scheme of Investigation approved under condition (3) and the provision made for analysis and publication where appropriate.

Reason: In the interests of protecting any archaeological remains present within the development site. The significance of heritage assets with archaeological interest can be harmed/destroyed by development. This is in accordance with Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM3 of the Development Management Policies LDD (adopted July 2013).

C13 Parking Management Plan:

The allocation of the parking spaces to be provided on site for residents of the development and visitors to it (including the allocation of spaces for disabled persons and members of the development's electric car club), and the car park management and operation shall accord with the agreed Parking Management Plan dated May 2024 (as agreed by 24/0890/NMA granted by the Local Planning Authority on 1 July 2024) which shall be adhered to at all times throughout the lifetime of the development.

No dwelling shall be occupied until the access road, on-site car parking spaces and turning areas to be provided on the site have been laid out, demarcated, levelled, surfaced (and drainage measures installed) in accordance with approved plan reference PL500 Rev C and the agreed Parking Management Plan. Thereafter the access road, on-site car parking spaces and turning areas shall be permanently retained.

Reason: To ensure the on-site parking spaces are made exclusively available only for residents and visitors to the site to enable adequate supply of parking having regard to Appendix 5 of the Development Management Policies LDD (adopted July 2013).

C14 External Cycle storage:

Prior to the first occupation of the development hereby permitted, the external Sheffield cycle stands as shown on drawing number PL500 Rev B shall be erected and permanently retained thereafter.

Reason: In order to ensure bicycle parking facilities are provided and encourage use

of sustainable modes of travel in accordance with Policies CP1, CP10 and CP12 of the Core Strategy (adopted October 2011), Policy DM13 and Appendix 5 of the Development Management Policies LDD (adopted July 2013) and Policy BW AM1 of the Batchworth Neighbourhood Plan 2023-2038

C15 Hard and Soft Landscaping including maintenance:

Prior to the first occupation of the development hereby permitted, all hard landscaping works shall take place in accordance with drawing numbers MCS23387-11M and MCS23387-15D.

All planting, seeding or turfing comprised in drawing numbers MCS23387-11M and MCS23387-15D shall be carried out in the first planting and seeding seasons following the occupation of the development or the completion of the development, whichever is sooner; and any trees or plants which within a period of 5 years from the completion of the development die, are removed or become seriously damaged or diseased shall be replaced in the next planting season with others of similar size and species.

The external areas of soft landscaping shall be managed in accordance with the Soft Landscaping Specification, dated March 2024.

Reason: This condition is required to ensure the completed scheme has a satisfactory visual impact on the character and appearance of the area in the interests of the visual amenity of the area in accordance with Policies CP1 and CP12 of the Core Strategy (adopted October 2011) and Policy DM6 of the Development Management Policies LDD (adopted July 2013).

C16 Flood Warning Measures (Emergency Plan):

Prior to the first occupation of the development hereby permitted, an Emergency Plan based on the Draft Emergency Flood Response Plan V2 dated May prepared by SLR Consulting document shall be submitted to and approved in writing by the Local Planning Authority. The Plan shall follow guidance set out within the Flood Risk emergency plans for new development and include:

- measures to ensure occupiers are aware of the likely frequency and duration of flood events; and
- safe access to and from the development

The plan shall be implemented in accordance with the approved details and maintained thereafter.

Reason: To ensure that the development would not be subject to unacceptable risk of flooding in accordance with Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM8 of the Development Management Policies LDD (adopted July 2013).

C17 Electric Car Club:

The Electric Car Club shall be implemented and managed in accordance with the details set out within the Travel Plan Statement (February 2025), as agreed via Approval of Details Application 25/0106/DIS granted by the Local Planning Authority on 3 April 2025

Reason: To ensure that sustainable travel options associated with the development are promoted and maximised to be in accordance with Policies CP1 and CP10 of the Core Strategy (adopted July 2013) and Policy BW AM1 of the Batchworth Neighbourhood Plan 2023-2038

C18 Obscure Privacy Screens:

The privacy screens shall be implemented and permanently retained in accordance with drawing numbers 508-01 P01 and 508-04 P01, agreed via Approval of Details Application 25/0106/DIS granted by the Local Planning Authority on 13 October 2025.

Reason: To protect neighbouring privacy levels in accordance with Policy CP12 of the Core Strategy (adopted October 2011) and Policy DM1 and Appendix 2 of the Development Management Policies LDD (adopted July 2013).

C19 AOV Obscure windows within the northern elevation:

Prior to the first occupation of the development hereby permitted, the Automatic Opening Vents windows in northern elevation (closest to the northern boundary of the application site) above ground floor level, shall be fitted with purpose made obscured glazing with the level of obscurity at level 5, and, shall only be openable in the case of emergencies. The windows shall be permanently retained in that condition thereafter.

Reason: To safeguard the amenities of the occupiers of neighbouring residential properties in accordance with Policies CP1 and CP12 of the Core Strategy (adopted October 2011) and Policy DM1 and Appendix 2 of the Development Management Policies LDD (adopted July 2013).

C20 Staircase windows within northern elevation:

The windows serving the stairwell within the northern elevation (closest to the northern boundary of the application site) above ground floor level, shall be fitted with purpose made obscured glazing and shall be top level opening at 1.7m above the floor level, or, fitted with a restrictor to ensure that no part of the windows below a height of 1.7m (measured from the internal floor level) can open outwards by more than 50mm past the external frame. The windows shall be maintained thereafter in accordance with the above details. In the case whereby a restrictor is removed or broken to enable emergency access, the restrictor shall be re-installed or a new one installed as necessary in accordance with the above details within 1 MONTH with this process maintained thereafter in perpetuity.

Reason: To safeguard the amenities of the occupiers of neighbouring residential properties in accordance with Policies CP1 and CP12 of the Core Strategy (adopted October 2011) and Policy DM1 and Appendix 2 of the Development Management Policies LDD (adopted July 2013).

C21 Use of Flat Roof

The flat roof immediately adjacent to Flats labelled RL13R-SB and RL21 SB on the submitted plans at third floor level of the building hereby permitted shall only be accessed for maintenance purposes. The roof shall not at any time be used as a balcony or for amenity purposes.

Reason: To safeguard the amenities of the occupiers of neighbouring residential properties in accordance with Policies CP1 and CP12 of the Core Strategy (adopted October 2011) and Policy DM1 and Appendix 2 of the Development Management Policies LDD (adopted July 2013).

C22 External Lighting Details:

The external lighting installed on the site and affixed to the building shall be undertaken in accordance with the details set out within the document titled "2782 – Rickmansworth_External Project" and be installed before the first occupation of the development hereby permitted.

No other external lighting shall be installed on the site or affixed to the building on the site unless the Local Planning Authority has first approved in writing details of the

position, height, design and intensity. The submitted lighting details shall be installed in accordance with the approved details before the use commences.

Reason: In the interests of visual amenity, to preserve the character and appearance of the Rickmansworth Conservation Area, safeguard biodiversity and to meet the requirements of Policies CP1, CP9 and CP12 of the Core Strategy (adopted October 2011), Policies DM3, DM6 and DM9 of the Development Management Policies LDD (adopted July 2013) and the Rickmansworth Conservation Area Appraisal and Character Assessment (adopted 1993).

C23 Retention of existing signage:

The existing signage above the access into the application site shall be retained (or if temporarily removed during the construction phase it shall be re-installed prior the first occupation of the development) and be permanently maintained thereafter following completion of the development.

Reason: To preserve the character and appearance of the Rickmansworth Conservation Area in accordance with Policies CP1 and CP12 of the Core Strategy (adopted October 2011), Policies DM1, DM3 and Appendix 2 of the Development Management Policies LDD (adopted July 2013) and the Rickmansworth Conservation Area Appraisal and Character Assessment (adopted 1993).

C24 SuDS Infiltration of surface water into ground:

No drainage systems for the infiltration of surface water to the ground are permitted other than with the written consent of the Local Planning Authority. Any proposals for such systems must be supported by an assessment of the risks to controlled waters. The development shall be carried out in accordance with the approved details.

Reason: To ensure that the development does not contribute to and is not put at unacceptable risk from or adversely affected by unacceptable levels of water pollution from previously unidentified contamination sources at the development site. This is in line with Policy DM9 of the Development Management Policies LDD (adopted July 2013), Policy BW CC3 of the Batchworth Neighbourhood Plan 2023-2038 and the NPF (2024).

C25 In accordance with drainage strategy:

The development permitted by this planning permission shall be carried out in accordance with the approved Flood Risk Assessment and Drainage Strategy (carried out by SLR, ref: 425.05039.00023, rev: 05, dated: May 2022) and the response to the LLFA's Consultation dated: 11th January 2022, ref: 425.05039.00023, dated: 14.01.2022) and the following mitigation measures:

1. Limiting the surface water run-off generated by the critical storm events so that it will not exceed the surface water run-off rate of 1.0/s during the 1 in 100 year event plus 40% of climate change event.
2. Providing storage to ensure no increase in surface water run-off volumes for all rainfall events up to and including the 1 in 100 year + climate change event in lined geo-cellular crates, lined permeable paved area and a pond/wetland area.
3. Discharge of surface water from the site into the Town Ditch main river at a restricted rate of 1.0l/s

Reason: To reduce the risk of flooding to the proposed development and future occupants in accordance with Policy CP1 of the Core Strategy (adopted October 2011), Policy DM8 of the Development Management Policies LDD (adopted July 2013) and Policy BW CC3 of the Batchworth Neighbourhood Plan 2023-2038

C26 Verification Report:

The development hereby permitted shall not be occupied until a verification report, (appended with substantiating evidence demonstrating the approved construction details and specifications have been implemented in accordance with the surface water drainage scheme), has been submitted to and approved in writing by the Local Planning Authority. The verification report shall include photographs of excavations and soil profiles/horizons, installation of any surface water structure (during construction and final make up) and Control mechanism.

Reason: To prevent flooding by ensuring the satisfactory storage of and disposal of surface water from the site in accordance with Policy CP1 of the Core Strategy (adopted October 2011) and Policy DM8 of the Development Management Policies LDD (adopted July 2013).

C27 Management and maintenance plan for the SuDS:

Upon completion of the drainage works for each site in accordance with the timing/phasing, a management and maintenance plan for the SuDS features and drainage network must be submitted to and approved in writing by the Local Planning Authority. The scheme shall include;

1. Provision of complete set of built drawings for site drainage.
2. Maintenance and operational activities.
3. Arrangements for adoption and any other measures to secure the operation of the scheme throughout its lifetime.

The development shall be carried out in accordance with the approved scheme.

Reason: To ensure the drainage strategy can be maintained throughout the lifetime of the development in accordance with Policy CP1 of the Core Strategy (adopted October 2011), Policy DM8 of the Development Management Policies LDD (adopted July 2013) and Policy BW CC3 of the Batchworth Neighbourhood Plan 2023-2038.

7.2 Informatives:

- 11 With regard to implementing this permission, the applicant is advised as follows: All relevant planning conditions must be discharged prior to the commencement of work. Requests to discharge conditions must be made by formal application. Fees are £145 per request (or £43 where the related permission is for extending or altering a dwellinghouse or other development in the curtilage of a dwellinghouse). Please note that requests made without the appropriate fee will be returned unanswered.

There may be a requirement for the approved development to comply with the Building Regulations.

Please contact Hertfordshire Building Control (HBC) on 01438 879990 or at buildingcontrol@hertfordshirebc.co.uk who will be happy to advise you on building control matters and will protect your interests throughout your build project by leading the compliance process. Further information is available at www.hertfordshirebc.co.uk.

Community Infrastructure Levy (CIL) - Your development may be liable for CIL payments and you are advised to contact the CIL Officer for clarification with regard to this (cil@threeivers.gov.uk). If your development is CIL liable, even if you have been granted exemption from the levy, please be advised that before commencement of any works it is a requirement under Regulation 67 of The Community Infrastructure Levy Regulations 2010 (As Amended) that CIL form 6 (Commencement Notice) must be completed, returned and acknowledged by Three Rivers District Council before building works start.

Failure to do so will mean you lose the right to payment by instalments (where applicable), and a surcharge will be imposed. However, please note that a Commencement Notice is not required for residential extensions IF relief has been granted.

Following the grant of planning permission by the Local Planning Authority it is accepted that new issues may arise post determination, which require modification of the approved plans. Please note that regardless of the reason for these changes, where these modifications are fundamental or substantial, a new planning application will need to be submitted. Where less substantial changes are proposed, the following options are available to applicants:

(a) Making a Non-Material Amendment

(b) Amending the conditions attached to the planning permission, including seeking to make minor material amendments (otherwise known as a section 73 application).

It is important that any modifications to a planning permission are formalised before works commence otherwise your planning permission may be unlawful and therefore could be subject to enforcement action. In addition, please be aware that changes to a development previously granted by the LPA may affect any previous Community Infrastructure Levy (CIL) owed or exemption granted by the Council. If you are in any doubt whether the new/amended development is now liable for CIL you are advised to contact the Community Infrastructure Levy Officer (01923 776611) for clarification. Information regarding CIL can be found on the Three Rivers website (<https://www.threerivers.gov.uk/services/planning/community-infrastructure-levy>)

Care should be taken during the building works hereby approved to ensure no damage occurs to the verge or footpaths during construction. Vehicles delivering materials to this development shall not override or cause damage to the public footway. Any damage will require to be made good to the satisfaction of the Council and at the applicant's expense.

Where possible, energy saving and water harvesting measures should be incorporated. Any external changes to the building which may be subsequently required should be discussed with the Council's Development Management Section prior to the commencement of work. Further information on how to incorporate changes to reduce your energy and water use is available at:

<https://www.threerivers.gov.uk/services/environment-climate-emergency/home-energy-efficiency-sustainable-living#Greening%20your%20home>

- 12 The effect of paragraph 13 of Schedule 7A to the Town and Country Planning Act 1990 is that planning permission granted for the development of land in England is deemed to have been granted subject to the condition "(the biodiversity gain condition)" that development may not begin unless:

- a) a Biodiversity Gain Plan has been submitted to the planning authority, and
- b) the planning authority has approved the plan.

The planning authority, for the purposes of determining whether to approve a Biodiversity Gain Plan if one is required in respect of this permission would be Three Rivers District Council.

There are statutory exemptions and transitional arrangements which mean that the biodiversity gain condition does not apply.

Based on the information available, this permission is considered to be one which will not require the approval of a biodiversity gain plan before development is begun because the following statutory exemption or transitional arrangement is considered to apply.

Development which is not 'major development' (within the meaning of article 2(1) of the Town and Country Planning (Development Management Procedure) (England) Order 2015) where:

- a) the application for planning permission was made before 2 April 2024
- b) planning permission is granted which has effect before 2 April 2024; or
- c) planning permission is granted on an application made under section 73 of the Town and Country Planning Act 1990 where the original permission to which the section 73 permission relates was exempt by virtue of 3 (a) or (b).

Where the local planning authority considers that the permission falls within paragraph 19 of Schedule 7A to the Town and Country Planning Act 1990, the permission which has been granted has the effect of requiring or permitting the development to proceed in phases. The modifications in respect of the biodiversity gain condition which are set out in Part 2 of the Biodiversity Gain (Town and Country Planning) (Modifications and Amendments) (England) Regulations 2024 apply.

Biodiversity gain plans are required to be submitted to, and approved by, the planning authority before development may be begun, and, if subject to phased development, before each phase of development may be begun.

If the onsite habitat includes irreplaceable habitat (within the meaning of the Biodiversity Gain Requirements (Irreplaceable Habitat) Regulations 2024) there are additional requirements for the content and approval of Biodiversity Gain Plans. The Biodiversity Gain Plan must include, in addition to information about steps taken or to be taken to minimise any adverse effect of the development on the habitat, information on arrangements for compensation for any impact the development has on the biodiversity of the irreplaceable habitat.

The planning authority can only approve a Biodiversity Gain Plan if satisfied that the adverse effect of the development on the biodiversity of the irreplaceable habitat is minimised and appropriate arrangements have been made for the purpose of compensating for any impact which do not include the use of biodiversity credits.

More information can be found in the Planning Practice Guidance online at <https://www.gov.uk/guidance/biodiversity-net-gain>.

- 13 The applicant is reminded that this planning permission is subject to either a unilateral undertaking or an agreement made under the provisions of Section 106 of the Town and Country Planning Act 1990. It is extremely important that the applicant is aware of the stipulations, covenants and obligations set out within any legal agreements tied to the planning permission. This may include the requirement to notify the Council prior to commencement of the development (as defined within the legal agreement) if certain obligations are required to be paid, for example, an affordable housing contribution including indexation.

- 14 The Local Planning Authority has been positive and proactive in its consideration of this planning application, in line with the requirements of the National Planning Policy Framework and in accordance with the Town and Country Planning (Development Management Procedure) (England) Order 2015

The Local Planning Authority suggested modifications to the development during the course of the application and the applicant and/or their agent submitted amendments which result in a form of development that maintains/improves the economic, social and environmental conditions of the District.

- 15 Waste Comments

The application indicates that SURFACE WATER will NOT be discharged to the public network and as such Thames Water has no objection, however approval should be sought from the Lead Local Flood Authority. Should the applicant subsequently seek a connection to discharge surface water into the public network in the future then we would consider this to be a material change to the proposal, which would require an amendment to the application at which point we would need to review our position.

Thames Water would advise that with regard to FOUL WATER sewerage network infrastructure capacity, we would not have any objection to the above planning application, based on the information provided.

Thames Water recognises this catchment is subject to high infiltration flows during certain groundwater conditions. The scale of the proposed development doesn't materially affect the sewer network and as such we have no objection, however care needs to be taken when designing new networks to ensure they don't surcharge and cause flooding. In the longer term Thames Water, along with other partners, are working on a strategy to reduce groundwater entering the sewer networks.

Water Comment

The applicant is advised that their development boundary falls within a Source Protection Zone for groundwater abstraction. These zones may be at particular risk from polluting activities on or below the land surface. To prevent pollution, the Environment Agency and Thames Water (or other local water undertaker) will use a tiered, risk-based approach to regulate activities that may impact groundwater resources. The applicant is encouraged to read the Environment Agency's approach to groundwater protection (available at <https://www.gov.uk/government/publications/groundwaterprotectionposition-statements>) and may wish to discuss the implication for their development with a suitably qualified environmental consultant.

With regard to water supply, this comes within the area covered by the Affinity Water Company. For your information the address to write to is - Affinity Water Company The Hub, Tamblin Way, Hatfield, Herts, AL10 9EZ - Tel - 0845 782 3333.

Water efficiency

Being within a water stressed area, we expect that the development includes water efficient fixtures and fittings. Measures such as rainwater harvesting and grey water recycling help the environment by reducing pressure for abstractions in chalk stream catchments. They also minimise potable water use by reducing the amount of potable water used for washing, cleaning and watering gardens. This in turn reduces the carbon emissions associated with treating this water to a standard suitable for drinking, and will help in our efforts to get emissions down in the borough.

Infrastructure connections and diversions

There are potentially water mains running through or near to part of proposed development site. If the development goes ahead as proposed, the developer will need to get in contact with our Developer Services Team to discuss asset protection or diversionary measures. This can be done through the My Developments Portal (<https://affinitywater.custhelp.com/>) or [w_developerservices@custhelp.com](mailto:aw_developerservices@custhelp.com).

In this location Affinity Water will supply drinking water to the development. To apply for a new or upgraded connection, please contact our Developer Services Team by going through their My Developments Portal (<https://affinitywater.custhelp.com/>) or aw_developerservices@custhelp.com. The Team also handle C3 and C4 requests to cost potential water mains diversions. If a water mains plan is required, this can also be obtained by emailing maps@affinitywater.co.uk. Please note that charges may apply.

16 The applicant is hereby advised to remove all site notices on or near the site that were displayed pursuant to the application.

17 Highway Authority:

Storage of materials:

The applicant is advised that the storage of materials associated with the construction of this development should be provided within the site on land which is not public highway, and the use of such areas must not interfere with the public highway. If this is not possible, authorisation should be sought from the Highway Authority before construction works commence.

Further information is available via the website <https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/highways-roads-and-pavements.aspx> or by telephoning 0300 1234047.

Obstruction of public highway land:

It is an offence under section 137 of the Highways Act 1980 for any person, without lawful authority or excuse, in any way to wilfully obstruct the free passage along a highway or public right of way. If this development is likely to result in the public highway or public right of way network becoming routinely blocked (fully or partly) the applicant must contact the Highway Authority to obtain their permission and requirements before construction works commence. Further information is available via the website

<https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/highways-roads-and-pavements.aspx> telephoning 0300 1234047.

Road Deposits:

It is an offence under section 148 of the Highways Act 1980 to deposit mud or other debris on the public highway, and section 149 of the same Act gives the Highway Authority powers to remove such material at the expense of the party responsible. Therefore, best practical means shall be taken at all times to ensure that all vehicles leaving the site during construction of the development are in a condition such as not to emit dust or deposit mud, slurry or other debris on the highway. Further information is available via the website

<https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/highways-roads-and-pavements.aspx> or by telephoning 0300 1234047.

Estate Road Adoption:

The applicant is advised that Hertfordshire County Council as Highway Authority no longer adopts new highway as maintainable at the public expense unless a wider public benefit can be demonstrated. The developer should put in place a permanent arrangement for long term maintenance, and at the entrance of any such residential estates, a road name plate should indicate that it is a private road to inform purchasers of their future maintenance liabilities. Further information is available via the website

<https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/highways-roads-and-pavements.aspx> or by telephoning 0300 1234047.

Works within the highway (section 278):

The applicant is advised that in order to comply with this permission it will be necessary for the developer of the site to enter into an agreement with Hertfordshire County Council as Highway Authority under Section 278 of the Highways Act 1980 to ensure the satisfactory completion of the access and associated road improvements. The construction of such works must be undertaken to the satisfaction and

specification of the Highway Authority, and by a contractor who is authorised to work in the public highway. Before works commence the applicant will need to apply to the Highway Authority to obtain their permission and requirements. Further information is available via the County Council website at:

<https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/business-and-developer-information/development-management/highways-development-management.aspx> or by telephoning 0300 1234047.

Travel Plan (TP):

- i) A revised and approved Travel Plan at least 3 months before first occupation, consisting of a written agreement with the County Council which sets out a scheme to encourage, regulate, and promote sustainable travel measures for owners, occupiers, and visitors to the Development in accordance with the provisions of the County Council's Travel Plan Guidance (March 2020) or any subsequent replacement guidance.
- ii) The Travel Plan is subject to an 'Evaluation and Support Contribution' totalling £6,000 (index linked by RPI from March 2014), payable before first occupation of the development. This contribution is to cover the County Council's costs of administrating and monitoring the objectives of the Travel Plan and engaging in any Travel Plan Review. The applicant's attention is drawn to Hertfordshire County Council's guidance on Travel Plans in this respect.
- iii) A Travel Plan Remedial Measures Notice clause within the Legal Agreement, enabling the County Council to serve notice in writing on the Owner via the Travel Plan Co-ordinator where the Owner has failed to meet one or more of the targets identified in the Travel Plan, and specifying the remedial measures and/or actions required to be taken by the Owner to remedy the failed implementation towards the agreed targets with a reasonable time provision.

18 Environment Agency Advice:

We note that a Generic Quantitative Risk Assessment (GQRA) has been provided in the Phase II Geoenvironmental Assessment prepared by Delta Simons (Ref: 98854.599535, dated June 2024). The GQRA ruled out risks to groundwater quality as no groundwater strikes were encountered during the investigation works. However section 2.5.1 Ground Investigation Works of the report titled 'HCP Watford - Surface water drainage strategy' prepared by Evolve (Ref: 3681-EVE-00-XX-T-C-0130 dated June 2024) provides evidence for the existence of a licensed groundwater abstraction for spray irrigation located on-site, and data from nearby adjacent sites indicate that the permanent water table varies from a depth of approximately 5 – 12 m bgl in the vicinity of the site. As such, we are not comfortable that the hydrogeological situation beneath the proposed development site has been adequately assessed. Given the industrial usage of the site we feel that groundwater quality information from beneath the site will be required to inform the risk assessment and remediation strategy to enable the redevelopment of the site.

Due to vulnerability of the principal chalk aquifer, its limited natural protection to Groundwater, the site investigation would need to cover the entirety of the developing area, including all areas of the proposed buildings to be demolished, in order to satisfy (3).

The use of piled foundations and other types of intrusive groundworks have the potential to create new pollutant linkages, potentially resulting in the deterioration of groundwater quality beneath the site.

If piling techniques will be used during the construction of this development, information to address the above issues will need to be included as part of a risk assessment and should consider the following:

- identification of relevant receptors and baseline monitoring;
- determination of contaminants of concern and establishment of trigger values;
- a monitoring strategy to be implemented during and after piling;

Deep-piled foundations that could penetrate into the sensitive chalk aquifers that underlie the site would significantly alter the risk profile with respect to groundwater quality for this development, and we strongly recommend exploring the feasibility of shallower foundations as much as possible.

Water Resources

Increased water efficiency in new developments potentially enables more growth to be realised without an increased availability of water resources. Developers can highlight responsible water use as a positive corporate social responsibility message that will boost the commercial appeal of the development. For the homeowner/tenant, lower water usage also reduces water and energy bills.

We endorse the use of water efficiency measures in all developments, particularly in those that are new. Use of technology that ensures efficient use of natural resources could support the environmental benefits of future proposals and could help attract investment to the area. Therefore, water efficient technology, fixtures and fittings should be all considered as an integral part of new developments and/or refurbishments. The technology used to achieve improved water efficiency (e.g. efficient fittings, greywater recycling, etc) is also an attractive feature for many prospective building owners and tenants.

Commercial/Industrial developments

We recommend that all new non-residential developments of 1000sqm gross floor area or more (i.e. 'major' developments) should achieve the BREEAM 'excellent' standard for water consumption (category 'WAT 01'), or equivalent. This standard may already be a requirement of the local planning authority.

We also recommend you contact your local planning authority for more information.

Pre-Application Advice

Regarding future applications, if you would like us to review a revised technical report prior to a formal submission, outside of a statutory consultation, and/or meet to discuss our position, this will be chargeable in line with our planning advice service. If you wish to request a document review or meeting, please contact our team email address at HNLsustainableplaces@environment-agency.gov.uk.

Further information on our charged planning advice service is available at:

<https://www.gov.uk/government/publications/planning-advice-environment-agencystandard-terms-and-conditions>.

This page is intentionally left blank


Appendix 1: Comparisons and photographs

Larger windows and change to stairwell windows to the northern elevation:

As approved:



Proposed:



Plans updated to ensure consistency between floor plans and elevations plus safety railing added to eastern elevation

As approved:




Proposed:



Addition of roof hatches:


As approved:

ROOF PLAN:



Proposed:

ROOF PLAN:



Omission of external stack balconies to western elevation and corner elevations:

As approved:




Proposed:




Site Layouts:

As approved:



Proposed:



Photographs:














Above: AOV windows to northern elevation



Above: Restrictor to stairwell windows.

From Ebury Road:





PLANNING COMMITTEE – 22 January 2026

25/1722/RSP – Part Retrospective: Construction of two outbuildings and alterations to rear land levels and landscaping works at 38 MOOR LANE, RICKMANSWORTH, HERTFORDSHIRE, WD3 1LG

Parish: Batchworth Community Council.

Ward: Rickmansworth Town

Expiry of Statutory Period: 03.12.2025
Extension of time agreed to 26.01.26

Case Officer: Lauren Edwards

Recommendation: That Part Retrospective Planning Permission be approved subject to conditions.

Reason for consideration by the Committee: The application has been called in by the Parish Council as detailed at 4.1.2 below.

To view all documents forming part of this application please go to the following website:

<https://www3.threerivers.gov.uk/online-applications/applicationDetails.do?activeTab=documents&keyVal=T3QXZ9QFIC400>

1 Relevant planning and enforcement history

- 1.1 W/4865/73 - Garage - Permitted
- 1.2 24/1071/FUL - Construction of two storey rear extension, loft conversion including rear dormer and front/side rooflights, internal alterations, rear juliet balcony, addition of windows to side elevations – Permitted, currently under construction.
- 1.3 25/1495/CLPD - Certificate of Lawfulness Proposed Development: Construction of an outbuilding – Permitted
- 1.4 25/0095/COMP- Enforcement enquiry- pending consideration.

2 Site description

- 2.1 The application site is an irregular shaped plot and is located on the southern side of Moor Lane, Rickmansworth. Land levels slope steeply upwards from the highway towards the rear of the site. The application dwelling is a detached two storey dwelling and is currently implementing the extensions consented via 24/1071/FUL.
- 2.2 To the front of the site is a driveway with steps up onto a terraced front garden. To the rear is a patio which steps up to an area of lawn.
- 2.3 The neighbour at No.36 is a detached two storey dwelling and extends deeper than the application dwelling at the rear.
- 2.4 The neighbour at No.40 is a two storey detached dwelling finished in a cream painted render and extends deeper than the application dwelling at the rear.

3 Description of proposed development and background

- 3.1 This application seeks part retrospective planning permission for the construction of two outbuildings and alterations to rear land levels and landscaping works.

- 3.2 The previous condition of the rear garden was such that there were 4 main sections; a patio at the ground level adjacent to the house, 2 sections of sloping lawn and a flat section at the rearmost parcel.
- 3.3 The land levels in situ still comprise of 4 similar sections however each level is now flat. In order to accommodate the extension and new patio these sections have also moved rearwards. Retaining walls have been constructed with central steps to facilitate the level changes.
- 3.4 Two outbuildings have been constructed which are located on the third level from the dwelling. They are built against the retaining wall of the highest section.
- 3.5 Outbuilding A which is located to the western side has a width of 5.5m and a depth of 4.5m. This building has a flat roof with a height of 2.5m (level with the upper level) and has a green roof.
- 3.6 Outbuilding B is located to the eastern side and has a width of 6m and a depth of 4.5m. This outbuilding has a height of 3.5m (protruding 1m above the highest section of the garden).
- 3.7 Amended plans have been received to confirm the use of the outbuildings (Outbuilding A would be a store/shed and outbuilding B would be a games room). The fenestration serving outbuilding B has also been revised on the drawings to accurately reflect that in situ.

4 Consultation

4.1 Statutory Consultation

4.1.1 National Grid: [No response received]

4.1.2 Batchworth Parish Council: [Objection]

BCC strongly objects to this application which was initially based on 25/1495/CLPD. However, what has been built is an unlawful development of this plan, which will almost certainly adversely affect the neighbouring properties and their amenity space.

There are also no details on the possible effect on drainage and water course.

BCC would like to call this application to committee unless officers are minded to refuse.

Officer comment: The scheme subject to 25/1495/CLPD pertained solely to an outbuilding that was to be sited on the patio level immediately adjacent the rear elevation of the dwelling. It did not include the elements subject to this application. During the course of the investigation of an enforcement enquiry it was ascertained that the works that had been undertaken relating to the development subject to this application (land level changes and construction of two different outbuildings, unrelated to that subject of 25/1495/CLPD) were not considered to be permitted development and express planning permission was required. As a result this application was submitted which seeks to remedy the breach by obtaining retrospective planning permission. All material considerations including drainage and the impact on neighbouring amenity is considered below.

4.2 Public/Neighbour Consultation

4.2.1 Neighbours consulted: 2

4.2.2 Responses received: 0

4.2.3 Site Notice: Expired 11.11.2025.

4.2.4 Press Notice: Not required

5 Reason for Delay

5.1 Committee cycle.

6 Relevant Planning Policy, Guidance and Legislation

6.1 Planning applications are required to be determined in accordance with the statutory development plan unless material considerations indicate otherwise as set out within S38 (6) Planning and Compulsory Purchase Act 2004 and S70 of Town and Country Planning Act 1990).

6.2 National Planning Policy Framework and National Planning Practice Guidance

In 2024 the new National Planning Policy Framework was published. This is read alongside the National Planning Practice Guidance (NPPG). The determination of planning applications is made mindful of Central Government advice and the Local Plan for the area. It is recognised that Local Planning Authorities must determine applications in accordance with the statutory Development Plan, unless material considerations indicate otherwise, and that the planning system does not exist to protect the private interests of one person against another. The NPPF is clear that “existing policies should not be considered out-of-date simply because they were adopted or made prior to the publication of this Framework. Due weight should be given to them, according to their degree of consistency with this Framework”.

The NPPF states that 'good design is a key aspect of sustainable development, creates better places in which to live and work and helps make development acceptable to communities'. The NPPF retains a presumption in favour of sustainable development. This applies unless any adverse impacts of a development would 'significantly and demonstrably' outweigh the benefits.

6.3 The Three Rivers Local Plan

The application has been considered against the policies of the Local Plan, including the Core Strategy (adopted October 2011), the Development Management Policies Local Development Document (adopted July 2013) and the Site Allocations Local Development Document (adopted November 2014) as well as government guidance. The policies of Three Rivers District Council reflect the content of the NPPF.

The Core Strategy was adopted on 17 October 2011 having been through a full public participation process and Examination in Public. Relevant policies include Policies CP1, CP9, CP10 and CP12.

The Development Management Policies Local Development Document (DMLDD) was adopted on 26 July 2013 after the Inspector concluded that it was sound following Examination in Public which took place in March 2013. Relevant policies include DM1, DM4, DM6, DM8, DM13 and Appendices 2 and 5.

The Batchworth Neighbourhood Plan 2023-2038 (adopted May 2025). Relevant policies include Policies BW GB1 and BW DE1.

6.4 Other

The Community Infrastructure Levy (CIL) Charging Schedule (adopted February 2015).

The Localism Act received Royal Assent on 15 November 2011. The growth and Infrastructure Act achieved Royal Assent on 25 April 2013.

The Wildlife and Countryside Act 1981 (as amended), the Conservation of Habitats and Species Regulations 2010, the Natural Environment and Rural Communities Act 2006 and the Habitat Regulations 1994 may also be relevant.

Environment Act 2021.

7 Planning Analysis

7.1 Impact on the character and appearance of the host dwelling and the locality

- 7.1.1 Policy CP1 of the Core Strategy (adopted October 2011) seeks to promote buildings of a high enduring design quality that respect local distinctiveness and Policy CP12 of the Core Strategy relates to design and states that in seeking a high standard of design, the Council will expect development proposals to have regard to the local context and conserve or enhance the character, amenities and quality of an area.
- 7.1.2 Policy BW DE1 sets out that new development in the Batchworth Neighbourhood Plan area shall be based upon a design-led approach to development underpinned by good practice principles and reflecting a thorough site appraisal. Respond positively to guidance and principles established in the Batchworth Neighbourhood Design Code, including but not limited to prevailing building heights, materials, development frontages, plot widths, boundary treatments and street enclosure.
- 7.1.3 Owing to the land level changes across the site from the highway, the garden and outbuildings are visible from some oblique views along Moor Lane. However all of the dwellings on this side of Moor Lane have sloping land levels and as such there have been a variety of physical interventions made including different levelling works and retaining walls/steps which are evident across the rear gardens of neighbouring properties. As such it is not considered that the land level alterations and retaining walls appear as unduly prominent or incongruous additions to the character of the locality.
- 7.1.4 The outbuildings in situ are not excessive in their overall scale such that they appear disproportionate to the application site. They are contemporary in their design with dark cladding and green roofs however this reflects and compliments the dark slate used for the retaining walls and overall it is not considered that they appear as unduly prominent additions to either the application site or wider streetscene.
- 7.1.5 In summary it is not considered that the proposed development would result in any adverse impact on the character or appearance of the host dwelling, streetscene or area and the development would be acceptable in this regard in accordance with Policies CP1 and CP12 of the Core Strategy, Policy DM1 and Appendix 2 of the DMP LDD and Policy CA2 of the Croxley Green Neighbourhood Plan.

7.2 Impact on amenity of neighbours

- 7.2.1 Policy CP12 of the Core Strategy states that development should 'protect residential amenities by taking into account the need for adequate levels and disposition of privacy, prospect, amenity and garden space'. Policy DM1 and Appendix 2 of the Development Management Policies document set out that development should not result in loss of light to the windows of neighbouring properties nor allow overlooking and should not be excessively prominent in relation to adjacent properties.
- 7.2.2 The resultant land levels are such that no point would be higher overall than the previous sections. It is noted that some views could be had from the upper levels towards neighbouring gardens however it is not considered that unacceptable overlooking would now occur in comparison with the pre-existing condition of the land and inherent views from the change in levels along this side of Moor Lane. Owing to the separation distances from

the rear of neighbouring properties, together with modest scale and siting, it is not considered that the outbuildings have resulted in an overbearing impact or loss of light to neighbouring amenity. Owing to the positioning of the outbuildings against the retaining wall and mature boundary vegetation it is not considered that outbuildings would result in unacceptable overlooking towards neighbouring properties.

- 7.2.3 In summary it is not considered that the development in situs results in any adverse impact on the residential amenity of any neighbouring dwelling so as to justify refusal of the application in this regard and the development would therefore be acceptable in this regard in accordance with Policies CP1 and CP12 of the Core Strategy (adopted October 2011) and Policy DM1 and Appendix 2 of the Development Management Policies LDD (adopted July 2013).

7.3 Highways & Parking

- 7.3.1 Core Strategy Policy CP10 requires development to provide a safe and adequate means of access and to make adequate provision for all users, including car parking. Policy DM13 and Appendix 5 of the Development Management Policies document set out parking standards.

- 7.3.2 The development does not impact the requirement for or the provision of parking.

7.4 Rear Garden Amenity Space

- 7.4.1 Policy CP12 of the Core Strategy states that development should take into account the need for adequate levels and disposition of privacy, prospect, amenity and garden space.

- 7.4.2 The development has not increased the amount of bedrooms the dwelling has and ample useable garden is retained to serve a dwelling of this size.

7.5 Trees & Landscape

- 7.5.1 Policy DM6 of the Development Management Policies LDD sets out that development proposals should seek to retain trees and other landscape and nature conservation features, and that proposals should demonstrate that trees will be safeguarded and managed during and after development in accordance with the relevant British Standards.

- 7.5.2 The application site is not located within a conservation area nor are there protected trees on or near the site. As such it is not considered that the proposal has/or would have an unacceptable impact in this respect.

7.6 Biodiversity

- 7.6.1 Section 40 of the Natural Environment and Rural Communities Act 2006 requires Local Planning Authorities to have regard to the purpose of conserving biodiversity. This is further emphasised by regulation 3(4) of the Habitat Regulations 1994 which state that Councils must have regard to the strict protection for certain species required by the EC Habitats Directive. The Habitats Directive places a legal duty on all public bodies to have regard to the habitats directive when carrying out their functions.

- 7.6.2 The protection of biodiversity and protected species is a material planning consideration in the assessment of this application in accordance with Policy CP9 of the Core Strategy and Policy DM6 of the Development Management Policies document. National Planning Policy requires Local Authorities to ensure that a protected species survey is undertaken for applications where biodiversity may be affected prior to the determination of a planning application. A Biodiversity Checklist was submitted with the application and states that no protected species or biodiversity interests will be affected as a result of the application.

7.9 Biodiversity Net Gain

7.9.1 Paragraph 13 of Schedule 7A of the Town and Country Planning Act 1990 sets out that every planning permission granted for the development of land in England shall be deemed to have been granted subject to the 'biodiversity gain condition' requiring development to achieve a net gain of 10% of biodiversity value. This is subject to exemptions as set out in The Biodiversity Gain Requirements (Exemptions) Regulations 2024.

7.9.2 In this case a biodiversity net gain plan would not be required owing to the retrospective and householder nature of the development.

7.7 Flooding and drainage

7.7.1 The application site is not located within an area at risk of flooding as identified by the Environment Agency (very low risk of surface water flooding and very low change of flooding from rivers and the sea). It is noted that there have been physical interventions to alter the land levels however areas of lawn have been retained and more flat sections of ground created in comparison to the pre-existing slope. Overall it is not considered that the development has or would result in any significant adverse increase in surface water flooding across the site.

8 **Recommendation**

8.1 That PART RETROSPECTIVE PLANNING PERMISSION BE GRANTED subject to conditions:

C1 The development hereby permitted shall be carried out and maintained in accordance with the following approved plans: 2403-LA-01 REV A, 2403-LA-02 REV C, 2403-LA-03 REV C, 2403-LA-04 REV C, 2403-LA-07 REV A, 2403-PL-08 REV C, 23758-TOPO (Existing), 23758-TOPO (Proposed)

Reason: For the avoidance of doubt, in the proper interests of planning and in accordance with Policies CP1, CP9, CP10 and CP12 of the Core Strategy (adopted October 2011), Policies DM1, DM6, DM8, DM9, DM13 and Appendices 2 and 5 of the Development Management Policies LDD (adopted July 2013) and the Batchworth Neighbourhood Plan (2025).

C2 The outbuildings hereby permitted shall not be occupied or used at any time other than incidental to the enjoyment of, or ancillary to, the residential dwelling located on the site and it shall not be used as an independent dwelling or for commercial purposes at any time.

Reason: The creation and use of a separate and independent unit would not comply with Policies CP1 and CP12 of the Core Strategy (adopted October 2011) and Policy DM1 and Appendix 2 of the Development Management Policies LDD (adopted July 2013).

8.2 Informatives

I1 With regard to implementing this permission, the applicant is advised as follows:

All relevant planning conditions must be discharged prior to the commencement of work. Requests to discharge conditions must be made by formal application. Fees are £145 per request (or £43 where the related permission is for extending or altering a dwellinghouse or other development in the curtilage of a dwellinghouse). Please note that requests made without the appropriate fee will be returned unanswered.

There may be a requirement for the approved development to comply with the Building Regulations. Please contact Hertfordshire Building Control (HBC) on 01438 879990 or at buildingcontrol@hertfordshirebc.co.uk who will be happy to advise you on building control matters and will protect your interests throughout your build project by leading the compliance process. Further information is available at www.hertfordshirebc.co.uk.

Community Infrastructure Levy (CIL) - Your development may be liable for CIL payments and you are advised to contact the CIL Officer for clarification with regard to this (cil@threerivers.gov.uk). If your development is CIL liable, even if you have been granted exemption from the levy, please be advised that before commencement of any works it is a requirement under Regulation 67 of The Community Infrastructure Levy Regulations 2010 (As Amended) that CIL form 6 (Commencement Notice) must be completed, returned and acknowledged by Three Rivers District Council before building works start. Failure to do so will mean you lose the right to payment by instalments (where applicable), and a surcharge will be imposed. However, please note that a Commencement Notice is not required for residential extensions IF relief has been granted.

Following the grant of planning permission by the Local Planning Authority it is accepted that new issues may arise post determination, which require modification of the approved plans. Please note that regardless of the reason for these changes, where these modifications are fundamental or substantial, a new planning application will need to be submitted. Where less substantial changes are proposed, the following options are available to applicants:

{\b (a)} Making a Non-Material Amendment

{\b (b)} Amending the conditions attached to the planning permission, including seeking to make minor material amendments (otherwise known as a section 73 application).

It is important that any modifications to a planning permission are formalised before works commence otherwise your planning permission may be unlawful and therefore could be subject to enforcement action. In addition, please be aware that changes to a development previously granted by the LPA may affect any previous Community Infrastructure Levy (CIL) owed or exemption granted by the Council. If you are in any doubt whether the new/amended development is now liable for CIL you are advised to contact the Community Infrastructure Levy Officer (01923 776611) for clarification. Information regarding CIL can be found on the Three Rivers website (<https://www.threerivers.gov.uk/services/planning/community-infrastructure-levy>).

Care should be taken during the building works hereby approved to ensure no damage occurs to the verge or footpaths during construction. Vehicles delivering materials to this development shall not override or cause damage to the public footway. Any damage will require to be made good to the satisfaction of the Council and at the applicant's expense.

Where possible, energy saving and water harvesting measures should be incorporated. Any external changes to the building which may be subsequently required should be discussed with the Council's Development Management Section prior to the commencement of work. Further information on how to incorporate changes to reduce your energy and water use is available at: <https://www.threerivers.gov.uk/services/environment-climate-emergency/home-energy-efficiency-sustainable-living#Greening%20your%20home>.

- 12 The applicant is reminded that the Control of Pollution Act 1974 stipulates that construction activity (where work is audible at the site boundary) should be restricted to 0800 to 1800 Monday to Friday, 0900 to 1300 on Saturdays and not at all on Sundays and Bank Holidays.
- 13 The Local Planning Authority has been positive and proactive in its consideration of this planning application, in line with the requirements of the National Planning Policy Framework and in accordance with the Town and Country Planning (Development Management Procedure) (England) Order 2015. The development maintains/improves the economic, social and environmental conditions of the District.
- 15 The effect of paragraph 13 of Schedule 7A to the Town and Country Planning Act 1990 is that planning permission granted for the development of land in England is deemed to have

been granted subject to the condition "(the biodiversity gain condition)" that development may not begin unless:

- a) a Biodiversity Gain Plan has been submitted to the planning authority, and
- b) the planning authority has approved the plan.

The planning authority, for the purposes of determining whether to approve a Biodiversity Gain Plan if one is required in respect of this permission would be Three Rivers District Council.

There are statutory exemptions and transitional arrangements which mean that the biodiversity gain condition does not apply.

Based on the information available this permission is considered to be one which will not require the approval of a biodiversity gain plan before development is begun because the following statutory exemption or transitional arrangement is considered to apply.

Development which is subject of a householder application within the meaning of article 2(1) of the Town and Country Planning (Development Management Procedure) (England) Order 2015. A "householder application" means an application for planning permission for development for an existing dwellinghouse, or development within the curtilage of such a dwellinghouse for any purpose incidental to the enjoyment of the dwellinghouse which is not an application for change of use or an application to change the number of dwellings in a building.



Where the local planning authority considers that the permission falls within paragraph 19 of Schedule 7A to the Town and Country Planning Act 1990, the permission which has been granted has the effect of requiring or permitting the development to proceed in phases. The modifications in respect of the biodiversity gain condition which are set out in Part 2 of the Biodiversity Gain (Town and Country Planning) (Modifications and Amendments) (England) Regulations 2024 apply.

Biodiversity gain plans are required to be submitted to, and approved by, the planning authority before development may be begun, and, if subject to phased development, before each phase of development may be begun.

If the onsite habitat includes irreplaceable habitat (within the meaning of the Biodiversity Gain Requirements (Irreplaceable Habitat) Regulations 2024) there are additional requirements for the content and approval of Biodiversity Gain Plans. The Biodiversity Gain Plan must include, in addition to information about steps taken or to be taken to minimise any adverse effect of the development on the habitat, information on arrangements for compensation for any impact the development has on the biodiversity of the irreplaceable habitat.

The planning authority can only approve a Biodiversity Gain Plan if satisfied that the adverse effect of the development on the biodiversity of the irreplaceable habitat is minimised and appropriate arrangements have been made for the purpose of compensating for any impact which do not include the use of biodiversity credits.

More information can be found in the Planning Practice Guidance online at <https://www.gov.uk/guidance/biodiversity-net-gain>.





PLANNING COMMITTEE - Thursday 22 January 2026

25/1754/ADV - Advertising Consent: Display of flags at THREE RIVERS HOUSE, NORTHWAY, RICKMANSWORTH, HERTFORDSHIRE, WD3 QRL

Parish: Batchworth Community Council
Expiry of Statutory Period: 28.01.2026

Ward: Rickmansworth Town
Case Officer: Lilly Varnham

Recommendation: That ADVERTISEMENT CONSENT BE GRANTED subject to conditions.

Reason for consideration by the Committee: The applicant is Three Rivers District Council.

To view all documents forming part of this application please go to the following website:

[25/1754/ADV | Advertising Consent: Display of flags | Three Rivers House Northway Rickmansworth Hertfordshire WD3 1RL](#)

1 Relevant planning history

- 1.1 8/120/88: Erection of office building and ancillary car park. Permitted and implemented.
- 1.2 10/2174/FUL: Change of use of part of the ground floor of Three Rivers House to a police station with associated parking, including the erection of a small storage shed. Permitted and implemented.
- 1.3 12/1444/FUL: Change of use of part of ground floor from Council office space to use as part of Police Station either for office use or locker/amenity area and for storage; increase in parking from 12 spaces to 25 spaces. Permitted and implemented.
- 1.4 12/1981/FUL: Reallocation of parking spaces at Three Rivers House to provide 25 spaces in total (increase of 13) for the Police in order to provide sufficient parking for Intervention Team Officers. Erection of 2 metre high green paladin fencing to side of bays 20 and 21 (Rose Garden) and automatic barrier. Permitted and implemented.
- 1.5 15/1874/FUL: District Council Application: Installation of photovoltaic panels to roofslopes – Permitted and implemented.
- 1.6 22/2255/FUL: Installation of 7no. Air source heat pumps within timber enclosure in south western corner of top floor of car park – Permitted and Implemented.
- 1.7 25/1595/PDNE - Permitted Development Notice: Installation of solar panels – Permitted. Not Implemented.

2 Site description

- 2.1 Three Rivers House is the principal office of Three Rivers District Council, additionally, following the grant of planning permission 10/2174/FUL a large section of the East Wing of the building has been occupied by the Police since February 2011 following the closure of Rickmansworth Police Station. The application relates only to the two areas of the building where there are existing and well-established flagpoles. The site is located within the Rickmansworth Town Centre Conservation Area.
- 2.2 The building is three storeys but when viewed from the north it has a two-storey appearance due to the change in levels on Northway rising up to the north from the south. There is a double decked car park to the east of the office building with a public right of way crossing it in an east to west direction between the Cloisters to the east and Northway to the west.
- 2.3 To the south of the building is Basing House, a two storey Grade II Listed Building, and Rickmansworth Library, a single storey flat roofed building. Beyond the library is the High Street which is mainly occupied by commercial premises.

3 Description of proposed development

- 3.1 This application seeks advertisement consent to allow for the flying of various flags at Three Rivers House which do not benefit from deemed consent under The Town and Country Planning (Control of Advertisements) (England) Regulations 2007 (as amended) and therefore require advertisement consent.
- 3.2 The list of flags proposed have been included with this application and include the following: 1978 Pride Flag (Rainbow), Armed Forces, Commonwealth, Emergency Services, Ensign, Holocaust Memorial Day, Intersex-Inclusive Progress Pride Flag, NHS, Pride, Progress Pride Flag, St George, TRDC, Ukraine, Union / Union Jack and White Ribbon Flag.
- 3.3 Some of the flags in the above list do not require consent, these include the Armed Forces Day flag, flag of the Commonwealth, the Union/Union Jack Flag and St George Flag as these fall under Schedule 1 Class H of the Regulations but have been included within the list for completeness.
- 3.4 The flags will be flown on two existing flag poles at Three Rivers House, one of which faces west towards Northway and the other north towards Three Rivers Rose Garden Car Park. It is understood that the dimensions of the flags are 1.52m x 0.91m with the exception of the Union/Union Jack flag which has a maximum size 1.6m x 1m. The height from the ground to the base of the advertisement is 6m and the maximum projection of the advertisement from the face of the building is 1m.
- 3.5 The flags are not illuminated and are a knitted or woven polyester.

4 Consultee responses

- 4.1 National Grid – [No response received]
- 4.2 Batchworth Community Council - BCC notices that the Union Flag is not included in the illustrated list and wishes for it to be added for inclusion.
- 4.3 Conservation Officer – [No Objection]

Three Rivers House is in the Rickmansworth Conservation Area and is not a nationally or locally listed building. The proposed flag location faces towards the Grade II listed War Memorial Statue (List Entry Number: 1348251). It is also close to the Grade II listed Basing House (List Entry Number: 1100850).

The proposed flagpole and flags are appropriate for this location; they would not impact the setting of the designated heritage assets described above.

On this basis, there is no heritage objection to the proposal.

This response has been made with regard to Sections 72 (1) and 66 (1) of the Planning Listed Buildings and Conservation Areas) Act 1990 and the National Planning Policy Framework Chapter 16 'Conserving and Enhancing the Historic Environment'.

- 4.4 **Officer Comment:** Comments from the parish are noted. The list of flags has been updated to include the Union Flag.

5 Neighbour consultation

- 5.1 Site Notice Posted: 11.07.2025, Expired: 01.08.2025
- 5.2 Press Notice Published: 11.07.2025, Expired: 01.08.2025
- 5.3 No. consulted: 0 No. of responses: 1 [1 Objection Received]
- 5.4 Summary of responses:

- Support display of official, unifying civic flags only: The Union Flag, the St George's Cross, and appropriate County/Town or civic ceremonial flags.
- Broad consent would allow non-official, campaign, pressure-group or politically associated flags/ When a flag is flown it will be widely interpreted as an official Council endorsement, undermining confidence in the Councils neutrality and risking division in the community.
- Approval would set an unhelpful precedent. Once wide permissions exists, refusing future requests becomes contentious and invites disputes about which causes qualify, drawing the Council into political or international controversies outside its proper civic role.
- From an amenity perspective, a changing range of flags can create visual clutter and harm the appearance of a prominent public building and the streetscene.
- There are also safety and security risks: contentious displays can attract protests, counter-protests or vandalism, increasing risk to staff and visitors and creating avoidable expense.
- A wider flag programme brings ongoing cost for purchase, replacement, storage and maintenance, plus staff time to manage requests and complaints, and the costs of the consent process itself.
- Application should be refused. Or approved only with strict conditions limiting flags to official national and local civic/ceremonial flags, with clear limits on number, size, siting and duration, backed by a published policy protecting political neutrality and community cohesion.

Officer Comment: Comments from the neighbour are noted. The only flags proposed are those listed within the submission.

6 Relevant Local and National Planning Policies

6.1 Legislation

Outdoor advertisements are within the scope of the control regime specified by the Secretary of State in the Town and Country Planning (Control of Advertisements) Regulations 2007 (as amended).

S72 of Planning (Listed Buildings and Conservation Areas) Act 1990 requires LPAs to have special regard to the desirability of preserving or enhancing the character or appearance of conservation areas.

The Localism Act received Royal Assent on 15 November 2011. The Growth and Infrastructure Act achieved Royal Assent on 25 April 2013.

The Wildlife and Countryside Act 1981 (as amended), the Conservation of Habitats and Species Regulations 2010, the Natural Environment and Rural Communities Act 2006 and the Habitat Regulations 1994 may also be relevant.

The Environment Act 2021.

6.2 Policy/Guidance

National Planning Policy Framework and National Planning Practice Guidance

In December 2024 the revised NPPF was published, to be read alongside the online National Planning Practice Guidance. The 2024 NPPF is clear that "existing policies should not be considered out-of-date simply because they were adopted or made prior to the publication of this Framework. Due weight should be given to them, according to their degree of consistency with this Framework".

The NPPF retains a presumption in favour of sustainable development. This applies unless any adverse impacts of a development would 'significantly and demonstrably' outweigh the benefits unless there is a clear reason for refusing the development (harm to a protected area).

The Three Rivers Local Development Plan

The application has been considered against the policies of the Local Plan, including the Core Strategy (adopted October 2011), the Development Management Policies Local Development Document (adopted July 2013) and the Site Allocations Local Development Document (adopted November 2014) as well as government guidance. The policies of Three Rivers District Council reflect the content of the NPPF.

The Core Strategy was adopted on 17 October 2011 having been through a full public participation process and Examination in Public. Relevant policies include Policies CP1, CP9, CP10, and CP12.

The Development Management Policies Local Development Document (DMLDD) was adopted on 26 July 2013 after the Inspector concluded that it was sound following Examination in Public which took place in March 2013. Relevant policies include DM3, DM6 and DM9.

Batchworth Neighbourhood Plan 2023-2038 (Referendum Version, November 2025)

6.3 Other

Rickmansworth Conservation Area Appraisal (1993).

7 **Analysis**

7.1 Advert Regulations

7.1.1 Outdoor advertisements are within the scope of the control regime specified by the Secretary of State in the Town and Country Planning (Control of Advertisements) Regulations 2007 (as amended).

7.1.2 This regime enables local planning authorities to control advertisements, when it is justified, in the interests of “amenity” and “public safety”.

7.1.3 Amenity is not defined in the regulations, although it includes aural and visual amenity and factors relevant to amenity include the general characteristics of the locality and the presence of any feature of historic, architectural, cultural or similar interest.

7.1.4 Paragraph 141 of the National Planning Policy Framework advises that the quality and character of places can suffer when advertisements are poorly sited and designed. It also advises that advertisements should be subject to control only in the interests of amenity and public safety, taking account of cumulative impacts

7.2 Amenity

7.2.1 Policy CP1 of the Core Strategy (adopted October 2011) seeks to promote buildings of a high enduring design quality that respect local distinctiveness. Policy CP12 of the Core Strategy states that development should ‘have regard to the local context and conserve or enhance the character, amenities and quality of an area’ and ‘conserve and enhance natural and heritage assets’.

7.2.2 Officers note that the flying of flags already takes place at Three Rivers House, and this application seeks advertisement consent for a wider range of flags which are not granted deemed consent from the regulations.

7.2.3 The flags will be flown from the existing flagpoles, which are considered ancillary to the display of the flags under Section 222 of the Town and Country Planning Act. Section 222 provides that planning permission is deemed to be granted for any development of land involved in the display of advertisements in accordance with the relevant regulations.

7.2.4 Consent under Section 222 does not extend to the erection of any structure unless its primary purpose is to display advertisements. In this instance, the primary purpose of the existing flag poles is the flying of flags. Accordingly, should advertisement consent be granted for the flags, the flagpoles themselves would be considered ancillary structures associated with the approved display.

7.2.5 The flags themselves would project minimally from the face of the host building and are non-illuminated. The flags are a standard size with the exception of the Union/Union Jack flag which is slightly larger. As such, they are not considered to be visually prominent or a contrived feature within the streetscene or wider area. In addition, whilst flags are not a common feature of the streetscene, it is not considered to be uncommon for a civic building to fly flags of a similar nature. The proposal would not detract from the architectural character of the host building, and by virtue of its limited scale and discreet appearance would preserve the character and appearance of the Rickmansworth Town Centre Conservation Area.

7.3 Policy CP12 of the Core Strategy states that development should 'protect residential amenities by taking into account the need for adequate levels of disposition of privacy, prospect, amenity and garden space'.

7.3.1 The flying of the flags in these locations would not give rise to any unacceptable impact on residential amenity. The flags are modest in scale, non-illuminated, and would be flown from the existing poles which remain separated from any neighbouring built form. The flags would not result in overlooking, loss of privacy or any material change in outlook for nearby residents. Given their limited projection and lightweight nature, the flags would not result in any loss of daylight nor are they considered to result in a sense of enclosure or adversely affect the use or enjoyment of nearby private amenity space. As such, the proposed is considered acceptable and is not considered to result in any harm to amenity. Given that the flags would be limited in number (one to each existing pole) at any given time, it is not considered that they would result in undue visual clutter when read in their immediate context.

The proposed flag location(s) face towards the Grade II listed War Memorial Statue (List Entry Number: 1348251) and are near to the Grade II listed Basing House (List Entry Number: 1100850). The Conservation Officer was consulted on the application and advised that the proposed flagpole and flags are appropriate for this location; owing to the separation of the flag poles / flags from the above designated heritage assets it is not considered that they would have any impact on their setting. Thus, there is no heritage objection to the proposal.

7.3.2 Overall, it is considered that the flags would be an appropriate development within its setting and would not result in harm to amenity, either the character and amenity of the area or residential amenities of neighbouring occupiers. The development would be acceptable in accordance with Policy CP12 of the Core Strategy (adopted October 2011).

7.4 Public Safety

7.4.1 Core Strategy Policy CP10 (adopted October 2011) requires development to make adequate provision for all users, including car parking.

7.4.2 The proposed flags would be flown from the existing flag poles which are set well above the level of the public footway and carriageway. As such, the flying of flags would not result in any obstruction to pedestrian movement or vehicular visibility, nor would it impede access along the existing adjacent highways. The flags are not considered to interfere with driver sight lines or create any distraction or hazard to highway users. Given their elevated siting, modest projection, and lightweight nature, the proposal is not considered to result in any demonstrable harm to public safety in accordance with the Town and Country Planning (Control of Advertisement) Regulations 2007 (as amended) and CP10 of the Core Strategy (Adopted October 2011).

7.5 Consent:

7.5.1 Part 3, Section 15(b) of the Regulations sets out that any consent granted shall expire where no period is so specified, at the end of a period of 5 years. It should be noted that following the expiration of the 5 year period, deemed consent is granted by Schedule 3, Class 14 of the Regulations, unless it would contravene a condition subject to which express consent was granted or an application for renewal of consent has been refused. The conditions relating to Class 14 state that the terms of the express consent, including any conditions to which it was subject, shall be treated as applying to the continued display.

8 Recommendation

8.1 That ADVERTISEMENT CONSENT BE GRANTED subject to the following conditions:

C1 Standard advertisement conditions:

1] No advertisement is to be displayed without the permission of the owner of the site or any other person with an interest in the site entitled to grant permission.

2] No advertisement shall be sited or displayed so as to;

(a) Endanger persons using any highway, railway, waterway, dock, harbour or aerodrome (civil or military);

(b) Obscure, or hinder the ready interpretation of, any traffic sign, railway signal or aid to navigation by water or air; or

(c) Hinder the operation of any device used for the purpose of security or surveillance or for measuring the speed of any vehicle.

3] Any advertisement displayed, and any site used for the display of advertisements, shall be maintained in a condition that does not impair the visual amenity of the site.

4] Any structure or hoarding erected or used principally for the purpose of displaying advertisements shall be maintained in a condition that does not endanger the public.

5] Where an advertisement is required under these Regulations to be removed, the site shall be left in a condition that does not endanger the public or impair visual amenity

Reason: To comply with the Town and Country Planning (Control of Advertisements) Regulations 2007 (as amended) and in accordance with Policies CP1 and CP12 of the Core Strategy (adopted October 2011).

C2 The flags hereby permitted to be displayed at the application site(s) shall only include those listed at TRDC01 (Amended List of Flags) and shall not exceed a size of 1.6m in length by 1m in width.

Reason: For the avoidance of doubt, in the proper interests of planning in accordance with the requirements of the Town and Country Planning (Control of Advertisement) Regulations 2007 (as amended), Policies CP1, CP9, CP10 and CP12 of the Core Strategy (adopted October 2011) and Policies DM3, DM6 and DM9 of the Development Management Policies LDD (adopted July 2013).

8.2 Informative

I1 The applicant is hereby advised to remove all site notices on or near the site that were displayed pursuant to the application.

25/1754/ADV – Three Rivers House – Site Photographs







This page is intentionally left blank

PLANNING COMMITTEE - Thursday 22nd January 2026

25/1987/FUL - Construction of part-single, part-two storey side and rear extensions and single storey side extension at 18 GREENWAYS, ABBOTS LANGLEY, HERTFORDSHIRE, WD5 0EU

Parish: Abbots Langley Parish Council
Expiry of Statutory Period: 29.01.2026 (Agreed Extension)

Ward: Abbots Langley and Bedmond
Case Officer: Lilly Varnham

Development Type: Householder

Recommendation: That PLANNING PERMISSION BE GRANTED subject to conditions.

Reason for consideration by the Committee: The agent for this application is a Three Rivers District Council Ward Councillor.

To view all documents forming part of this application please go to the following website:

[25/1987/FUL | Construction of part-single, part-two storey side and rear extension and single storey side extension | 18 Greenways Abbots Langley Hertfordshire WD5 0EU](#)

1 Relevant Planning and Enforcement History

- 1.1 8/600/83 - Room Over Garage.

2 Description of Application Site

- 2.1 The application site contains a two-storey semi-detached dwelling located on Greenways, Abbots Langley. The dwelling has a dark tiled pitched roof with a two-storey front gable projection. There is a catslide roof to the side of the dwelling which is built up to the shared boundary with the adjoining neighbour at No. 20 Greenways. The dwelling has been previously extended with a dormer window that sits within the existing catslide. To the rear of the dwelling is also a single storey flat roofed rear projection, it is unclear whether this projection is original or an extension.
- 2.2 To the front of the dwelling is an existing gravelled driveway, with off street parking provision for up to three vehicles. To the rear of the dwelling is an amenity garden predominantly laid as lawn. To the rear boundary of the site there is a group of protected trees G3, which consists of 2 Ash, 2 Hawthorn and 1 Maple Tree. The group is protected by TPO129 and sits on the boundary with No. 20.
- 2.3 The wider context of Greenways consists of a mix of detached and semi-detached dwellings of varying architectural styles and designs, many of which appear to have been extended or altered.

3 Description of Proposed Development

- 3.1 This application seeks planning permission for the construction of part single, part two storey side and rear extensions and single storey side extension.
- 3.2 The proposed single storey side extension would be set back from the main front building line of the host dwelling and extend in line with the existing rear building line. It would project beyond the side wall by approximately 3m and have a depth of approximately 10.9m. The roof form would be part flat and part hipped. The ridge of the hipped roof would sit at a total height of approximately 4m with the flat roof section to the rear having a total height of approximately 3m. The extension would be finished in render to match the existing, the

hipped roof would be tiled and the flat roof section would have a UPVC fascia and soffit board. Fenestration is proposed within the front side and rear of the side extension.

- 3.3 The proposed rear extension would extend in line with the flank walls of the existing rear projection for a total depth of approximately 3m and a width of approximately 8m. The rear projection would have a flat roof with a ridge height of 3m. As above, the extension would be finished in render with a UPVC fascia and soffit board around the flat roof. Fenestrations are proposed within the side and rear elevation of the rear extension.
- 3.4 A single storey infill is also proposed to the side of the existing rear projection which would be minimally set in from the shared boundary with No. 20. This extension would have a depth of approximately 2.8m and would infill the space adjacent to the existing rear projection. This addition would have a flat roof with a ridge height of 3m. As above, the extension would be finished in render with a UPVC fascia and soffit board around the flat roof. A new door is proposed within the rear elevation of this addition.
- 3.5 To the rear/side of the dwelling at the first-floor level the existing cat slide roof would be built out, extending from the existing dormer window. This would be built up to the shared boundary with No. 20 and would have a total depth of approximately 2.6m. The dormer would sit on top of the flat roof of the proposed single storey side infill extension but would remain set at the same total height as the existing dormer. A new window is proposed within the rear of the extended dormer; from the front façade the dormer and cat slide roof remain unchanged. It is noted that this proposed extension to some degree mirrors that of the adjoining neighbour at No. 20. The extended dormer will be finished in tile hanging to match the existing.
- 3.6 At the time of the officer site visit works appeared to have commenced on site in relation to drainage matters. The applicant advised that no further works would be taken place in relation to the proposed development until permission were to be granted except for those works that relate to the drainage matters. On the basis of the works carried out to date, it is not considered that the application needs to be made part retrospective, particularly given that works in relation to the current proposal have ceased until such time that consent is obtained.

4 Consultation

4.1 Statutory Consultation

- 4.1.1 National Grid – [No response received]
- 4.1.2 Abbots Langley Parish Council – No comment.

4.2 Public/Neighbour Consultation

- 4.2.1 Number consulted: 5 No of responses received: 0
- 4.2.2 Site Notice / Press Notice: [Not required]
- 4.2.3 Summary of Responses: [No response received]

5 Reason for Delay

- 5.1 Committee cycle, Extension of Time agreed.

6 Relevant Planning Policy, Guidance and Legislation

6.1 Legislation

Planning applications are required to be determined in accordance with the statutory development plan unless material considerations indicate otherwise as set out within S38(6) Planning and Compulsory Purchase Act 2004 and S70 of Town and Country Planning Act 1990).

The Localism Act received Royal Assent on 15 November 2011. The Growth and Infrastructure Act achieved Royal Assent on 25 April 2013.

The Wildlife and Countryside Act 1981 (as amended), the Conservation of Habitats and Species Regulations 2010, the Natural Environment and Rural Communities Act 2006 and the Habitat Regulations 1994 may also be relevant.

The Environment Act 2021.

6.2 Planning Policy and Guidance

National Planning Policy Framework and National Planning Practice Guidance

In December 2024 the revised NPPF was published, to be read alongside the online National Planning Practice Guidance. The 2024 NPPF is clear that “existing policies should not be considered out-of-date simply because they were adopted or made prior to the publication of this Framework. Due weight should be given to them, according to their degree of consistency with this Framework”.

The NPPF retains a presumption in favour of sustainable development. This applies unless any adverse impacts of a development would 'significantly and demonstrably' outweigh the benefits unless there is a clear reason for refusing the development (harm to a protected area).

The Three Rivers Local Development Plan

The application has been considered against the policies of the Local Plan, including the Core Strategy (adopted October 2011), the Development Management Policies Local Development Document (adopted July 2013) and the Site Allocations Local Development Document (adopted November 2014) as well as government guidance. The policies of Three Rivers District Council reflect the content of the NPPF.

The Core Strategy was adopted on 17 October 2011 having been through a full public participation process and Examination in Public. Relevant policies include Policies CP1, CP9, CP10, and CP12.

The Development Management Policies Local Development Document (DMLDD) was adopted on 26 July 2013 after the Inspector concluded that it was sound following Examination in Public which took place in March 2013. Relevant policies include DM1, DM6, DM13, Appendix 2 and Appendix 5.

Other

The Community Infrastructure Levy (CIL) Charging Schedule (adopted February 2015).

7 Planning Analysis

7.1 Design and Impact on the Street Scene

- 7.1.1 Policy CP1 of the Core Strategy (adopted October 2011) seeks to promote buildings of a high enduring design quality that respect local distinctiveness. Policy CP12 of the Core Strategy states that development should ‘have regard to the local context and conserve or enhance the character, amenities and quality of an area’ and ‘conserve and enhance natural and heritage assets’.

- 7.1.2 Policy DM1 and Appendix 2 of the Development Management Policies Local Development Document (adopted July 2013) set out that development should not lead to a gradual deterioration in the quality of the built environment, have a significant impact on the visual amenities of the area and that extensions should respect the existing character of the dwelling, particularly with regard to the roof form, positioning and style of windows and doors, and materials.
- 7.1.3 As set out in Appendix 2, new development should not be excessively prominent in relation to adjacent properties or general street scene and should not result in a loss of light to the windows of neighbouring properties nor allow for overlooking. The design criteria at Appendix 2 sets out that generally, the maximum depth should be 3.6m in the case of semi-detached dwellings. This distance may be reduced if the extension would adversely affect adjoining properties or is unduly prominent. Single storey side extension proximity to the flank boundary will be individually assessed.
- 7.1.4 The Design Criteria sets out that side extensions should maintain an appropriate spacing between properties in character with the locality and in order to prevent the creation of a terracing effect. With regards to first floor extensions (i.e. over a garage or previous ground floor extension), Appendix 2 advises that these should generally be a minimum of 1.2 metres from the flank boundary to provide appropriate spacing and prevent a terracing effect.
- 7.1.5 The proposed single storey side extension would be visible from the site frontage; however, it is considered that views are likely to be somewhat passing and limited owing to existing front boundary treatments at the application site. The extension would remain set back from the main front building line of the host dwelling and would not extend beyond the existing rear building line. It would also remain set off the boundary with the neighbour at No. 16 Greenways. The roof form comprises a part hipped, part flat roof; the flat roof section would not be readily visible from the streetscene given its siting towards the rear of the dwelling and the extension remains single storey in nature. Thus, it is considered that the proposed extension would remain subservient to the host dwelling and would not unduly increase its prominence within the streetscene. The extension would be finished in render and roof tiles to match the existing dwelling which would further retain its character within the street.
- 7.1.6 With regard to the single storey rear extension, this would remain within the confines of the existing width of the host dwelling, extending from the flank walls of the existing rear projection which planning records indicate forms part of the dwelling's original layout. The proposed extension therefore has a total depth of approximately 3m, in accordance with the design criteria set out in Appendix 2. The extension remains considerably set in from both flank boundaries, and its scale and overall form ensure that it reads as a subordinate addition to the host dwelling. Given the existing site circumstances and the pattern of neighbouring development, this addition is not considered to result in demonstrable harm to the character or appearance of the host dwelling or wider streetscene. As above, the materials are proposed to match the existing which would further retain its character.
- 7.1.7 The single storey rear/side infill extension would occupy the area currently adjacent to the existing rear projection and the boundary with the adjoining neighbour. The extension remains single storey in height and incorporates a flat roof consistent with that of the proposed rear extension assessed above. Owing to its overall limited scale, infill nature and discreet siting, the extension is considered to appear as a subordinate addition to the host dwelling. As such, it is not considered to result in demonstrable harm to the character or appearance of the host dwelling or streetscene.
- 7.1.8 The proposed first floor side/rear extension would result in the enlargement of the existing dormer within the catslide roof that adjoins the host dwelling to its neighbour at No. 20. When viewed from the front façade, the cat slide roof and dormer arrangement would remain unchanged, with no alteration to the roof angle, the dormers position on the front roofslope or its total height. The extension would therefore only be visible to the rear, where

it would project from the existing dormer. This rearward enlargement would reflect the form and design of the adjoining neighbour's dormer, resulting in a comparable scale and appearance. The proposal would remove the rear catslide roof, with the dormer instead positioned above the proposed single storey infill extension. While this increases the massing to the rear particularly at first floor level and would be built up to the boundary, contrary to the guidance within Appendix 2, it is acknowledged that the existing development is built up to the boundary at both the application site and at the adjoining neighbour. As such whilst this would not strictly accord with the spacing requirements, when viewed in the context of the existing built form and the neighbouring properties existing dormer, it is not considered that the proposal would result in an unduly prominent form of development nor would it result in demonstrable harm to the character or appearance of the host dwelling or streetscene such to justify a refusal in this regard. The use of matching materials would further ensure the character and appearance of the dwelling are retained.

- 7.1.9 In summary, the proposed development would not result in any adverse harm to the character or appearance of the host dwelling, streetscene or area. The development would be acceptable in accordance with Policies CP1 and CP12 of the Core Strategy (2011) and Policy DM1 and Appendix 2 of the Development Management Policies LDD (2013).

7.2 Impact on amenity of neighbours

- 7.2.1 Policy CP12 of the Core Strategy states that development should 'protect residential amenities by taking into account the need for adequate levels of disposition of privacy, prospect, amenity and garden space'.
- 7.2.2 Policy DM1 and Appendix 2 of the Development Management Policies document set out that development should not result in the loss of light to the windows of neighbouring properties nor allow overlooking, and should not be excessively prominent in relation to adjacent properties.
- 7.2.3 The neighbour to the east of the application site is No. 16 Greenways, this neighbour has implemented consent for the demolition of the existing dwelling and its replacement with a two-storey detached dwelling via LPA ref 14/0221/FUL which is now what is in situ at the neighbouring site. The proposed side extension would remain set off the shared boundary with No. 16 by approximately 0.6m. The side extension would not project beyond this neighbours current rear building line and the rear section incorporates a flat roof which sits at a lower height relative to the hipped section. Owing to its single storey nature, limited height and the spacing maintained to the boundary it is not considered that this addition would result in an overbearing form of development or harmful loss of light to the occupiers of this neighbouring dwelling.
- 7.2.4 With regards to the single storey rear extension, this would remain set in from the shared boundary with No. 16 by approximately 2m. The depth is considered to comply with the design criteria above, and whilst this would result in a projection beyond the neighbours rear building line, owing to its modest height, flat roof form and separation to the boundary is not considered to give rise to an overbearing impact or harmful loss of light to the occupiers of this neighbouring dwelling.
- 7.2.5 With respect to the adjoining neighbour, the proposed single storey side/rear infill extension would sit only marginally off the shared boundary. However, it would not project beyond the host dwellings existing rear building line, nor would it extend beyond the neighbours current rear building line. Given its flat roofed form, and limited scale and height, this element is not considered to result in any material harm to the neighbouring amenity of the adjoining occupiers.
- 7.2.6 The proposed single storey rear extension would remain set off the shared boundary with the adjoining neighbour at No. 20 by approximately 1.5m and would project approximately 1m beyond this neighbours current single storey rear projection. Owing to the degree of

separation retained and the single storey flat roof nature of this element it is not considered to give rise to an overbearing form of development or unacceptable loss of light.

- 7.2.7 The proposed enlargement to the existing dormer would not increase its overall height or alter its roof form from the front façade. To the rear the enlargement would replace the existing catslide roof and sit above the flat roof of the proposed infill extension and set in a manner consistent with the neighbouring dormer. Given its scale, siting and alignment with the adjoining neighbouring property, the enlarged dormer is not considered to result in a significant increase in massing or overshadowing, nor is it considered to give rise to an unacceptable sense of enclosure. As such, when read in the existing site context and neighbouring development, the dormer is not considered to result in demonstrable harm to the residential amenities of the occupiers of this neighbouring dwelling.
- 7.2.8 The fenestration within the front and rear elevations of the single storey extensions would predominantly have outlook of the application site frontage and rear amenity space and as such are not considered to facilitate additional overlooking of any neighbour. It is acknowledged that the single storey rear extension has flank windows which face the boundaries with both No. 16 and No. 20. However, owing to their siting at the ground floor level and the separation retained to the boundaries it is not considered that these windows would result in unacceptable overlooking of these neighbours such to justify a refusal in this regard. Whilst the enlarged dormer would include a new first floor rear window this would predominantly overlook the application sites rear amenity space, with only oblique views towards the neighbour which would not be dissimilar to those achievable from existing first floor rear windows. Accordingly, the proposals are not considered to result in unacceptable harm to neighbouring amenity.
- 7.2.9 In summary, the proposed development would not result in any adverse impact on any neighbouring dwelling, and the development would be acceptable in accordance with Policies CP1 and CP12 of the Core Strategy and Policies DM1, DM9 and Appendix 2 of the Development Management Policies LDD.

7.3 Wildlife and Biodiversity

- 7.3.1 Section 40 of the Natural Environment and Rural Communities Act 2006 requires Local Planning Authorities to have regard to the purpose of conserving biodiversity. This is further emphasised by regulation 3(4) of the Habitat Regulations 1994 which state that Councils must have regard to the strict protection for certain species required by the EC Habitats Directive. The Habitats Directive places a legal duty on all public bodies to have regard to the habitats directive when carrying out their functions.
- 7.3.2 The protection of biodiversity and protected species is a material planning consideration in the assessment of this application in accordance with Policy CP9 of the Core Strategy and Policy DM6 of the Development Management Policies LDD. National Planning Policy requires Local Authorities to ensure that a protected species survey is undertaken for applications where biodiversity may be affected prior to the determination of a planning application.
- 7.3.3 The application is accompanied by a biodiversity checklist which states that no protected species or biodiversity interests will be affected as a result of the application. The Local Planning Authority is not aware of any records of protected species within the immediate area that would necessitate further surveying work being undertaken.

7.4 Mandatory Biodiversity Net Gain

- 7.4.1 Paragraph 13 of Schedule 7A of the Town and Country Planning Act 1990 sets out that every planning permission granted for the development of land in England shall be deemed to have been granted subject to the 'biodiversity gain condition' requiring development to achieve a net gain of 10% of biodiversity value. This is subject to exemptions, and an

exemption applies in relation to planning permission for a development which is the subject of a householder application, within the meaning of article 2(1) of the Town and Country Planning (Development Management Procedure) (England) Order (2015).

- 7.4.2 The applicant has confirmed that if permission is granted for the development to which this application relates the biodiversity gain condition would not apply because the application relates to householder development.

7.5 Trees and Landscaping

- 7.5.1 Policy DM6 of the DMP LDD sets out that development proposals should seek to retain trees and other landscape and nature conservation features, and that proposals should demonstrate that trees will be safeguarded and managed during and after development in accordance with the relevant British Standards.

- 7.5.2 The application site is not located within a Conservation Area, there is however a group of protected trees to the rear of the site, G3, protected by TPO129. Given the distance maintained from the proposed works and these protected trees it is not considered that these would be affected by the proposed development. The proposal is therefore considered acceptable in this regard.

7.6 Rear amenity

- 7.6.1 Policy CP12 of the Core Strategy states that development should take into account the need for adequate levels and disposition of amenity and garden space. Section 3 (Amenity Space) of Appendix 2 of the Development Management Policies document provides indicative levels of amenity/garden space provision.

- 7.6.2 The application dwelling has four bedrooms as existing requiring 105sqm of rear amenity space. The proposal would not increase the number of bedrooms within the dwelling and therefore this requirement would remain unchanged. The application site would retain approximately 178sqm of rear amenity space exceeding the criteria at Appendix 2 of the DMP LDD. The proposal is therefore considered acceptable in this regard.

7.7 Highways, Access and Parking

- 7.7.1 Core Strategy Policy CP10 (adopted October 2011) requires development to make adequate provision for all users, including car parking. Policy DM13 in the Development Management Policies document (adopted July 2013) states that development should make provision for parking in accordance with the Parking Standards set out within Appendix 5.

- 7.7.2 The existing dwelling has four bedrooms and therefore requires 3 assigned spaces within the dwelling's curtilage. The proposal would not increase the number of bedrooms within the dwelling, and the existing requirement would remain unchanged. The application site has an existing gravelled driveway with off street parking provision for three vehicles and therefore meets the requirement at Appendix 5. The proposal is therefore considered acceptable in this regard.

8 Recommendation

- 8.1 That PLANNING PERMISSION BE GRANTED subject to the following conditions:

- C1 The development hereby permitted shall be begun before the expiration of three years from

the date of this permission.

Reason: In pursuance of Section 91(1) of the Town and Country Planning Act 1990 and as amended by the Planning and Compulsory Purchase Act 2004.

- C2 The development hereby permitted shall be carried out in accordance with the following approved plans: 2510-SK-100 REV B, 2510-SK-101 REV B

Reason: For the avoidance of doubt, and in the proper interests of planning in accordance with Policies CP1, CP9, CP10 and CP12 of the Core Strategy (adopted October 2011) and Policies DM1, DM6 and DM13 and Appendices 2 and 5 of the Development Management Policies (adopted July 2013).

- C3 Unless specified on the approved plans, all new works or making good to the retained fabric shall be finished to match in size, colour, texture and profile those of the existing building.

Reason: To prevent the building being constructed in inappropriate materials in accordance with Policies CP1 and CP12 of the Core Strategy (adopted October 2011) and Policy DM1 and Appendix 2 of the Development Management Policies LDD (adopted July 2013).

8.2 Informatives

- I1 With regard to implementing this permission, the applicant is advised as follows:

All relevant planning conditions must be discharged prior to the commencement of work. Requests to discharge conditions must be made by formal application. Fees are £145 per request (or £43 where the related permission is for extending or altering a dwellinghouse or other development in the curtilage of a dwellinghouse). Please note that requests made without the appropriate fee will be returned unanswered.

There may be a requirement for the approved development to comply with the Building Regulations. Please contact Hertfordshire Building Control (HBC) on 01438 879990 or at buildingcontrol@hertfordshirebc.co.uk who will be happy to advise you on building control matters and will protect your interests throughout your build project by leading the compliance process. Further information is available at www.hertfordshirebc.co.uk.

Community Infrastructure Levy (CIL) - Your development may be liable for CIL payments and you are advised to contact the CIL Officer for clarification with regard to this (cil@threerivers.gov.uk). If your development is CIL liable, even if you have been granted exemption from the levy, please be advised that before commencement of any works it is a requirement under Regulation 67 of The Community Infrastructure Levy Regulations 2010 (As Amended) that CIL form 6 (Commencement Notice) must be completed, returned and acknowledged by Three Rivers District Council before building works start. Failure to do so will mean you lose the right to payment by instalments (where applicable), and a surcharge will be imposed. However, please note that a Commencement Notice is not required for residential extensions if relief has been granted.

Following the grant of planning permission by the Local Planning Authority it is accepted that new issues may arise post determination, which require modification of the approved plans. Please note that regardless of the reason for these changes, where these modifications are fundamental or substantial, a new planning application will need to be submitted. Where less substantial changes are proposed, the following options are available to applicants:

{\b (a)} Making a Non-Material Amendment

{\b (b)} Amending the conditions attached to the planning permission, including seeking to make minor material amendments (otherwise known as a section 73 application).

It is important that any modifications to a planning permission are formalised before works commence otherwise your planning permission may be unlawful and therefore could be subject to enforcement action. In addition, please be aware that changes to a development previously granted by the LPA may affect any previous Community Infrastructure Levy (CIL) owed or exemption granted by the Council. If you are in any doubt whether the new/amended development is now liable for CIL you are advised to contact the Community Infrastructure Levy Officer (01923 776611) for clarification. Information regarding CIL can be found on the Three Rivers website (<https://www.threerivers.gov.uk/services/planning/community-infrastructure-levy>).

Care should be taken during the building works hereby approved to ensure no damage occurs to the verge or footpaths during construction. Vehicles delivering materials to this development shall not override or cause damage to the public footway. Any damage will require to be made good to the satisfaction of the Council and at the applicant's expense.

Where possible, energy saving and water harvesting measures should be incorporated. Any external changes to the building which may be subsequently required should be discussed with the Council's Development Management Section prior to the commencement of work. Further information on how to incorporate changes to reduce your energy and water use is available at: <https://www.threerivers.gov.uk/services/environment-climate-emergency/home-energy-efficiency-sustainable-living#Greening%20your%20home>

12 The applicant is reminded that the Control of Pollution Act 1974 allows local authorities to restrict construction activity (where work is audible at the site boundary). In Three Rivers such work audible at the site boundary, including deliveries to the site and running of equipment such as generators, should be restricted to 0800 to 1800 Monday to Friday, 0900 to 1300 on Saturdays and not at all on Sundays and Bank Holidays.

13 The Local Planning Authority has been positive and proactive in its consideration of this planning application, in line with the requirements of the National Planning Policy Framework and in accordance with the Town and Country Planning (Development Management Procedure) (England) Order 2015. The development maintains/improves the economic, social and environmental conditions of the District.

14 The effect of paragraph 13 of Schedule 7A to the Town and Country Planning Act 1990 is that planning permission granted for the development of land in England is deemed to have been granted subject to the condition "(the biodiversity gain condition)" that development may not begin unless:

- a) a Biodiversity Gain Plan has been submitted to the planning authority, and
- b) the planning authority has approved the plan.

The planning authority, for the purposes of determining whether to approve a Biodiversity Gain Plan if one is required in respect of this permission would be Three Rivers District Council.

There are statutory exemptions and transitional arrangements which mean that the biodiversity gain condition does not apply.

Based on the information available this permission is considered to be one which will not require the approval of a biodiversity gain plan before development is begun because the following statutory exemption or transitional arrangement is considered to apply.

Development which is subject of a householder application within the meaning of article 2(1) of the Town and Country Planning (Development Management Procedure) (England) Order 2015. A "householder application" means an application for planning permission for development for an existing dwellinghouse, or development within the curtilage of such a dwellinghouse for any purpose incidental to the enjoyment of the dwellinghouse which is not an application for change of use or an application to change the number of dwellings in a building.

Where the local planning authority considers that the permission falls within paragraph 19 of Schedule 7A to the Town and Country Planning Act 1990, the permission which has been granted has the effect of requiring or permitting the development to proceed in phases. The modifications in respect of the biodiversity gain condition which are set out in Part 2 of the Biodiversity Gain (Town and Country Planning) (Modifications and Amendments) (England) Regulations 2024 apply.

Biodiversity gain plans are required to be submitted to, and approved by, the planning authority before development may be begun, and, if subject to phased development, before each phase of development may be begun.

If the onsite habitat includes irreplaceable habitat (within the meaning of the Biodiversity Gain Requirements (Irreplaceable Habitat) Regulations 2024) there are additional requirements for the content and approval of Biodiversity Gain Plans. The Biodiversity Gain Plan must include, in addition to information about steps taken or to be taken to minimise any adverse effect of the development on the habitat, information on arrangements for compensation for any impact the development has on the biodiversity of the irreplaceable habitat.

The planning authority can only approve a Biodiversity Gain Plan if satisfied that the adverse effect of the development on the biodiversity of the irreplaceable habitat is minimised and appropriate arrangements have been made for the purpose of compensating for any impact which do not include the use of biodiversity credits.

More information can be found in the Planning Practice Guidance online at <https://www.gov.uk/guidance/biodiversity-net-gain>.

- 15t Bats are protected under domestic and European legislation where, in summary, it is an offence to deliberately capture, injure or kill a bat, intentionally or recklessly disturb a bat in a roost or deliberately disturb a bat in a way that would impair its ability to survive, breed or rear young, hibernate or migrate, or significantly affect its local distribution or abundance; damage or destroy a bat roost; possess or advertise/sell/exchange a bat; and intentionally or recklessly obstruct access to a bat roost.

If bats are found all works must stop immediately and advice sought as to how to proceed from either of the following organisations:

The UK Bat Helpline: 0845 1300 228

Natural England: 0300 060 3900

Herts & Middlesex Bat Group: www.hmbg.org.uk

or an appropriately qualified and experienced ecologist.

(As an alternative to proceeding with caution, the applicant may wish to commission an ecological consultant before works start to determine whether or not bats are present).

25/1987/FUL – 18 Greenways – Site Photographs









PLANNING COMMITTEE – Thursday 22 January 2026

25/2091/RSP – Retrospective: Construction of single storey rear extension at 39 - 41 HIGH STREET, ABBOTS LANGLEY, HERTFORDSHIRE, WD5 0AA

Parish: Abbots Langley Parish Council
Expiry of Statutory Period: 28.01.2026

Ward: Abbots Langley and Bedmond
Case Officer: Nicholas Withers

Development Type: ‘Minor other’ development

Recommendation: That retrospective planning permission be **granted**.

Reason for consideration by the Committee: The acting agent on the application is an elected Ward Councillor (Cllr Jon Tankard).

To view all documents forming part of this application please go to the following website:

[25/2091/RSP | Retrospective: Construction of single storey rear extension | 39 - 41 High Street Abbots Langley Hertfordshire WD5 0AA](#)

1 Relevant Planning and Enforcement History

- 1.1 No relevant planning history.
- 1.2 21/0213/COMP - Erection of signage – Pending Consideration.
- 1.3 25/0143/COMP - Change of use and unauthorised extension of kitchen – Pending Consideration (subject of this application).

2 Description of Application Site

- 2.1 The application site consists of a two storey end terrace building located on the eastern side of High Street, Abbots Langley. The site is classified as being located within a Secondary Shopping Frontage area of Abbots Langley town centre and is located within the Abbots Langley Conservation Area. The High Street mostly consists of commercial units at ground floor with residential use above.
- 2.2 The building is currently used as an Indian restaurant/takeaway (Class A3/A5) with the first floor level being used for storage and ancillary accommodation with a study/office. To the rear of the application site is a service road which provides access to the host building, other commercial units and residential dwellings located along The Crescent. No.1 The Crescent, a detached dwelling set back from the road immediately adjoins the application site to the east. This property has a car port up to the boundary with the application site.
- 2.3 To the north of the application site is a car park for an adjacent vacant restaurant. To the south and attached to the application is No. 43, a Chinese restaurant/takeaway.
- 2.4 There are restricted parking bays along High Street and there is also a public car park further to the south, close to the junction with Abbots Road

3 Description of Proposed Development

- 3.1 This application is for retrospective planning permission for the construction of a single storey rear extension.

- 3.2 The extension has been fully constructed and is used as an enclosed storage yard in association with and physically attached to the restaurant operating from the application site
- 3.3 The extension has a depth of 3.6m and a width of 3.6m. It has a mono pitch roof with a maximum height of 2.4m that slopes down to 2.1m. There is a doorway on the southern flank which exits into the courtyard / service yard to the rear.
- 3.4 The extension is constructed from timber cladding that has been painted black and has translucent UPVC roofing with a timber frame.

4 Consultation

4.1 Statutory Consultation

4.2 Abbots Langley Parish Council: No comment

4.3 National Grid: [No response]

4.4 TRDC Environmental Health: No objection

4.5 Watford Environmental Health: No objection

4.6 Public/Neighbour Consultation

4.7 Number consulted: 9 No of responses received: 0

4.8 Site Notice: Expired 05/01/2026 Press notice: Expired 05/01/2026

4.9 Summary of Responses: None received.

5 Relevant Planning Policy, Guidance and Legislation

5.1 Legislation

Planning applications are required to be determined in accordance with the statutory development plan unless material considerations indicate otherwise as set out within S38(6) Planning and Compulsory Purchase Act 2004 and S70 of Town and Country Planning Act 1990).

S72 of Planning (Listed Buildings and Conservation Areas) Act 1990 requires LPAs to have special regard to the desirability of preserving or enhancing the character or appearance of conservation areas.

The Localism Act received Royal Assent on 15 November 2011. The Growth and Infrastructure Act achieved Royal Assent on 25 April 2013.

The Wildlife and Countryside Act 1981 (as amended), the Conservation of Habitats and Species Regulations 2010, the Natural Environment and Rural Communities Act 2006 and the Habitat Regulations 1994 may also be relevant.

The Environment Act 2021.

5.2 Planning Policy and Guidance

National Planning Policy Framework and National Planning Practice Guidance

In December 2024 the revised NPPF was published, to be read alongside the online National Planning Practice Guidance. The 2024 NPPF is clear that “existing policies should not be considered out-of-date simply because they were adopted or made prior to the

publication of this Framework. Due weight should be given to them, according to their degree of consistency with this Framework”.

The NPPF retains a presumption in favour of sustainable development. This applies unless any adverse impacts of a development would 'significantly and demonstrably' outweigh the benefits unless there is a clear reason for refusing the development (harm to a protected area).

The Three Rivers Local Development Plan

The application has been considered against the policies of the Local Plan, including the Core Strategy (adopted October 2011), the Development Management Policies Local Development Document (adopted July 2013) and the Site Allocations Local Development Document (adopted November 2014) as well as government guidance. The policies of Three Rivers District Council reflect the content of the NPPF.

The Core Strategy was adopted on 17 October 2011 having been through a full public participation process and Examination in Public. Relevant policies include Policies CP1, CP9, and CP12.

The Development Management Policies Local Development Document (DMLDD) was adopted on 26 July 2013 after the Inspector concluded that it was sound following Examination in Public which took place in March 2013. Relevant policies include DM3, DM6 and DM9.

6 Planning Analysis

6.1 Design and Impact on the character of the area and Conservation Area.

6.2 Policy CP1 of the Core Strategy (adopted October 2011) seeks to promote buildings of a high enduring design quality that respect local distinctiveness. Policy CP12 of the Core Strategy states that development should 'have regard to the local context and conserve or enhance the character, amenities and quality of an area' and 'conserve and enhance natural and heritage assets'.

6.3 The application site is located in the Abbots Langley Conservation Area; as such Policy DM3 of the Development Management Policies LDD (adopted July 2013) applies. With regard to development in Conservation Areas, Policy DM3 states that development will only be permitted if the proposal is of a design and scale that preserves or enhances the character and appearance of the area.

6.4 The extension is located to the rear of the property, viewed in conjunction with other additions and is only 3.6m in depth and is single storey in height. The extension is therefore considered a small form of development which by virtue of its scale and materiality preserves the character and appearance of the building and does not impact upon the wider character of the area, including the Abbots Langley Conservation Area.

6.5 In summary, the development does not result in any adverse harm to the character or appearance of the building, streetscene or Abbots Langley Conservation Area. The development is acceptable in accordance with Policies CP1 and CP12 of the Core Strategy, Policy DM3 and Appendix 2 of the Development Management Policies LDD and the NPPF.

6.6 Impact on Neighbouring Amenity

6.7 Policy CP12 of the Core Strategy (adopted October 2011) relates to design and states that in seeking a high standard of design the Council will expect development proposals to 'have

regard to the local context and conserve or enhance the character, amenities and quality of an area'.

- 6.8 Policy DM9 of the Development Management Policies document also states that planning permission will not be granted for development which has an unacceptable impact on the indoor and outdoor acoustic environment of existing or planned development.
- 6.9 The extension is located to the rear of the building at ground floor level and is adjacent to a neighbouring car port of similar scale. Given its siting and single-storey nature of the extension, it is not considered that the development results in an un-neighbourly or loss of light to neighbouring properties.
- 6.10 In terms of noise associated with the extension, it is used for storage purposes ancillary to the restaurant. Given the limited floorspace and relationship with No.1 The Crescent and nearby flats it is not considered its use has an unacceptable impact on neighbouring amenity. Furthermore, as there are no windows or openings on the eastern elevation, there would be no loss of privacy or overlooking to No.1 The Crescent. The Environmental Health Officer was also consulted on the application and has raised no objections.
- 6.11 In summary, the development does not result in any adverse impact on any neighbouring dwelling and the development would be acceptable in accordance with Policies CP1 and CP12 of the Core Strategy and Policy DM9 and Appendix 2 of the Development Management Policies LDD.
- 6.12 Highways and parking provision
- 6.13 Core Strategy Policy CP10 (adopted October 2011) requires development to make adequate provision for all users, including car parking. Policy DM13 in the Development Management Policies document (adopted July 2013) states that development should make provision for parking in accordance with the Parking Standards set out within Appendix 5.
- 6.14 The development does not alter the requirement for any additional parking to support the nature of the business or nor does it decrease the availability of parking. As such, no objection is raised in this regard.
- 6.15 Trees and Landscaping
- 6.16 Policy DM6 of the Development Management Policies LDD sets out that development proposals should seek to retain trees and other landscape and nature conservation features, and that proposals should demonstrate that trees will be safeguarded and managed during and after development in accordance with the relevant British Standards.
- 6.17 The application site is located within a conservation area however there are no protected trees on or near the site that have been or are affected by the development. Therefore, no objection is raised in this regard.
- 6.18 Wildlife and Biodiversity
- 6.19 Section 40 of the Natural Environment and Rural Communities Act 2006 requires Local Planning Authorities to have regard to the purpose of conserving biodiversity. This is further emphasised by regulation 3(4) of the Habitat Regulations 1994 which state that Councils must have regard to the strict protection for certain species required by the EC Habitats Directive.
- 6.20 The protection of biodiversity and protected species is a material planning consideration in the assessment of applications in accordance with Policy CP9 of the Core Strategy (adopted October 2011) and Policy DM6 of the DMLDD. National Planning Policy requires Local Authorities to ensure that a protected species survey is undertaken for applications

that may be affected prior to determination of a planning application. A Biodiversity Checklist was submitted with the application and states that no protected species or biodiversity interests have been affected as a result of the development.

6.21 Mandatory Biodiversity Net Gain

6.22 Paragraph 13 of Schedule 7A of the Town and Country Planning Act 1990 sets out that every planning permission granted for the development of land in England shall be deemed to have been granted subject to the 'biodiversity gain condition' requiring development to achieve a net gain of 10% of biodiversity value. This is subject to exemptions, and an exemption applies in relation to planning permission for a development which is the subject of a householder application, within the meaning of article 2(1) of the Town and Country Planning (Development Management Procedure) (England) Order (2015).

6.23 The applicant has confirmed that if permission is granted for the development to which this application relates the biodiversity gain condition would not apply because the application relates to development which is subject to the de minimis exemption.

7 Recommendation

7.1 That RETROSPECTIVE PLANNING PERMISSION BE GRANTED unconditionally.

Informatives:

I1 The Local Planning Authority has been positive and proactive in its consideration of this planning application, in line with the requirements of the National Planning Policy Framework and in accordance with the Town and Country Planning (Development Management Procedure) (England) Order 2015. The development maintains/improves the economic, social and environmental conditions of the District.

I2 The effect of paragraph 13 of Schedule 7A to the Town and Country Planning Act 1990 is that planning permission granted for the development of land in England is deemed to have been granted subject to the condition "(the biodiversity gain condition)" that development may not begin unless:

- a) a Biodiversity Gain Plan has been submitted to the planning authority, and
- b) the planning authority has approved the plan.

The planning authority, for the purposes of determining whether to approve a Biodiversity Gain Plan if one is required in respect of this permission would be Three Rivers District Council.

There are statutory exemptions and transitional arrangement which mean that the biodiversity gain conditions does not always apply..

Based on the information available, this permission is considered to be one which will not require the approval of a biodiversity gain plan before development is begun because the following statutory exemption or transitional arrangement is considered to apply.

The planning permission relates to development to which section 73A of the Town and Country Planning Act 1990 (planning permission for development already carried out applies).

Where the local planning authority considers that the permission falls within paragraph 19 of Schedule 7A to the Town and Country Planning Act 1990, the permission which has been granted has the effect of requiring or permitting the

development to proceed in phases. The modifications in respect of the biodiversity gain condition which are set out in Part 2 of the Biodiversity Gain (Town and Country Planning) (Modifications and Amendments) (England) Regulations 2024 apply.

Biodiversity gain plans are required to be submitted to, and approved by, the planning authority before development may be begun, and, if subject to phased development, before each phase of development may be begun.

If the onsite habitat includes irreplaceable habitat (within the meaning of the Biodiversity Gain Requirements (Irreplaceable Habitat) Regulations 2024) there are additional requirements for the content and approval of Biodiversity Gain Plans. The Biodiversity Gain Plan must include, in addition to information about steps taken or to be taken to minimise any adverse effect of the development on the habitat, information on arrangements for compensation for any impact the development has on the biodiversity of the irreplaceable habitat.

The planning authority can only approve a Biodiversity Gain Plan if satisfied that the adverse effect of the development on the biodiversity of the irreplaceable habitat is minimised and appropriate arrangements have been made for the purpose of compensating for any impact which do not include the use of biodiversity credits.

More information can be found in the Planning Practice Guidance online at <https://www.gov.uk/guidance/biodiversity-net-gain>.









PLANNING COMMITTEE - Thursday 22 January 2026

25/2102/FUL - Erection of a timber pergola at CROXLEY GUILD BOWLS CLUB, THE GREEN, CROXLEY GREEN, RICKMANSWORTH, HERTFORDSHIRE, WD3 3HT

Parish: Croxley Green Parish Council
Expiry of Statutory Period: 02.02.2026

Ward: Dickinsons
Case Officer: Lilly Varnham

Recommendation: That PLANNING PERMISSION BE GRANTED subject to the conditions set out below.

Reason for consideration by the Committee: The application site is owned by Three Rivers District Council.

To view all documents forming part of this application please go to the following website:

[25/2102/FUL | Erection of a timber pergola. | Croxley Guild Bowls Club The Green Croxley Green Rickmansworth Hertfordshire WD3 3HT](#)

1 Relevant planning history

- 1.1 8/547/91 - Multi use sports surface court for recreational use.
- 1.2 8/417/91 - Single storey extension to existing changing rooms – Permitted 29.08.1991.
- 1.3 8/513/91 - Resurfacing and installation of 1 tennis court, re-siting of pavilion and installation of floodlights – Permitted 17.10.1991.
- 1.4 8/658/91 - Erection of new pavilion – Withdrawn 20.01.1992.
- 1.5 8/176/92 - Erection of building for use as changing rooms – Permitted 21.05.1992.
- 1.6 8/311/92 - Refurbishment of pavillion (S.64 Determination) – Non-Determination 16.06.1992.
- 1.7 94/758/8 - Demolition of existing changing room and erection of replacement at Bowling Green – Permitted 15.12.1994.
- 1.8 98/0323 - Demolition of clubhouse – Conservation Area Consent 26.06.1998.
- 1.9 97/0969 - Erection of replacement club house – Conditional Permission 06.08.1998.
- 1.10 99/0082 - Erection of 22.5 metre high mast three cross polar antennas two dish antennas and one radio equipment housing – Refused 05.09.1999.
- 1.11 01/00155/FUL - Single storey rear extension, internal alterations to existing clubhouse and erection of new sports changing facility – Permitted 13.09.2001.
- 1.12 02/01467/FUL - Temporary portacabin – Permitted 07.01.2023.
- 1.13 03/0648/FUL - Renewal of planning permission ref 97/0969/8 - Replacement clubhouse – Permitted 17.07.2003.
- 1.14 03/0647/CAC - Conservation Area Consent: Demolition of existing clubhouse – Permitted 18.07.2003.
- 1.15 05/1442/FUL - Demolition and erection of replacement clubhouse – Permitted 01.12.2005.
- 1.16 05/1443/CAC - Conservation Area Consent: Demolition of clubhouse – Permitted 02.12.2005.
- 1.17 12/1530/FUL - Bringing onto site 2 small containers for safe storage for essential equipment in order to support junior football and other sports – Permitted 10.10.2012.

2 Site description

- 2.1 The application site is currently occupied by Croxley Guild Bowls Club and is located within the Croxley Green Conservation Area. The site is accessible via the service road from The Green which is single track. An existing close boarded fence forms the boundary between the application site and the existing car park.
- 2.2 The site contains a club house building, the bowling green with a concrete path around its perimeter. There is an existing pergola structure and other detached buildings which include changing rooms and two small sheds around the perimeter of the bowling green.
- 2.3 To the east of the site is the Croxley Tennis Club and Croxley Guild of Sports & Social Club. To the west are a number of residential dwellings that front The Green.

3 Description of proposed development

- 3.1 The application seeks full planning permission for the erection of a timber pergola.
- 3.2 The proposed pergola would replace the existing in a similar location on the existing area of hardstanding to the east of the clubhouse building. The pergola would have a depth of approximately 3m and a total width of approximately 12m, set along the boundary with the tennis courts to the south. The pergola would have a hipped roof with a total ridge height of approximately 3m.
- 3.3 The pergola would remain open on all four sides, with its roof form supported by 10 wooden posts. The material will either be either European Oak or Red Spruce and the roof form is proposed to be felt to match the clubhouse roof. It is understood that the pergola will act as a shelter providing shade for players and visitors of the club.

4 Consultation

4.1 Statutory Consultation

4.1.1 National Grid – [No response received]

4.1.2 Croxley Green Parish Council

Subject to Conservation Officers' views, no reason to object, but the planning officers should be satisfied that enough information has been provided to allow a proper determination of the application.

4.1.3 Three Rivers District Council Property Services – [Objection]

The Property Team object to the application on the basis that the applicant has not sought consent from TRDC as landlord to the Guild of Sport site. I would urge the applicant to make early contact with the Property Team (property@threerivers.gov.uk) in order to discuss their proposals.

4.1.4 Conservation Officer – [No Objection]

The application is for Erection of a timber pergola.

The site is in Croxley Green Conservation Area.

It is also close to a high concentration of locally and nationally listed buildings which face onto The Green.

The Grade II listed Halewood Cottage (List Entry Number: 1100843) is a short distance to the northwest. Grade II listed Providence Hall (List Entry Number: 1348261) is located to the southwest. The pergola would be located at the southern end of the bowling green on an area of hardstanding, close to the tennis courts and existing structures. It would be a lightweight open structure built in natural materials.

It is appropriate for this location and context and there is no objection in heritage terms, subject to the materials being like those shown in the submission, i.e., a primarily wooden structure. **On this basis there is no objection to the proposal in heritage terms.**

This response has been made with regard to Sections 72 (1) and 66 (!) of the Planning (Listed Buildings and Conservation Areas) Act 1990 and the National Planning Policy Framework Chapter 16 'Conserving and Enhancing the Historic Environment'.

5 Public/Neighbour Consultation

5.1.1 Number consulted: 12 No of Responses received: 0

5.1.2 Site Notice Posted: 10.12.2025, Expired: 03.01.2026

5.1.3 Press notice Published: 19.12.2025, Expired: 12.01.2026

5.1.4 Summary of responses: None received

5.2 Reason for Delay

5.2.1 Committee Cycle

6 Relevant Local and National Planning Policies

Legislation

Planning applications are required to be determined in accordance with the statutory development plan unless material considerations indicate otherwise as set out within S38(6) Planning and Compulsory Purchase Act 2004 and S70 of Town and Country Planning Act 1990).

S72 of Planning (Listed Buildings and Conservation Areas) Act 1990 requires LPAs to have special regard to the desirability of preserving or enhancing the character or appearance of conservation areas.

The Localism Act received Royal Assent on 15 November 2011. The Growth and Infrastructure Act achieved Royal Assent on 25 April 2013.

The Wildlife and Countryside Act 1981 (as amended), the Conservation of Habitats and Species Regulations 2010, the Natural Environment and Rural Communities Act 2006 and the Habitat Regulations 1994 may also be relevant.

The Environment Act 2021.

Policy/Guidance

National Planning Policy Framework and National Planning Practice Guidance

In December 2024 the revised NPPF was published, to be read alongside the online National Planning Practice Guidance. The 2024 NPPF is clear that "existing policies should not be considered out-of-date simply because they were adopted or made prior to the publication of this Framework. Due weight should be given to them, according to their degree of consistency with this Framework".

The NPPF retains a presumption in favour of sustainable development. This applies unless any adverse impacts of a development would 'significantly and demonstrably' outweigh the benefits unless there is a clear reason for refusing the development (harm to a protected area).

The Three Rivers Local Development Plan

The application has been considered against the policies of the Local Plan, including the Core Strategy (adopted October 2011), the Development Management Policies Local Development Document (adopted July 2013) and the Site Allocations Local Development Document (adopted November 2014) as well as government guidance. The policies of Three Rivers District Council reflect the content of the NPPF.

The Core Strategy was adopted on 17 October 2011 having been through a full public participation process and Examination in Public. Relevant policies include Policies CP1, CP9, CP10, and CP12.

The Development Management Policies Local Development Document (DMLDD) was adopted on 26 July 2013 after the Inspector concluded that it was sound following Examination in Public which took place in March 2013. Relevant policies include DM3, DM6, DM13 and Appendix 5.

Croxley Green Neighbourhood Plan Referendum Version (2018).

Other

Croxley Green Conservation Area Appraisal (1996)

The Community Infrastructure Levy (CIL) Charging Schedule (adopted February 2015).

7 Analysis

7.1 Design and impact on the character of the Streetscene and Conservation Area

7.1.1 Policy CP1 of the Core Strategy (adopted October 2011) seeks to promote buildings of a high enduring design quality that respect local distinctiveness. Policy CP12 of the Core Strategy states that development should 'have regard to the local context and conserve or enhance the character, amenities and quality of an area' and 'conserve and enhance natural and heritage assets'.

7.1.2 The application site is located within the Croxley Green Conservation Area, therefore Policy DM3 applies. Policy DM3 sets out that within Conservation Areas development will only be permitted if the proposal:

- i) Is of a design and scale that preserves or enhances the character or appearance of the area
- ii) Uses building materials, finishes, including those for features such as walls, railings, gates and hard surfacing, that are appropriate to the local context
- iii) Retains historically significant boundaries, important open spaces and other elements of the area's established pattern of development, character and historic value, including gardens, roadside banks and verges
- iv) Retains and restores, where relevant, traditional features such as shop fronts, walls, railings, paved surfaces and street furniture, and improves the condition of structures worthy of retention
- v) Does not harm important views into, out of or within the Conservation area
- vi) Protects trees, hedgerows and other significant landscape features and incorporates landscaping appropriate to the character and appearance of the Conservation Area
- vii) Results, where relevant, in the removal of unsympathetic features and the restoration or reinstatement of missing features.

7.1.3 The proposal would result in the replacement of the existing pergola on site in a similar location, albeit on a slightly larger footprint with the existing measuring approximately 2.8m x 10m and the proposed measuring approximately 3m x 12m. The proposed pergola would remain open sided on all four sides and would be of a modest scale in terms of its total height which is less than the existing structure. Although visible above the height of the existing fence which forms the boundary to the Tennis Club and adjacent car park it is read in the backdrop of existing recreational development. The application site is set back from The Green and whilst some views of the development may be had from The Green and wider Conservation Area it is considered that these views would be obscured by both existing residential development and read in its context adjacent to the Tennis Courts.

7.1.4 The open nature of the structure would allow for the continued perception of openness and would not create a dominant or visually intrusive feature on the site. By virtue of its modest scale and limited height, the structure would not appear visually dominant or intrusive within the streetscene. Its lightweight timber form would preserve the sense of openness and would not detract from the

significance or setting of the Conservation Area. It is noted that the proposed structure incorporates a hipped roof form, which would give it a slightly more permanent appearance compared with the existing structure. However, this form is not considered to be harmful to the character or appearance of the site or wider Conservation Area, and it would remain set below the height of the existing clubhouse which the hipped roof intends to mimic. The hipped roof would present a balanced form and due to its open sided nature will allow the structure to be read comfortably within its surroundings.

7.1.5 The Conservation Officer was consulted on the application and advises that owing to its lightweight open structure built in natural materials it would be appropriate for this location and context and there is therefore no objection in heritage terms, subject to the materials being like those shown in the submission, i.e., a primarily wooden structure.

7.1.6 Accordingly, the proposal would remain of an appropriate scale and design which is considered to preserve the character and appearance of the Conservation Area.

7.1.7 In summary, the proposed development would not result in any adverse harm to the character or appearance of the streetscene and would preserve the character of the Conservation Area. The development would be acceptable in accordance with Policies CP1 and CP12 of the Core Strategy, Policy DM3 of the Development Management Policies LDD (2013), the Croxley Green Neighbourhood Plan Referendum Version (2018) and the Croxley Green Conservation Area Appraisal (1996)

7.2 Impact on Neighbours

7.2.1 Policy CP12 of the Core Strategy states that development should 'protect residential amenities by taking into account the need for adequate levels of disposition of privacy, prospect, amenity and garden space'.

7.2.2 To the north/northeast of the application site are the neighbouring dwellings Saltram Cottage, Rose Cottage, Fearnley House, Greenside and Roseville. On the opposing side of the highway also to the east of the application site is No1-5 Old Barn Mews. These residential neighbours front The Green. The area of proposed development would be separated from the closest residential neighbours by approximately 27m and by virtue of the existing clubhouse building. The timber pergola would be sited on the existing concrete path to replace the existing pergola structure, albeit on a slightly larger scale in terms of its footprint. By virtue of its open-sided form and limited height which would appear to be less than the existing structure is not considered to result in a sense of enclosure or appear overbearing when viewed from neighbouring properties by virtue of the separation distance retained. The proposed pergola is not considered to introduce opportunities for overlooking or result in a loss of privacy to the adjacent residential neighbours.

7.2.3 To the west/southwest of the application site is Croxley Tennis Club and the Croxley Guild of Sports and Social Club. The proposed pergola is not considered to result in an adverse impact on the amenity of the adjacent Tennis or Sports Club given that it would remain to be read in the context of existing recreational development and would replace the existing structure on site. By virtue of its openside design and modest scale, it is not considered that the proposal would result in an overbearing presence when experienced from the adjoining sports facilities. Nor is it considered to interfere with the continued operation of the adjacent premises. The proposal is therefore considered acceptable in amenity terms.

7.2.4 In summary, the proposed development would not result in any adverse impact on any neighbouring dwelling or premises, and the development would be acceptable in accordance with Policies CP1 and CP12 of the Core Strategy.

7.3 Highways and parking provision

7.3.1 Core Strategy Policy CP10 (adopted October 2011) requires development to make adequate provision for all users, including car parking. Policy DM13 in the Development Management Policies document (adopted July 2013) states that development should make provision for parking in accordance with the Parking Standards set out within Appendix 5.

7.3.2 The existing parking provision for the site is provided in the existing parking area adjacent to the bowls club, it is also noted that there is a further parking area adjacent to the tennis courts and existing tennis pavilion. The proposed development would replace an existing structure intended to support the club's current use and is not considered to be associated with additional comings and goings from the site or materially impact how the use functions. The structure remains within the confines of the bowls club and would therefore not impact on the existing parking provision which is considered to be sufficient for its current use. The proposal is therefore considered acceptable in this regard.

7.4 Wildlife considerations

7.4.1 Section 40 of the Natural Environment and Rural Communities Act 2006 requires Local Planning Authorities to have regard to the purpose of conserving biodiversity. This is further emphasised by regulation 3(4) of the Habitat Regulations 1994 which state that Councils must have regard to the strict protection for certain species required by the EC Habitats Directive. The Habitats Directive places a legal duty on all public bodies to have regard to the habitats directive when carrying out their functions.

7.4.2 The protection of biodiversity and protected species is a material planning consideration in the assessment of this application in accordance with Policy CP9 of the Core Strategy and Policy DM6 of the Development Management Policies document. National Planning Policy requires Local Authorities to ensure that a protected species survey is undertaken for applications where biodiversity may be affected prior to the determination of a planning application.

7.4.3 A Biodiversity Checklist was submitted with the application and states that no protected species or biodiversity interests will be affected as a result of the application. The Local Planning Authority is not aware of any records of bats (or other protected species) within the immediate area that would necessitate further surveying work being undertaken.

7.5 Mandatory Biodiversity Net Gain

7.5.1 Paragraph 13 of Schedule 7A of the Town and Country Planning Act 1990 sets out that every planning permission granted for the development of land in England shall be deemed to have been granted subject to the 'biodiversity gain condition' requiring development to achieve a net gain of 10% of biodiversity value. This is subject to exemptions.

7.5.2 The applicant has confirmed that if permission is granted for the development to which this application relates the biodiversity gain condition would not apply because the application relates to the de-minimis exemption. Officers acknowledge that the total area of the proposed pergola is approximately 37sqm and therefore in excess of the 25sqm set out within the accepted exemption. However, it is acknowledged that the pergola is replacing an existing structure and the pergola would sit on an area of existing hardstanding and is therefore not considered to impact any on site habitat, or impact a priority habitat. The proposal is therefore considered to be exempt from mandatory BNG.

7.6 Trees and landscape

7.6.1 Policy DM6 of the DMP LDD sets out that development proposals should seek to retain trees and other landscape and nature conservation features, and that proposals should demonstrate that trees will be safeguarded and managed during and after development in accordance with the relevant British Standards.

7.6.2 The application site is located within the Croxley Green Conservation Area therefore all trees are afforded protection by way of this designation. There are however no trees in the area of the proposed development which consists largely of existing hardstanding. It is therefore not considered that any trees would be impacted by the proposed development. The proposal is therefore considered acceptable in this regard.

8 **Recommendation**

8.1 That PLANNING PERMISSION BE GRANTED subject to the following conditions:

- C1 The development hereby permitted shall be begun before the expiration of three years from the date of this permission.

Reason: In pursuance of Section 91(1) of the Town and Country Planning Act 1990 and as amended by the Planning and Compulsory Purchase Act 2004.

- C2 The development hereby permitted shall be carried out in accordance with the following approved plans: 5.12.25, TRDC01 (Block Plan), TRDC02 (Location Plan), TRDC03 (Heritage Statement)

Reason: For the avoidance of doubt, and in the proper interests of planning in accordance with Policies CP1, CP9, CP10 and CP12 of the Core Strategy (adopted October 2011), Policies DM3, DM6 and DM13 and Appendix 5 of the Development Management Policies (adopted July 2013), Croxley Green Neighbourhood Plan Referendum Version (2018) and the Croxley Green Conservation Area Appraisal (1996).

- C3 The pergola shall not be erected other than in the materials as have been approved in writing by the Local Planning Authority as stated in the submitted application form; and no external materials shall be used other than those approved.

Reason: To ensure that the external appearance of the building is satisfactory in accordance with Policies CP1 and CP12 of the Core Strategy (adopted October 2011) and Policy DM3 of the Development Management Policies LDD (adopted July 2013).

8.2 Informatives

- I1 With regard to implementing this permission, the applicant is advised as follows:

All relevant planning conditions must be discharged prior to the commencement of work. Requests to discharge conditions must be made by formal application which includes a fee.

There may be a requirement for the approved development to comply with the Building Regulations. Please contact Hertfordshire Building Control (HBC) on 01438 879990 or at buildingcontrol@hertfordshirebc.co.uk who will be happy to advise you on building control matters and will protect your interests throughout your build project by leading the compliance process. Further information is available at www.hertfordshirebc.co.uk.

Community Infrastructure Levy (CIL) - Your development may be liable for CIL payments and you are advised to contact the CIL Officer for clarification with regard to this (cil@threeivers.gov.uk). If your development is CIL liable, even if you have been granted exemption from the levy, please be advised that before commencement of any works it is a requirement under Regulation 67 of The Community Infrastructure Levy Regulations 2010 (As Amended) that CIL form 6 (Commencement Notice) must be completed, returned and acknowledged by Three Rivers District Council before building works start. Failure to do so will mean you lose the right to payment by instalments (where applicable), and a surcharge will be imposed. However, please note that a Commencement Notice is not required for residential extensions if relief has been granted.

Following the grant of planning permission by the Local Planning Authority it is accepted that new issues may arise post determination, which require modification of the approved plans. Please note that regardless of the reason for these changes, where these modifications are fundamental or substantial, a new planning application will need to be submitted. Where less substantial changes are proposed, the following options are available to applicants:

{b (a)} Making a Non-Material Amendment

{b (b)} Amending the conditions attached to the planning permission, including seeking to make minor material amendments (otherwise known as a section 73 application).

It is important that any modifications to a planning permission are formalised before works commence otherwise your planning permission may be unlawful and therefore could be subject to enforcement

action. In addition, please be aware that changes to a development previously granted by the LPA may affect any previous Community Infrastructure Levy (CIL) owed or exemption granted by the Council. If you are in any doubt whether the new/amended development is now liable for CIL you are advised to contact the Community Infrastructure Levy Officer (01923 776611) for clarification. Information regarding CIL can be found on the Three Rivers website (<https://www.threerivers.gov.uk/services/planning/community-infrastructure-levy>).

Care should be taken during the building works hereby approved to ensure no damage occurs to the verge or footpaths during construction. Vehicles delivering materials to this development shall not override or cause damage to the public footway. Any damage will require to be made good to the satisfaction of the Council and at the applicant's expense.

Where possible, energy saving and water harvesting measures should be incorporated. Any external changes to the building which may be subsequently required should be discussed with the Council's Development Management Section prior to the commencement of work. Further information on how to incorporate changes to reduce your energy and water use is available at: <https://www.threerivers.gov.uk/services/environment-climate-emergency/home-energy-efficiency-sustainable-living#Greening%20your%20home>.

- 12 The applicant is reminded that the Control of Pollution Act 1974 allows local authorities to restrict construction activity (where work is audible at the site boundary). In Three Rivers such work audible at the site boundary, including deliveries to the site and running of equipment such as generators, should be restricted to 0800 to 1800 Monday to Friday, 0900 to 1300 on Saturdays and not at all on Sundays and Bank Holidays.
- 13 The Local Planning Authority has been positive and proactive in its consideration of this planning application, in line with the requirements of the National Planning Policy Framework and in accordance with the Town and Country Planning (Development Management Procedure) (England) Order 2015. The development maintains/improves the economic, social and environmental conditions of the District.
- 14 The applicant is hereby advised to remove all site notices on or near the site that were displayed pursuant to the application.
- 15 The effect of paragraph 13 of Schedule 7A to the Town and Country Planning Act 1990 is that planning permission granted for the development of land in England is deemed to have been granted subject to the condition "(the biodiversity gain condition)" that development may not begin unless:
 - a) a Biodiversity Gain Plan has been submitted to the planning authority, and
 - b) the planning authority has approved the plan.

The planning authority, for the purposes of determining whether to approve a Biodiversity Gain Plan if one is required in respect of this permission would be Three Rivers District Council.

There are statutory exemptions and transitional arrangements which mean that the biodiversity gain condition does not apply.

Based on the information available this permission is considered to be one which will not require the approval of a biodiversity gain plan before development is begun because the following statutory exemption or transitional arrangement is considered to apply.

Development below the de minimis threshold, meaning development which:

- a) does not impact an onsite priority habitat (a habitat specified in a list published under section 41 of the Natural Environment and Rural Communities Act 2006); and
- b) impacts less than 25 square metres of onsite habitat that has biodiversity value greater than zero and less than 5 metres in length of onsite linear habitat (as defined in the statutory metric).

Where the local planning authority considers that the permission falls within paragraph 19 of Schedule 7A to the Town and Country Planning Act 1990, the permission which has been granted has the effect of requiring or permitting the development to proceed in phases. The modifications in respect of the biodiversity gain condition which are set out in Part 2 of the Biodiversity Gain (Town and Country Planning) (Modifications and Amendments) (England) Regulations 2024 apply.

Biodiversity gain plans are required to be submitted to, and approved by, the planning authority before development may be begun, and, if subject to phased development, before each phase of development may be begun.

If the onsite habitat includes irreplaceable habitat (within the meaning of the Biodiversity Gain Requirements (Irreplaceable Habitat) Regulations 2024) there are additional requirements for the content and approval of Biodiversity Gain Plans. The Biodiversity Gain Plan must include, in addition to information about steps taken or to be taken to minimise any adverse effect of the development on the habitat, information on arrangements for compensation for any impact the development has on the biodiversity of the irreplaceable habitat.

The planning authority can only approve a Biodiversity Gain Plan if satisfied that the adverse effect of the development on the biodiversity of the irreplaceable habitat is minimised and appropriate arrangements have been made for the purpose of compensating for any impact which do not include the use of biodiversity credits.

More information can be found in the Planning Practice Guidance online at <https://www.gov.uk/guidance/biodiversity-net-gain>.

- 16 The applicant is reminded that prior to the commencement of works, approval will be required from the Council as land owner, via the Property Services team. You should contact the property services team prior to the works taking place via 01923 776611 or by email to property@threerivers.gov.uk.

This page is intentionally left blank

25/2102/ FUL – Croxley Guild Bowls Club – Site Photographs



Figure 1: View from Rear of Tennis Courts





PLANNING COMMITTEE – 22 January 2026

25/2150/FUL - Extension of existing crossover and alterations to driveway at 10 Oak Green, Abbots Langley, Hertfordshire, WD5 OPG.

Parish: Abbots Langley Parish Council
Expiry of Statutory Period: 09.01.2026

Ward: Abbots Langley And Bedmond
Case Officer: Danielle Kavanagh

Recommendation: That planning permission be GRANTED subject to conditions.

Reason for consideration by the Committee: The agent for the application is a District Councillor.

To view all documents forming part of this application, please go to the following website:
[25/2150/FUL - Extension of existing crossover and alterations to driveway at 10 Oak Green, Abbots Langley, Hertfordshire](#)

1 Relevant Planning History

- 1.1 25/0658/FUL - Conversion of existing garage to habitable accommodation, including alterations to fenestration and extension to existing hardstanding to frontage. - 23.05.2025 – Permitted (partially implemented, garage conversion)
- 1.2 25/0645/CLPD - Certificate of Lawfulness Proposed Development: Construction of outbuilding to rear, loft conversion including rear dormer and front rooflight – 05.06.2025 – Permitted, implemented

2 Description of Application Site

- 2.1 The application site contains a semi-detached two-story dwelling, located on the northern side of Oak Green, Abbots Langley. Land levels on the site rise from front to rear in a south to north direction.
- 2.2 The streetscene of Oak Green is characterised by a variety of red brick dwellings, including terraced, semi-detached and link detached dwellings, set on gently staggered building lines.
- 2.3 The application dwelling is finished in mixed red brick with tile hanging at part of the first floor level. The dwelling's integrated garage has been converted to provide habitable accommodation. Within the frontage, there is space for one car to park and an area of lawn. To the rear of the dwelling is a patio with the majority of the amenity area laid to lawn. All boundaries to the rear of the dwelling are marked by close-board wooden fencing. The dwelling benefits from an outbuilding to the rear of the site.
- 2.4 The attached semi-detached neighbour No. 11 Oak Green is built in a similar style to the host dwelling and sits on the same land level. The neighbour to the west No. 9 Oak Green is a link detached red brick dwelling. This neighbour is set forward of the host dwelling.

3 Description of Proposed Development

- 3.1 This application seeks full planning permission for the extension of existing crossover and alterations to driveway.
- 3.2 The driveway extension would require the removal of an area of lawn and the creation of an area of water-permeable hardstanding. The extension would be splayed and measure 4.8m wide at the front boundary, increasing to 6.6m at the rear of the frontage. It would be 5.8m deep, the resulting increased area of hardstanding would be 31.9 sqm. It would be constructed on the western side of the existing driveway. The driveway finish was confirmed

by the agent and would be block paving with open joints for drainage, and would feature an additional drainage grill at the front boundary. The proposal would create space for two cars to park.

3.3 The proposed crossover extension would result in one additional section (approximately 0.9m) of dropped kerb being added to the existing vehicular crossover.

3.4 Amended plans were sought and received during the course of the application, reducing the extent of the proposed crossover extension.

4 Statutory Consultation

4.1 National Grid: [No response received]

4.2 Abbots Langley Parish Council: [No response received]

4.3 Hertfordshire County Council Highways: [Comment 1, Objection]

Recommendation Notice is given under article 22 of the Town and Country Planning (Development Management Procedure) (England) Order 2015 that Hertfordshire County Council as Highway Authority recommends that permission be refused for the following reasons:

1) The proposed extended vehicle crossover (VXO) is not in accordance with Hertfordshire County Council's (HCC) specifications and has the potential to negatively impact on the free and safe flow of pedestrian highway user on the adjacent local access road due to the unnecessarily long VXO / dropped kerb in which pedestrians would need to cross. The proposals are therefore contrary to policy guidelines as outlined in the National Planning Policy Framework (NPPF) 2019 and Hertfordshire's Local Transport Plan (LTP4) 2018.

Comments

The development site is located on Oak Green, an unclassified local access road subject to a 20mph speed limit and is considered highway maintainable at public expense. On Hertfordshire County Council's Place and Movement network, Oak Green is categorised as P2/M1 (e.g. Residential Street). No reportable highway collisions recorded within the immediate vicinity of the application site (5-year rolling). No Public Right of Way (as shown on the PRow map) directly affects the site or would be affected by the proposal. The site currently shared a dropped kerb and vehicle crossover with number 11, comprising of (approximately) seven dropped kerbs and two ramped kerbs. Each dropped/ramped kerb is 0.9m in length, meaning the length of the current dropped kerb is 6.3m (8.1m including ramped). The proposals include extending this a further 2.7m (3.6m including ramped kerbs). This means the dropped kerb would be extended to 10 flat kerbs and two ramped kerbs.

Hertfordshire County Council's Residential Dropped Kerb Policy states that:

"If the property already has a dropped kerb, we will only extend the existing access up to a maximum of four flat kerbs which equals 3.6m. This is the widest dropped kerb that we will allow. You will also be provided with one or two ramped kerbs depending on your property. Please do not apply for a dropped kerb wider than this as it will be refused"

It also states that: "A double dropped kerb which serves two properties will get 6 flat kerbs. Please do not apply for a dropped kerb wider than this as it will be refused."

A proposed dropped kerb arrangement totalling 10 flat kerbs cannot be accepted and is contention with the Dropped Kerb Policy and resultantly, Hertfordshire County Council's

Local Transport Plan (LTP4 - adopted 2018) Policy 5(b) - safe and acceptable access arrangements.

The Highway Authority is therefore recommending refusal on this application for the above reasons. The HA would not be minded to refuse an application which extended the current arrangement by one flat kerb (0.9m), meaning both properties received the four flat kerb maximum specified in the Residential Dropped Kerb Policy. As far as it is concerned, the current seven kerb arrangement provides four for the neighbouring property and three for number 10, as highlighted in the image below.



4.4 Hertfordshire County Council Highways: [Comment 2, Objection overcome]

Notice is given under article 22 of the Town and Country Planning (Development Management Procedure) (England) Order 2015 that Hertfordshire County Council as Highway Authority does not wish to restrict the grant of permission.

Informatives

HCC as Highway Authority recommends inclusion of the following Advisory Note (AN) / highway informative to ensure that any works within the highway are carried out in accordance with the provisions of the Highway Act 1980:

AN1) New or amended vehicle crossover access (section 184): Where works are required within the public highway to facilitate a new or amended vehicular access, the Highway Authority require the construction of such works to be undertaken to their satisfaction and specification, and by a contractor who is authorised to work in the public highway. If any of the works associated with the construction of the access affects or requires the removal and/or the relocation of any equipment, apparatus or structures (e.g. street name plates, bus stop signs or shelters, statutory authority equipment etc.) the applicant will be required to bear the cost of such removal or alteration. Before works commence the applicant will need to apply to the Highway Authority to obtain their permission, requirements and for the work to be carried out on the applicant's behalf. Further information is available via the County Council website at: <https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/changes-to-your-road/dropped-kerbs/dropped-kerbs.aspx>

AN2) Storage of materials: The applicant is advised that the storage of materials associated with the construction of this development should be provided within the site on land which is not public highway, and the use of such areas must not interfere with the public highway. If this is not possible, authorisation should be sought from the Highway Authority before

construction works commence. Further information is available via the website: <https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/business-and-developer-information/business-licences/business-licences.aspx> or by telephoning 0300 1234047.

AN3) Obstruction of highway: It is an offence under section 137 of the Highways Act 1980 for any person, without lawful authority or excuse, in any way to wilfully obstruct the free passage along a highway or public right of way. If this development is likely to result in the public highway or public right of way network becoming routinely blocked (fully or partly) the applicant must contact the Highway Authority to obtain their permission and requirements before construction works commence. Further information is available via the County Council website at: <https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/business-and-developer-information/business-licences/business-licences.aspx> or by telephoning 0300 1234047.

AN4) Debris and deposits on the highway: It is an offence under section 148 of the Highways Act 1980 to deposit compost, dung or other material for dressing land, or any rubbish on a made-up carriageway, or any or other debris on a highway to the interruption of any highway user. Section 149 of the same Act gives the Highway Authority powers to remove such material at the expense of the party responsible. Therefore, best practical means shall be taken at all times to ensure that all vehicles leaving the site during construction of the development and use thereafter are in a condition such as not to emit dust or deposit mud, slurry or other debris on the highway. Further information is available by telephoning 0300 1234047.

Comments

Amended plan: Following initial comments made by the Highway Authority on 23 December 2025, in which we recommended refusal based on an overly-long dropped kerb proposal, a modified plan removing this has been submitted. The Highway Authority is therefore re-assessing this application based on the amendments.

Context: The development site is located on Oak Green, an unclassified local access road subject to a 20mph speed limit and is considered highway maintainable at public expense. On Hertfordshire County Council's Place and Movement network, Oak Green is categorised as P2/M1 (e.g. Residential Street). No reportable highway collisions recorded within the immediate vicinity of the application site (5-year rolling). No Public Right of Way (as shown on the PRow map) directly affects the site or would be affected by the proposal.

Access: The site currently shares a vehicle crossover and dropped kerb with the neighbouring property, number 11, comprising of (approx.) 7 flat kerbs and 2 ramped kerbs. This is the sole vehicular access to the site. The proposals, following amendments demonstrated in drawing no. 2448-SK-500-B, comprise of extending the existing drive by 1 kerb, meaning the crossover will subsequently comprise of 8 flat kerbs and 2 ramped kerbs. This is in line with the Residential Dropped Kerb Policy which states that one dwelling can have a maximum of 4 flat kerbs, meaning the two dwellings together will have a dropped kerb made up of 8 flat kerbs and have 4 each. No issues have therefore been identified by the Highway Authority following these amendments.

Parking: As a result of the widened crossover, the development proposes to increase the number of parking spaces available to two. The Local Planning Authority will need to be content that proposals meet local parking standards, however the Highway Authority has no issue with the addition of an extra parking space at this location.

Surface water flood risk to the highway: The applicant is reminded that surface water must not be allowed to flow or be discharged onto land considered highway maintainable at public expense. Considering the nature and extent of the development the Highway Authority is content that this risk has not increased as a result of this development.

Emergency vehicle access: No changes to the current emergency access have been identified and all parts of the building will be within the 45m distance required for a fire tender to be able to reach in an emergency.

Access for waste collection vehicles: No changes to the waste collection arrangements are proposed or identified.

4.5 **Public/Neighbour Consultation**

4.6 Neighbours consulted: 5

4.7 Responses received: 0

5 Reason for Delay

5.1 No Delay

6 Relevant Planning Policy, Guidance and Legislation

6.1 Legislation

6.2 Planning applications are required to be determined in accordance with the statutory development plan unless material considerations indicate otherwise as set out within S38 (6) Planning and Compulsory Purchase Act 2004 and S70 of Town and Country Planning Act 1990).

6.3 The Localism Act received Royal Assent on 15 November 2011. The Growth and Infrastructure Act achieved Royal Assent on 25 April 2013.

6.4 The Wildlife and Countryside Act 1981 (as amended), the Conservation of Habitats and Species Regulations 2010, the Natural Environment and Rural Communities Act 2006 and the Habitat Regulations 1994 may also be relevant.

6.5 The Environment Act 2021.

6.6 National Planning Policy Framework and National Planning Practice Guidance

In 2024 the National Planning Policy Framework was revised. This is read alongside the National Planning Practice Guidance (NPPG). The determination of planning applications is made mindful of Central Government advice and the Local Plan for the area. It is recognised that Local Planning Authorities must determine applications in accordance with the statutory Development Plan, unless material considerations indicate otherwise, and that the planning system does not exist to protect the private interests of one person against another. The NPPF is clear that “existing policies should not be considered out-of-date simply because they were adopted or made prior to the publication of this Framework. Due weight should be given to them, according to their degree of consistency with this Framework”.

The NPPF states that 'good design is a key aspect of sustainable development, creates better places in which to live and work and helps make development acceptable to communities'. The NPPF retains a presumption in favour of sustainable development. This applies unless any adverse impacts of a development would 'significantly and demonstrably' outweigh the benefits.

6.7 The Three Rivers Local Plan

The application has been considered against the policies of the Local Plan, including the Core Strategy (adopted October 2011), the Development Management Policies Local Development Document (adopted July 2013) and the Site Allocations Local Development

Document (adopted November 2014) as well as government guidance. The policies of Three Rivers District Council reflect the content of the NPPF.

The Core Strategy was adopted on 17 October 2011 having been through a full public participation process and Examination in Public. Relevant policies include Policies CP1, CP9, CP10 and CP12.

The Development Management Policies Local Development Document (DMLDD) was adopted on 26 July 2013 after the Inspector concluded that it was sound following Examination in Public which took place in March 2013. Relevant policies include DM1, DM6, DM8, DM13 and Appendices 2 and 5.

7 Planning Analysis

7.1 Background

- 7.1.1 This application follows application 25/0658/FUL for the conversion of the existing garage to habitable accommodation, including alterations to fenestration and extension to the existing hardstanding to the frontage, which was approved at the May 2025 Planning Committee Meeting. The differences between the previous application and this one are an increase in the area of hardstanding to the front of the dwelling (a 24.8 sqm increase was approved, and a 31.9 sqm increase is proposed. The proposed driveway would be wider at the front boundary than the approved scheme which had a splayed western flank line.) and a proposed extension of the vehicular crossover. The garage conversion approved as part of the previous application has been implemented and is not included in this application.

7.2 Impact on the character and appearance of the host dwelling

- 7.2.1 Policy CP1 of the Core Strategy (adopted October 2011) seeks to promote buildings of a high enduring design quality that respect local distinctiveness and Policy CP12 of the Core Strategy relates to design and states that in seeking a high standard of design, the Council will expect development proposals to have regard to the local context and conserve or enhance the character, amenities and quality of an area.
- 7.2.2 Policy DM1 and Appendix 2 of the Development Management Policies Local Development Document (adopted July 2013) set out that development should not lead to a gradual deterioration in the quality of the built environment, have a significant impact on the visual amenities of the area and that extensions should respect the existing character of the dwelling, particularly with regard to the roof form, positioning and style of windows and doors, and materials.
- 7.2.3 The proposed driveway extension would result in the removal of an area of lawn and an increase in usable driveway space for the host dwelling, providing an additional assigned parking space within the frontage. While the loss of an area of soft landscaping is regrettable, a modest area of soft landscaping adjacent to the boundary with No. 9 would be maintained, which would soften the appearance of the driveway and help to preserve the character and appearance of the street scene.
- 7.2.4 In summary, the proposed development would not result in any adverse harm to the character or appearance of the host dwelling or streetscene. The development would be acceptable in accordance with Policies CP1 and CP12 of the Core Strategy (2011) and Policy DM1 and Appendix 2 of the Development Management Policies LDD (2013)

7.3 Impact on amenity of neighbours

- 7.3.1 Policy CP12 of the Core Strategy states that development should 'protect residential amenities by taking into account the need for adequate levels and disposition of privacy, prospect, amenity and garden space'. Policy DM1 and Appendix 2 of the Development

Management Policies document set out that development should not result in loss of light to the windows of neighbouring properties nor allow overlooking and should not be excessively prominent in relation to adjacent properties.

7.3.2 The proposed driveway extension would result in an increase in hardstanding to the frontage of the host dwelling of 31.9 sqm. This change is not considered to be of a scale that would be harmful to or impact neighbouring amenity.

7.3.3 The proposed development would therefore be acceptable in this regard in accordance with Policies CP1 and CP12 of the Core Strategy (2011) and Policy DM1 and Appendix 2 of the Development Management Policies LDD (2013).

7.4 Highways & Parking

7.4.1 Policy DM13 of the Development Management Policies LDD requires development to make provision for parking in accordance with the parking standards set out at Appendix 5 of the Development Management Policies LDD.

7.4.2 Hertfordshire Highways were consulted on the proposed development after an initial objection, amended plans were sought and reconsulted on. No objection was raised to the amended plans. They concluded that the proposal would not give rise to an unacceptable impact on the safety or operation of the surrounding highway. Hertfordshire Highways recommended the inclusion of highway informative/advisory notes.

7.4.3 The existing property benefits from 4 bedrooms, and no increase in the number of bedrooms is proposed. The parking standards require 3 spaces for a property of this size. The proposed development would result in three assigned parking spaces being provided, based on Hertfordshire Highways standard space size of 2.4m x 4.8m. Therefore, the proposed parking arrangement for the dwelling would be fully compliant with the guidance in Appendix 5.

7.4.4 A condition was applied to the grant of consent for application 25/0658/FUL, requiring the driveway alterations to be implemented prior to the conversion of the garage. Due to the driveway being obscured by building materials and a skip during the site visit, it is unclear if this condition has been adhered to. However, this application has been assessed on its own merits and is found to provide an adequate parking arrangement for the host dwelling.

7.4.5 As noted above, the driveway is proposed to be constructed in a permeable material with a drainage grill at the front boundary to capture any surface run off from the hard standing. These measures will ensure that surface water is disposed of within the site in accordance with Policy DM8 of the Development Management Policies LDD (adopted July 2013).

7.5 Rear Garden Amenity Space

7.5.1 Policy CP12 of the Core Strategy states that development should take into account the need for adequate levels and disposition of privacy, prospect, amenity and garden space.

7.5.2 The proposed development would not encroach upon the rear amenity space of the host dwelling, 132 sqm of useable amenity space would remain, which is acceptable to serve the four-bedroom dwelling.

7.6 Trees & Landscape

7.6.1 Policy DM6 of the Development Management Policies LDD sets out that development proposals should seek to retain trees and other landscape and nature conservation features, and that proposals should demonstrate that trees will be safeguarded and managed during and after development in accordance with the relevant British Standards. The proposed development would not involve the removal of any trees or lie in close proximity to trees.

- 7.6.2 The proposed development would not require the removal of any trees nor is considered to result in any harm to others.

7.7 Biodiversity

- 7.7.1 Section 40 of the Natural Environment and Rural Communities Act 2006 requires Local Planning Authorities to have regard to the purpose of conserving biodiversity. This is further emphasised by regulation 3(4) of the Habitat Regulations 1994 which state that Councils must have regard to the strict protection for certain species required by the EC Habitats Directive. The Habitats Directive places a legal duty on all public bodies to have regard to the habitats directive when carrying out their functions.

- 7.7.2 Biodiversity protection and protected species are a material planning consideration during the application process of this application. This is in accordance with Policy CP9 of the Core strategy in addition to Policy DM6 of the Development Management Policies Local Development Document. Local Authorities, in line with National Planning Policy, are required to ensure that a protected species survey is completed for applications whereby biodiversity may be affected prior to the determination of the application.

- 7.7.3 A biodiversity checklist was submitted with the application this stated that no protected species or biodiversity factors will be affected as a result of the application. The Local Planning Authority is not aware of any protected species within the immediate area that would require further assessment.

7.8 Mandatory Biodiversity Net Gain

- 7.8.1 Paragraph 13 of Schedule 7A of the Town and Country Planning Act 1990 sets out that every planning permission granted for the development of land in England shall be deemed to have been granted subject to the 'biodiversity gain condition' requiring development to achieve a net gain of 10% of biodiversity value. This is subject to exemptions as set out in The Biodiversity Gain Requirements (Exemptions) Regulations 2024.

- 7.8.2 In this case, the applicant has confirmed that if permission is granted for the development to which this application relates the biodiversity gain condition would not apply because the application relates to householder development.

8 **Recommendation**

- 8.1 That subject to no new material planning considerations being raised, that PLANNING PERMISSION IS GRANTED subject to the following conditions:

- C1 The development hereby permitted shall be begun before the expiration of three years from the date of this permission.

Reason: In pursuance of Section 91(1) of the Town and Country Planning Act 1990 and as amended by the Planning and Compulsory Purchase Act 2004.

- C2 The development hereby permitted shall be carried out in accordance with the following approved plans: 2448SK500B.

Reason: For the avoidance of doubt, and in the proper interests of planning in accordance with Policies CP1, CP9, CP10 and CP12 of the Core Strategy (adopted October 2011) and Policies DM1, DM6, DM8 and DM13 and Appendices 2 and 5 of the Development Management Policies (adopted July 2013).

- C3 The driveway extension shall be undertaken in a permeable material or provision made to direct run off water to a permeable or porous area or surface within the site. The driveway shall be retained as such thereafter.

Reason: In the interests of highway safety and to ensure sufficient on site parking is provided in accordance with Policies CP1, CP10 and CP12 of the Core Strategy (adopted October 2011) and Policies DM8, DM13 and Appendix 5 of the Development Management Policies LDD (adopted July 2013).

Informatives

- I1 With regard to implementing this permission, the applicant is advised as follows:

All relevant planning conditions must be discharged prior to the commencement of work. Requests to discharge conditions must be made by formal application which includes a fee. There may be a requirement for the approved development to comply with the Building Regulations. Please contact Hertfordshire Building Control (HBC) on 01438 879990 or at buildingcontrol@hertfordshirebc.co.uk who will be happy to advise you on building control matters and will protect your interests throughout your build project by leading the compliance process. Further information is available at www.hertfordshirebc.co.uk.

Community Infrastructure Levy (CIL) - Your development may be liable for CIL payments and you are advised to contact the CIL Officer for clarification with regard to this (cil@threeivers.gov.uk). If your development is CIL liable, even if you have been granted exemption from the levy, please be advised that before commencement of any works it is a requirement under Regulation 67 of The Community Infrastructure Levy Regulations 2010 (As Amended) that CIL form 6 (Commencement Notice) must be completed, returned and acknowledged by Three Rivers District Council before building works start. Failure to do so will mean you lose the right to payment by instalments (where applicable), and a surcharge will be imposed. However, please note that a Commencement Notice is not required for residential extensions IF relief has been granted.

Following the grant of planning permission by the Local Planning Authority it is accepted that new issues may arise post determination, which require modification of the approved plans. Please note that regardless of the reason for these changes, where these modifications are fundamental or substantial, a new planning application will need to be submitted. Where less substantial changes are proposed, the following options are available to applicants:

{\b (a)} Making a Non-Material Amendment

{\b (b)} Amending the conditions attached to the planning permission, including seeking to make minor material amendments (otherwise known as a section 73 application).

It is important that any modifications to a planning permission are formalised before works commence otherwise your planning permission may be unlawful and therefore could be subject to enforcement action. In addition, please be aware that changes to a development previously granted by the LPA may affect any previous Community Infrastructure Levy (CIL) owed or exemption granted by the Council. If you are in any doubt whether the new/amended development is now liable for CIL you are advised to contact the Community Infrastructure Levy Officer (01923 776611) for clarification. Information regarding CIL can be found on the Three Rivers website (<https://www.threerivers.gov.uk/services/planning/community-infrastructure-levy>).

Care should be taken during the building works hereby approved to ensure no damage occurs to the verge or footpaths during construction. Vehicles delivering materials to this development shall not override or cause damage to the public footway. Any damage will require to be made good to the satisfaction of the Council and at the applicant's expense.

Where possible, energy saving and water harvesting measures should be incorporated. Any external changes to the building which may be subsequently required should be discussed

with the Council's Development Management Section prior to the commencement of work. Further information on how to incorporate changes to reduce your energy and water use is available at: <https://www.threerivers.gov.uk/services/environment-climate-emergency/home-energy-efficiency-sustainable-living#Greening%20your%20home>

- 12 The applicant is reminded that the Control of Pollution Act 1974 stipulates that construction activity (where work is audible at the site boundary) should be restricted to 0800 to 1800 Monday to Friday, 0900 to 1300 on Saturdays and not at all on Sundays and Bank Holidays.
- 13 The Local Planning Authority has been positive and proactive in its consideration of this planning application, in line with the requirements of the National Planning Policy Framework and in accordance with the Town and Country Planning (Development Management Procedure) (England) Order 2015. The Local Planning Authority suggested modifications to the development during the course of the application and the applicant and/or their agent submitted amendments which result in a form of development that maintains/improves the economic, social and environmental conditions of the District.
- 14 The effect of paragraph 13 of Schedule 7A to the Town and Country Planning Act 1990 is that planning permission granted for the development of land in England is deemed to have been granted subject to the condition "(the biodiversity gain condition)" that development may not begin unless:
- a) a Biodiversity Gain Plan has been submitted to the planning authority, and
 - b) the planning authority has approved the plan.

The planning authority, for the purposes of determining whether to approve a Biodiversity Gain Plan if one is required in respect of this permission would be Three Rivers District Council.

There are statutory exemptions and transitional arrangements which mean that the biodiversity gain condition does not apply.

Based on the information available this permission is considered to be one which will not require the approval of a biodiversity gain plan before development is begun because the following statutory exemption or transitional arrangement is considered to apply.

Development which is subject of a householder application within the meaning of article 2(1) of the Town and Country Planning (Development Management Procedure) (England) Order 2015. A "householder application" means an application for planning permission for development for an existing dwellinghouse, or development within the curtilage of such a dwellinghouse for any purpose incidental to the enjoyment of the dwellinghouse which is not an application for change of use or an application to change the number of dwellings in a building.

Where the local planning authority considers that the permission falls within paragraph 19 of Schedule 7A to the Town and Country Planning Act 1990, the permission which has been granted has the effect of requiring or permitting the development to proceed in phases. The modifications in respect of the biodiversity gain condition which are set out in Part 2 of the Biodiversity Gain (Town and Country Planning) (Modifications and Amendments) (England) Regulations 2024 apply.

Biodiversity gain plans are required to be submitted to, and approved by, the planning authority before development may be begun, and, if subject to phased development, before each phase of development may be begun.

If the onsite habitat includes irreplaceable habitat (within the meaning of the Biodiversity Gain Requirements (Irreplaceable Habitat) Regulations 2024) there are additional requirements for the content and approval of Biodiversity Gain Plans. The Biodiversity Gain

Plan must include, in addition to information about steps taken or to be taken to minimise any adverse effect of the development on the habitat, information on arrangements for compensation for any impact the development has on the biodiversity of the irreplaceable habitat.

The planning authority can only approve a Biodiversity Gain Plan if satisfied that the adverse effect of the development on the biodiversity of the irreplaceable habitat is minimised and appropriate arrangements have been made for the purpose of compensating for any impact which do not include the use of biodiversity credits.

More information can be found in the Planning Practice Guidance online at <https://www.gov.uk/guidance/biodiversity-net-gain>.

- 15 New or amended vehicle crossover access (section 184): Where works are required within the public highway to facilitate a new or amended vehicular access, the Highway Authority require the construction of such works to be undertaken to their satisfaction and specification, and by a contractor who is authorised to work in the public highway. If any of the works associated with the construction of the access affects or requires the removal and/or the relocation of any equipment, apparatus or structures (e.g. street name plates, bus stop signs or shelters, statutory authority equipment etc.) the applicant will be required to bear the cost of such removal or alteration. Before works commence the applicant will need to apply to the Highway Authority to obtain their permission, requirements and for the work to be carried out on the applicant's behalf. Further information is available via the County Council website at: <https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/changes-to-your-road/dropped-kerbs/dropped-kerbs.aspx>
- 16 Storage of materials: The applicant is advised that the storage of materials associated with the construction of this development should be provided within the site on land which is not public highway, and the use of such areas must not interfere with the public highway. If this is not possible, authorisation should be sought from the Highway Authority before construction works commence. Further information is available via the website: <https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/business-and-developer-information/business-licences/business-licences.aspx> or by telephoning 0300 1234047.
- 17 Obstruction of highway: It is an offence under section 137 of the Highways Act 1980 for any person, without lawful authority or excuse, in any way to wilfully obstruct the free passage along a highway or public right of way. If this development is likely to result in the public highway or public right of way network becoming routinely blocked (fully or partly) the applicant must contact the Highway Authority to obtain their permission and requirements before construction works commence. Further information is available via the County Council website at: <https://www.hertfordshire.gov.uk/services/highways-roads-and-pavements/business-and-developer-information/business-licences/business-licences.aspx> or by telephoning 0300 1234047.
- 18 Debris and deposits on the highway: It is an offence under section 148 of the Highways Act 1980 to deposit compost, dung or other material for dressing land, or any rubbish on a made-up carriageway, or any or other debris on a highway to the interruption of any highway user. Section 149 of the same Act gives the Highway Authority powers to remove such material at the expense of the party responsible. Therefore, best practical means shall be taken at all times to ensure that all vehicles leaving the site during construction of the development and use thereafter are in a condition such as not to emit dust or deposit mud, slurry or other debris on the highway. Further information is available by telephoning 0300 1234047.

This page is intentionally left blank



